

E.T.S. de Ingeniería Industrial,
Informática y de Telecomunicación

Compressors test life bench under wet compression conditions



Grado en Ingeniería
en Tecnologías Industriales

FINAL PROJECT

Natalia Medina Cabello

A handwritten signature in black ink, appearing to be 'N. Medina Cabello'.

Jose Ignacio Arocena

Pamplona, 26 de Junio del 2014





FINAL PROJECT

Date: **19.06.2014**

Page: **2**

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1



FINAL PROJECT

Date: **19.06.2014**

Page: **3**

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

THANKS TO MY FAMILY, TEACHERS AND FRIENDS FOR THE GREAT SUPPORT PROVIDED WHEN IT WAS NEEDED THE MOST. WHEN THE PERSPECTIVE OF ENDING THE CAREER WAS STILL TOO FAR AWAY TO ACTUALLY BELIEVE IT.

I ALSO WANT TO THANK B/S/H FOR THE GIVEN OPPORTUNITY.

THANK YOU ALL FOR HELPING ME TO REACH THIS POINT, FOR WATCHING ME PASS TO A NEW PHASE OF MY LIFE AND TO ENCOURAGE ME TO BECOME AN ENGINEER.

Natalia Medina



FINAL PROJECT

Date: **19.06.2014**

Page: **4**

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1



FINAL PROJECT

Date: 20.06.2014

Page: 5

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

1.-PROJECT REPORT

INDEX

CHAPTER 1: PROBLEM

1	PROBLEM APPROACH	6
2	PROJECT PURPOSE.....	6
3	PLANIFICATION	7
3.1	STAGE 1.....	7
3.2	STAGE 2.....	7
3.3	STAGE 3.....	7
3.4	STAGE 4.....	7

CHAPTER 2: THEORETICAL INTRODUCTION

1	DEVELOPMENT.....	8
2	THEORETICAL BASE	9
2.1	REFRIGERANT CIRCULATION	9
2.2	AIR CIRCULATION	10
3	RELEVANT VARIABLES	11
4	CYCLE CONCEPT	11
4.1	PROCESS 1-2: COMPRESSOR.....	11
4.2	PROCESS 2-3: CONDENSER.....	12
4.3	PROCESS 3-4: EXPANSION VALVE	12
4.4	PROCESS 4-1: EVAPORATOR	12
5	OPERATIONAL DEFINITION	12
6	THERMS.....	14

CHAPTER 3: FIRST STAGE

1	ALTERNATIVES.....	15
1.1	OPTION 1: DESIGN ADAPTATION	15



FINAL PROJECT

Date: **20.06.2014**

Page: **6**

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

1.1.1	OPERATING POINT TWO CALCULATIONS.....	16
1.1.2	OPERATING POINT ONE CALCULATIONS.....	17
1.1.3	CONDENSER	18
1.1.4	OPERATING POINT THREE.....	19
1.1.5	ADVANTAGES AND DISADVANTAGES	20
1.2	OPTION 2: MODIFICATIONS	21
1.2.1	HEATING PROCESS 2-2r.....	22
1.2.2	ADVANTAGES AND DISADVANTAGES	23
2	WATER REFRIGERATION	23
3	SELECTION PROCESS	24
4	COMPONENTS FOR THE THERMODYNAMIC CIRCUIT.....	24
4.1	COMPRESSOR.....	24
4.2	CONDENSER	25
4.3	ELECTRONIC EXPANSION VALVE (EEV).....	25
4.4	PLOMBING	26
4.5	VARIABLE SPEED PUMP.....	26
4.6	CHILLER	27
4.7	HEATING RESISTANCE	27
5	SELECTION OF THE THERMODYNAMIC EQUIPMENT AND THE INSTRUMENTATION	28
5.1	EQUIPMENT	28
5.1.1	CONDENSER	28
5.1.2	EEV	28
5.1.3	CHILLER	28
5.1.4	VARIABLE SPEED WATER PUMP.....	28
5.1.5	HEATING RESISTANCE	29
5.2	INSTRUMENTATION	29
5.2.1	PREASSURE & TEMPERATURE SENSOR.....	29
5.2.2	WATER FLUX SENSOR.....	29
5.2.3	CORIOLIS REFRIGERANT FLUX SENSOR	29



FINAL PROJECT

Date: 20.06.2014

Page: 7

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

6	SENSORS, INPUTS Y OUTPUTS.....	30
6.1	SENSORS.....	30
6.1.1	OPTION 1.....	31
6.1.2	OPTION 2.....	33
6.2	BUDGET.....	35
6.2.1	OPTION 1.....	35
6.2.2	OPTION 2.....	36
7	OBSTACLES AND CALCULATIONS.....	37
7.1	REFRIGERANT'S FLOW AND CORIOLIS SENSOR.....	37
7.1.1	RESEARCHING GROUPS.....	37
7.2	CALCULATIONS.....	38
<u>CHAPTER 4: FOURTH STAGE</u>		
1	CONTROL DESIGN.....	39
1.1	CODE DIAGRAM.....	41
1.2	STEP 7.....	42
1.3	WINCC.....	45
1.4	VISUAL BASIC.....	45
1.5	EES.....	45
2	CONNECTION.....	46
2.1	HARDWARE.....	46
2.2	INDUSTRIAL ETHERNET.....	47
<u>CHAPTER 5: CONCLUSIONS</u>		
1	OBJECTIVES ACHIEVE.....	49
2	LIMITATIONS.....	50
3	IMPROVEMENTS.....	50

	<h1>FINAL PROJECT</h1>	Date: 20.06.2014 Page: 8
PROJECT: “Compressors test life bench under wet compression conditions”		PROJECT REPORT: 1

FIGURES

Figure 1- Mollier diagram of a complete refrigeration cycle	9
Figure 2-Cycle described by the air in a dryer machine	10
Figure 3--Mollier diagram of the first cycle designed	15
Figure 4-Condenser behavior	18
Figure 5- Option two, modified cycle.....	21
Figure 6-Water circuit	23
Figure 7- OPTION1- Thermodynamic cycle and the sensors employed	31
Figure 8-OPTION2-Thermodynamic cycle and the sensors employed	33
Figure 9-Thermodynamic table 1-Biphasic	39
Figure 10-Thermodynamic table 2- Superheated	40
Figure 11- Manual control detail	44
Figure 12-Automatic control detail.....	44
Figure 13- Hardware	46
Figure 14-Connection of the PLC, the remotes (ET200S) and the HMI tactile panel.....	47
Figure 15-CPU's IP and HMI's IP	48
Figure 16- Station 1 IP.....	48
Figure 17-Improvement- cycle to be implemented.....	50

TABLES

Table 1-Condenser limit.....	25
Table 2-Water flux limits.....	26
Table 3-Heating resistance limits.....	27
Table 4-Distribution of sensors.....	30
Table 5-Option 1-Distribution of sensors.....	32
Table 6-Option 1- Signals	32
Table 7-Option 2- Distribution of sensors.....	34
Table 8-Option 2- Signals	34
Table 9-Option 1- Budget.....	35
Table 10-Option 2- Budget.....	36
Table 11- Component's delivery time	49



FINAL PROJECT

Date: 19.06.2014

Page: 9

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

2.-ANNEX

INDEX

ANNEX I: CALCULATIONS

1	CODE "EES"	2
2	CALCULATIONS.....	5
2.1	REFRIGERANT R134A--- 5000 rpm 11.4 cc/rev	5
2.1.1	Summary R134 A --- 5000 rpm 11.4 cc/rev.....	10
2.2	REFRIGERANT R134 A---3000rpm, 7 cc/rev	11
2.2.1	Summary R134 A ---3000 rpm, 7 cc/rev.....	15
2.3	REFRIGERANT R410 A ---5000 rpm, 11.4 cc/rev	16
2.3.1	Summary R410 A--- 5000 rpm ,11.4 cc/rev.....	21
2.4	REFRIGERANT R 410 A --- 3000rpm, 7 cc/rev.....	22
2.4.1	Summary R410 A--- 3000 rpm, 7 cc/rev.....	27
2.5	REFRIGERANT R407 C --- 5000 rpm, 11.4 cc/rev.....	28
2.5.1	Summary R407 C ---5000 rpm, 11.4 cc/rev.....	33
2.6	REFRIGERANT R407 C ---3000 rpm , 7 cc/rev.....	34
2.6.1	Summary R407 C --- 3000 rpm, 7 cc/rev.....	39
2.7	REFRIGERANT R22 ---5000 rpm, 11.4 cc/rev.....	40
2.7.1	Summary R22--- 5000 rpm, 11.4 cc/rev.....	45
2.8	REFRIGERANT R 22 --- 3000 rpm, 7 cc/rev.....	46
2.8.1	Summary R 22 ---3000 rpm, 7 cc/rev.....	51

ANNEX II: SECOND STAGE

1	PRESSURE SENSORS	52
2	TEMPERATURE SENSORS	53
2.1	THERMORESISTANCES	53
3	WATER FLUX.....	53



FINAL PROJECT

Date: 19.06.2014

Page: 10

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

4	ELECTRONIC EXAPANSION VALVE.....	54
4.1	PECOMARK.....	54
5	VARIABLE SPEED PUMP.....	55
5.1	EBARA.....	55
5.2	PRODEL.....	55
6	CONDENSER.....	55
6.1	JOSE NEGREDO.....	55
6.2	PECOMARK.....	57

ANNEX III: SOFTWARE SELECTION

1	LABVIEW.....	58
1.1	PROS.....	58
1.2	CONS.....	58
2	SIMATIC- STEP 7.....	59
2.1	PROS.....	59
2.2	CONS.....	59
2.3	WEIGHTED METHODS.....	60

ANNEX IV: IMPROVEMENTS

1	IMPROVEMENT: SAUNIER DUVAL PROPOSAL.....	61
1.1.1	OPERATING POINT TWO CALCULATIONS.....	62
1.1.2	OPERATING POINT ONE CALCULATIONS.....	64
1.1.3	CONTROL OF THE OPERATING POINT THREE AND FOUR.....	64
1.1.4	CONDENSER.....	65
1.1.5	SECOND EXPANSION AND FINAL PROCESS.....	66
1.1.6	ADVANTAGES AND DISADVANTAGES.....	66
2	MODIFICATION.....	66
3	CALCULATIONS.....	67
3.1	"EES" CODE.....	67
3.2	REFRIGERANT R134 A--> 5000 rpm, 11 cc/rev.....	71
3.2.1	Summary R134 A--- 5000 rpm, 11.4 cc/rev.....	76



FINAL PROJECT

Date: **19.06.2014**

Page: **11**

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

3.3	REFRIGERANT R 134A --> 3000rpm, 7 cc/rev.....	77
3.3.1	Summary R 134 A--- 3000 rpm, 7 cc/rev.....	82
3.4	REFRIGERANT R410 A --> 5000 rpm, 11.4 cc/rev.....	83
3.4.1	Summary R410 A--- 5000 rpm, 11.4 cc/rev.....	88
3.5	REFRIGERANT R410 A--> 3000 rpm, 7 cc/rev.....	89
3.5.1	Summary R410 A--- 3000rpm, 7cc/rev	94
3.6	REFRIGERANT R407 C -->5000 rpm, 11.4 cc/rev.....	95
3.6.1	Summary R407 C---5000 rpm, 11.4 cc/rev.....	100
3.7	REFRIGERANT R407 C --> 3000 rpm, 7cc/rev	101
3.7.1	Summary R407 C--- 3000 rpm, 7 cc/rev	106
3.8	REFRIGERANT R 22--> 5000 rpm, 11.4cc/rev	107
3.8.1	Summary R 22--- 5000 rpm, 11.4 cc/rev	112
3.9	REFRIGERANT R 22--> 3000 rpm, 7cc/rev.....	113
3.9.1	Summary R 22-->3000 rpm, 7 cc/rev	118

ANNEX V: WINCC

1.	SCADA STRUCTURE	119
2	SCREENS.....	120
2.1	HOME SCREEN.....	120
2.2	MAIN MENU.....	121
2.3	STATIONS HABILITATION	122
2.4	STATIONS EQUIPMENT	123
2.5	STATIONS SETTINGS.....	124
2.6	STATIONS MENU	125
2.7	MENU 1	126
2.8	EQUIPMENT 1	127
2.9	SETTING AUTOMATIC.....	128
2.10	SETTING MANUAL.....	130
2.11	DATA 1.....	131
2.12	COMPARATIONS 1.....	133



FINAL PROJECT

Date: 19.06.2014

Page: 12

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

2.13	DIAGRAM 1	135
2.14	GRAPHICS 1	137
2.15	GRAPHIC P&T	139
2.16	GRAPHIC FLUX.....	141
3	CONNECTIVITY & VARIABLES & TEXT LISTS.....	142
3.1	CONNECTIVITY	142
3.2	VARIABLES.....	144
3.3	TEXT LISTS	145

ANNEX VI: EXCEL AND VISUAL BASIC CODE

1	INTERFACE WITH WINCC	147
1.1	WORKBOOK.....	147
1.2	MODULE 1	152
1.3	MODULE 2	155
1.4	SHEET 1	161
2	DATA LOGGER	163
2.1	DATA LOGGER FUNCTION	163
3	CALCULATION FILE	164

ANNEX VII: STEP 7

1	STRUCTURE	168
2	INPUTS & OUTPUTS	186
3	OB 1.....	190
4	FC 1.....	192
5	FC 2.....	210
6	FC 3.....	211
7	FC 4.....	212
8	FC 5.....	218
9	FC 6.....	231
10	FC 7.....	236
11	FC 8.....	240



FINAL PROJECT

Date: 19.06.2014

Page: 13

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

12	FC 9.....	245
13	FC 10.....	252
14	FC 94.....	259
15	FC 95.....	262
16	FC 96.....	264
17	FC 97.....	267
18	FC 98.....	274
19	FC 99.....	279
20	DB 10.....	280
21	DB 11.....	281
22	UDT 1.....	282
23	UDT 2.....	283
24	UDT 3.....	284
25	UDT 4.....	285
26	UDT 5.....	286
27	UDT 6.....	287
28	UDT 7.....	288
29	UDT 8.....	289
30	UDT 9.....	290
31	UDT 10.....	291
32	UDT 11.....	292
33	UDT 12.....	293
34	HARDWARE & PLC- HMI CONNECTION.....	294
34.1	HARDWARE	294
34.2	PLC-HMI CONNECTION	295

ANNEX VIII: UNCERTAINTIES

1	EES CODE.....	296
2	RESULT	297

ANNEX IX: DATA SHEETS



FINAL PROJECT

Date: 19.06.2014

Page: 14

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

1	PUMP	298
2	WATER FLUX.....	304
3	REFRIGERANT FLUX.....	334
4	PRESSURE SENSOR	335
5	TEMPERATURE SENSORS	343

ANNEX X: OFFERS

1	EMERSON	346
2	EBARA.....	349
3	JUMO.....	351
4	IFM	353
5	OMEGA.....	354
6	ELECTROLUMEN	355

FIGURES

Figure 1.-Improvement, S&D cycle	61
Figure 2-Thermodynamic components cycle.....	66
Figure 3-WINCC structure	119
Figure 4-Home screen.....	120
Figure 5-Main menu.....	121
Figure 6-Stations habilitation.....	122
Figure 7-Stations equipment	123
Figure 8-Stations settings.....	124
Figure 9-Stations menu.....	125
Figure 10-Station 1 Menu	126
Figure 11-Station 1 Equipment	127
Figure 12-Settings station 1, automatic.....	128
Figure 13-Settings station1, automatic (No Tin sensor)	129
Figure 14-Settings station 1, manual	130
Figure 15-Data station 1.....	131
Figure 16-Data station 1, alarms.....	132
Figure 17-Comparison 1	133



FINAL PROJECT

Date: 19.06.2014

Page: 15

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

Figure 18-Comparation 1, alarms	134
Figure 19- Diagram station 1.....	135
Figure 20-Diagram station 1, alarms.....	136
Figure 21-Graphics station 1	137
Figure 22-Graphic station 1, no sensors connected	138
Figure 23-T&P graphic.....	139
Figure 24- T&P graphic, no sensors connected	140
Figure 25- Flux graphic.....	141
Figure 26-Flux graphic, no sensors connected.....	142
Figure 27-Connectivity	143
Figure 28-IP Adress. Connection between PLC and the HMI.....	144
Figure 29-WINCC Variables	145
Figure 30- Text Lists	146
Figure 31-WINCC Structure	147
Figure 32-Excel interface.....	162
Figure 33- Data Logger	164
Figure 34-Summary data import-export.....	165
Figure 35-R134A import-export data.....	166
Figure 36-R410A & R407C import_export data	166
Figure 37-R32 & R290 import_export data.....	167
Figure 38- Hardware connection, 12 stations.....	294
Figure 39- PLC,HMI and remotes connection	295
Figure 40- IP adress of the CPU, the HMI and the first station.....	295
Figure 41- Uncertainties.....	297

TABLES

Table 1- R134 A- 5000 rpm, 11.4 cc/rev-cycle 1	5
Table 2-Summary R134A- 5000 rpm, 11.4 cc/rev- cycle 1.....	10
Table 3-R134 A -3000rpm, 7 cc/rev- cycle 1	11
Table 4-Summary R134 A- 3000rpm, 7 cc/rev- cycle 1.....	15
Table 5-R410 A- 5000 rpm, 11.4 cc/rev- cycle 1	16
Table 6-Summary R410 A- 5000 rpm, 11.4 cc/rev- cycle 1.....	21
Table 7- R410 A- 3000 rpm, 7 cc/rev- cycle 1	22
Table 8-Summary R410 A- 3000 rpm, 7 cc/rev- cycle 1.....	27
Table 9- R407 C- 5000rpm, 11.4 cc/rev- cycle 1	28
Table 10- Summary R407 C- 5000 rpm, 11.4 cc/rev- cycle 1	33
Table 11- Summary R407 C- 3000 rpm, 7cc/rev- cycle 1	34



FINAL PROJECT

Date: **19.06.2014**

Page: **16**

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

Table 12- Summary R407 C- 3000 rpm , 7 cc/rev- cycle 1	39
Table 13- R22- 5000 rpm, 11.4 cc/rev-cycle 1	40
Table 14-Summary R22- 5000 rpm, 11.4 cc/rev-cycle 1	45
Table 15- R22- 3000 rpm, 7 cc/rev-cycle 1	46
Table 16-Summary R22- 3000 rpm, 7cc/rev- cycle 1	51
Table 17-Pressure sensors	52
Table 18-Thermoresistances.....	53
Table 19- Water flux.....	53
Table 20-Electronic expansion valve.....	54
Table 21- Pekomark	54
Table 22-Pekomark-condenser	57
Table 23-Software selection procedure.....	60
Table 24-R134 A- 5000rpm, 11.4 cc/rev- improvement	71
Table 25-Summary R134 A-5000rpm, 11.4 cc/rev- improvement.....	76
Table 26-R134 A- 3000rpm, 7 cc/rev- improvement	77
Table 27- Summary R134A- 3000rpm, 7 cc/rev - improvement.....	82
Table 28-R410 A-5000 rpm, 11.4 cc/rev- improvement	83
Table 29-Summary R410 -5000rpm, 11.4 cc/rev- improvement.....	88
Table 30-R410 A- 3000 rpm, 7 cc/rev- improvement	89
Table 31-Summary R410 A- 3000 rpm, 7 cc/rev- improvement.....	94
Table 32-R407C-5000 rpm, 11.4 cc/rev- improvement	95
Table 33-Summary R407C-5000 rpm, 11.4 cc/rev- improvement.....	100
Table 34-R407C- 3000 rpm, 7cc/rev- improvement	101
Table 35-Summary R407C-3000rpm, 7cc/rev- improvement.....	106
Table 36- R22- 5000rpm, 11.4 cc/rev- improvement	107
Table 37-Summary R22- 5000rpm, 11.4 cc/rev- improvement.....	112
Table 38-R22- 3000 rpm, 7 cc/rev- improvement	113
Table 39- Summary R22- 3000rpm, 7 cc/rev- improvement.....	118

3.-PLANES

INDEX

1	PID OPTION1	<u>1</u>
2	PID OPTION 2	<u>2</u>
3	TEST RIG BENCH.....	<u>3</u>



FINAL PROJECT

Date: **19.06.2014**

Page: **2**

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

E.T.S. de Ingeniería Industrial,
Informática y de Telecomunicación

Compressors test life bench under wet compression conditions



Grado en Ingeniería
en Tecnologías Industriales

PROJECT REPORT

Natalia Medina Cabello

A handwritten signature in black ink, appearing to be 'N. Medina'.

Jose Ignacio Arocena

Pamplona, 26 de Junio del 2014





FINAL PROJECT

Date: **19.06.2014**

Page: **2**

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 1
PROJECT: “Compressors test life bench under wet compression conditions”		PROJECT REPORT: 1

PROJECT REPORT’S INDEX

CHAPTER 1: PROBLEM

1	PROBLEM APPROACH	6
2	PROJECT PURPOSE.....	6
3	PLANIFICATION	7
3.1	STAGE 1	7
3.2	STAGE 2	7
3.3	STAGE 3	7
3.4	STAGE 4	7

CHAPTER 2: THEORETICAL INTRODUCTION

1	DEVELOPMENT.....	8
2	THEORETICAL BASE	9
2.1	REFRIGERANT CIRCULATION	9
2.2	AIR CIRCULATION	10
3	RELEVANT VARIABLES	11
4	CYCLE CONCEPT	11
4.1	PROCESS 1-2: COMPRESSOR	11
4.2	PROCESS 2-3: CONDENSER.....	12
4.3	PROCESS 3-4: EXPANSION VALVE	12
4.4	PROCESS 4-1: EVAPORATOR	12
5	OPERATIONAL DEFINITION	12
6	THERMS.....	14

CHAPTER 3: FIRST STAGE

1	ALTERNATIVES.....	15
1.1	OPTION 1: DESIGN ADAPTATION	15
1.1.1	OPERATING POINT TWO CALCULATIONS.....	16
1.1.2	OPERATING POINT ONE CALCULATIONS.....	17



FINAL PROJECT

Date: 19.06.2014

Page: 2

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

1.1.3	CONDENSER	18
1.1.4	OPERATING POINT THREE	19
1.1.5	ADVANTAGES AND DISADVANTAGES	20
1.2	OPTION 2: MODIFICATIONS	21
1.2.1	HEATING PROCESS 2-2r.....	22
1.2.2	ADVANTAGES AND DISADVANTAGES	23
2	WATER REFRIGERATION	23
3	SELECTION PROCESS	24
4	COMPONENTS FOR THE THERMODYNAMIC CIRCUIT	24
4.1	COMPRESSOR.....	24
4.2	CONDENSER	25
4.3	ELECTRONIC EXPANSION VALVE (EEV).....	25
4.4	PLOMBING	26
4.5	VARIABLE SPEED PUMP.....	26
4.6	CHILLER	27
4.7	HEATING RESISTANCE	27
5	SELECTION OF THE THERMODYNAMIC EQUIPMENT AND THE INSTRUMENTATION	28
5.1	EQUIPMENT	28
5.1.1	CONDENSER	28
5.1.2	EEV	28
5.1.3	CHILLER	28
5.1.4	VARIABLE SPEED WATER PUMP	28
5.1.5	HEATING RESISTANCE	29
5.2	INSTRUMENTATION	29
5.2.1	PREASSURE & TEMPERATURE SENSOR.....	29
5.2.2	WATER FLUX SENSOR.....	29
5.2.3	CORIOLIS REFRIGERANT FLUX SENSOR	29
6	SENSORS, INPUTS Y OUTPUTS.....	30
6.1	SENSORS.....	30



FINAL PROJECT

Date: 20.06.2014

Page: 3

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

6.1.1	OPTION 1.....	31
6.1.2	OPTION 2.....	33
6.2	BUDGET.....	35
6.2.1	OPTION 1.....	35
6.2.2	OPTION 2.....	36
7	OBSTACLES AND CALCULATIONS.....	37
7.1	REFRIGERANT'S FLOW AND CORIOLIS SENSOR.....	37
7.1.1	RESEARCHING GROUPS.....	37
7.2	CALCULATIONS.....	38
CHAPTER 4: FOURTH STAGE		
1	CONTROL DESIGN.....	39
1.1	CODE DIAGRAM.....	41
1.2	STEP 7.....	42
1.3	WINCC.....	45
1.4	VISUAL BASIC.....	45
1.5	EES.....	45
2	CONNECTION.....	46
2.1	HARDWARE.....	46
2.2	INDUSTRIAL ETHERNET.....	47
CHAPTER 5: CONCLUSIONS		
1	OBJECTIVES ACHIEVE.....	49
2	LIMITATIONS.....	50
3	IMPROVEMENTS.....	50

	<h1>FINAL PROJECT</h1>	Date: 20.06.2014 Page: 4
PROJECT: “Compressors test life bench under wet compression conditions”		PROJECT REPORT: 1

PROJECT REPORT’S FIGURES

Figure 1- Mollier diagram of a complete refrigeration cycle	9
Figure 2-Cycle described by the air in a dryer machine	10
Figure 3--Mollier diagram of the first cycle designed	15
Figure 4-Condenser behavior	18
Figure 5- Option two, modified cycle.....	21
Figure 6-Water circuit	23
Figure 7- OPTION1- Thermodynamic cycle and the sensors employed	31
Figure 8-OPTION2-Thermodynamic cycle and the sensors employed	33
Figure 9-Thermodynamic table 1-Biphasic	39
Figure 10-Thermodynamic table 2- Superheated	40
Figure 11- Manual control detail	44
Figure 12-Automatic control detail.....	44
Figure 13- Hardware	46
Figure 14-Connection of the PLC, the remotes (ET200S) and the HMI tactile panel.....	47
Figure 15-CPU's IP and HMI's IP	48
Figure 16- Station 1 IP.....	48
Figure 17-Improvement- cycle to be implemented.....	50

PROJECT REPORT’S TABLES

Table 1-Condenser limit	25
Table 2-Water flux limits.....	26
Table 3-Heating resistance limits.....	27
Table 4-Distribution of sensors	30
Table 5-Option 1-Distribution of sensors.....	32
Table 6-Option 1- Signals	32
Table 7-Option 2- Distribution of sensors.....	34
Table 8-Option 2- Signals	34
Table 9-Option 1- Budget.....	35
Table 10-Option 2- Budget.....	36
Table 11- Component's delivery time	49



FINAL PROJECT

Date: **19.06.2014**

Page: **5**

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1



FINAL PROJECT

Date: 19.06.2014

Page: 6

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

CHAPTER 1: PROBLEM

1 PROBLEM APPROACH

The correct operation of the BSH group dryers is guaranteed within a range of temperatures of 10 °C to 35 °C.

However, due to the growing trend of placing them on the outside (or in areas not climatically controlled), there is a necessity to check the correct operation of the components at lower temperatures, such as 5 °C.

The disadvantage of operating at low temperatures is the refrigerant behavior of the "Bottom group". It is found that the state of the refrigerant at the compressor inlet is biphasic at 5°C.

The compressors are properly equipped with an accumulator to store the liquid refrigerant, which does not pass through the compressor. Nevertheless, the oil of the compressor has a small proportion of the liquid refrigerant mixed.

Previously, tests proved the correct sizing of the accumulator, as they are prepared to store the total refrigerant charge of the liquid circuit, were made.

2 PROJECT PURPOSE

It is intend to design, control, build and set up, an essay for testing the compressors life when operating in wet compression condition.

The purpose of this "bench", is to determine the consequences of a biphasic refrigerant inlet, in terms of the rotary compressor reliability, as manufactures recommend to avoid these use.

Therefore, it will be necessary to build a "test bench" that allows the test of different compressors models in a reduced compression-expansion cycle. The "bench" should permit the selection and the constant maintenance of the input conditions of the refrigerant (pressure, temperature, quality) the input condition of the refrigerant in terms of pressure, temperature and steam quality for different refrigerants.

The refrigerants taken into consideration when computing the calculus are: R22, R134a, R410a, and R407c.

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 7
PROJECT: “Compressors test life bench under wet compression conditions”		PROJECT REPORT: 1

The operation of this “bench” shall be governed by a system of controls to access and independently parameterize several test stations, although only one will be developed during the project.

3 PLANIFICATION

3.1 STAGE 1

Since the beginning of the practice (24th February) there would be about a month (until the end of March) to carry out the following assignments:

- Bibliography review.
- Visit to an associate Enterprise with a similar facility in progress.
- Definition of the thermodynamic circuit components taking into consideration the compatibility and the connection to the automatic control system.

3.2 STAGE 2

The second stage is expected to last approximately a two months, so it is supposed to end during the first week of June.

- Purchase orders and reception of the thermodynamic components.
- Design of the control system and necessary equipment.

3.3 STAGE 3

Within June the bench it is supposed to be assembled and the control system must be receipt (once that the purchase orders of the control system have been given).

3.4 STAGE 4

Until the end of the practice in BSH Group, the control system must be connected and the program code optimized.

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 8
PROJECT: "Compressors test life bench under wet compression conditions"		PROJECT REPORT: 1

CHAPTER 2: THEORETICAL INTRODUCTION

1 DEVELOPMENT

Mainly, the tasks that will be developed in chronological order are:

1. Design of the bench, taking into consideration both the equipment and main components, and the instrumentation necessary for its control. For this, the bibliography on the subject must be reviewed.
2. Necessary automatic control design for test bench, taking into consideration the possible raise of the number of station in the bench (up to 12 stations), although initially only one will be established.
3. Participation in the acquisition and management of purchasing the equipment and major components with the support of purchasing departments and engineering processes, ensuring that they fulfill the specifications of the design stage.
4. Construction of the bench, supported by the laboratory technicians.
5. Programming and control setting.
6. Start the test bench. Readjustments of the automatic control system. (*)

() This part would not be considered in this project, as the practice in BSH is not concluded. This point would be implemented in July.*



FINAL PROJECT

Date: 19.06.2014

Page: 9

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

2 THEORETICAL BASE

2.1 REFRIGERANT CIRCULATION

The complete refrigeration cycle, that the refrigerant experiment in the bottom group of the dryer appliances, is the illustrated in the Figure 1.




Figure 1- Mollier diagram of a complete refrigeration cycle

THE PRESSURES IN THE GRAPHIC WERE SET IN ORDER TO EASE THE UNDERSTANDING OF IT, THEY DO NOT REPRESENT THE REAL VALUES

In a standard refrigeration cycle, the refrigerant is in a gaseous state at the compressor inlet. Is in it, in which the refrigerant undergoes a pressure increase with the corresponding increase in its temperature.

Then, the refrigerant is subjected to a cooling process, due to its passage through a condenser. Along its stay in the condenser, a heat exchange between the refrigerant and the medium (water or even the air) is produced, so that a liquefaction occurs.



FINAL PROJECT

Date: 19.06.2014

Page: 10

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

Then the pressure is reduced with the aid of an expansion valve (e.g.: capillary) so it recovers the pressure at the beginning of the cycle.

Finally, despite to have recovered the starting pressure point of the cycle, there is still a difference of enthalpies. To overcome this, it is required the use of an evaporator so that a medium of high temperature (output air of the dryer drum) will yield heat to the refrigerant to reach the state and temperature of the cycle starting point of the required.

2.2 AIR CIRCULATION

Along the previous section the refrigeration cycle experimented in a dryer appliance by the refrigerant was defined. However, in this section it would be described the cycle for air, as shown in Figure 2.




Figure 2-Cycle described by the air in a dryer machine

The air at the condenser inlet is at low temperature and without humidity. Along the condenser, the refrigerant absorbs the heat from the condenser, increasing its temperature. This warm air goes through the dryer drum, and absorbs some of the clothes dampness's. While leaving the drum, the air has gained humidity and its temperature has been decreased (although it is still high).

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 11
PROJECT: “Compressors test life bench under wet compression conditions”		PROJECT REPORT: 1

Straightaway the drum, the air enters the evaporator. Along the evaporator, the refrigerant loses heat and the humidity absorbed from the laundry, is condensed.

Once again, the cold air leaving the evaporator is redirected to the inlet of the condenser, to absorb heat from the refrigerant.

3 RELEVANT VARIABLES

In the complete cooling cycle we have as variables, the pressures and temperatures of the different operating points. In addition to that, if these points are within the biphasic bell, we will need to know other additional thermodynamic magnitude as the enthalpy, title ... in order to calculate the operating point.

Besides, ideally, the flow of the compressor refrigerant and the air flow and its temperature would be monitor.

However, note that a complete refrigeration circuit won't be made for the test of compressors lifes. It is intended to simplify the cycle components simplify, maintaining the operating conditions of the compressor unchanged, as only the consequences of the wet compression are to be considered.

4 CYCLE CONCEPT

At the execution of the cycle, some processes can simplify the theoretical calculation, taking into the account certain assumptions and / or approximations made as certain.

In some cases, these assumptions are taken as certain without using any “correction factors or methods.” However, in other procedures, the assumptions are used to calculate ideal intermediate operation points for the later use of corrective methods (such as efficiencies) and find the actual operating point.

4.1 PROCESS 1-2: COMPRESSOR

In this process, an isentropic approximation can be made, due to the fact of the inexistence of a delivered heat exchange.

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 12
PROJECT: “Compressors test life bench under wet compression conditions”		PROJECT REPORT: 1

Nevertheless, there would be some “heat losses” even if there is thermal isolation. For these reason, the isentropic hypothesis will be used to calculate an intermediate ideal operation point (point 2s), knowing the entropy of point 1.

Once that the isentropic operating point is obtained, employing the isentropic efficiency of the compressor in the following formula, an approximation of the real operating point can be made (point two).

$$h_2 = h_1 + \frac{h_{2s} - h_1}{\eta_{iso}}$$

4.2 PROCESS 2-3: CONDENSER

The approximation employed in this particular process, is the assumption of the pressure maintenance. We consider this process, as isobaric (even if it does exist a small pressure drop).

4.3 PROCESS 3-4: EXPANSION VALVE

It is considered as an isenthalpic process, and it is noteworthy that it is the most accurate of the hypothesis employed.

This is because, if a proper thermal isolation of the expansion valve is executed, it would barely be any heat losses.

4.4 PROCESS 4-1: EVAPORATOR

The process of heat absorption by the refrigerant from the air, can be considered as the antagonist heat exchange made in the condenser.

In both processes, there is only an action on the thermal state of the refrigerant, so that in this case the process carried out in the evaporator would have also an isobaric consideration.

5 OPERATIONAL DEFINITION

The assumptions, approximations and hypothesis made in the previous section, are helpful when performing a theoretical calculation of the cycle (exclusively employing the inputs of the system).

The calculation process has been defined to employ thermodynamic tables to calculate the results. However, a thermodynamic software, such as EES (Engineering Equations Solver) was also used.



FINAL PROJECT

Date: 19.06.2014

Page: 13

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

Employing this software, it is possible to calculate a thermodynamic magnitude with two other thermodynamic magnitudes and the substance name, what can be really helpful.

- **PROCES 1-2: COMPRESSOR**

- Point 2s (isentropic) is calculated: Thermodynamic tables must be employed to calculate the temperature, knowing the entropy and the pressure at this point.
- Once that the temperature is calculated, and knowing the pressure, the enthalpy can be calculated.
- To obtain the real point 2: Knowing the isentropic efficiency of the compressor we can employ the following formula

$$h_2 = h_1 + \frac{h_{2s} - h_1}{\eta_{iso}}$$

- **PROCESS 2-3: CONDENSER**

- The pressure and the sub cooling are known, so the temperature can be computed. With these data the enthalpy of point 3 is computed.

With the enthalpy difference, the heat exchange with the air can be calculated.

$$\dot{Q} = \dot{m}_{ref} \cdot (h_2 - h_3) = \dot{m}_{air} \cdot Cp \cdot (T_{OUT} - T_{IN})$$

- **PROCESS 3-4: EXPANSION VALVE**

- As it is considered as an isenthalpic process, not only the pressure is known (the same as the pressure in the first operating point). The enthalpy of point 4 is equal to the one calculated in point 3.

- **PROCESS 4-1: EVAPORATOR**

- All the operating points have already been defined and calculated. With the enthalpies data of points 4 and 1, the heat exchange absorbed by the air can be calculated.

$$\dot{Q} = \dot{m}_{ref} \cdot (h_1 - h_4) = \dot{m}_{aire} \cdot Cp \cdot (T_{IN} - T_{OUT})$$

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 14
PROJECT: “Compressors test life bench under wet compression conditions”		PROJECT REPORT: 1

6 THERMS

EEV: Electronic expansion valve. The valve is controlled by an input signal, to achieve the pressure difference desired.

CONDENSER: A device unit to condense vapor into liquid. The condensing media employed in the complete cycle (performed by the dryer machine) is air. However, in the thermodynamic cycle designed (test rig), water is used due to its ease of control.

SUBCOOLING: Refers to a liquid existing at a temperature below its normal saturation temperature.

ISENTROPIC: An isentropic process is one in which it is assumed that the process takes place without an increase or decrease in the entropy of the system.

ISENTHALPIC: Is a process that proceeds without any change in enthalpy.

OPERATING POINT: Defined points along the thermodynamic cycle, to determine which process comes next and which one has been performed. This notation, provides the author a useful tool to explain the process and name the magnitudes.

EES: Engineering Equations Software. Thermodynamic software used to perform the calculations needed.

S&D: It stands for “Saunier Duval”, and it is used to indicate when an equipment has been provided by them.

VOLUMETRIC EFFICIENCY: Refers to the efficiency with which the engine can move the charge into and out.

QUALITY: It refers to the proportion of refrigerant that is in vapor state over the total refrigerant mass.

CW: It stands to “Calendar Week”.



CHAPTER 3: FIRST STAGE

1 ALTERNATIVES

1.1 OPTION 1: DESIGN ADAPTATION




Figure 3--Mollier diagram of the first cycle designed

The compressor would determine the pressure difference of the cycle. The expansion valve will fix the pressure at the first operating point (P1), so the pressure of the second operating point would be determined by the compression achieved by the compressor.



FINAL PROJECT

Date: 19.06.2014

Page: 16

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

On the other hand, with the condenser it is determined the heat exchange, therefore it would be possible to determine the enthalpy difference experimented by the refrigerant.

As conclusion, the cycle would be perfectly determined.

1.1.1 OPERATING POINT TWO CALCULATIONS

At this point, the temperature and pressure are measured (P_{2_EXP} and T_{2_EXP}). Depending on the compressor type it would be possible to obtain a greater compression, and therefore a bigger pressure difference.

Temperature Sensor	T_{2_EXP}
Pressure sensor	P_{2_EXP}
Flux sensor	m_{REF}

For determining the zone in which the refrigerant works (biphasic or overheated steam), the temperature measured (T_{2_EXP}) can be compared with the saturation temperature at the pressure P_{2_EXP} .

With the values of the temperature and pressure, and the knowledge of the zone in which the refrigerant works, the enthalpy of the operating point 2 can be calculated. There are several way to obtain its value (thermodynamic software programs...) one of them would be:

$$h_{2_EXP} = u_2 + P_{2_EXP} \cdot Y_2$$

The specific volume must be calculated in order to use the previous formula. When the refrigerant is in the overheated steam zone, it is obtained using the thermodynamic and the values of pressure and temperature measured.

On the other hand, if the refrigerant is in the biphasic zone to calculate the specific volume the use of a thermodynamic software would be needed.

To avoid its use, some assumptions can be made: The process can be considered as isentropic, so the enthalpy at the operating point two can be calculate with the help of the entropy of the operating point one. This way, the enthalpy "h2s" (enthalpy of the isentropic point two) would be obtained:

1. The operating point 2s and its enthalpy are calculated. To do so, theoretical values of point one must be used.

Knowing the entropy at the point 2s ($s_1=s_{2s}$), and the vaporization and liquefaction entropies the quality of the operating point it is calculated. Once the quality has been obtained, the enthalpy of the isentropic operating point 2 (h_{2s}) can be calculated.



FINAL PROJECT

Date: 19.06.2014

Page: 17

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

2. With the isentropic efficiency of the compressor, and the values of the enthalpies of the points one, and the isentropic point two:

$$h_2 = h_1 + \frac{h_{2s} - h_1}{\eta_{iso}}$$

After the compressor, the refrigerant goes through the first electronic expansion valve decreasing its pressure and temperature. There would be another expansion valve, so between both of them the pressure difference generated by the compressor must be equated. Modifying the pressure drop proportion in the first and second valve, the pressure desired in the operating point three can be achieved at the same time that the operating point one and two are properly defined.

In the condenser, the enthalpies difference required to force the operating point four to have the same enthalpy as in the operating point one, it is achieved.

Finally, the second expansion valve recovers the pressure at the starting operating point.

One important aspect of this point is the possible biphasic nature of the refrigerant at the exit of the compressor. This aspect would be specially conditioned by the quality at the entering of the compressor.

The main problem of this biphasic nature is the impossibility (or the unviability) to measure the refrigerant flux. The value of the refrigerant flux, as it would be explained later, will be necessary to obtain the heat exchange between the refrigerant and the water, and therefore the water flux.

All the calculation can be directly computed using the "Engineering Equations Solver" (EES), a thermodynamic program. It is possible to create personalized thermodynamic tables, to avoid intermediate calculations.

1.1.2 OPERATING POINT ONE CALCULATIONS

As inputs, the quality and pressures of the compressor would be introduced.

Temperature Sensor	T_{1EXP}
Pressure sensor	P_{1EXP}

With the stored data of the pressure and temperature of the first operating point, the thermodynamic tables can be employed to obtain the fusion and vaporization enthalpies to calculate the enthalpy at the operating point, as it is shown below:



FINAL PROJECT

Date: 19.06.2014

Page: 18

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

$$h_1 = h_{f1} + x_1 \cdot (h_{g1} - h_{f1})$$

This enthalpy value, is the one to be achieved once that the cycle has been stabilized and works according to the parameters fixed.

This value of enthalpy is also the one that, theoretically should be at the operating point four, since the expansion is considered an isenthalpic process.

(*) EES CAN BE USED TO CALCULATE THE ENTHALPY DIRECTLY

1.1.3 CONDENSER

After going through the compressor, the refrigerant is ready to come across the condenser.

The operating point three is determined, since it is supposed to have the same pressure value as the one in the second operating point of the cycle ($P_2 = P_{3_{TH}}$), and the same enthalpy of the first operating point ($h_1 = h_{3_{TH}}$). The pressure is not going to be the exact same value, due to the drop pressure of the condenser.




Figure 4-Condenser behavior

The enthalpy difference that must be achieved by the cooling process of the condenser is calculated, as the enthalpies of the operating points two and three are known: $\Delta h = h_3 - h_2 \sim h_1 - h_2$

This cooling process would be determined by the input water temperature ($T_{W_{IN}}$) and by the existing water flux in the condenser. Studying the equations, it is shown that there are two possible magnitudes which control would give us the chance to modify the heat exchanged:

$$\dot{Q} = \dot{m}_{REF} \cdot (h_3 - h_2)$$
$$\dot{Q} = \dot{m}_W \cdot C_p \cdot (T_{OUT_W} - T_{IN_W})$$



FINAL PROJECT

Date: 19.06.2014

Page: 19

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

Temperature Sensor	$T_{W_{IN}}, T_{W_{OUT}}$
Flux sensor	m_w

As the thermodynamic magnitudes have an important thermal inertia, to control the heat exchanged it is better to modify the water flux instead its input temperature, because it would occasioned a faster response. For being able to change the water flux, a variable speed pump would have to be chosen.

1.1.4 OPERATING POINT THREE

It would be possible to determine whether the refrigerant works in the biphasic or in the subcooled zone.

Temperature Sensor	$T_{3_{EXP}}$
Pressure sensor	$P_{3_{EXP}}$

Employing the thermodynamic tables to determine the saturation temperature for the pressure measured at the operating point three ($P_{3_{EXP}}$), and comparing it with the corresponding temperature measured at the same point.

Whether the measured temperature is lower than the corresponding temperature for the measured pressure at the operating point three, the refrigerant would be working in the subcooled zone, and viceversa.

The ascertainment of the situation of the operating point three would be different depending on the refrigerant zone in which the refrigerant works:

- **ENTHALPY ASCERTAINMENT AT THE BIPHASIC ZONE**

With the measured values of pressure and temperature and the access to the thermodynamic tables the calculation of the enthalpy at that point is performed.

$$h_{3_{EXP}} = u_3 + P_{3_{EXP}} \cdot \gamma_3$$



FINAL PROJECT

Date: 19.06.2014

Page: 20

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

- **ENTHALPY ASCERTAINMENT AT THE SUBCOOLED ZONE**

With the same measured data, the Access to the thermodynamic tables is performed to directly obtain the value of the enthalpy at the operating point three ($h_{3_{EXP}}$).

$h_{3_{TH}} - h_{3_{EXP}} > 0$	The refrigerant has been cooled in excess.
$h_{3_{TH}} - h_{3_{EXP}} = 0$	The real value is the same as the theoretical. The operating point has been achieved.
$h_{3_{TH}} - h_{3_{EXP}} < 0$	The refrigerant needs to be cooled.

If the refrigerant needs to be cooled, then the heat exchange needs to be increased. In order to do so, the water flux must also be raised. The opposite control action (decreased the water flux) would have to be taken, if the refrigerant has been cooled in excess.

After the condenser, the refrigerant must pass through the electronic expansion valve (considered as an isenthalpic process).

As the expansion valve generates a pressure drop without any heat losses (at least not perceptible ones), the refrigerant will return to the first operating point state, closing the cycle.

The conditions after the expansion valve (the first operating point) must be double checked to obtain the exact same values as at the beginning of the cycle to make the cycle stable. To do so, the circuit would be thermally isolated, to minimize the heat losses at the compressor and at the expansion valve.

1.1.5 ADVANTAGES AND DISADVANTAGES

The cycle has been simplified by removing an electronic expansion valve, and modifying the processes order. However, the cycle still needs the acquisition and analysis of multiple analogue signals.

The main inconvenient of this cycle, is the possibility of the refrigerant to be working in the biphasic zone at the exit of the compressor, which would complicate the measurement of the compressor flux.

This phenomena, theoretically occurs when the input quality of the refrigerant is low. Besides, the heat exchange between the compressor walls and the refrigerant has not been taken into consideration, so it is possible that the refrigerant at the exit of the compressor would be overheated steam, even if the calculations shows the opposite.



FINAL PROJECT

Date: 19.06.2014

Page: 21

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

1.2 OPTION 2: MODIFICATIONS

Given that the main inconvenient for the previous design is the possible (according to the theoretical results in ANNEX I) biphasic nature of the refrigerant at the exit of the compressor, it is intended to be solved with a small modification of the cycle design.

With the effect of a heating resistance, it is intended to provide the heat needed for the fully evaporation of the refrigerant.




Figure 5- Option two, modified cycle



FINAL PROJECT

Date: **19.06.2014**

Page: **22**

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

The cycle would be kept in the exact same way, except for this modification. The introduction of other component of the thermodynamic circuit will generate a new operating point that would be called "operating point 2r" (the "r" stands for the heating resistance).

For a better understanding, the added process will be explained in detail.

1.2.1 HEATING PROCESS 2-2r

At the operating point two the thermodynamic magnitudes will not be measured, they would be checked after the heating resistance. The heating resistance would provide to the refrigerant the heat required to evaporate (its temperature would be three degree increased above the saturation temperature at pressure P2r).

Temperature Sensor	T2r _{EXP}
Pressure sensor	P2r _{EXP}

If after the temperature ascertainment, the refrigerant is conclude to be at the biphasic zone then the heating resistance must be turned on to guarantee its fully evaporation.

The heat provide by the heating resistance would be calculated to make the refrigerant achieve a temperature higher (e.g. three degrees more) than the saturation temperature at the pressure measured P2r. This way, the refrigerant would be at the overheated zone, and its flux will be measured.

The enthalpy of the operating point 2r can be calculated with the data measures (P2r, T2r) and the assistance of the thermodynamic tables.

$$h_{2r} = u_2 + P_{2r} \cdot Y_2$$

Depending on the working zone in which the refrigerant is, the value of the enthalpy could be obtain directly from the thermodynamic tables.



FINAL PROJECT

Date: 19.06.2014

Page: 23

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

1.2.2 ADVANTAGES AND DISADVANTAGES

With this design, the main problem in the previous design is solved, while its advantages are maintain. The cycle control it's simplified at the same time that the problem with the measurement of the refrigerant flux is solved.

2 WATER REFRIGERATION

A chiller machine would be disposed to keep constant the input water temperature of the condenser. The input water temperature (T_{wIN}) would be fixed and the signal controlling the water pump speed would be varied to generate a minor or greater water flux, so the heat exchange in the condenser could be controlled.




Figure 6-Water circuit

The pump speed control, and its flux, must be implemented in an automatically way employing a compatible software such as STEP7 or LABVIEW.

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 24
PROJECT: “Compressors test life bench under wet compression conditions”		PROJECT REPORT: 1

3 SELECTION PROCESS

Among the two options considered, the second one is chosen due to its relative simplicity and the resolution of the refrigerant flux measurement.

Nevertheless, the supplier's management was developed for both, the first and second option. Besides, the calculation for option 2 were also made (for refrigerants R134A, R407C, R410A and R22), to determine its viability for the refrigerant measurement. The change in the refrigerants considered also create a new supplier's management stage, since the components specifications were altered.

The quality of the refrigerant at the entrance of the compressor, even though in the calculations it is considered a range between $x1 \in (0'5-1)$, the actual range in which the quality might vary would be reduced and with higher values ($x1=0'8, 0'9\dots$).

It is proved that for quality values higher than 0'96, the refrigerant at the exit of the compressor would be in a complete gaseous state. In case of working with minor quality values, the heating resistance would be activate to avoid the possible biphasic nature of the refrigerant.

The heating resistance control would done fixing the temperature to be achieve, and controlling it with a pulse PID.

4 COMPONENTS FOR THE THERMODYNAMIC CIRCUIT

The thermodynamic components needed for the cycle defined in option three are the followings:

4.1 COMPRESSOR

The objective of the test bench was to check different compressors to determine its use at adverse conditions. Therefore, this component would not be able to be fixed because the interest resides in the possibility of changing the compressors tested.



FINAL PROJECT

Date: 19.06.2014

Page: 25

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

4.2 CONDENSER

It must be able to absorb the heat necessary to recover the enthalpy state that the refrigerant had at the entering of the compressor.

The condensing medium employed would be the water, this is due to the ease of the water flux and temperature control.

Studying the calculations of the ANNEX I, the maximum enthalpy differences requested and therefore, the maximum heats exchanged are:

Table 1-Condenser limit

	R134a		R410a		R407c		R22	
	Q min [kW]	Q máx. [kW]	Q min [kW]	Q máx. [kW]	Q min [kW]	Q máx. [kW]	Q min [kW]	Q máx. [kW]
3000 rpm and 7 cc/rev	0.18	1.29	0.41	1.15	0.27	1.08	0.27	1.04
5000 rpm and 11,4 cc/rev	0.48	2.58	1.13	3.12	0.73	2.93	0.73	2.81

Applying an oversizing of 20%:

$$\dot{Q} = 3.516 \text{ kW} \sim 3.6 \text{ kW}$$

Besides, the condenser must be able to stand a pressure of 50-60 bars, and the possible corrosion due to the refrigerants.

4.3 ELECTRONIC EXPANSION VALVE (EEV)

The electronic expansion valve must be capable of reducing a pressure of 50 bars, to a pressure of 3 bars (the refrigerant R410A has a pressure of 40 bars when its temperature achieve the 70 °C).



FINAL PROJECT

Date: 19.06.2014

Page: 26

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

This is the most extreme case, so if this pressure requirement is fulfilled the rest of pressure specifications would be as well fulfilled.

4.4 PLOMBING

The adaptors used for the equipment annexing and the rest of materials must be taken into consideration when the budget is calculated.

4.5 VARIABLE SPEED PUMP

The heat exchange dissipated in the condenser, can be modified varying the water flux within it, or the water temperature.

To be able to vary the water flux through the condenser, the use of a variable speed pump is required.

The water flux ranges for the project, depending on the refrigerant employed, is shown below:

Table 2-Water flux limits

	R134a		R410a		R407c		R22	
	\dot{m}_W min [l/min]	\dot{m}_W max [l/min]	\dot{m}_W min [l/min]	\dot{m}_W max [l/min]	\dot{m}_W min [l/min]	\dot{m}_W max [l/min]	\dot{m}_W min [l/min]	\dot{m}_W max [l/min]
3000 rpm and 7 cc/rev	0.26	1.85	0.6	1.65	0.39	1.55	0.38	1.49
5000 rpm and 11,4 cc/rev	0.68	3.71	1.62	4.47	1.05	4.21	1.04	4.03

Applying an oversizing of 10%:

$$\dot{m}_w = 4.95 \frac{l}{min} \sim 5 l/min$$



FINAL PROJECT

Date: 19.06.2014

Page: 27

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

4.6 CHILLER

A "water cooler machine" is needed, in order to keep the input water temperature of the condenser at a constant value. This way, to modify the heat exchanged in the condenser the program would have to act on the value of the water flux.

4.7 HEATING RESISTANCE

As it was explained above, when the input quality of the refrigerant is below 0'9, the calculations leads us to biphasic nature of the refrigerant at the exit of the compressor.

Therefore, the heating resistance is needed to evaporate the refrigerant at the output of the condenser and be able to measure its flux.

Depending on the refrigerant employed, and the input quality of the refrigerant at the entering of the compressor, a different amount of heat would be demanded. A representative summary of the calculations made are shown in the following table.

Table 3-Heating resistance limits

	R134a		R410a		R407c		R22	
	\dot{Q}_{min} [kW]	\dot{Q}_{max} [kW]	\dot{Q}_{min} [kW]	\dot{Q}_{max} [kW]	\dot{Q}_{min} [kW]	\dot{Q}_{max} [kW]	\dot{Q}_{min} [kW]	\dot{Q}_{max} [kW]
3000 rpm and 7 cc/rev	0.0	0.50	0.0	0.53	0.0	0.44	0.0	0.42
5000 rpm and 11,4 cc/rev	0.0	1.34	0.0	1.43	0.0	1.19	0.0	1.15

As expected, the minimum heat to be provided by the heating resistance is zero, that would mean that the quality of the input refrigerant has a "high" value (E.g.: greater than 0,96 for the refrigerant R134A).

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 28
PROJECT: "Compressors test life bench under wet compression conditions"		PROJECT REPORT: 1

5 SELECTION OF THE THERMODYNAMIC EQUIPMENT AND THE INSTRUMENTATION

The data sheets of the selected equipment are in ANNEX IX

5.1 EQUIPMENT

5.1.1 CONDENSER

A 5'5 kW condenser has been selected. It would be provided by PEKOMARK for 166.14 €.

(S&D) HOWEVER, SAUNIER & DUVAL HAS ACCEDED TO PROVIDED US A CONDENSER OF 3,5 kW, A CHILLER AND THREE DIFFERENT ELECTRONIC EXPANSION VALVES AMONG OTHERS.

5.1.2 EEV

An E2V05BSF00 Carel expansion valve was selected for its 50 bar of maximum pressure and its 35 bar of maximum pressure difference to be achieved. It would also be provided by pekomark and it would cost 515.67 € (drivers and electronic included).

(S&D)

5.1.3 CHILLER

Although other suppliers were considered, as Saunier Duval offered to provided us a chiller machine save us 5390 € (the price of the chiller 15 kW selected).

(S&D)

5.1.4 VARIABLE SPEED WATER PUMP

The pump selected had to have a control over the water flux provided, such as: EGO ROSCADA ER 15-130/40.

This pump, has an input signal 0-10 V to control the water flux.

The suppliers is EBARA, and it has a cost of 322.90 €.

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 29
PROJECT: “Compressors test life bench under wet compression conditions”		PROJECT REPORT: 1

5.1.5 HEATING RESISTANCE

Even if different options were considered, at the end CSH5082000/240 of the OMEGA supplier was selected. It can provide the system 2kW, so it fulfilled the specifications.

5.2 INSTRUMENTATION

5.2.1 PREASSURE & TEMPERATURE SENSOR

Both sensors have been ordered to the same supplier, JUMO. For the temperature sensor, a thermocouple K has been chosen specially for its oxidation properties (it also has a wide range of temperatures to be measured).

The pressure sensor has a limit of 60 bars, enough to assure its correct functioning.

Each temperature sensor (plus its support) has a cost of 106€, and for the pressure transmitter (output of 4-20 mA, two wire) 432 €.

5.2.2 WATER FLUX SENSOR

For the water flux and its corresponding electronic and adaptors, the SMR12GGXFRKG/US-100 for 304 € (water flux sensor) and the ADOAH040MSS0005H04 4.2€ have been offered, and selected, by IFM components. It measures 0.1-25 l/min and has an output of 4-20 mA (4 wire).

5.2.3 CORIOLIS REFRIGERANT FLUX SENSOR

EMERSON has offered F025S1115CCANSZZZZ sensor (2774.70 €) and 1700I13ABMSZZZ (691.65 €).

This sensor and its electronic have been selected because of their accuracy (<1%) at the refrigerant flux range: 4 g/s-160 g/s.



FINAL PROJECT

Date: 19.06.2014

Page: 30

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

6 SENSORS, INPUTS Y OUTPUTS

6.1 SENSORS

Once that the thermodynamic cycle has been determined, the amount of sensors to be employed must be decided.

The following table represents the summary of possible options, when the selecting decision was to be made.

Table 4-Distribution of sensors

OPTION 1	5 temperature sensors (in the operating points 1, 2r, 3, and at the input-output water of the condenser). 3 pressure sensors (at the three operating points of the cycle). [2] It has both flux sensors, for the water and the refrigerant, [1] It has a heating resistance.
OPTION 2	5 temperature sensors (in the operating points 1, 2r, 3, and at the input-output water of the condenser). 3 pressure sensors (at the three operating points of the cycle). [1] It has only the water flux sensor [1] It has a heating resistance.
OPTION 3	4 temperature sensors (in the operating points 1, 2r and at the input-output water of the condenser). 2 pressure sensors (at the first and second operating points of the cycle). For the third operation point, a manometer would be set. [1] It has only the water flux sensor
OPTION 4	4 temperature sensors (in the operating points 1, 2r and at the input-output water of the condenser). 3 pressure sensors (at the three operating points of the cycle). [2] It has both flux sensors, for the water and the refrigerant, [1] It has a heating resistance.
OPTION 5	4 temperature sensors (in the operating points 1, 2r and at the input-output water of the condenser). 3 pressure sensors (at the three operating points of the cycle). [1] It has both flux sensors, for the water and the refrigerant,

For the first station, OPTION 1 would be chosen as it is the more complete. Once, their measurements have been studied the employment of sensors could be re-evaluated.



FINAL PROJECT

Date: 19.06.2014

Page: 31

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

A priori, option two will be used for the rest of the stations, but the election of the sensors distribution would be conditioned by the data measured in station one.

6.1.1 OPTION 1

In this project, it is intend to begin with the installation of one station of the test bench, and extend its capacity up to 12 stations.

When implementing the first station, it is advisable that it was well monitored with sensors, even if it means measures that would not be strictly necessary. Once the measurements of this first station are studied, it may be determined that sensors are "redundant" or without whose contributions the system can continue to operate within the range of accuracy required. This knowledge will permit a reduction in the cost of sensors employed. The possibility of use less sensors, must be considered when the programing code is being developed.




Figure 7- OPTION1- Thermodynamic cycle and the sensors employed



FINAL PROJECT

Date: 19.06.2014

Page: 32

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

In the Figure 7 (and in the table below), it is shown the sensors employed and their location in the thermodynamic cycle.

Table 5-Option 1-Distribution of sensors

SENSORS	REFRIGERANT CIRCUIT			WATER CIRCUIT	
	POINT 1	POINT 2r	POINT 3	INLET OF THE CONDENSER	OUTLET OF THE CONDENSER
TEMPERATURE SENSOR	X	X	X	X	X
PRESSURE SENSOR	X	X	X		
FLUX SENSOR		X		X	

6.1.1.1 SIGNALS

Table 6-Option 1- Signals

Signals		1x Compressor	11x Compressors	
Analog Inputs	Temperature	Thermocouple K	5	55
	Pressure	4-20 mA	3	33
	Flux	0-5V/4-20mA 0-5V/4-20 mA	2	22
TOTAL AI			10	110
Analog Outputs	Variable speed pump	0-10 V	1	11
	EEV	0-5V/4-20mA	1	11
TOTAL AO			2	22
Digital outputs	Compressor	Relay	1	11
	Heating resistance	Relay	1	11
TOTAL DO			2	22
TOTAL SIGNALS			14	154



FINAL PROJECT

Date: 19.06.2014

Page: 33

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

6.1.2 OPTION 2

The only difference between this option and the option 1 considered above, is the use of the refrigerant coriolis sensor. It means one less analog signal to be process, and a reduction in the budget, since the coriolis sensor is very expensive.

After the study of the measurements of the station one, the value of the measured value of the refrigerant flux would be compared with the theoretical value calculated. If calculations and corrections in the formula can be made to improve the accuracy of the calculated value, the use of the coriolis sensor would no longer be needed.

As it was explained above, this option is being considered for the rest of the stations, but it would depend on the results of station one.




Figure 8-OPTION2-Thermodynamic cycle and the sensors employed



FINAL PROJECT

Date: 19.06.2014

Page: 34

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

Table 7-Option 2- Distribution of sensors

SENSORS	REFRIGERANT CIRCUIT			WATER CIRCUIT	
	POINT 1	POINT 2r	POINT 3	INLET OF THE CONDENSER	OUTLET OF THE CONDENSER
TEMPERATURE SENSOR	X	X	X	X	X
PRESSURE SENSOR	X	X	X		
FLUX SENSOR				X	

6.1.2.1 SIGNALS

Table 8-Option 2- Signals

Signals		1x Compressor	11x Compressors	
Analog Inputs	Temperature	Thermocouple K	5	55
	Pressure	4-20 mA	3	33
	Flux	0-5V/4-20mA	1	11
TOTAL AI			9	99
Analog Outputs	Variable speed pump	0-10 V	1	11
	EEV	0-5V/4-20mA	1	11
TOTAL AO			2	22
Digital outputs	Compressor	Relay	1	11
	Heating resistance	Relay	1	11
TOTAL DO			2	22
TOTAL SIGNALS			13	143



FINAL PROJECT

Date: 19.06.2014

Page: 35

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

6.2 BUDGET

6.2.1 OPTION 1

Table 9-Option 1- Budget

EQUIPMENT	QUANTITY FOR 1	POINTS	PRICE FOR 1
<i>Temperature</i>	5	Tin,Tout,T1,T2r,T3	530,00 €
<i>Pressure</i>	3	P1,P2,P3	432,00 €
<i>Water flux</i>	1	Input water	322,90 €
<i>Refrigerant flux</i>	1	Punto 2	3.286,35 €
<i>Pump</i>	1	Input water	212,70 €
<i>Condenser</i>	(S&D)	(S&D)	- €
<i>Chiller</i>	(S&D)	(S&D)	- €
<i>Electronic Expansion Valve</i>	(S&D)	(S&D)	- €
<i>Rele</i>	1	Point 2r	63,00 €
<i>Heating resistance</i>	1	Exit of the compressor	72,30 €
<i>Manual Valve</i>	3		13,80 €
SUBTOTAL			4.933,05 €
<i>Distribution Panel</i>	1		2.000,00 €
<i>PLC+HMI</i>	1		5.440,00 €
<i>Closet</i>	1		500,00 €
<i>Plumbing</i>	1		1.000,00 €
TOTAL			13.873,05 €



FINAL PROJECT

Date: 19.06.2014

Page: 36

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

6.2.2 OPTION 2

Table 10-Option 2- Budget

EQUIPMENT	QUANTITY FOR 1	POINTS	PRICE FOR 1
<i>Temperature</i>	5	T1,Tin,Tout,T2r,T3	530,00 €
<i>Pressure</i>	3	P1,P2,P3	432,00 €
<i>Water flux</i>	1	Input water	322,90 €
<i>Refrigerant flux</i>	0	Point 2	- €
<i>Pump</i>	1	Input water	212,70 €
<i>Condenser</i>	(S&D)	(S&D)	- €
<i>Chiller</i>	(S&D)	(S&D)	- €
<i>Electronic Expansion Valve</i>	(S&D)	(S&D)	- €
<i>Rele</i>	1	Point 2r	63,00 €
<i>Heating resistance</i>	1	Exit of the compressor	72,30 €
<i>Manual Valve</i>	3		13,80 €
SUBTOTAL			1.646,70 €
<i>Distribution Panel</i>	1		2.000,00 €
<i>PLC+HMI</i>	1		5.440,00 €
<i>Closet</i>	1		500,00 €
<i>Plumbing</i>	1		1.000,00 €
TOTAL			10.586,70 €

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 37
PROJECT: "Compressors test life bench under wet compression conditions"		PROJECT REPORT: 1

7 OBSTACLES AND CALCULATIONS

7.1 REFRIGERANT'S FLOW AND CORIOLIS SENSOR

To measure the refrigerant's mass flow a Coriolis sensor is used. This kind of sensor should measure the substance in an only stage. If we expect to do the same with a two-phase substance, important unpredictable variations (noise) will appear due to the gas bubbles dissolved in the liquid.

It is necessary to find out if there is a kind of coriolis sensor that helps measuring the overheated vapour. It could be placed at the output of the compressor and obtain the measurement when we get overheated vapour.

Nevertheless, as the working point is variable, it could happen that two-phase coolant's mixture appears at the output of the compressor, so we couldn't trust the sensor's measurements.

To assure the gas state of the coolant, we could overheat it at the compressor's output.

For the cases where the measurement cannot be trusted, it will be necessary calculate the coolant's flow theoretically (it can always be calculated theoretically with the purpose of supporting the experimental data).

Having the density of the coolant (of the specific volume) for a given temperature and pressure. Also, as technical compressor's specifications, we have capacity $\frac{cc}{rev}$ (it will turn into $\frac{m^3}{rev}$), of the compressor's rpm (The units will have to be turned into RPS) and its isentropic efficiency.

$$\dot{m}_{R134a} = \frac{1}{\gamma} \cdot \frac{rev}{s} \cdot \frac{m^3}{rev} \cdot \eta = kg/s$$

7.1.1 RESEARCHING GROUPS

Matching information with other researching groups from the University of Valencia, we know that the measure of the coolant at the output of the compressor, even if it is believed that it will be gas in each case (due to the overheating of the compressor's sides which will cause the coolant's evaporation), will cause problems.

In order to do a suitable measure, other kind of devices should be used, which will raise the bench testing's price.

As the coolant's flow can be calculated theoretically we will do without it (as it has already been explained at point five).

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 38
PROJECT: "Compressors test life bench under wet compression conditions"		PROJECT REPORT: 1

7.2 CALCULATIONS

The aim of the testing bench is to introduce to the compressor a two-phase coolant and check how it works under these untraditional circumstances. Theoretically, we would be able to modify the two-phase's title in a range of $x_1 = (0,5, 1)$, even if during the practice we will be working with higher values ($>0,85$).

The calculations will be done supposing a difference between water's temperature at the inlet and outlet of the condenser of 10°C .

These calculations are shown at ANNEX I.



FINAL PROJECT

Date: 19.06.2014

Page: 39

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

CHAPTER 4: FOURTH STAGE

Once the budgets are done (and matched between different suppliers) the buying orders are sent.

The control system's design follow the next structure.

1 CONTROL DESIGN

The first objective is fixing the pressures which are being used.

- The enthalpy at point 1 is calculated with the desired information of the title and pressure (adjusted so the desired pressure and the theoretical one are the same). To succeed in this the diagrams about de values of fusion and vaporization will be checked or, as it is done in the project, a thermodynamic table depending on the pressure ant the quality would be defined.

P[1] [bar]	x[1]	h[1] [kJ/kg]	rho[1] [kg/m3]
1	0,5	125,9	10,35
1	0,5183	129,8	9,985
1	0,5373	134	9,635
1	0,5569	138,2	9,297
1	0,5773	142,7	8,971
1	0,5985	147,2	8,656
1	0,6204	152	8,352
1	0,6431	156,9	8,059
1	0,6666	162	7,776
1	0,691	167,3	7,503
1	0,7163	172,8	7,24
1	0,7425	178,5	6,985
1	0,7697	184,4	6,74
1	0,7979	190,6	6,503

Figure 9-Thermodynamic table 1-Biphasic

At this operating point, the refrigerant density would also have to be calculated, in order to be able to compute the refrigerant flux theoretically.

- The pressure and temperature at point 2 (at the entering of the condenser, or after the heating resistance) are measured and the enthalpy of the point is calculated. As it was explained above, it has opted to use thermodynamic tables created from EES, so the tables are customize.



FINAL PROJECT

Date: 19.06.2014

Page: 40

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

P[3] [bar]	T_sat [° C]	Delta_T	T[3] [° C]	h[3] [kJ/kg]	rho[3] [kg/m3]
1	-26,37	5	-21,37	238,4	5,072
1	-26,37	10	-16,37	242,4	4,958
1	-26,37	15	-11,37	246,4	4,85
1	-26,37	20	-6,375	250,4	4,747
1	-26,37	25	-1,375	254,5	4,649
1	-26,37	30	3,625	258,5	4,556
1	-26,37	35	8,625	262,7	4,467
1	-26,37	40	13,63	266,8	4,382
1	-26,37	45	18,63	271	4,3
1	-26,37	50	23,63	275,2	4,222
1	-26,37	55	28,63	279,5	4,147
1	-26,37	60	33,63	283,8	4,074

Figure 10-Thermodynamic table 2- Superheated

- Once the enthalpy values of points one and two are written down, as in point 3 it is necessary to have the same enthalpy as in point 1, the heat exchange can be fixed in the condenser. The temperatures of the water inlet and outlet to the condenser are measured and with the theoretical refrigerant flux, the water's mass flux is calculated. The suitable control signal will be emitted, and therefore the bomb will provide the flow desired.
- Pressure at point 3 is measured, so it can be calculated the drop pressure in the condenser.
- It is possible to know where the refrigerant "is" (refers to its pressure-temperature condition) in each step.

The state of the measures should be checked and the needed parameters recalculated constantly. It is essential during the first seconds after starting the bench testing, as until the desired points are reached.

The Excel in which the calculation would be performed ("Station1"), would be "refresh" each five seconds. This "refreshing" time can be modified, changing the visual basic code of the "excel_interface" (it is in charge of obtaining the inputs needed from the WINCC, and to return the result of the calculations of the "Station1" file).



FINAL PROJECT


Date: 19.06.2014

Page: 41

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

1.1 CODE DIAGRAM



	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 42
PROJECT: “Compressors test life bench under wet compression conditions”		PROJECT REPORT: 1

1.2 STEP 7

The code has been added in the **ANNEX VII**, and it would also be included in a zip file along the whole project.

In the main program (OB1) the user would “called” the functions in charge of every station, and the Start all/Stop all security subroutine.

The function in charge of every station (FC10 for the first one) would managed the use of the rest of subroutines in charge of: sensor measurement, etc...

The subroutines for the first station have been defined:

1. Sensor measurement

In this subroutine a scale procedure of the input signals is set, fixing the limits of the magnitude measured and improving its resolution.

2. Configuration

It would be mainly done through the WINCC tactile panel. The selection of the refrigerant employed, the specification of the “rpm”, the efficiencies, the displacement...and other parameter would have to be set.

In an intuitive way, the stations to be tested and the sensors employed in each one, would be indicated through the tactile panel.

3. Start/Stop

The start/stop code in STEP 7, is closely related to the graphic interface. If all the stations implemented happened to be in “stop” mode, then the “ALL STOP” indicator would be activated and turned off softly.

To turn off the stations, except for the compressor, it would be done by a PID controller, so the components do not suffer.

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 43
PROJECT: “Compressors test life bench under wet compression conditions”		PROJECT REPORT: 1

The same would happen if all the stations were in the “start “mode, but in this case it would activate the “ALL START “indicator, and the next time that the OB1 is executed, the Station would be executed.

4. Sensors not employed

The theoretical values of pressure, temperature, etc... of each operating point have been calculated.

If during the configuration, one sensor was not set as “employed”, then it would not be possible to employ the signal measured and the theoretical value would be used instead.

5. PID control orders

The three PID controls of the Pump, the EEV and the heating resistance are mostly done (Must be reviewed).

- Pump: It would have to compare the water flux measured with the water flux desired¹⁾ (exported from the EES program), and determined an action in the corresponding analog output to achieve that goal.
- EEV: The ratio of the pressure P3/P1 would be given, in order to achieve that difference of pressures desired¹⁾, modifying the value of its control analog output.
- Heating resistance: It would be control through a digital output (and a relay). With the PID control, you fixed whether the digital output must be active or not, according to the temperature value measured, and the temperature¹⁾ that must be achieved.

The functions/subroutines employed for the first station program code, were parameterized²⁾ in order to allow their use, for the rest of the stations code.

- 1) All these “desired values” are already calculated but must be exported from the EES
- 2) For “parameterized”, we referred to the possibility of define a function so when it is summoned, the input/output variable’s labels, can be related with the convenient input/output directions. This will allow using the same program code, changing the input/output directions, from the ones employed for the first station to the directions for the rest of the bench’s stations.



FINAL PROJECT

Date: 19.06.2014

Page: 44

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

6. Mode

Two different modes can be selected:

- **Manual:** It is defined to check the correct functioning of the components. In the tactile panel a proportional controller has been defined to check the components without making them suffer.




Figure 11- Manual control detail

- **Automatic:** It is the mode that would currently be executed. Settings and alarms must be defined, employing the tactile panel.




Figure 12-Automatic control detail

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 45
PROJECT: “Compressors test life bench under wet compression conditions”		PROJECT REPORT: 1

1.3 WINCC

The graphic interface for the first station has been programmed. For the rest of the future stations, we would have to copy the “images” of the first one, and defined/change the variables employed.

There is a “Main Menu” with four different options:

1. Habilitation of the stations
2. Equipment of the stations abled
3. Settings of the stations
4. Station Menu

The configuration of the stations must follow the order shown.

In the station menu, you can only choose between the accesses to the different stations that have been habilitated.

1.4 VISUAL BASIC

It is explained in detail in **ANNEX VI**.

The refrigerant tables are stored in excel, and besides the operations to calculate the enthalpies... it must act like a data logger.

Some variables would be exported from the station DB, as well as others would be imported (enthalpies, saturation temperatures...).

1.5 EES

It has been used for the calculations of **ANNEX I**, and **ANNEX IV**. It was intended to use this software to obtain the enthalpies corresponding to the pressures and temperatures measured, however it cannot be run “automatically”, so it had to be excluded.

The thermodynamic tables of the excel, that were employed in the “excel_interface”, were created using this software.



FINAL PROJECT

Date: 19.06.2014

Page: 46

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

2 CONNECTION

2.1 HARDWARE

The hardware connection, between the remotes, the HMI and the PLC has been defined in the STEP 7 program. Besides, it has been added to the remotes the external modules needed.




Figure 13- Hardware



FINAL PROJECT

Date: 19.06.2014

Page: 47

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

2.2 INDUSTRIAL ETHERNET

As the CPU selected has two different type of connection (PN/DP), it must be specified.




Figure 14-Connection of the PLC, the remotes (ET200S) and the HMI tactile panel

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 48
PROJECT: "Compressors test life bench under wet compression conditions"		PROJECT REPORT: 1

Each component has its own IP adress, belonging to the same network:




Figure 15-CPU's IP and HMI's IP




Figure 16- Station 1 IP



FINAL PROJECT

Date: 19.06.2014

Page: 49

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

CHAPTER 5: CONCLUSIONS

1 OBJECTIVES ACHIEVE

The thermodynamic cycle has been defined and the purchase order has been sent, however not all the equipment has been received. This is due to the multiple changes of the circuit limitations, such as the number of refrigerants that can be employed, or even the cycle itself.

Besides, some of the components such as the coriolis refrigerant flux sensor which delivery time is 5 weeks:

Table 11- Component's delivery time

COMPANY	EQUIPMENT	PURCHASE ORDER STATUS (DATE)	DELIVERY TIME	DELIVERY DATE
JUMO	Temperature sensor	SENT CW 22	4 Weeks	CW 26 approx.
	Pressure sensor		3 / 4 Weeks	CW 26 approx.
IFM	Water flux sensor	SENT- CW 19	1 / 2 Weeks	CW 21 received
EMERSON	Refrigerant flux sensor	SENT CW 22	5 Weeks	CW 27
EBARA-SALTOKI	Pump	SENT- CW 22	2 Weeks	CW 24 approx
OMEGA	Heating resistance	SENT- CW 22	1 / 2 Weeks	CW 22 received

The task to be developed in the "Stage 3", are been developed. The bench's being assembled and the reception of the control system is about to be complete.

In general, it has been a delay in the development of the task. However, the practical's period has been extended two month, in order to be able to finish the project.



FINAL PROJECT

Date: 19.06.2014

Page: 50

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

2 LIMITATIONS

The components of the cycle can stand up to 50 bars and 90 °C, nevertheless the critical pressure of some of the refrigerant is below this limit. Besides, even if for some refrigerants, its critical pressure was above the limit, the compressors would not achieve a pressure greater than this value.

3 IMPROVEMENTS

The improvements to be included are explained in detail, along with its calculations, in [ANNEX IV](#). A resume of what can be found in this annex:




Figure 17-Improvement- cycle to be implemented

This would be the thermodynamic cycle to be implemented in the test rig bench.



FINAL PROJECT

Date: **19.06.2014**

Page: **51**

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

The reason why this cycled is preferred to the other option considered, is mainly the stability of point 2. The effect of the condenser water flux was dismissed, but it can vary the pressure of the point 2, and therefore, perturb the stability of the cycle.

This cycle is been prograded and it is supposed to be functioning in two months' time, after the code had been checked and reviewed.



FINAL PROJECT

Date: **19.06.2014**

Page: **52**

PROJECT:
"Compressors test life bench under wet compression conditions"

PROJECT REPORT:
1

E.T.S. de Ingeniería Industrial,
Informática y de Telecomunicación

Compressors test life bench under wet compression conditions



Grado en Ingeniería
en Tecnologías Industriales

ANNEX

Natalia Medina Cabello

Jose Ignacio Arocena

Pamplona, 26 de Junio del 2014





FINAL PROJECT

Date: **19.06.2014**

Page: **3**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2



FINAL PROJECT

Date: 19.06.2014

Page: 4

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

ANNEX'S INDEX

ANNEX I: CALCULATIONS

1	CODE "EES"	2
2	CALCULATIONS.....	5
2.1	REFRIGERANT R134A--- 5000 rpm 11.4 cc/rev	5
2.1.1	Summary R134 A --- 5000 rpm 11.4 cc/rev.....	10
2.2	REFRIGERANT R134 A---3000rpm, 7 cc/rev	11
2.2.1	Summary R134 A ---3000 rpm, 7 cc/rev.....	15
2.3	REFRIGERANT R410 A ---5000 rpm, 11.4 cc/rev	16
2.3.1	Summary R410 A--- 5000 rpm ,11.4 cc/rev.....	21
2.4	REFRIGERANT R 410 A --- 3000rpm, 7 cc/rev.....	22
2.4.1	Summary R410 A--- 3000 rpm, 7 cc/rev.....	27
2.5	REFRIGERANT R407 C --- 5000 rpm, 11.4 cc/rev.....	28
2.5.1	Summary R407 C ---5000 rpm, 11.4 cc/rev.....	33
2.6	REFRIGERANT R407 C ---3000 rpm , 7 cc/rev	34
2.6.1	Summary R407 C --- 3000 rpm, 7 cc/rev	39
2.7	REFRIGERANT R22 ---5000 rpm, 11.4 cc/rev	40
2.7.1	Summary R22--- 5000 rpm, 11.4 cc/rev	45
2.8	REFRIGERANT R 22 --- 3000 rpm, 7 cc/rev	46
2.8.1	Summary R 22 ---3000 rpm, 7 cc/rev	51

ANNEX II: SECOND STAGE

1	PRESSURE SENSORS	52
2	TEMPERATURE SENSORS	53
2.1	THERMORESISTANCES	53
3	WATER FLUX.....	53
4	ELECTRONIC EXAPANSION VALVE.....	54
4.1	PECOMARK.....	54



FINAL PROJECT

Date: 19.06.2014

Page: 5

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

5	VARIABLE SPEED PUMP.....	55
5.1	EBARA.....	55
5.2	PRODEL.....	55
6	CONDENSER	55
6.1	JOSE NEGREDO.....	55
6.2	PECOMARK.....	57

ANNEX III: SOFTWARE SELECTION

1	LABVIEW.....	58
1.1	PROS.....	58
1.2	CONS	58
2	SIMATIC- STEP 7	59
2.1	PROS.....	59
2.2	CONS	59
2.3	WEIGHTED METHODS	60

ANNEX IV: IMPROVEMENTS

1	IMPROVEMENT: SAUNIER DUVAL PROPOSAL	61
1.1.1	OPERATING POINT TWO CALCULATIONS.....	62
1.1.2	OPERATING POINT ONE CALCULATIONS.....	64
1.1.3	CONTROL OF THE OPERATING POINT THREE AND FOUR	64
1.1.4	CONDENSER	65
1.1.5	SECOND EXPANSION AND FINAL PROCESS	66
1.1.6	ADVANTAGES AND DISADVANTAGES	66
2	MODIFICATION.....	66
3	CALCULATIONS.....	67
3.1	"EES" CODE	67
3.2	REFRIGERANT R134 A--> 5000 rpm, 11 cc/rev.....	71
3.2.1	Summary R134 A-- 5000 rpm, 11.4 cc/rev.....	76
3.3	REFRIGERANT R 134A --> 3000rpm, 7 cc/rev.....	77
3.3.1	Summary R 134 A-- 3000 rpm, 7 cc/rev.....	82



FINAL PROJECT

Date: 19.06.2014

Page: 6

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3.4	REFRIGERANT R410 A --> 5000 rpm, 11.4 cc/rev.....	83
3.4.1	Summary R410 A--- 5000 rpm, 11.4 cc/rev.....	88
3.5	REFRIGERANT R410 A--> 3000 rpm, 7 cc/rev.....	89
3.5.1	Summary R410 A--- 3000rpm, 7cc/rev	94
3.6	REFRIGERANT R407 C -->5000 rpm, 11.4 cc/rev.....	95
3.6.1	Summary R407 C---5000 rpm, 11.4 cc/rev.....	100
3.7	REFRIGERANT R407 C --> 3000 rpm, 7cc/rev	101
3.7.1	Summary R407 C--- 3000 rpm, 7 cc/rev	106
3.8	REFRIGERANT R 22--> 5000 rpm, 11.4cc/rev	107
3.8.1	Summary R 22--- 5000 rpm, 11.4 cc/rev	112
3.9	REFRIGERANT R 22--> 3000 rpm, 7cc/rev.....	113
3.9.1	Summary R 22-->3000 rpm, 7 cc/rev	118

ANNEX V: WINCC

1.	SCADA STRUCTURE	119
2	SCREENS.....	120
2.1	HOME SCREEN.....	120
2.2	MAIN MENU.....	121
2.3	STATIONS HABILITATION	122
2.4	STATIONS EQUIPMENT	123
2.5	STATIONS SETTINGS.....	124
2.6	STATIONS MENU	125
2.7	MENU 1	126
2.8	EQUIPMENT 1	127
2.9	SETTING AUTOMATIC.....	128
2.10	SETTING MANUAL.....	130
2.11	DATA 1.....	131
2.12	COMPARATIONS 1.....	133
2.13	DIAGRAM 1	135
2.14	GRAPHICS 1	137



FINAL PROJECT

Date: 19.06.2014

Page: 7

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.15	GRAPHIC P&T	139
2.16	GRAPHIC FLUX.....	141
3	CONNECTIVITY & VARIABLES & TEXT LISTS.....	142
3.1	CONNECTIVITY	142
3.2	VARIABLES.....	144
3.3	TEXT LISTS	145

ANNEX VI: EXCEL AND VISUAL BASIC CODE

1	INTERFACE WITH WINCC	147
1.1	WORKBOOK.....	147
1.2	MODULE 1.....	152
1.3	MODULE 2.....	155
1.4	SHEET 1	161
2	DATA LOGGER	163
2.1	DATA LOGGER FUNCTION	163
3	CALCULATION FILE	164

ANNEX VII: STEP 7

1	STRUCTURE	168
2	INPUTS & OUTPUTS	186
3	OB 1.....	190
4	FC 1.....	192
5	FC 2.....	210
6	FC 3.....	211
7	FC 4.....	212
8	FC 5.....	218
9	FC 6.....	231
10	FC 7.....	236
11	FC 8.....	240
12	FC 9.....	245
13	FC 10.....	252



FINAL PROJECT

Date: 19.06.2014

Page: 8

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

14	FC 94.....	259
15	FC 95.....	262
16	FC 96.....	264
17	FC 97.....	267
18	FC 98.....	274
19	FC 99.....	279
20	DB 10.....	280
21	DB 11.....	281
22	UDT 1.....	282
23	UDT 2.....	283
24	UDT 3.....	284
25	UDT 4.....	285
26	UDT 5.....	286
27	UDT 6.....	287
28	UDT 7.....	288
29	UDT 8.....	289
30	UDT 9.....	290
31	UDT 10.....	291
32	UDT 11.....	292
33	UDT 12.....	293
34	HARDWARE & PLC- HMI CONNECTION.....	294
34.1	HARDWARE	294
34.2	PLC-HMI CONNECTION	295

ANNEX VIII: UNCERTAINTIES

1	EES CODE.....	296
2	RESULT	297

ANNEX IX: DATA SHEETS

1	PUMP	298
2	WATER FLUX.....	304



FINAL PROJECT

Date: 19.06.2014

Page: 9

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3	REFRIGERANT FLUX.....	334
4	PRESSURE SENSOR.....	335
5	TEMPERATURE SENSORS.....	343

ANNEX X: OFFERS

1	EMERSON.....	346
2	EBARA.....	349
3	JUMO.....	351
4	IFM.....	353
5	OMEGA.....	354
6	ELECTROLUMEN.....	355

ANNEX'S FIGURES

Figure 1.-Improvement, S&D cycle.....	61
Figure 2-Thermodynamic components cycle.....	66
Figure 3-WINCC structure.....	119
Figure 4-Home screen.....	120
Figure 5-Main menu.....	121
Figure 6-Stations habilitation.....	122
Figure 7-Stations equipment.....	123
Figure 8-Stations settings.....	124
Figure 9-Stations menu.....	125
Figure 10-Station 1 Menu.....	126
Figure 11-Station 1 Equipment.....	127
Figure 12-Settings station 1, automatic.....	128
Figure 13-Settings station1, automatic (No Tin sensor).....	129
Figure 14-Settings station 1, manual.....	130
Figure 15-Data station 1.....	131
Figure 16-Data station 1, alarms.....	132
Figure 17-Comparation 1.....	133
Figure 18-Comparation 1, alarms.....	134
Figure 19- Diagram station 1.....	135
Figure 20-Diagram station 1, alarms.....	136
Figure 21-Graphics station 1.....	137
Figure 22-Graphic station 1, no sensors connected.....	138



FINAL PROJECT

Date: **19.06.2014**

Page: **10**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

Figure 23-T&P graphic.....	139
Figure 24- T&P graphic, no sensors connected	140
Figure 25- Flux graphic.....	141
Figure 26-Flux graphic, no sensors connected.....	142
Figure 27-Connectivity	143
Figure 28-IP Adress. Connection between PLC and the HMI.....	144
Figure 29-WINCC Variables	145
Figure 30- Text Lists	146
Figure 31-WINCC Structure.....	147
Figure 32-Excel interface.....	162
Figure 33- Data Logger	164
Figure 34-Summary data import-export.....	165
Figure 35-R134A import-export data.....	166
Figure 36-R410A & R407C import_export data	166
Figure 37-R32 & R290 import_export data.....	167
Figure 38- Hardware connection, 12 stations.....	294
Figure 39- PLC,HMI and remotes connection	295
Figure 40- IP adress of the CPU, the HMI and the first station.....	295
Figure 41- Uncertainties.....	297

ANNEX'S TABLES

Table 1- R134 A- 5000 rpm, 11.4 cc/rev-cycle 1	5
Table 2-Summary R134A- 5000 rpm, 11.4 cc/rev- cycle 1.....	10
Table 3-R134 A -3000rpm, 7 cc/rev- cycle 1	11
Table 4-Summary R134 A- 3000rpm, 7 cc/rev- cycle 1.....	15
Table 5-R410 A- 5000 rpm, 11.4 cc/rev- cycle 1	16
Table 6-Summary R410 A- 5000 rpm, 11.4 cc/rev- cycle 1.....	21
Table 7- R410 A- 3000 rpm, 7 cc/rev- cycle 1	22
Table 8-Summary R410 A- 3000 rpm, 7 cc/rev- cycle 1.....	27
Table 9- R407 C- 5000rpm, 11.4 cc/rev- cycle 1	28
Table 10- Summary R407 C- 5000 rpm, 11.4 cc/rev- cycle 1	33
Table 11- Summary R407 C- 3000 rpm, 7cc/rev- cycle 1	34
Table 12- Summary R407 C- 3000 rpm , 7 cc/rev- cycle 1	39
Table 13- R22- 5000 rpm, 11.4 cc/rev-cycle 1	40



FINAL PROJECT

Date: **19.06.2014**

Page: **11**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

Table 14-Summary R22- 5000 rpm, 11.4 cc/rev-cycle 1	45
Table 15- R22- 3000 rpm, 7 cc/rev-cycle 1	46
Table 16-Summary R22- 3000 rpm, 7cc/rev- cycle 1	51
Table 17-Pressure sensors	52
Table 18-Thermoresistances.....	53
Table 19- Water flux.....	53
Table 20-Electronic expansion valve.....	54
Table 21- Pekomark	54
Table 22-Pekomark-condenser	57
Table 23-Software selection procedure.....	60
Table 24-R134 A- 5000rpm, 11.4 cc/rev- improvement	71
Table 25-Summary R134 A-5000rpm, 11.4 cc/rev- improvement.....	76
Table 26-R134 A- 3000rpm, 7 cc/rev- improvement	77
Table 27- Summary R134A- 3000rpm, 7 cc/rev - improvement.....	82
Table 28-R410 A-5000 rpm, 11.4 cc/rev- improvement	83
Table 29-Summary R410 -5000rpm, 11.4 cc/rev- improvement.....	88
Table 30-R410 A- 3000 rpm, 7 cc/rev- improvement	89
Table 31-Summary R410 A- 3000 rpm, 7 cc/rev- improvement.....	94
Table 32-R407C-5000 rpm, 11.4 cc/rev- improvement	95
Table 33-Summary R407C-5000 rpm, 11.4 cc/rev- improvement.....	100
Table 34-R407C- 3000 rpm, 7cc/rev- improvement	101
Table 35-Summary R407C-3000rpm, 7cc/rev- improvement.....	106
Table 36- R22- 5000rpm, 11.4 cc/rev- improvement	107
Table 37-Summary R22- 5000rpm, 11.4 cc/rev- improvement.....	112
Table 38-R22- 3000 rpm, 7 cc/rev- improvement	113
Table 39- Summary R22- 3000rpm, 7 cc/rev- improvement.....	118



FINAL PROJECT

Date: **19.06.2014**

Page: 1

PROJECT:
"Compressors test live bench under wet compression conditions"

PLANES:
3



FINAL PROJECT

Date: 19.06.2014

Page: 2

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

ANNEX I: CALCULATIONS

1 CODE "EES"

"Functions"

"Enthalpy 2"

```
Function f_h2 (rend_iso; h1; h2s)
h2=h1+((h2s-h1)/rend_iso)
f_h2=h2
end
```

"Refrigerant flux"

```
function f_m_ref(rho_ref ; rend_vol ; rps ; displ)
m_ref=(rho_ref*displ*rps*rend_vol)/(1000000)
f_m_ref=m_ref
end
```

"Water flux"

```
function f_m_w(Q; Cp ;delta_T)
m_w=(Q/( Cp *delta_T))
f_m_w=m_w
end
```

"Compressor data"

```
displ=7 "cc" " Displacement of the compressor"
rpm=3000 " Revolutions per minute of the compressor"
rps=rpm/60 " Rev. per second"
rend_vol=0,9 " Assumption of constant volumetric efficiency"
rend_iso=0,5 " Assumption of constant isentropic efficiency"
```

"Water circuit data"

```
Cp=Cp(Water;T=Tout;P=P_atm) "kJ/kg-K" " Cp of the water at a given temperature"
Tin=15 "°C" " Input temperature of the water at the entering of the condenser"
Tout=25 "°C" " Outout temperature of the water, at the exit of the condenser, after the heat exchange had taken place"

delta_T=(Tout-Tin) "K"
```



FINAL PROJECT

Date: 19.06.2014

Page: 3

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

$P_{atm}=101,3$ "kPa"

"REFRIGERANT"

$R=R134a$

"INPUTS"
{ $T[1]=5$ "°C"

" Temperature at the charging point of the compressor"

$x_1=0,8$

" Quality of the refrigerant at the entering of the compressor"

$T[2]= 70$ "°C"

" Temperature at the discharge point of the compressor"

$P1_{sat}=\text{pressure}(R;T=T[1];x=1)$
 $P2_{sat}=\text{pressure}(R;T=T[2];x=1)$

*****POINT 1*****

$h_1=\text{ENTHALPY}(R;P=P1_{sat};x=x_1)$
 $s_1=\text{ENTROPY}(R;P=P1_{sat};x=x_1)$

*****POINT 2 ISENTROPIC*****

$s_2s=s_1$
 $h_2s=\text{enthalpy}(R;P=P2_{sat};s=s_2s)$

*****POINT 2***** DISCHARGE OF THE COMPRESSOR"

$h_2=f_h_2(\text{rend_iso};h_1;h_2s)$
 $T2_real=\text{temperature}(R;h=h_2;P=P2_{sat})$

*****POINT 3***** AFTER THE HEATING RESISTANCE "

$T[3]=T[2]+3$

"We set the temperature 3 degrees over the saturation temperature, to assure the gaseous nature of the refrigerant"

$h_3=\text{enthalpy}(R;P=P2_{sat};T=T[3])$

*****POINT 4*****

$h_4=h_3$
 $T[4]=\text{temperature}(R;P=P2_{sat};h=h_4)$



FINAL PROJECT

Date: 19.06.2014

Page: 4

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

*****HEAT EXCHANGE*****

delta_enthalpy=h3-h4

"Difference of enthalpies that must be obtained with the condenser, in order to return to the enthalpic state in POINT 1"

rho_ref=density(R\$, h=h1; P=P1sat)

"Density at the entering of the compressor, to calculate the flux"

rho_ref_after_resistance=density(R\$, h=h3; P=P2sat)

"Density of the refrigerant gas, after the heating resistance, to dimensionate the refrigerant flux sensor"

m_ref=f_m_ref(rho_ref ; rend_vol ; rps ; displ)

"Call the function 'refrigerant flux' "

Q=m_ref * delta_enthalpy "kW"

"Heat exchange in the condenser"

m_w=f_m_w(Q; Cp ;delta_T)

"Water flux needed to exchange the calculated heat"

rho_water=Density(Water;T=Tin;P=P_atm) "kg/m3"

"Density of the water at a given temperature"

flow_w_lit_min=m_w/rho_water*60000

"Water flux in liters per minute"

{flow_w_lit_h=flow_w_lit_min*60

"Water flux in liters per hour"}
*****HEATING RESISTANCE *****

delta_h_res=h3-h2

"Difference of enthalpies that must be obtained with the heating resistance"

Qres=delta_h_res*m_ref

" Heat flux that must be exchange within the resistance and the refrigerant flux, to fully evaporate the refrigerant"

This is the program code of the EES software that was used in the solving process. By employing a parametric table, it can return the values of the enthalpies, the heat exchange, etc... according to different values of T1, T2 and X1.

Below, the resulting calculations are shown. In some cases, the software was not able to calculate the parameters, due to an overflow issue.



FINAL PROJECT

Date: 19.06.2014

Page: 5

PROJECT:
"Compressors test live bench under wet compression conditions"

PLANES:
3

2 CALCULATIONS

2.1 REFRIGERANT R134A--- 5000 rpm 11.4 cc/rev

Table 12- R134 A- 5000 rpm, 11.4 cc/rev-cycle 1

T1	T2	X1	mref	flow_l_min	P1	P2	Q	Qres	desnity after resistance	h1	h2	h3	h4
5,00	30,00	0,75	0,02	1,82	349,90	770,64	1,26817	0,802393	36,85	204,66	228,59	269,83	204,66
8,33	34,44	0,75	0,02	2,00	392,28	873,87	1,39400	0,866412	41,91	207,69	232,05	272,04	207,69
11,67	38,89	0,76	0,02	2,19	438,48	987,17	1,52686	0,931968	47,55	210,71	235,43	274,15	210,71
15,00	43,33	0,76	0,03	2,39	488,70	1111,16	1,66637	0,998443	53,85	213,69	238,73	276,16	213,69
18,33	47,78	0,76	0,03	2,60	543,17	1246,48	1,81192	1,065007	60,88	216,63	241,95	278,06	216,63
21,67	52,22	0,76	0,03	2,82	602,12	1393,83	1,96260	1,130562	68,75	219,55	245,10	279,82	219,55
25,00	56,67	0,77	0,04	3,04	665,78	1553,90	2,11716	1,193642	77,57	222,43	248,17	281,43	222,43
28,33	61,11	0,77	0,04	3,26	734,40	1727,45	2,27380	1,252289	87,50	225,26	251,15	282,87	225,26
31,67	65,56	0,77	0,04	3,49	808,21	1915,28	2,43006	1,303872	98,71	228,06	254,04	284,11	228,06
35,00	70,00	0,77	0,05	3,71	887,47	2118,24	2,58250	1,344821	111,44	230,81	256,84	285,12	230,81
5,00	30,00	0,78	0,02	1,63	349,90	770,64	1,13496	0,667440	36,85	209,57	234,40	269,83	209,57
8,33	34,44	0,78	0,02	1,79	392,28	873,87	1,24788	0,718214	41,91	212,55	237,80	272,04	212,55
11,67	38,89	0,78	0,02	1,96	438,48	987,17	1,36709	0,769730	47,55	215,49	241,12	274,15	215,49
15,00	43,33	0,78	0,03	2,14	488,70	1111,16	1,49221	0,821372	53,85	218,40	244,37	276,16	218,40



FINAL PROJECT

Date: 19.06.2014

Page: 6

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

18,33	47,78	0,79	0,03	2,33	543,17	1246,48	1,62266	0,872329	60,88	221,27	247,53	278,06	221,27
21,67	52,22	0,79	0,03	2,52	602,12	1393,83	1,75756	0,921522	68,75	224,11	250,61	279,82	224,11
25,00	56,67	0,79	0,03	2,72	665,78	1553,90	1,89570	0,967527	77,57	226,92	253,61	281,43	226,92
28,33	61,11	0,79	0,04	2,92	734,40	1727,45	2,03534	1,008442	87,50	229,68	256,52	282,87	229,68
31,67	65,56	0,80	0,04	3,12	808,21	1915,28	2,17412	1,041715	98,71	232,39	259,33	284,11	232,39
35,00	70,00	0,80	0,05	3,31	887,47	2118,24	2,30871	1,063888	111,44	235,06	262,05	285,12	235,06
5,00	30,00	0,80	0,02	1,45	349,90	770,64	1,01001	0,540859	36,85	214,49	240,20	269,83	214,49
8,33	34,44	0,80	0,02	1,59	392,28	873,87	1,11077	0,579161	41,91	217,40	243,55	272,04	217,40
11,67	38,89	0,81	0,02	1,75	438,48	987,17	1,21712	0,617448	47,55	220,27	246,82	274,15	220,27
15,00	43,33	0,81	0,03	1,91	488,70	1111,16	1,32868	0,655108	53,85	223,11	250,00	276,16	223,11
18,33	47,78	0,81	0,03	2,07	543,17	1246,48	1,44488	0,691339	60,88	225,91	253,11	278,06	225,91
21,67	52,22	0,81	0,03	2,25	602,12	1393,83	1,56488	0,725085	68,75	228,68	256,12	279,82	228,68
25,00	56,67	0,82	0,03	2,42	665,78	1553,90	1,68749	0,754955	77,57	231,40	259,05	281,43	231,40
28,33	61,11	0,82	0,04	2,60	734,40	1727,45	1,81107	0,779099	87,50	234,09	261,89	282,87	234,09
31,67	65,56	0,82	0,04	2,78	808,21	1915,28	1,93329	0,795039	98,71	236,72	264,62	284,11	236,72
35,00	70,00	0,82	0,04	2,94	887,47	2118,24	2,05096	0,799417	111,44	239,30	267,26	285,12	239,30
5,00	30,00	0,83	0,02	1,28	349,90	770,64	0,89257	0,421895	36,85	219,41	246,00	269,83	219,41
8,33	34,44	0,83	0,02	1,41	392,28	873,87	0,98187	0,448433	41,91	222,25	249,30	272,04	222,25
11,67	38,89	0,83	0,02	1,54	438,48	987,17	1,07608	0,474235	47,55	225,05	252,51	274,15	225,05
15,00	43,33	0,83	0,02	1,69	488,70	1111,16	1,17483	0,498690	53,85	227,82	255,64	276,16	227,82
18,33	47,78	0,84	0,03	1,83	543,17	1246,48	1,27757	0,521005	60,88	230,55	258,68	278,06	230,55
21,67	52,22	0,84	0,03	1,99	602,12	1393,83	1,38347	0,540144	68,75	233,25	261,64	279,82	233,25
25,00	56,67	0,84	0,03	2,14	665,78	1553,90	1,49140	0,554745	77,57	235,89	264,49	281,43	235,89



FINAL PROJECT

Date: 19.06.2014

Page: 7

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

28,33	61,11	0,84	0,04	2,30	734,40	1727,45	1,59975	0,563005	87,50	238,50	267,26	282,87	238,50
31,67	65,56	0,85	0,04	2,45	808,21	1915,28	1,70627	0,562512	98,71	241,05	269,92	284,11	241,05
35,00	70,00	0,85	0,04	2,60	887,47	2118,24	1,80789	0,550003	111,44	243,55	272,47	285,12	243,55
5,00	30,00	0,85	0,02	1,12	349,90	770,64	0,78200	0,309879	36,85	224,33	251,80	269,83	224,33
8,33	34,44	0,85	0,02	1,24	392,28	873,87	0,86047	0,325304	41,91	227,10	255,05	272,04	227,10
11,67	38,89	0,86	0,02	1,35	438,48	987,17	0,94320	0,339303	47,55	229,83	258,21	274,15	229,83
15,00	43,33	0,86	0,02	1,48	488,70	1111,16	1,02984	0,351269	53,85	232,53	261,28	276,16	232,53
18,33	47,78	0,86	0,03	1,61	543,17	1246,48	1,11983	0,360414	60,88	235,19	264,26	278,06	235,19
21,67	52,22	0,86	0,03	1,74	602,12	1393,83	1,21238	0,365719	68,75	237,81	267,15	279,82	237,81
25,00	56,67	0,87	0,03	1,88	665,78	1553,90	1,30639	0,365850	77,57	240,38	269,94	281,43	240,38
28,33	61,11	0,87	0,04	2,01	734,40	1727,45	1,40029	0,359043	87,50	242,91	272,63	282,87	242,91
31,67	65,56	0,87	0,04	2,14	808,21	1915,28	1,49192	0,342950	98,71	245,38	275,21	284,11	245,38
35,00	70,00	0,87	0,04	2,27	887,47	2118,24	1,57827	0,314395	111,44	247,80	277,68	285,12	247,80
5,00	30,00	0,88	0,02	0,97	349,90	770,64	0,67770	0,204222	36,85	229,24	257,60	269,83	229,24
8,33	34,44	0,88	0,02	1,07	392,28	873,87	0,74592	0,209129	41,91	231,95	260,80	272,04	231,95
11,67	38,89	0,88	0,02	1,17	438,48	987,17	0,81779	0,211955	47,55	234,61	263,91	274,15	234,61
15,00	43,33	0,88	0,02	1,28	488,70	1111,16	0,89295	0,212090	53,85	237,24	266,92	276,16	237,24
18,33	47,78	0,89	0,03	1,39	543,17	1246,48	0,97086	0,208753	60,88	239,83	269,84	278,06	239,83
21,67	52,22	0,89	0,03	1,51	602,12	1393,83	1,05075	0,200938	68,75	242,38	272,66	279,82	242,38
25,00	56,67	0,89	0,03	1,62	665,78	1553,90	1,13155	0,187335	77,57	244,87	275,38	281,43	244,87
28,33	61,11	0,89	0,03	1,74	734,40	1727,45	1,21172	0,166220	87,50	247,32	278,00	282,87	247,32
31,67	65,56	0,90	0,04	1,85	808,21	1915,28	1,28919	0,135299	98,71	249,71	280,50	284,11	249,71
35,00	70,00	0,90	0,04	1,95	887,47	2118,24	1,36101	0,091477	111,44	252,04	282,89	285,12	252,04



FINAL PROJECT

Date: 19.06.2014

Page: 8

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

5,00	30,00	0,90	0,02	0,83	349,90	770,64	0,57916	0,104395	36,85	234,16	263,40	269,83	234,16
8,33	34,44	0,90	0,02	0,92	392,28	873,87	0,63767	0,099336	41,91	236,80	266,55	272,04	236,80
11,67	38,89	0,91	0,02	1,00	438,48	987,17	0,69923	0,091569	47,55	239,40	269,60	274,15	239,40
15,00	43,33	0,91	0,02	1,10	488,70	1111,16	0,76350	0,080481	53,85	241,96	272,56	276,16	241,96
18,33	47,78	0,91	0,02	1,19	543,17	1246,48	0,82995	0,065297	60,88	244,47	275,42	278,06	244,47
21,67	52,22	0,91	0,03	1,29	602,12	1393,83	0,89782	0,045022	68,75	246,94	278,17	279,82	246,94
25,00	56,67	0,92	0,03	1,39	665,78	1553,90	0,96605	0,018369	77,57	249,36	280,82	281,43	249,36
28,33	61,11	0,92	0,03	1,51	734,40	1727,45	1,05	0,000000	87,19	251,73	283,37	283,37	251,73
31,67	65,56	0,92	0,04	1,66	808,21	1915,28	1,16	0,000000	97,49	254,04	285,80	285,80	254,04
35,00	70,00	0,92	0,04	1,83	887,47	2118,24	1,27	0,000000	108,92	256,29	288,11	288,11	256,29
5,00	30,00	0,93	0,02	0,70	349,90	770,64	0,48591	0,009931	36,85	239,08	269,20	269,83	239,08
8,33	34,44	0,93	0,02	0,77	392,28	873,87	0,54	0,000000	41,84	241,65	272,30	272,30	241,65
11,67	38,89	0,93	0,02	0,87	438,48	987,17	0,61	0,000000	47,22	244,18	275,30	275,30	244,18
15,00	43,33	0,93	0,02	0,98	488,70	1111,16	0,69	0,000000	53,17	246,67	278,20	278,20	246,67
18,33	47,78	0,94	0,02	1,10	543,17	1246,48	0,77	0,000000	59,76	249,11	280,99	280,99	249,11
21,67	52,22	0,94	0,03	1,23	602,12	1393,83	0,86	0,000000	67,04	251,51	283,68	283,68	251,51
25,00	56,67	0,94	0,03	1,37	665,78	1553,90	0,95	0,000000	75,11	253,85	286,27	286,27	253,85
28,33	61,11	0,94	0,03	1,51	734,40	1727,45	1,05	0,000000	84,04	256,14	288,74	288,74	256,14
31,67	65,56	0,95	0,04	1,67	808,21	1915,28	1,16	0,000000	93,92	258,37	291,09	291,09	258,37
35,00	70,00	0,95	0,04	1,84	887,47	2118,24	1,28	0,000000	104,88	260,54	293,32	293,32	260,54
5,00	30,00	0,95	0,02	0,68	349,90	770,64	0,48	0,000000	35,77	244,00	275,01	275,01	244,00
8,33	34,44	0,95	0,02	0,78	392,28	873,87	0,54	0,000000	40,46	246,50	278,05	278,05	246,50
11,67	38,89	0,96	0,02	0,88	438,48	987,17	0,61	0,000000	45,66	248,96	280,99	280,99	248,96



FINAL PROJECT

Date: **19.06.2014**

Page: **9**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

15,00	43,33	0,96	0,02	0,99	488,70	1111,16	0,69	0,000000	51,41	251,38	283,83	283,83	251,38
18,33	47,78	0,96	0,02	1,10	543,17	1246,48	0,77	0,000000	57,78	253,75	286,57	286,57	253,75
21,67	52,22	0,96	0,03	1,23	602,12	1393,83	0,86	0,000000	64,81	256,07	289,20	289,20	256,07
25,00	56,67	0,97	0,03	1,37	665,78	1553,90	0,95	0,000000	72,59	258,34	291,71	291,71	258,34
28,33	61,11	0,97	0,03	1,52	734,40	1727,45	1,06	0,000000	81,19	260,55	294,11	294,11	260,55
31,67	65,56	0,97	0,03	1,68	808,21	1915,28	1,17	0,000000	90,71	262,70	296,38	296,38	262,70
35,00	70,00	0,97	0,04	1,84	887,47	2118,24	1,28	0,000000	101,25	264,78	298,53	298,53	264,78
5,00	30,00	0,98	0,01	0,69	349,90	770,64	0,48	0,000000	34,66	248,91	280,81	280,81	248,91
8,33	34,44	0,98	0,02	0,78	392,28	873,87	0,54	0,000000	39,21	251,35	283,80	283,80	251,35
11,67	38,89	0,98	0,02	0,88	438,48	987,17	0,61	0,000000	44,25	253,74	286,69	286,69	253,74
15,00	43,33	0,98	0,02	0,99	488,70	1111,16	0,69	0,000000	49,82	256,09	289,47	289,47	256,09
18,33	47,78	0,99	0,02	1,11	543,17	1246,48	0,77	0,000000	55,97	258,39	292,15	292,15	258,39
21,67	52,22	0,99	0,03	1,24	602,12	1393,83	0,86	0,000000	62,78	260,64	294,71	294,71	260,64
25,00	56,67	0,99	0,03	1,37	665,78	1553,90	0,96	0,000000	70,29	262,83	297,17	297,17	262,83
28,33	61,11	0,99	0,03	1,52	734,40	1727,45	1,06	0,000000	78,59	264,96	299,50	299,50	264,96
31,67	65,56	1,00	0,03	1,68	808,21	1915,28	1,17	0,000000	87,77	267,03	301,72	301,72	267,03
35,00	70,00	1,00	0,04	0,86	887,47	2118,24	0,60	-0,69	111,44	269,03	303,81	285,12	269,03



FINAL PROJECT

Date: 19.06.2014

Page: 10

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.1.1 Summary R134 A --- 5000 rpm 11.4 cc/rev

Table 13-Summary R134A- 5000 rpm, 11.4 cc/rev- cycle 1

	mref [g/s]	flow (l/min)	P1 (kPa)	P2	Q (kW)	Qres (kW)	desnsity after resistance	h1	h2	h3	h4
min	14,99	0,68	349,90	770,64	0,47714	0,000000	34,66	204,66	228,59	269,83	204,66
max	47,55	3,71	887,47	2118,24	2,58250	1,344821	111,44	269,03	303,81	303,81	269,03
X1_para minimo	0,98	0,95	0,75	0,75	0,95202	0,919192	0,98	0,75	0,75	0,75	0,75
X1_para maximo	0,77	0,77	0,77	0,77	0,77273	0,772727	0,77	1,00	1,00	1,00	1,00



FINAL PROJECT

Date: 19.06.2014

Page: 11

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.2 REFRIGERANT R134 A---3000rpm, 7 cc/rev

Table 14-R134 A -3000rpm, 7 cc/rev- cycle 1

T1	T2	X1	mref	flow_l_min	P1	P2	Q	Qres	desnsity after resistence	h1	h2	h3	h4
5,00	30,00	0,75	0,01	0,67	349,90	770,64	0,46722	0,295618	36,85	204,66	228,59	269,83	204,66
8,33	34,44	0,75	0,01	0,74	392,28	873,87	0,51358	0,319204	41,91	207,69	232,05	272,04	207,69
11,67	38,89	0,76	0,01	0,81	438,48	987,17	0,56253	0,343357	47,55	210,71	235,43	274,15	210,71
15,00	43,33	0,76	0,01	0,88	488,70	1111,16	0,61393	0,367847	53,85	213,69	238,73	276,16	213,69
18,33	47,78	0,76	0,01	0,96	543,17	1246,48	0,66755	0,392371	60,88	216,63	241,95	278,06	216,63
21,67	52,22	0,76	0,01	1,04	602,12	1393,83	0,72306	0,416523	68,75	219,55	245,10	279,82	219,55
25,00	56,67	0,77	0,01	1,12	665,78	1553,90	0,78001	0,439763	77,57	222,43	248,17	281,43	222,43
28,33	61,11	0,77	0,01	1,20	734,40	1727,45	0,83772	0,461370	87,50	225,26	251,15	282,87	225,26
31,67	65,56	0,77	0,02	1,29	808,21	1915,28	0,89529	0,480374	98,71	228,06	254,04	284,11	228,06
35,00	70,00	0,77	0,02	1,37	887,47	2118,24	0,95145	0,495460	111,44	230,81	256,84	285,12	230,81
5,00	30,00	0,78	0,01	0,60	349,90	770,64	0,41814	0,245899	36,85	209,57	234,40	269,83	209,57
8,33	34,44	0,78	0,01	0,66	392,28	873,87	0,45974	0,264605	41,91	212,55	237,80	272,04	212,55
11,67	38,89	0,78	0,01	0,72	438,48	987,17	0,50366	0,283585	47,55	215,49	241,12	274,15	215,49
15,00	43,33	0,78	0,01	0,79	488,70	1111,16	0,54976	0,302611	53,85	218,40	244,37	276,16	218,40



FINAL PROJECT

Date: 19.06.2014

Page: 12

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

18,33	47,78	0,79	0,01	0,86	543,17	1246,48	0,59782	0,321384	60,88	221,27	247,53	278,06	221,27
21,67	52,22	0,79	0,01	0,93	602,12	1393,83	0,64752	0,339508	68,75	224,11	250,61	279,82	224,11
25,00	56,67	0,79	0,01	1,00	665,78	1553,90	0,69841	0,356457	77,57	226,92	253,61	281,43	226,92
28,33	61,11	0,79	0,01	1,08	734,40	1727,45	0,74986	0,371531	87,50	229,68	256,52	282,87	229,68
31,67	65,56	0,80	0,02	1,15	808,21	1915,28	0,80099	0,383790	98,71	232,39	259,33	284,11	232,39
35,00	70,00	0,80	0,02	1,22	887,47	2118,24	0,85058	0,391959	111,44	235,06	262,05	285,12	235,06
5,00	30,00	0,80	0,01	0,53	349,90	770,64	0,37211	0,199264	36,85	214,49	240,20	269,83	214,49
8,33	34,44	0,80	0,01	0,59	392,28	873,87	0,40923	0,213375	41,91	217,40	243,55	272,04	217,40
11,67	38,89	0,81	0,01	0,64	438,48	987,17	0,44841	0,227481	47,55	220,27	246,82	274,15	220,27
15,00	43,33	0,81	0,01	0,70	488,70	1111,16	0,48951	0,241356	53,85	223,11	250,00	276,16	223,11
18,33	47,78	0,81	0,01	0,76	543,17	1246,48	0,53232	0,254704	60,88	225,91	253,11	278,06	225,91
21,67	52,22	0,81	0,01	0,83	602,12	1393,83	0,57653	0,267137	68,75	228,68	256,12	279,82	228,68
25,00	56,67	0,82	0,01	0,89	665,78	1553,90	0,62171	0,278141	77,57	231,40	259,05	281,43	231,40
28,33	61,11	0,82	0,01	0,96	734,40	1727,45	0,66724	0,287037	87,50	234,09	261,89	282,87	234,09
31,67	65,56	0,82	0,02	1,02	808,21	1915,28	0,71226	0,292909	98,71	236,72	264,62	284,11	236,72
35,00	70,00	0,82	0,02	1,08	887,47	2118,24	0,75562	0,294522	111,44	239,30	267,26	285,12	239,30
5,00	30,00	0,83	0,01	0,47	349,90	770,64	0,32884	0,155435	36,85	219,41	246,00	269,83	219,41
8,33	34,44	0,83	0,01	0,52	392,28	873,87	0,36174	0,165212	41,91	222,25	249,30	272,04	222,25
11,67	38,89	0,83	0,01	0,57	438,48	987,17	0,39645	0,174718	47,55	225,05	252,51	274,15	225,05
15,00	43,33	0,83	0,01	0,62	488,70	1111,16	0,43283	0,183728	53,85	227,82	255,64	276,16	227,82
18,33	47,78	0,84	0,01	0,68	543,17	1246,48	0,47068	0,191949	60,88	230,55	258,68	278,06	230,55
21,67	52,22	0,84	0,01	0,73	602,12	1393,83	0,50970	0,199001	68,75	233,25	261,64	279,82	233,25



FINAL PROJECT

Date: 19.06.2014

Page: 13

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

25,00	56,67	0,84	0,01	0,79	665,78	1553,90	0,54946	0,204380	77,57	235,89	264,49	281,43	235,89
28,33	61,11	0,84	0,01	0,85	734,40	1727,45	0,58938	0,207423	87,50	238,50	267,26	282,87	238,50
35,00	70,00	0,90	0,02	0,72	887,47	2118,24	0,50143	0,033702	111,44	252,04	282,89	285,12	252,04
5,00	30,00	0,90	0,01	0,31	349,90	770,64	0,21338	0,038461	36,85	234,16	263,40	269,83	234,16
8,33	34,44	0,90	0,01	0,34	392,28	873,87	0,23493	0,036598	41,91	236,80	266,55	272,04	236,80
11,67	38,89	0,91	0,01	0,37	438,48	987,17	0,25761	0,033736	47,55	239,40	269,60	274,15	239,40
15,00	43,33	0,91	0,01	0,40	488,70	1111,16	0,28129	0,029651	53,85	241,96	272,56	276,16	241,96
18,33	47,78	0,91	0,01	0,44	543,17	1246,48	0,30577	0,024057	60,88	244,47	275,42	278,06	244,47
21,67	52,22	0,91	0,01	0,47	602,12	1393,83	0,33078	0,016587	68,75	246,94	278,17	279,82	246,94
25,00	56,67	0,92	0,01	0,51	665,78	1553,90	0,35591	0,006767	77,57	249,36	280,82	281,43	249,36
28,33	61,11	0,92	0,03	1,51	734,40	1727,45	1,05	0,000000	87,19	251,73	283,37	283,37	251,73
31,67	65,56	0,92	0,04	1,66	808,21	1915,28	1,16	0,000000	97,49	254,04	285,80	285,80	254,04
35,00	70,00	0,92	0,04	1,83	887,47	2118,24	1,27	0,000000	108,92	256,29	288,11	288,11	256,29
5,00	30,00	0,93	0,01	0,26	349,90	770,64	0,17902	0,003659	36,85	239,08	269,20	269,83	239,08
8,33	34,44	0,93	0,02	0,77	392,28	873,87	0,54	0,000000	41,84	241,65	272,30	272,30	241,65
11,67	38,89	0,93	0,02	0,87	438,48	987,17	0,61	0,000000	47,22	244,18	275,30	275,30	244,18
15,00	43,33	0,93	0,02	0,98	488,70	1111,16	0,69	0,000000	53,17	246,67	278,20	278,20	246,67
18,33	47,78	0,94	0,02	1,10	543,17	1246,48	0,77	0,000000	59,76	249,11	280,99	280,99	249,11
21,67	52,22	0,94	0,03	1,23	602,12	1393,83	0,86	0,000000	67,04	251,51	283,68	283,68	251,51
25,00	56,67	0,94	0,03	1,37	665,78	1553,90	0,95	0,000000	75,11	253,85	286,27	286,27	253,85
28,33	61,11	0,94	0,03	1,51	734,40	1727,45	1,05	0,000000	84,04	256,14	288,74	288,74	256,14
31,67	65,56	0,95	0,04	1,67	808,21	1915,28	1,16	0,000000	93,92	258,37	291,09	291,09	258,37
35,00	70,00	0,95	0,04	1,84	887,47	2118,24	1,28	0,000000	104,88	260,54	293,32	293,32	260,54



FINAL PROJECT

Date: 19.06.2014

Page: 14

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

5,00	30,00	0,95	0,02	0,68	349,90	770,64	0,48	0,000000	35,77	244,00	275,01	275,01	244,00
8,33	34,44	0,95	0,02	0,78	392,28	873,87	0,54	0,000000	40,46	246,50	278,05	278,05	246,50
11,67	38,89	0,96	0,02	0,88	438,48	987,17	0,61	0,000000	45,66	248,96	280,99	280,99	248,96
15,00	43,33	0,96	0,02	0,99	488,70	1111,16	0,69	0,000000	51,41	251,38	283,83	283,83	251,38
18,33	47,78	0,96	0,02	1,10	543,17	1246,48	0,77	0,000000	57,78	253,75	286,57	286,57	253,75
21,67	52,22	0,96	0,03	1,23	602,12	1393,83	0,86	0,000000	64,81	256,07	289,20	289,20	256,07
25,00	56,67	0,97	0,03	1,37	665,78	1553,90	0,95	0,000000	72,59	258,34	291,71	291,71	258,34
28,33	61,11	0,97	0,03	1,52	734,40	1727,45	1,06	0,000000	81,19	260,55	294,11	294,11	260,55
31,67	65,56	0,97	0,03	1,68	808,21	1915,28	1,17	0,000000	90,71	262,70	296,38	296,38	262,70
35,00	70,00	0,97	0,04	1,84	887,47	2118,24	1,28	0,000000	101,25	264,78	298,53	298,53	264,78
5,00	30,00	0,98	0,01	0,69	349,90	770,64	0,48	0,000000	34,66	248,91	280,81	280,81	248,91
8,33	34,44	0,98	0,02	0,78	392,28	873,87	0,54	0,000000	39,21	251,35	283,80	283,80	251,35
11,67	38,89	0,98	0,02	0,88	438,48	987,17	0,61	0,000000	44,25	253,74	286,69	286,69	253,74
15,00	43,33	0,98	0,02	0,99	488,70	1111,16	0,69	0,000000	49,82	256,09	289,47	289,47	256,09
18,33	47,78	0,99	0,02	1,11	543,17	1246,48	0,77	0,000000	55,97	258,39	292,15	292,15	258,39
21,67	52,22	0,99	0,03	1,24	602,12	1393,83	0,86	0,000000	62,78	260,64	294,71	294,71	260,64
25,00	56,67	0,99	0,03	1,37	665,78	1553,90	0,96	0,000000	70,29	262,83	297,17	297,17	262,83
28,33	61,11	0,99	0,03	1,52	734,40	1727,45	1,06	0,000000	78,59	264,96	299,50	299,50	264,96
31,67	65,56	1,00	0,03	1,68	808,21	1915,28	1,17	0,000000	87,77	267,03	301,72	301,72	267,03
35,00	70,00	1,00	0,04	1,85	887,47	2118,24	1,29	0,000000	97,92	269,03	303,81	303,81	269,03



FINAL PROJECT

Date: 19.06.2014

Page: 15

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.2.1 Summary R134 A ---3000 rpm, 7 cc/rev

Table 15-Summary R134 A- 3000rpm, 7 cc/rev- cycle 1

	mref [g/s]	flow (l/min)	P1 (kPa)	P2	Q (kW)	Qres (kW)	desnsity after resistance	h1	h2	h3	h4
min	5,82	0,26	349,90	770,64	0,17902	0,000000	34,66	204,66	228,59	269,83	204,66
max	40,07	1,85	887,47	2118,24	1,29185	0,495460	111,44	269,03	303,81	303,81	269,03
X1_para minimo	0,93	0,93	0,75	0,75	0,92677	0,919192	0,98	0,75	0,75	0,75	0,75
X1_para maximo	0,92	1,00	0,77	0,77	1,00000	0,772727	0,77	1,00	1,00	1,00	1,00



FINAL PROJECT

Date: 19.06.2014

Page: 16

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.3 REFRIGERANT R410 A ---5000 rpm, 11.4 cc/rev

Table 16-R410 A- 5000 rpm, 11.4 cc/rev- cycle 1

T1	T2	X1	mref	flow_l_min	P1	P2	Q	Qres	desnsity after resistence	h1	h2	h3	h4
5,00	30,00	0,75	0,04	3,60	933,18	1883,41	2,51	1,40	74,08	369,01	396,38	430,96	369,01
8,33	34,44	0,75	0,04	3,82	1032,35	2108,78	2,66	1,42	84,28	371,47	399,22	431,06	371,47
11,67	38,89	0,76	0,05	4,04	1139,26	2354,04	2,81	1,43	95,92	373,85	401,91	430,84	373,85
15,00	43,33	0,76	0,05	4,22	1254,29	2620,47	2,94	1,40	109,27	376,15	404,46	430,26	376,15
18,33	47,78	0,76	0,06	4,37	1377,83	2909,51	3,05	1,34	124,69	378,36	406,85	429,26	378,36
21,67	52,22	0,76	0,07	4,47	1510,31	3222,74	3,11	1,23	142,72	380,48	409,08	427,74	380,48
25,00	56,67	0,77	0,07	4,47	1652,14	3562,00	3,12	1,05	164,06	382,49	411,13	425,60	382,49
28,33	61,11	0,77	0,08	4,36	1803,77	3929,48	3,04	0,77	189,79	384,38	413,00	422,66	384,38
31,67	65,56	0,77	0,09	4,08	1965,67	4327,98	2,84	0,35	221,50	386,14	414,66	418,71	386,14
35,00	70,00	0,77	0,10	3,90	2138,33	4761,73	2,72	0,00	254,73	387,76	416,13	416,13	387,76
5,00	30,00	0,78	0,04	3,18	933,18	1883,41	2,22	1,10	74,08	374,45	402,79	430,96	374,45
8,33	34,44	0,78	0,04	3,37	1032,35	2108,78	2,35	1,11	84,28	376,79	405,53	431,06	376,79
11,67	38,89	0,78	0,05	3,55	1139,26	2354,04	2,48	1,09	95,92	379,06	408,12	430,84	379,06
15,00	43,33	0,78	0,05	3,71	1254,29	2620,47	2,58	1,04	109,27	381,24	410,55	430,26	381,24



FINAL PROJECT

Date: **19.06.2014**

Page: **17**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

18,33	47,78	0,79	0,06	3,83	1377,83	2909,51	2,67	0,95	124,69	383,33	412,83	429,26	383,33
21,67	52,22	0,79	0,06	3,89	1510,31	3222,74	2,71	0,82	142,72	385,32	414,93	427,74	385,32
25,00	56,67	0,79	0,07	3,87	1652,14	3562,00	2,69	0,61	164,06	387,20	416,85	425,60	387,20
28,33	61,11	0,79	0,08	3,73	1803,77	3929,48	2,60	0,32	189,79	388,95	418,57	422,66	388,95
31,67	65,56	0,80	0,08	3,59	1965,67	4327,98	2,50	0,00	218,59	390,57	420,07	420,07	390,57
35,00	70,00	0,80	0,09	3,92	2138,33	4761,73	2,73	0,00	241,89	392,03	421,41	421,41	392,03
5,00	30,00	0,80	0,04	2,79	933,18	1883,41	1,94	0,83	74,08	379,88	409,20	430,96	379,88
8,33	34,44	0,80	0,04	2,95	1032,35	2108,78	2,06	0,81	84,28	382,12	411,84	431,06	382,12
11,67	38,89	0,81	0,05	3,10	1139,26	2354,04	2,16	0,77	95,92	384,28	414,32	430,84	384,28
15,00	43,33	0,81	0,05	3,23	1254,29	2620,47	2,25	0,70	109,27	386,34	416,65	430,26	386,34
18,33	47,78	0,81	0,06	3,31	1377,83	2909,51	2,31	0,59	124,69	388,31	418,80	429,26	388,31
21,67	52,22	0,81	0,06	3,34	1510,31	3222,74	2,33	0,43	142,72	390,17	420,78	427,74	390,17
25,00	56,67	0,82	0,07	3,30	1652,14	3562,00	2,30	0,21	164,06	391,91	422,56	425,60	391,91
28,33	61,11	0,82	0,07	3,29	1803,77	3929,48	2,29	0,00	187,22	393,53	424,13	424,13	393,53
31,67	65,56	0,82	0,08	3,61	1965,67	4327,98	2,51	0,00	207,73	395,00	425,50	425,50	395,00
35,00	70,00	0,82	0,09	3,95	2138,33	4761,73	2,75	0,00	230,21	396,31	426,71	426,71	396,31
5,00	30,00	0,83	0,04	2,42	933,18	1883,41	1,68	0,57	74,08	385,32	415,61	430,96	385,32
8,33	34,44	0,83	0,04	2,55	1032,35	2108,78	1,78	0,53	84,28	387,45	418,15	431,06	387,45
11,67	38,89	0,83	0,05	2,67	1139,26	2354,04	1,86	0,46	95,92	389,49	420,53	430,84	389,49
15,00	43,33	0,83	0,05	2,77	1254,29	2620,47	1,93	0,37	109,27	391,44	422,74	430,26	391,44
18,33	47,78	0,84	0,05	2,83	1377,83	2909,51	1,97	0,25	124,69	393,28	424,78	429,26	393,28
21,67	52,22	0,84	0,06	2,83	1510,31	3222,74	1,97	0,07	142,72	395,01	426,62	427,74	395,01
25,00	56,67	0,84	0,07	3,01	1652,14	3562,00	2,10	0,00	160,28	396,63	428,27	428,27	396,63



FINAL PROJECT

Date: **19.06.2014**

Page: **18**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

28,33	61,11	0,84	0,07	3,31	1803,77	3929,48	2,30	0,00	178,17	398,10	429,70	429,70	398,10
31,67	65,56	0,85	0,08	3,63	1965,67	4327,98	2,53	0,00	197,87	399,43	430,95	430,95	399,43
35,00	70,00	0,85	0,09	3,98	2138,33	4761,73	2,77	0,00	219,55	400,58	432,03	432,03	400,58
5,00	30,00	0,85	0,04	2,07	933,18	1883,41	1,44	0,32	74,08	390,75	422,02	430,96	390,75
8,33	34,44	0,85	0,04	2,18	1032,35	2108,78	1,52	0,26	84,28	392,77	424,46	431,06	392,77
11,67	38,89	0,86	0,04	2,27	1139,26	2354,04	1,58	0,18	95,92	394,70	426,74	430,84	394,70
15,00	43,33	0,86	0,05	2,34	1254,29	2620,47	1,63	0,07	109,27	396,53	428,84	430,26	396,53
18,33	47,78	0,86	0,05	2,48	1377,83	2909,51	1,73	0,00	123,21	398,25	430,75	430,75	398,25
21,67	52,22	0,86	0,06	2,74	1510,31	3222,74	1,91	0,00	137,27	399,86	432,47	432,47	399,86
25,00	56,67	0,87	0,06	3,02	1652,14	3562,00	2,10	0,00	152,81	401,34	433,98	433,98	401,34
28,33	61,11	0,87	0,07	3,32	1803,77	3929,48	2,31	0,00	169,97	402,67	435,30	435,30	402,67
31,67	65,56	0,87	0,08	3,65	1965,67	4327,98	2,54	0,00	188,90	403,85	436,44	436,44	403,85
35,00	70,00	0,87	0,09	4,01	2138,33	4761,73	2,79	0,00	209,81	404,85	437,39	437,39	404,85
5,00	30,00	0,88	0,03	1,74	933,18	1883,41	1,21	0,09	74,08	396,19	428,43	430,96	396,19
8,33	34,44	0,88	0,04	1,82	1032,35	2108,78	1,27	0,01	84,28	398,10	430,77	431,06	398,10
11,67	38,89	0,88	0,04	2,02	1139,26	2354,04	1,41	0,00	94,44	399,91	432,94	432,94	399,91
15,00	43,33	0,88	0,05	2,25	1254,29	2620,47	1,56	0,00	105,47	401,63	434,93	434,93	401,63
18,33	47,78	0,89	0,05	2,49	1377,83	2909,51	1,73	0,00	117,66	403,23	436,73	436,73	403,23
21,67	52,22	0,89	0,06	2,75	1510,31	3222,74	1,92	0,00	131,14	404,71	438,32	438,32	404,71
25,00	56,67	0,89	0,06	3,03	1652,14	3562,00	2,11	0,00	146,05	406,05	439,72	439,72	406,05
28,33	61,11	0,89	0,07	3,34	1803,77	3929,48	2,33	0,00	162,51	407,25	440,94	440,94	407,25
31,67	65,56	0,90	0,08	3,68	1965,67	4327,98	2,56	0,00	180,71	408,28	441,97	441,97	408,28
35,00	70,00	0,90	0,08	4,04	2138,33	4761,73	2,82	0,00	200,89	409,12	442,79	442,79	409,12



FINAL PROJECT

Date: **19.06.2014**

Page: **19**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

5,00	30,00	0,90	0,03	1,62	933,18	1883,41	1,13	0,00	72,12	401,62	434,83	434,83	401,62
8,33	34,44	0,90	0,04	1,81	1032,35	2108,78	1,26	0,00	80,78	403,42	437,08	437,08	403,42
11,67	38,89	0,91	0,04	2,02	1139,26	2354,04	1,41	0,00	90,35	405,12	439,15	439,15	405,12
15,00	43,33	0,91	0,05	2,25	1254,29	2620,47	1,57	0,00	100,94	406,72	441,02	441,02	406,72
18,33	47,78	0,91	0,05	2,50	1377,83	2909,51	1,74	0,00	112,64	408,20	442,71	442,71	408,20
21,67	52,22	0,91	0,06	2,76	1510,31	3222,74	1,93	0,00	125,58	409,55	444,21	444,21	409,55
25,00	56,67	0,92	0,06	3,05	1652,14	3562,00	2,13	0,00	139,87	410,76	445,53	445,53	410,76
28,33	61,11	0,92	0,07	3,37	1803,77	3929,48	2,34	0,00	155,68	411,82	446,65	446,65	411,82
31,67	65,56	0,92	0,07	3,71	1965,67	4327,98	2,58	0,00	173,21	412,71	447,55	447,55	412,71
35,00	70,00	0,92											
5,00	30,00	0,93	0,03	1,62	933,18	1883,41	1,13	0,00	69,13	407,05	441,24	441,24	407,05
8,33	34,44	0,93	0,04	1,82	1032,35	2108,78	1,27	0,00	77,46	408,75	443,39	443,39	408,75
11,67	38,89	0,93	0,04	2,03	1139,26	2354,04	1,41	0,00	86,66	410,34	445,36	445,36	410,34
15,00	43,33	0,93	0,04	2,26	1254,29	2620,47	1,57	0,00	96,83	411,81	447,15	447,15	411,81
18,33	47,78	0,94	0,05	2,51	1377,83	2909,51	1,75	0,00	108,06	413,17	448,77	448,77	413,17
21,67	52,22	0,94	0,05	2,78	1510,31	3222,74	1,94	0,00	120,47	414,40	450,19	450,19	414,40
25,00	56,67	0,94	0,06	3,08	1652,14	3562,00	2,14	0,00	134,21	415,47	451,41	451,41	415,47
28,33	61,11	0,94	0,07	3,39	1803,77	3929,48	2,36	0,00	149,42	416,39	452,41	452,41	416,39
31,67	65,56	0,95	0,07	3,74	1965,67	4327,98	2,61	0,00	166,31	417,13	453,19	453,19	417,13
35,00	70,00	0,95	0,08	4,12	2138,33	4761,73	2,87	0,00	185,13	417,67	453,73	453,73	417,67
5,00	30,00	0,95	0,03	1,62	933,18	1883,41	1,13	0,00	66,41	412,49	447,68	447,68	412,49
8,33	34,44	0,95	0,04	1,82	1032,35	2108,78	1,27	0,00	74,42	414,07	449,76	449,76	414,07
11,67	38,89	0,96	0,04	2,04	1139,26	2354,04	1,42	0,00	83,27	415,55	451,67	451,67	415,55



FINAL PROJECT

Date: **19.06.2014**

Page: **20**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

15,00	43,33	0,96	0,04	2,28	1254,29	2620,47	1,59	0,00	93,04	416,91	453,40	453,40	416,91
18,33	47,78	0,96	0,05	2,53	1377,83	2909,51	1,76	0,00	103,83	418,14	454,93	454,93	418,14
21,67	52,22	0,96	0,05	2,81	1510,31	3222,74	1,95	0,00	115,77	419,24	456,25	456,25	419,24
25,00	56,67	0,97	0,06	3,11	1652,14	3562,00	2,16	0,00	128,99	420,19	457,36	457,36	420,19
28,33	61,11	0,97	0,06	3,43	1803,77	3929,48	2,39	0,00	143,65	420,96	458,25	458,25	420,96
31,67	65,56	0,97	0,07	3,78	1965,67	4327,98	2,63	0,00	159,96	421,56	458,89	458,89	421,56
35,00	70,00	0,97	0,08	4,17	2138,33	4761,73	2,90	0,00	178,15	421,94	459,28	459,28	421,94
5,00	30,00	0,98	0,03	1,64	933,18	1883,41	1,14	0,00	63,89	417,92	454,26	454,26	417,92
8,33	34,44	0,98	0,03	1,84	1032,35	2108,78	1,28	0,00	71,60	419,40	456,28	456,28	419,40
11,67	38,89	0,98	0,04	2,06	1139,26	2354,04	1,43	0,00	80,12	420,76	458,12	458,12	420,76
15,00	43,33	0,98	0,04	2,30	1254,29	2620,47	1,60	0,00	89,53	422,00	459,76	459,76	422,00
18,33	47,78	0,99	0,05	2,56	1377,83	2909,51	1,78	0,00	99,92	423,12	461,19	461,19	423,12
21,67	52,22	0,99	0,05	2,84	1510,31	3222,74	1,98	0,00	111,43	424,09	462,41	462,41	424,09
25,00	56,67	0,99	0,06	3,14	1652,14	3562,00	2,19	0,00	124,17	424,90	463,41	463,41	424,90
28,33	61,11	0,99	0,06	3,47	1803,77	3929,48	2,42	0,00	138,32	425,54	464,16	464,16	425,54
31,67	65,56	1,00	0,07	3,83	1965,67	4327,98	2,66	0,00	154,07	425,98	464,66	464,66	425,98
35,00	70,00	1,00	0,08	4,22	2138,33	4761,73	2,94	0,00	171,69	426,21	464,89	464,89	426,21



FINAL PROJECT

Date: 19.06.2014

Page: 21

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.3.1 Summary R410 A--- 5000 rpm ,11.4 cc/rev

Table 17-Summary R410 A- 5000 rpm, 11.4 cc/rev- cycle 1

	mref [g/s]	flow (l/min)	P1 (kPa)	P2	Q (kW)	Qres (kW)	desnsity after resistance	h1	h2	h3	h4
min	31,35	1,62	933,18	1883,41	1,13	0,00	63,89	369,01	396,38	416,13	369,01
max	95,75	4,47	2138,33	4761,73	3,12	1,43	254,73	426,21	464,89	464,89	426,21
X1_para minimo	0,98	0,90	0,75	0,75	0,90	0,77	0,98	0,75	0,75	0,77	0,75
X1_para maximo	0,77	0,77	0,77	0,77	0,77	0,76	0,77	1,00	1,00	1,00	1,00



FINAL PROJECT

Date: 19.06.2014

Page: 22

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.4 REFRIGERANT R 410 A --- 3000rpm, 7 cc/rev

Table 18- R410 A- 3000 rpm, 7 cc/rev- cycle 1

T1	T2	X1	mref	flow_l_min	P1	P2	Q	Qres	desnsity after resistance	h1	h2	h3	h4
5,00	30,00	0,75	0,01	1,33	933,18	1883,41	0,92	0,52	74,08	369,01	396,38	430,96	369,01
8,33	34,44	0,75	0,02	1,41	1032,35	2108,78	0,98	0,52	84,28	371,47	399,22	431,06	371,47
11,67	38,89	0,76	0,02	1,49	1139,26	2354,04	1,04	0,53	95,92	373,85	401,91	430,84	373,85
15,00	43,33	0,76	0,02	1,56	1254,29	2620,47	1,08	0,52	109,27	376,15	404,46	430,26	376,15
18,33	47,78	0,76	0,02	1,61	1377,83	2909,51	1,12	0,49	124,69	378,36	406,85	429,26	378,36
21,67	52,22	0,76	0,02	1,65	1510,31	3222,74	1,15	0,45	142,72	380,48	409,08	427,74	380,48
25,00	56,67	0,77	0,03	1,65	1652,14	3562,00	1,15	0,39	164,06	382,49	411,13	425,60	382,49
28,33	61,11	0,77	0,03	1,61	1803,77	3929,48	1,12	0,28	189,79	384,38	413,00	422,66	384,38
31,67	65,56	0,77	0,03	1,50	1965,67	4327,98	1,05	0,13	221,50	386,14	414,66	418,71	386,14
35,00	70,00	0,77	0,04	1,44	2138,33	4761,73	1,00	0,00	254,73	387,76	416,13	416,13	387,76
5,00	30,00	0,78	0,01	1,17	933,18	1883,41	0,82	0,41	74,08	374,45	402,79	430,96	374,45
8,33	34,44	0,78	0,02	1,24	1032,35	2108,78	0,87	0,41	84,28	376,79	405,53	431,06	376,79
11,67	38,89	0,78	0,02	1,31	1139,26	2354,04	0,91	0,40	95,92	379,06	408,12	430,84	379,06
15,00	43,33	0,78	0,02	1,37	1254,29	2620,47	0,95	0,38	109,27	381,24	410,55	430,26	381,24
18,33	47,78	0,79	0,02	1,41	1377,83	2909,51	0,98	0,35	124,69	383,33	412,83	429,26	383,33
21,67	52,22	0,79	0,02	1,43	1510,31	3222,74	1,00	0,30	142,72	385,32	414,93	427,74	385,32



FINAL PROJECT

Date: 19.06.2014

Page: 23

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

25,00	56,67	0,79	0,03	1,43	1652,14	3562,00	0,99	0,23	164,06	387,20	416,85	425,60	387,20
28,33	61,11	0,79	0,03	1,37	1803,77	3929,48	0,96	0,12	189,79	388,95	418,57	422,66	388,95
31,67	65,56	0,80	0,03	1,32	1965,67	4327,98	0,92	0,00	218,59	390,57	420,07	420,07	390,57
35,00	70,00	0,80	0,03	1,45	2138,33	4761,73	1,01	0,00	241,89	392,03	421,41	421,41	392,03
5,00	30,00	0,80	0,01	1,03	933,18	1883,41	0,72	0,30	74,08	379,88	409,20	430,96	379,88
8,33	34,44	0,80	0,02	1,09	1032,35	2108,78	0,76	0,30	84,28	382,12	411,84	431,06	382,12
11,67	38,89	0,81	0,02	1,14	1139,26	2354,04	0,80	0,28	95,92	384,28	414,32	430,84	384,28
15,00	43,33	0,81	0,02	1,19	1254,29	2620,47	0,83	0,26	109,27	386,34	416,65	430,26	386,34
18,33	47,78	0,81	0,02	1,22	1377,83	2909,51	0,85	0,22	124,69	388,31	418,80	429,26	388,31
21,67	52,22	0,81	0,02	1,23	1510,31	3222,74	0,86	0,16	142,72	390,17	420,78	427,74	390,17
25,00	56,67	0,82	0,03	1,21	1652,14	3562,00	0,85	0,08	164,06	391,91	422,56	425,60	391,91
28,33	61,11	0,82	0,03	1,21	1803,77	3929,48	0,84	0,00	187,22	393,53	424,13	424,13	393,53
31,67	65,56	0,82	0,03	1,33	1965,67	4327,98	0,93	0,00	207,73	395,00	425,50	425,50	395,00
35,00	70,00	0,82	0,03	1,45	2138,33	4761,73	1,01	0,00	230,21	396,31	426,71	426,71	396,31
5,00	30,00	0,83	0,01	0,89	933,18	1883,41	0,62	0,21	74,08	385,32	415,61	430,96	385,32
8,33	34,44	0,83	0,02	0,94	1032,35	2108,78	0,66	0,19	84,28	387,45	418,15	431,06	387,45
11,67	38,89	0,83	0,02	0,99	1139,26	2354,04	0,69	0,17	95,92	389,49	420,53	430,84	389,49
15,00	43,33	0,83	0,02	1,02	1254,29	2620,47	0,71	0,14	109,27	391,44	422,74	430,26	391,44
18,33	47,78	0,84	0,02	1,04	1377,83	2909,51	0,73	0,09	124,69	393,28	424,78	429,26	393,28
21,67	52,22	0,84	0,02	1,04	1510,31	3222,74	0,73	0,02	142,72	395,01	426,62	427,74	395,01
25,00	56,67	0,84	0,02	1,11	1652,14	3562,00	0,77	0,00	160,28	396,63	428,27	428,27	396,63
28,33	61,11	0,84	0,03	1,22	1803,77	3929,48	0,85	0,00	178,17	398,10	429,70	429,70	398,10
31,67	65,56	0,85	0,03	1,34	1965,67	4327,98	0,93	0,00	197,87	399,43	430,95	430,95	399,43



FINAL PROJECT

Date: **19.06.2014**

Page: **24**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

35,00	70,00	0,85	0,03	1,47	2138,33	4761,73	1,02	0,00	219,55	400,58	432,03	432,03	400,58
5,00	30,00	0,85	0,01	0,76	933,18	1883,41	0,53	0,12	74,08	390,75	422,02	430,96	390,75
8,33	34,44	0,85	0,01	0,80	1032,35	2108,78	0,56	0,10	84,28	392,77	424,46	431,06	392,77
11,67	38,89	0,86	0,02	0,84	1139,26	2354,04	0,58	0,07	95,92	394,70	426,74	430,84	394,70
15,00	43,33	0,86	0,02	0,86	1254,29	2620,47	0,60	0,03	109,27	396,53	428,84	430,26	396,53
18,33	47,78	0,86	0,02	0,91	1377,83	2909,51	0,64	0,00	123,21	398,25	430,75	430,75	398,25
21,67	52,22	0,86	0,02	1,01	1510,31	3222,74	0,70	0,00	137,27	399,86	432,47	432,47	399,86
25,00	56,67	0,87	0,02	1,11	1652,14	3562,00	0,78	0,00	152,81	401,34	433,98	433,98	401,34
28,33	61,11	0,87	0,03	1,22	1803,77	3929,48	0,85	0,00	169,97	402,67	435,30	435,30	402,67
31,67	65,56	0,87	0,03	1,34	1965,67	4327,98	0,94	0,00	188,90	403,85	436,44	436,44	403,85
35,00	70,00	0,87	0,03	1,48	2138,33	4761,73	1,03	0,00	209,81	404,85	437,39	437,39	404,85
5,00	30,00	0,88	0,01	0,64	933,18	1883,41	0,45	0,03	74,08	396,19	428,43	430,96	396,19
8,33	34,44	0,88	0,01	0,67	1032,35	2108,78	0,47	0,00	84,28	398,10	430,77	431,06	398,10
11,67	38,89	0,88	0,02	0,74	1139,26	2354,04	0,52	0,00	94,44	399,91	432,94	432,94	399,91
15,00	43,33	0,88	0,02	0,83	1254,29	2620,47	0,58	0,00	105,47	401,63	434,93	434,93	401,63
18,33	47,78	0,89	0,02	0,92	1377,83	2909,51	0,64	0,00	117,66	403,23	436,73	436,73	403,23
21,67	52,22	0,89	0,02	1,01	1510,31	3222,74	0,71	0,00	131,14	404,71	438,32	438,32	404,71
25,00	56,67	0,89	0,02	1,12	1652,14	3562,00	0,78	0,00	146,05	406,05	439,72	439,72	406,05
28,33	61,11	0,89	0,03	1,23	1803,77	3929,48	0,86	0,00	162,51	407,25	440,94	440,94	407,25
31,67	65,56	0,90	0,03	1,35	1965,67	4327,98	0,94	0,00	180,71	408,28	441,97	441,97	408,28
35,00	70,00	0,90	0,03	1,49	2138,33	4761,73	1,04	0,00	200,89	409,12	442,79	442,79	409,12
5,00	30,00	0,90	0,01	0,60	933,18	1883,41	0,41	0,00	72,12	401,62	434,83	434,83	401,62
8,33	34,44	0,90	0,01	0,67	1032,35	2108,78	0,47	0,00	80,78	403,42	437,08	437,08	403,42



FINAL PROJECT

Date: 19.06.2014

Page: 25

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

11,67	38,89	0,91	0,02	0,75	1139,26	2354,04	0,52	0,00	90,35	405,12	439,15	439,15	405,12
15,00	43,33	0,91	0,02	0,83	1254,29	2620,47	0,58	0,00	100,94	406,72	441,02	441,02	406,72
18,33	47,78	0,91	0,02	0,92	1377,83	2909,51	0,64	0,00	112,64	408,20	442,71	442,71	408,20
21,67	52,22	0,91	0,02	1,02	1510,31	3222,74	0,71	0,00	125,58	409,55	444,21	444,21	409,55
25,00	56,67	0,92	0,02	1,12	1652,14	3562,00	0,78	0,00	139,87	410,76	445,53	445,53	410,76
28,33	61,11	0,92	0,02	1,24	1803,77	3929,48	0,86	0,00	155,68	411,82	446,65	446,65	411,82
31,67	65,56	0,92	0,03	1,37	1965,67	4327,98	0,95	0,00	173,21	412,71	447,55	447,55	412,71
35,00	70,00	0,92											
5,00	30,00	0,93	0,01	0,60	933,18	1883,41	0,42	0,00	69,13	407,05	441,24	441,24	407,05
8,33	34,44	0,93	0,01	0,67	1032,35	2108,78	0,47	0,00	77,46	408,75	443,39	443,39	408,75
11,67	38,89	0,93	0,01	0,75	1139,26	2354,04	0,52	0,00	86,66	410,34	445,36	445,36	410,34
15,00	43,33	0,93	0,02	0,83	1254,29	2620,47	0,58	0,00	96,83	411,81	447,15	447,15	411,81
18,33	47,78	0,94	0,02	0,93	1377,83	2909,51	0,64	0,00	108,06	413,17	448,77	448,77	413,17
21,67	52,22	0,94	0,02	1,03	1510,31	3222,74	0,71	0,00	120,47	414,40	450,19	450,19	414,40
25,00	56,67	0,94	0,02	1,13	1652,14	3562,00	0,79	0,00	134,21	415,47	451,41	451,41	415,47
28,33	61,11	0,94	0,02	1,25	1803,77	3929,48	0,87	0,00	149,42	416,39	452,41	452,41	416,39
31,67	65,56	0,95	0,03	1,38	1965,67	4327,98	0,96	0,00	166,31	417,13	453,19	453,19	417,13
35,00	70,00	0,95	0,03	1,52	2138,33	4761,73	1,06	0,00	185,13	417,67	453,73	453,73	417,67
5,00	30,00	0,95	0,01	0,60	933,18	1883,41	0,42	0,00	66,41	412,49	447,68	447,68	412,49
8,33	34,44	0,95	0,01	0,67	1032,35	2108,78	0,47	0,00	74,42	414,07	449,76	449,76	414,07
11,67	38,89	0,96	0,01	0,75	1139,26	2354,04	0,52	0,00	83,27	415,55	451,67	451,67	415,55
15,00	43,33	0,96	0,02	0,84	1254,29	2620,47	0,58	0,00	93,04	416,91	453,40	453,40	416,91
18,33	47,78	0,96	0,02	0,93	1377,83	2909,51	0,65	0,00	103,83	418,14	454,93	454,93	418,14



FINAL PROJECT

Date: **19.06.2014**

Page: **26**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

21,67	52,22	0,96	0,02	1,03	1510,31	3222,74	0,72	0,00	115,77	419,24	456,25	456,25	419,24
25,00	56,67	0,97	0,02	1,14	1652,14	3562,00	0,80	0,00	128,99	420,19	457,36	457,36	420,19
28,33	61,11	0,97	0,02	1,26	1803,77	3929,48	0,88	0,00	143,65	420,96	458,25	458,25	420,96
31,67	65,56	0,97	0,03	1,39	1965,67	4327,98	0,97	0,00	159,96	421,56	458,89	458,89	421,56
35,00	70,00	0,97	0,03	1,53	2138,33	4761,73	1,07	0,00	178,15	421,94	459,28	459,28	421,94
5,00	30,00	0,98	0,01	0,60	933,18	1883,41	0,42	0,00	63,89	417,92	454,26	454,26	417,92
8,33	34,44	0,98	0,01	0,68	1032,35	2108,78	0,47	0,00	71,60	419,40	456,28	456,28	419,40
11,67	38,89	0,98	0,01	0,76	1139,26	2354,04	0,53	0,00	80,12	420,76	458,12	458,12	420,76
15,00	43,33	0,98	0,02	0,85	1254,29	2620,47	0,59	0,00	89,53	422,00	459,76	459,76	422,00
18,33	47,78	0,99	0,02	0,94	1377,83	2909,51	0,66	0,00	99,92	423,12	461,19	461,19	423,12
21,67	52,22	0,99	0,02	1,05	1510,31	3222,74	0,73	0,00	111,43	424,09	462,41	462,41	424,09
25,00	56,67	0,99	0,02	1,16	1652,14	3562,00	0,81	0,00	124,17	424,90	463,41	463,41	424,90
28,33	61,11	0,99	0,02	1,28	1803,77	3929,48	0,89	0,00	138,32	425,54	464,16	464,16	425,54
31,67	65,56	1,00	0,03	1,41	1965,67	4327,98	0,98	0,00	154,07	425,98	464,66	464,66	425,98
35,00	70,00	1,00	0,03	1,55	2138,33	4761,73	1,08	0,00	171,69	426,21	464,89	464,89	426,21



FINAL PROJECT

Date: 19.06.2014

Page: 27

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.4.1 Summary R410 A--- 3000 rpm, 7 cc/rev

Table 19-Summary R410 A- 3000 rpm, 7 cc/rev- cycle 1

	mref [g/s]	flow (l/min)	P1 (kPa)	P2	Q (kW)	Qres (kW)	desnsity after resistence	h1	h2	h3	h4
min	11,55	0,60	933,18	1883,41	0,41	0,00	63,89	369,01	396,38	416,13	369,01
max	35,27	1,65	2138,33	4761,73	1,15	0,53	254,73	426,21	464,89	464,89	426,21
X1_para minimo	0,98	0,90	0,75	0,75	0,90	0,77	0,98	0,75	0,75	0,77	0,75
X1_para maximo	0,77	0,77	0,77	0,77	0,77	0,76	0,77	1,00	1,00	1,00	1,00



FINAL PROJECT

Date: 19.06.2014

Page: 28

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.5 REFRIGERANT R407 C --- 5000 rpm, 11.4 cc/rev

Table 20- R407 C- 5000rpm, 11.4 cc/rev- cycle 1

T1	T2	X1	mref	flow_l_min	P1	P2	Q	Qres	desnsity after resistance	h1	h2	h3	h4
5,00	30,00	0,75	0,03	2,47	546,52	1175,14	1,72	0,967	49,65	359,51	388,30	425,23	359,51
8,33	34,44	0,75	0,03	2,69	610,42	1328,23	1,87	1,023	56,52	362,40	391,55	426,69	362,40
11,67	38,89	0,76	0,03	2,91	679,86	1496,04	2,02	1,074	64,25	365,25	394,71	427,99	365,25
15,00	43,33	0,76	0,04	3,13	755,15	1679,57	2,18	1,120	72,97	368,06	397,76	429,11	368,06
18,33	47,78	0,76	0,04	3,35	836,60	1879,91	2,34	1,156	82,83	370,81	400,71	430,02	370,81
21,67	52,22	0,76	0,04	3,57	924,55	2098,22	2,49	1,180	94,03	373,50	403,55	430,67	373,50
25,00	56,67	0,77	0,05	3,78	1019,34	2335,84	2,63	1,187	106,83	376,14	406,29	431,04	376,14
28,33	61,11	0,77	0,05	3,96	1121,33	2594,27	2,76	1,168	121,59	378,71	408,90	431,06	378,71
31,67	65,56	0,77	0,06	4,11	1230,88	2875,31	2,87	1,115	138,79	381,21	411,40	430,65	381,21
35,00	70,00	0,77	0,06	4,21	1348,38	3181,21	2,93	1,013	159,13	383,63	413,78	429,70	383,63
5,00	30,00	0,78	0,03	2,20	546,52	1175,14	1,53	0,781	49,65	364,82	394,45	425,23	364,82
8,33	34,44	0,78	0,03	2,39	610,42	1328,23	1,67	0,819	56,52	367,63	397,64	426,69	367,63
11,67	38,89	0,78	0,03	2,59	679,86	1496,04	1,80	0,853	64,25	370,40	400,72	427,99	370,40
15,00	43,33	0,78	0,03	2,78	755,15	1679,57	1,94	0,880	72,97	373,11	403,70	429,11	373,11
18,33	47,78	0,79	0,04	2,98	836,60	1879,91	2,08	0,897	82,83	375,76	406,57	430,02	375,76
21,67	52,22	0,79	0,04	3,17	924,55	2098,22	2,21	0,901	94,03	378,36	409,33	430,67	378,36



FINAL PROJECT

Date: **19.06.2014**

Page: **29**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

25,00	56,67	0,79	0,05	3,35	1019,34	2335,84	2,33	0,887	106,83	380,89	411,97	431,04	380,89
28,33	61,11	0,79	0,05	3,50	1121,33	2594,27	2,44	0,848	121,59	383,36	414,49	431,06	383,36
31,67	65,56	0,80	0,06	3,63	1230,88	2875,31	2,53	0,775	138,79	385,75	416,88	430,65	385,75
35,00	70,00	0,80	0,06	3,69	1348,38	3181,21	2,57	0,652	159,13	388,06	419,15	429,70	388,06
5,00	30,00	0,80	0,02	1,95	546,52	1175,14	1,36	0,606	49,65	370,13	400,58	425,23	370,13
8,33	34,44	0,80	0,03	2,11	610,42	1328,23	1,47	0,629	56,52	372,86	403,70	426,69	372,86
11,67	38,89	0,81	0,03	2,29	679,86	1496,04	1,59	0,646	64,25	375,53	406,71	427,99	375,53
15,00	43,33	0,81	0,03	2,46	755,15	1679,57	1,71	0,655	72,97	378,15	409,62	429,11	378,15
18,33	47,78	0,81	0,04	2,63	836,60	1879,91	1,83	0,654	82,83	380,71	412,41	430,02	380,71
21,67	52,22	0,81	0,04	2,79	924,55	2098,22	1,95	0,639	94,03	383,21	415,08	430,67	383,21
25,00	56,67	0,82	0,05	2,94	1019,34	2335,84	2,05	0,606	106,83	385,64	417,63	431,04	385,64
28,33	61,11	0,82	0,05	3,07	1121,33	2594,27	2,14	0,547	121,59	388,00	420,05	431,06	388,00
31,67	65,56	0,82	0,05	3,17	1230,88	2875,31	2,21	0,454	138,79	390,29	422,35	430,65	390,29
35,00	70,00	0,82	0,06	3,21	1348,38	3181,21	2,23	0,312	159,13	392,49	424,50	429,70	392,49
5,00	30,00	0,83	0,02	1,71	546,52	1175,14	1,19	0,443	49,65	375,43	406,69	425,23	375,43
8,33	34,44	0,83	0,03	1,85	610,42	1328,23	1,29	0,450	56,52	378,07	409,74	426,69	378,07
11,67	38,89	0,83	0,03	2,00	679,86	1496,04	1,40	0,451	64,25	380,65	412,68	427,99	380,65
15,00	43,33	0,83	0,03	2,15	755,15	1679,57	1,50	0,444	72,97	383,18	415,51	429,11	383,18
18,33	47,78	0,84	0,04	2,30	836,60	1879,91	1,60	0,426	82,83	385,65	418,22	430,02	385,65
21,67	52,22	0,84	0,04	2,44	924,55	2098,22	1,70	0,393	94,03	388,05	420,81	430,67	388,05
25,00	56,67	0,84	0,04	2,56	1019,34	2335,84	1,79	0,341	106,83	390,38	423,27	431,04	390,38
28,33	61,11	0,84	0,05	2,67	1121,33	2594,27	1,86	0,264	121,59	392,64	425,60	431,06	392,64
31,67	65,56	0,85	0,05	2,74	1230,88	2875,31	1,91	0,152	138,79	394,82	427,79	430,65	394,82



FINAL PROJECT

Date: 19.06.2014

Page: 30

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

35,00	70,00	0,85	0,06	2,76	1348,38	3181,21	1,92	0,000	158,94	396,90	429,83	429,83	396,90
5,00	30,00	0,85	0,02	1,48	546,52	1175,14	1,03	0,289	49,65	380,72	412,77	425,23	380,72
8,33	34,44	0,85	0,03	1,61	610,42	1328,23	1,12	0,282	56,52	383,28	415,76	426,69	383,28
11,67	38,89	0,86	0,03	1,74	679,86	1496,04	1,21	0,268	64,25	385,77	418,63	427,99	385,77
15,00	43,33	0,86	0,03	1,86	755,15	1679,57	1,30	0,245	72,97	388,21	421,39	429,11	388,21
18,33	47,78	0,86	0,04	1,99	836,60	1879,91	1,38	0,210	82,83	390,58	424,02	430,02	390,58
21,67	52,22	0,86	0,04	2,10	924,55	2098,22	1,46	0,161	94,03	392,89	426,52	430,67	392,89
25,00	56,67	0,87	0,04	2,20	1019,34	2335,84	1,53	0,092	106,83	395,12	428,89	431,04	395,12
28,33	61,11	0,87	0,05	2,29	1121,33	2594,27	1,59	0,00	121,53	397,27	431,12	431,12	397,27
31,67	65,56	0,87	0,05	2,52	1230,88	2875,31	1,75	0,00	135,92	399,34	433,21	433,21	399,34
35,00	70,00	0,87	0,06	2,76	1348,38	3181,21	1,93	0,00	151,96	401,31	435,15	435,15	401,31
5,00	30,00	0,88	0,02	1,27	546,52	1175,14	0,89	0,144	49,65	386,01	418,83	425,23	386,01
8,33	34,44	0,88	0,03	1,38	610,42	1328,23	0,96	0,124	56,52	388,48	421,75	426,69	388,48
11,67	38,89	0,88	0,03	1,48	679,86	1496,04	1,03	0,096	64,25	390,88	424,56	427,99	390,88
15,00	43,33	0,88	0,03	1,59	755,15	1679,57	1,11	0,058	72,97	393,23	427,24	429,11	393,23
18,33	47,78	0,89	0,03	1,69	836,60	1879,91	1,18	0,008	82,83	395,51	429,79	430,02	395,51
21,67	52,22	0,89	0,04	1,87	924,55	2098,22	1,30	0,00	93,00	397,71	432,21	432,21	397,71
25,00	56,67	0,89	0,04	2,07	1019,34	2335,84	1,44	0,00	104,15	399,84	434,49	434,49	399,84
28,33	61,11	0,89	0,05	2,28	1121,33	2594,27	1,59	0,00	116,54	401,89	436,63	436,63	401,89
31,67	65,56	0,90	0,05	2,52	1230,88	2875,31	1,75	0,00	130,33	403,85	438,61	438,61	403,85
35,00	70,00	0,90	0,06	2,76	1348,38	3181,21	1,93	0,00	145,72	405,71	440,44	440,44	405,71
5,00	30,00	0,90	0,02	1,06	546,52	1175,14	0,74	0,00	49,77	391,29	424,87	424,87	391,29
8,33	34,44	0,90	0,02	1,19	610,42	1328,23	0,83	0,00	56,15	393,67	427,73	427,73	393,67



FINAL PROJECT

Date: 19.06.2014

Page: 31

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

11,67	38,89	0,91	0,03	1,34	679,86	1496,04	0,94	0,00	63,23	395,98	430,46	430,46	395,98
15,00	43,33	0,91	0,03	1,50	755,15	1679,57	1,05	0,00	71,08	398,24	433,07	433,07	398,24
18,33	47,78	0,91	0,03	1,68	836,60	1879,91	1,17	0,00	79,78	400,42	435,54	435,54	400,42
21,67	52,22	0,91	0,04	1,86	924,55	2098,22	1,30	0,00	89,43	402,53	437,88	437,88	402,53
25,00	56,67	0,92	0,04	2,07	1019,34	2335,84	1,44	0,00	100,15	404,56	440,07	440,07	404,56
28,33	61,11	0,92	0,04	2,28	1121,33	2594,27	1,59	0,00	112,06	406,50	442,11	442,11	406,50
31,67	65,56	0,92											
35,00	70,00	0,92											
5,00	30,00	0,93	0,02	1,05	546,52	1175,14	0,73	0,00	47,97	396,56	430,88	430,88	396,56
8,33	34,44	0,93	0,02	1,19	610,42	1328,23	0,83	0,00	54,13	398,85	433,68	433,68	398,85
11,67	38,89	0,93	0,03	1,34	679,86	1496,04	0,93	0,00	60,96	401,08	436,34	436,34	401,08
15,00	43,33	0,93	0,03	1,50	755,15	1679,57	1,04	0,00	68,53	403,24	438,88	438,88	403,24
18,33	47,78	0,94	0,03	1,67	836,60	1879,91	1,17	0,00	76,92	405,33	441,27	441,27	405,33
21,67	52,22	0,94	0,04	1,86	924,55	2098,22	1,30	0,00	86,22	407,34	443,52	443,52	407,34
25,00	56,67	0,94											
28,33	61,11	0,94											
31,67	65,56	0,95											
35,00	70,00	0,95											
5,00	30,00	0,95	0,02	1,05	546,52	1175,14	0,73	0,00	46,34	401,82	436,87	436,87	401,82
8,33	34,44	0,95	0,02	1,19	610,42	1328,23	0,83	0,00	52,30	404,02	439,60	439,60	404,02
11,67	38,89	0,96	0,03	1,33	679,86	1496,04	0,93	0,00	58,90	406,16	442,20	442,20	406,16
15,00	43,33	0,96											
18,33	47,78	0,96											



FINAL PROJECT

Date: **19.06.2014**

Page: **32**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

21,67	52,22	0,96											
25,00	56,67	0,97											
28,33	61,11	0,97	0,04	2,29	1121,33	2594,27	1,60	0,00	104,21	415,70	453,25	453,25	415,70
31,67	65,56	0,97	0,05	2,53	1230,88	2875,31	1,76	0,00	116,46	417,32	455,02	455,02	417,32
35,00	70,00	0,97	0,05	2,79	1348,38	3181,21	1,95	0,00	130,10	418,84	456,64	456,64	418,84
5,00	30,00	0,98	0,02	1,05	546,52	1175,14	0,73	0,00	44,83	407,07	442,93	442,93	407,07
8,33	34,44	0,98	0,02	1,18	610,42	1328,23	0,82	0,00	50,60	409,19	445,63	445,63	409,19
11,67	38,89	0,98	0,03	1,33	679,86	1496,04	0,93	0,00	56,98	411,24	448,21	448,21	411,24
15,00	43,33	0,98	0,03	1,50	755,15	1679,57	1,04	0,00	64,04	413,22	450,64	450,64	413,22
18,33	47,78	0,99	0,03	1,68	836,60	1879,91	1,17	0,00	71,86	415,12	452,94	452,94	415,12
21,67	52,22	0,99	0,03	1,87	924,55	2098,22	1,30	0,00	80,51	416,93	455,09	455,09	416,93
25,00	56,67	0,99	0,04	2,08	1019,34	2335,84	1,45	0,00	90,10	418,65	457,09	457,09	418,65
28,33	61,11	0,99	0,04	2,30	1121,33	2594,27	1,60	0,00	100,74	420,28	458,94	458,94	420,28
31,67	65,56	1,00	0,05	2,55	1230,88	2875,31	1,77	0,00	112,55	421,80	460,62	460,62	421,80
35,00	70,00	1,00	0,05	2,81	1348,38	3181,21	1,96	0,00	125,71	423,20	462,15	462,15	423,20



FINAL PROJECT

Date: 19.06.2014

Page: 33

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.5.1 Summary R407 C ---5000 rpm, 11.4 cc/rev

Table 21- Summary R407 C- 5000 rpm, 11.4 cc/rev- cycle 1

	mref [g/s]	flow (l/min)	P1 (kPa)	P2	Q (kW)	Qres (kW)	desnsity after resistance	h1	h2	h3	h4
min	20,33	1,05	546,52	1175,14	0,73	0,000	44,83	359,51	388,30	424,87	359,51
max	63,61	4,21	1348,38	3181,21	2,93	1,187	159,13	423,20	462,15	462,15	423,20
X1_para minimo	0,98	0,98	0,75	0,75	0,98	0,848	0,98	0,75	0,75	0,90	0,75
X1_para maximo	0,77	0,77	0,77	0,77	0,77	0,765	0,77	1,00	1,00	1,00	1,00



FINAL PROJECT

Date: 19.06.2014

Page: 34

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.6 REFRIGERANT R407 C ---3000 rpm , 7 cc/rev

Table 22- Summary R407 C- 3000 rpm, 7cc/rev- cycle 1

T1	T2	X1	mref	flow_l_min	P1	P2	Q	Qres	desnsity after resistance	h1	h2	h3	h4
5,00	30,00	0,75	0,01	0,91	546,52	1175,14	0,63	0,356	49,65	359,51	388,30	425,23	359,51
8,33	34,44	0,75	0,01	0,99	610,42	1328,23	0,69	0,377	56,52	362,40	391,55	426,69	362,40
11,67	38,89	0,76	0,01	1,07	679,86	1496,04	0,75	0,396	64,25	365,25	394,71	427,99	365,25
15,00	43,33	0,76	0,01	1,15	755,15	1679,57	0,80	0,412	72,97	368,06	397,76	429,11	368,06
18,33	47,78	0,76	0,01	1,24	836,60	1879,91	0,86	0,426	82,83	370,81	400,71	430,02	370,81
21,67	52,22	0,76	0,02	1,32	924,55	2098,22	0,92	0,435	94,03	373,50	403,55	430,67	373,50
25,00	56,67	0,77	0,02	1,39	1019,34	2335,84	0,97	0,437	106,83	376,14	406,29	431,04	376,14
28,33	61,11	0,77	0,02	1,46	1121,33	2594,27	1,02	0,430	121,59	378,71	408,90	431,06	378,71
31,67	65,56	0,77	0,02	1,52	1230,88	2875,31	1,06	0,411	138,79	381,21	411,40	430,65	381,21
35,00	70,00	0,77	0,02	1,55	1348,38	3181,21	1,08	0,373	159,13	383,63	413,78	429,70	383,63
5,00	30,00	0,78	0,01	0,81	546,52	1175,14	0,56	0,288	49,65	364,82	394,45	425,23	364,82
8,33	34,44	0,78	0,01	0,88	610,42	1328,23	0,61	0,302	56,52	367,63	397,64	426,69	367,63
11,67	38,89	0,78	0,01	0,95	679,86	1496,04	0,66	0,314	64,25	370,40	400,72	427,99	370,40
15,00	43,33	0,78	0,01	1,03	755,15	1679,57	0,71	0,324	72,97	373,11	403,70	429,11	373,11
18,33	47,78	0,79	0,01	1,10	836,60	1879,91	0,76	0,331	82,83	375,76	406,57	430,02	375,76
21,67	52,22	0,79	0,02	1,17	924,55	2098,22	0,81	0,332	94,03	378,36	409,33	430,67	378,36



FINAL PROJECT

Date: 19.06.2014

Page: 35

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

25,00	56,67	0,79	0,02	1,23	1019,34	2335,84	0,86	0,327	106,83	380,89	411,97	431,04	380,89
28,33	61,11	0,79	0,02	1,29	1121,33	2594,27	0,90	0,312	121,59	383,36	414,49	431,06	383,36
31,67	65,56	0,80	0,02	1,34	1230,88	2875,31	0,93	0,285	138,79	385,75	416,88	430,65	385,75
35,00	70,00	0,80	0,02	1,36	1348,38	3181,21	0,95	0,240	159,13	388,06	419,15	429,70	388,06
5,00	30,00	0,80	0,01	0,72	546,52	1175,14	0,50	0,223	49,65	370,13	400,58	425,23	370,13
8,33	34,44	0,80	0,01	0,78	610,42	1328,23	0,54	0,232	56,52	372,86	403,70	426,69	372,86
11,67	38,89	0,81	0,01	0,84	679,86	1496,04	0,59	0,238	64,25	375,53	406,71	427,99	375,53
15,00	43,33	0,81	0,01	0,91	755,15	1679,57	0,63	0,241	72,97	378,15	409,62	429,11	378,15
18,33	47,78	0,81	0,01	0,97	836,60	1879,91	0,67	0,241	82,83	380,71	412,41	430,02	380,71
21,67	52,22	0,81	0,02	1,03	924,55	2098,22	0,72	0,236	94,03	383,21	415,08	430,67	383,21
25,00	56,67	0,82	0,02	1,08	1019,34	2335,84	0,76	0,223	106,83	385,64	417,63	431,04	385,64
28,33	61,11	0,82	0,02	1,13	1121,33	2594,27	0,79	0,202	121,59	388,00	420,05	431,06	388,00
31,67	65,56	0,82	0,02	1,17	1230,88	2875,31	0,81	0,167	138,79	390,29	422,35	430,65	390,29
35,00	70,00	0,82	0,02	1,18	1348,38	3181,21	0,82	0,115	159,13	392,49	424,50	429,70	392,49
5,00	30,00	0,83	0,01	0,63	546,52	1175,14	0,44	0,163	49,65	375,43	406,69	425,23	375,43
8,33	34,44	0,83	0,01	0,68	610,42	1328,23	0,48	0,166	56,52	378,07	409,74	426,69	378,07
11,67	38,89	0,83	0,01	0,74	679,86	1496,04	0,51	0,166	64,25	380,65	412,68	427,99	380,65
15,00	43,33	0,83	0,01	0,79	755,15	1679,57	0,55	0,164	72,97	383,18	415,51	429,11	383,18
18,33	47,78	0,84	0,01	0,85	836,60	1879,91	0,59	0,157	82,83	385,65	418,22	430,02	385,65
21,67	52,22	0,84	0,01	0,90	924,55	2098,22	0,63	0,145	94,03	388,05	420,81	430,67	388,05
25,00	56,67	0,84	0,02	0,94	1019,34	2335,84	0,66	0,126	106,83	390,38	423,27	431,04	390,38
28,33	61,11	0,84	0,02	0,98	1121,33	2594,27	0,68	0,097	121,59	392,64	425,60	431,06	392,64
31,67	65,56	0,85	0,02	1,01	1230,88	2875,31	0,70	0,056	138,79	394,82	427,79	430,65	394,82



FINAL PROJECT

Date: 19.06.2014

Page: 36

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

35,00	70,00	0,85	0,02	1,02	1348,38	3181,21	0,71	0,00	158,94	396,90	429,83	429,83	396,90
5,00	30,00	0,85	0,01	0,55	546,52	1175,14	0,38	0,106	49,65	380,72	412,77	425,23	380,72
8,33	34,44	0,85	0,01	0,59	610,42	1328,23	0,41	0,104	56,52	383,28	415,76	426,69	383,28
11,67	38,89	0,86	0,01	0,64	679,86	1496,04	0,45	0,099	64,25	385,77	418,63	427,99	385,77
15,00	43,33	0,86	0,01	0,69	755,15	1679,57	0,48	0,090	72,97	388,21	421,39	429,11	388,21
18,33	47,78	0,86	0,01	0,73	836,60	1879,91	0,51	0,078	82,83	390,58	424,02	430,02	390,58
21,67	52,22	0,86	0,01	0,77	924,55	2098,22	0,54	0,059	94,03	392,89	426,52	430,67	392,89
25,00	56,67	0,87	0,02	0,81	1019,34	2335,84	0,57	0,034	106,83	395,12	428,89	431,04	395,12
28,33	61,11	0,87	0,02	0,84	1121,33	2594,27	0,59	0,00	121,53	397,27	431,12	431,12	397,27
31,67	65,56	0,87	0,02	0,93	1230,88	2875,31	0,65	0,00	135,92	399,34	433,21	433,21	399,34
35,00	70,00	0,87	0,02	1,02	1348,38	3181,21	0,71	0,00	151,96	401,31	435,15	435,15	401,31
5,00	30,00	0,88	0,01	0,47	546,52	1175,14	0,33	0,053	49,65	386,01	418,83	425,23	386,01
8,33	34,44	0,88	0,01	0,51	610,42	1328,23	0,35	0,046	56,52	388,48	421,75	426,69	388,48
11,67	38,89	0,88	0,01	0,55	679,86	1496,04	0,38	0,035	64,25	390,88	424,56	427,99	390,88
15,00	43,33	0,88	0,01	0,59	755,15	1679,57	0,41	0,021	72,97	393,23	427,24	429,11	393,23
18,33	47,78	0,89	0,01	0,62	836,60	1879,91	0,43	0,003	82,83	395,51	429,79	430,02	395,51
21,67	52,22	0,89	0,01	0,69	924,55	2098,22	0,48	0,00	93,00	397,71	432,21	432,21	397,71
25,00	56,67	0,89	0,02	0,76	1019,34	2335,84	0,53	0,00	104,15	399,84	434,49	434,49	399,84
28,33	61,11	0,89	0,02	0,84	1121,33	2594,27	0,59	0,00	116,54	401,89	436,63	436,63	401,89
31,67	65,56	0,90	0,02	0,93	1230,88	2875,31	0,65	0,00	130,33	403,85	438,61	438,61	403,85
35,00	70,00	0,90	0,02	1,02	1348,38	3181,21	0,71	0,00	145,72	405,71	440,44	440,44	405,71
5,00	30,00	0,90	0,01	0,39	546,52	1175,14	0,27	0,003	49,65	391,29	424,87	425,23	391,29
8,33	34,44	0,90	0,01	0,44	610,42	1328,23	0,31	0,00	56,15	393,67	427,73	427,73	393,67



FINAL PROJECT

Date: 19.06.2014

Page: 37

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

11,67	38,89	0,91	0,01	0,49	679,86	1496,04	0,34	0,00	63,23	395,98	430,46	430,46	395,98
15,00	43,33	0,91	0,01	0,55	755,15	1679,57	0,39	0,00	71,08	398,24	433,07	433,07	398,24
18,33	47,78	0,91	0,01	0,62	836,60	1879,91	0,43	0,00	79,78	400,42	435,54	435,54	400,42
21,67	52,22	0,91	0,01	0,69	924,55	2098,22	0,48	0,00	89,43	402,53	437,88	437,88	402,53
25,00	56,67	0,92	0,01	0,76	1019,34	2335,84	0,53	0,00	100,15	404,56	440,07	440,07	404,56
28,33	61,11	0,92	0,02	0,84	1121,33	2594,27	0,59	0,00	112,06	406,50	442,11	442,11	406,50
31,67	65,56	0,92											
35,00	70,00	0,92											
5,00	30,00	0,93	0,01	0,39	546,52	1175,14	0,27	0,00	47,97	396,56	430,88	430,88	396,56
8,33	34,44	0,93	0,01	0,44	610,42	1328,23	0,31	0,00	54,13	398,85	433,68	433,68	398,85
11,67	38,89	0,93	0,01	0,49	679,86	1496,04	0,34	0,00	60,96	401,08	436,34	436,34	401,08
15,00	43,33	0,93	0,01	0,55	755,15	1679,57	0,38	0,00	68,53	403,24	438,88	438,88	403,24
18,33	47,78	0,94	0,01	0,62	836,60	1879,91	0,43	0,00	76,92	405,33	441,27	441,27	405,33
21,67	52,22	0,94	0,01	0,69	924,55	2098,22	0,48	0,00	86,22	407,34	443,52	443,52	407,34
25,00	56,67	0,94											
28,33	61,11	0,94											
31,67	65,56	0,95											
35,00	70,00	0,95											
5,00	30,00	0,95	0,01	0,39	546,52	1175,14	0,27	0,00	46,34	401,82	436,87	436,87	401,82
8,33	34,44	0,95	0,01	0,44	610,42	1328,23	0,30	0,00	52,30	404,02	439,60	439,60	404,02
11,67	38,89	0,96	0,01	0,49	679,86	1496,04	0,34	0,00	58,90	406,16	442,20	442,20	406,16
15,00	43,33	0,96											
18,33	47,78	0,96											



FINAL PROJECT

Date: **19.06.2014**

Page: **38**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

21,67	52,22	0,96											
25,00	56,67	0,97											
28,33	61,11	0,97	0,02	0,84	1121,33	2594,27	0,59	0,00	104,21	415,70	453,25	453,25	415,70
31,67	65,56	0,97	0,02	0,93	1230,88	2875,31	0,65	0,00	116,46	417,32	455,02	455,02	417,32
35,00	70,00	0,97	0,02	1,03	1348,38	3181,21	0,72	0,00	130,10	418,84	456,64	456,64	418,84
5,00	30,00	0,98	0,01	0,39	546,52	1175,14	0,27	0,00	44,83	407,07	442,93	442,93	407,07
8,33	34,44	0,98	0,01	0,44	610,42	1328,23	0,30	0,00	50,60	409,19	445,63	445,63	409,19
11,67	38,89	0,98	0,01	0,49	679,86	1496,04	0,34	0,00	56,98	411,24	448,21	448,21	411,24
15,00	43,33	0,98	0,01	0,55	755,15	1679,57	0,38	0,00	64,04	413,22	450,64	450,64	413,22
18,33	47,78	0,99	0,01	0,62	836,60	1879,91	0,43	0,00	71,86	415,12	452,94	452,94	415,12
21,67	52,22	0,99	0,01	0,69	924,55	2098,22	0,48	0,00	80,51	416,93	455,09	455,09	416,93
25,00	56,67	0,99	0,01	0,77	1019,34	2335,84	0,53	0,00	90,10	418,65	457,09	457,09	418,65
28,33	61,11	0,99	0,02	0,85	1121,33	2594,27	0,59	0,00	100,74	420,28	458,94	458,94	420,28
31,67	65,56	1,00	0,02	0,94	1230,88	2875,31	0,65	0,00	112,55	421,80	460,62	460,62	421,80
35,00	70,00	1,00	0,02	1,04	1348,38	3181,21	0,72	0,00	125,71	423,20	462,15	462,15	423,20



FINAL PROJECT

Date: 19.06.2014

Page: 39

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.6.1 Summary R407 C --- 3000 rpm, 7 cc/rev

Table 23- Summary R407 C- 3000 rpm , 7 cc/rev- cycle 1

	mref [g/s]	flow (l/min)	P1 (kPa)	P2	Q (kW)	Qres (kW)	desnsity after resistance	h1	h2	h3	h4
min	7,49	0,39	546,52	1175,14	0,27	0,000	44,83	359,51	388,30	425,23	359,51
max	23,43	1,55	1348,38	3181,21	1,08	0,437	159,13	423,20	462,15	462,15	423,20
X1_para minimo	0,98	0,98	0,75	0,75	0,98	0,848	0,98	0,75	0,75	0,75	0,75
X1_para maximo	0,77	0,77	0,77	0,77	0,77	0,765	0,77	1,00	1,00	1,00	1,00



FINAL PROJECT

Date: 19.06.2014

Page: 40

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.7 REFRIGERANT R22 ---5000 rpm, 11.4 cc/rev

Table 24- R22- 5000 rpm, 11.4 cc/rev-cycle 1

T1	T2	X1	mref	flow_l_min	P1	P2	Q	Qres	desnsity after resistance	h1	h2	h3	h4
5,00	30,00	0,75	0,03	2,44	584,29	1192,30	1,70	0,9814	49,71	356,58	382,06	416,99	356,58
8,33	34,44	0,75	0,03	2,63	647,63	1336,40	1,83	1,0260	55,95	358,95	384,91	418,07	358,95
11,67	38,89	0,76	0,03	2,82	715,98	1492,97	1,96	1,0662	62,88	361,28	387,68	419,02	361,28
15,00	43,33	0,76	0,04	3,02	789,57	1662,66	2,10	1,1005	70,56	363,56	390,37	419,83	363,56
18,33	47,78	0,76	0,04	3,21	868,65	1846,17	2,24	1,1268	79,10	365,81	392,96	420,50	365,81
21,67	52,22	0,76	0,04	3,40	953,47	2044,22	2,37	1,1427	88,61	368,00	395,46	420,99	368,00
25,00	56,67	0,77	0,05	3,59	1044,28	2257,56	2,50	1,1453	99,24	370,15	397,86	421,28	370,15
28,33	61,11	0,77	0,05	3,76	1141,34	2486,99	2,62	1,1304	111,17	372,24	400,16	421,35	372,24
31,67	65,56	0,77	0,06	3,91	1244,92	2733,38	2,73	1,0931	124,63	374,27	402,36	421,16	374,27
35,00	70,00	0,77	0,06	4,03	1355,28	2997,65	2,81	1,0264	139,91	376,24	404,44	420,67	376,24
5,00	30,00	0,78	0,03	2,16	584,29	1192,30	1,51	0,7874	49,71	361,65	388,04	416,99	361,65
8,33	34,44	0,78	0,03	2,33	647,63	1336,40	1,62	0,8159	55,95	363,95	390,84	418,07	363,95
11,67	38,89	0,78	0,03	2,50	715,98	1492,97	1,74	0,8393	62,88	366,21	393,55	419,02	366,21
15,00	43,33	0,78	0,04	2,67	789,57	1662,66	1,86	0,8561	70,56	368,42	396,17	419,83	368,42
18,33	47,78	0,79	0,04	2,84	868,65	1846,17	1,98	0,8644	79,10	370,58	398,70	420,50	370,58
21,67	52,22	0,79	0,04	3,01	953,47	2044,22	2,10	0,8618	88,61	372,69	401,12	420,99	372,69



FINAL PROJECT

Date: **19.06.2014**

Page: **41**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

25,00	56,67	0,79	0,05	3,17	1044,28	2257,56	2,21	0,8453	99,24	374,76	403,45	421,28	374,76
28,33	61,11	0,79	0,05	3,31	1141,34	2486,99	2,31	0,8112	111,17	376,76	405,67	421,35	376,76
31,67	65,56	0,80	0,06	3,44	1244,92	2733,38	2,39	0,7545	124,63	378,71	407,78	421,16	378,71
35,00	70,00	0,80	0,06	3,53	1355,28	2997,65	2,46	0,6685	139,91	380,59	409,78	420,67	380,59
5,00	30,00	0,80	0,03	1,90	584,29	1192,30	1,33	0,6054	49,71	366,73	394,03	416,99	366,73
8,33	34,44	0,80	0,03	2,05	647,63	1336,40	1,43	0,6187	55,95	368,95	396,77	418,07	368,95
11,67	38,89	0,81	0,03	2,20	715,98	1492,97	1,53	0,6262	62,88	371,13	399,42	419,02	371,13
15,00	43,33	0,81	0,04	2,35	789,57	1662,66	1,63	0,6265	70,56	373,27	401,98	419,83	373,27
18,33	47,78	0,81	0,04	2,49	868,65	1846,17	1,74	0,6177	79,10	375,35	404,44	420,50	375,35
21,67	52,22	0,81	0,04	2,63	953,47	2044,22	1,84	0,5975	88,61	377,39	406,79	420,99	377,39
25,00	56,67	0,82	0,05	2,77	1044,28	2257,56	1,93	0,5631	99,24	379,37	409,04	421,28	379,37
28,33	61,11	0,82	0,05	2,89	1141,34	2486,99	2,01	0,5107	111,17	381,29	411,18	421,35	381,29
31,67	65,56	0,82	0,05	2,99	1244,92	2733,38	2,08	0,4355	124,63	383,15	413,21	421,16	383,15
35,00	70,00	0,82	0,06	3,06	1355,28	2997,65	2,13	0,3312	139,91	384,94	415,11	420,67	384,94
5,00	30,00	0,83	0,03	1,66	584,29	1192,30	1,16	0,4342	49,71	371,80	400,01	416,99	371,80
8,33	34,44	0,83	0,03	1,79	647,63	1336,40	1,24	0,4332	55,95	373,95	402,70	418,07	373,95
11,67	38,89	0,83	0,03	1,91	715,98	1492,97	1,33	0,4257	62,88	376,06	405,29	419,02	376,06
15,00	43,33	0,83	0,03	2,04	789,57	1662,66	1,42	0,4103	70,56	378,12	407,79	419,83	378,12
18,33	47,78	0,84	0,04	2,16	868,65	1846,17	1,51	0,3854	79,10	380,13	410,18	420,50	380,13
21,67	52,22	0,84	0,04	2,28	953,47	2044,22	1,59	0,3485	88,61	382,08	412,46	420,99	382,08
25,00	56,67	0,84	0,04	2,39	1044,28	2257,56	1,67	0,2971	99,24	383,98	414,63	421,28	383,98
28,33	61,11	0,84	0,05	2,49	1141,34	2486,99	1,73	0,2273	111,17	385,82	416,69	421,35	385,82
31,67	65,56	0,85	0,05	2,56	1244,92	2733,38	1,79	0,1346	124,63	387,59	418,63	421,16	387,59



FINAL PROJECT

Date: 19.06.2014

Page: 42

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

35,00	70,00	0,85	0,06	2,61	1355,28	2997,65	1,82	0,0127	139,91	389,29	420,45	420,67	389,29
5,00	30,00	0,85	0,02	1,43	584,29	1192,30	1,00	0,2730	49,71	376,87	406,00	416,99	376,87
8,33	34,44	0,85	0,03	1,54	647,63	1336,40	1,07	0,2583	55,95	378,95	408,63	418,07	378,95
11,67	38,89	0,86	0,03	1,64	715,98	1492,97	1,15	0,2366	62,88	380,99	411,16	419,02	380,99
15,00	43,33	0,86	0,03	1,75	789,57	1662,66	1,22	0,2065	70,56	382,97	413,59	419,83	382,97
18,33	47,78	0,86	0,04	1,85	868,65	1846,17	1,29	0,1662	79,10	384,90	415,92	420,50	384,90
21,67	52,22	0,86	0,04	1,95	953,47	2044,22	1,36	0,1136	88,61	386,78	418,13	420,99	386,78
25,00	56,67	0,87	0,04	2,04	1044,28	2257,56	1,42	0,0459	99,24	388,59	420,23	421,28	388,59
28,33	61,11	0,87	0,05	2,17	1141,34	2486,99	1,51	0,00	110,36	390,34	422,20	422,20	390,34
31,67	65,56	0,87	0,05	2,38	1244,92	2733,38	1,66	0,00	121,51	392,02	424,06	424,06	392,02
35,00	70,00	0,87	0,06	2,60	1355,28	2997,65	1,81	0,00	133,65	393,63	425,79	425,79	393,63
5,00	30,00	0,88	0,02	1,21	584,29	1192,30	0,85	0,1209	49,71	381,94	411,98	416,99	381,94
8,33	34,44	0,88	0,03	1,30	647,63	1336,40	0,91	0,0933	55,95	383,95	414,56	418,07	383,95
11,67	38,89	0,88	0,03	1,39	715,98	1492,97	0,97	0,0581	62,88	385,92	417,04	419,02	385,92
15,00	43,33	0,88	0,03	1,48	789,57	1662,66	1,03	0,0139	70,56	387,82	419,40	419,83	387,82
18,33	47,78	0,89	0,04	1,62	868,65	1846,17	1,13	0,00	78,38	389,68	421,66	421,66	389,68
21,67	52,22	0,89	0,04	1,79	953,47	2044,22	1,25	0,00	86,65	391,47	423,80	423,80	391,47
25,00	56,67	0,89	0,04	1,98	1044,28	2257,56	1,38	0,00	95,65	393,20	425,82	425,82	393,20
28,33	61,11	0,89	0,05	2,18	1141,34	2486,99	1,52	0,00	105,46	394,87	427,72	427,72	394,87
31,67	65,56	0,90	0,05	2,39	1244,92	2733,38	1,66	0,00	116,15	396,46	429,49	429,49	396,46
35,00	70,00	0,90	0,05	2,61	1355,28	2997,65	1,82	0,00	127,80	397,98	431,12	431,12	397,98
5,00	30,00	0,90	0,02	1,04	584,29	1192,30	0,73	0,00	49,35	387,02	417,97	417,97	387,02
8,33	34,44	0,90	0,03	1,17	647,63	1336,40	0,82	0,00	54,96	388,96	420,49	420,49	388,96



FINAL PROJECT

Date: 19.06.2014

Page: 43

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

11,67	38,89	0,91	0,03	1,31	715,98	1492,97	0,91	0,00	61,08	390,84	422,91	422,91	390,84
15,00	43,33	0,91	0,03	1,46	789,57	1662,66	1,02	0,00	67,77	392,68	425,21	425,21	392,68
18,33	47,78	0,91	0,03	1,62	868,65	1846,17	1,13	0,00	75,05	394,45	427,40	427,40	394,45
21,67	52,22	0,91	0,04	1,80	953,47	2044,22	1,25	0,00	82,99	396,17	429,46	429,46	396,17
25,00	56,67	0,92	0,04	1,98	1044,28	2257,56	1,38	0,00	91,65	397,82	431,41	431,41	397,82
28,33	61,11	0,92	0,04	2,18	1141,34	2486,99	1,52	0,00	101,08	399,40	433,23	433,23	399,40
31,67	65,56	0,92	0,05	2,39	1244,92	2733,38	1,67	0,00	111,36	400,90	434,91	434,91	400,90
35,00	70,00	0,92	0,05	2,62	1355,28	2997,65	1,83	0,00	122,55	402,33	436,47	436,47	402,33
5,00	30,00	0,93	0,02	1,05	584,29	1192,30	0,73	0,00	47,31	392,09	423,95	423,95	392,09
8,33	34,44	0,93	0,03	1,17	647,63	1336,40	0,82	0,00	52,71	393,96	426,42	426,42	393,96
11,67	38,89	0,93	0,03	1,31	715,98	1492,97	0,92	0,00	58,61	395,77	428,78	428,78	395,77
15,00	43,33	0,93	0,03	1,47	789,57	1662,66	1,02	0,00	65,04	397,53	431,02	431,02	397,53
18,33	47,78	0,94	0,03	1,63	868,65	1846,17	1,13	0,00	72,06	399,23	433,14	433,14	399,23
21,67	52,22	0,94	0,04	1,80	953,47	2044,22	1,26	0,00	79,71	400,86	435,13	435,13	400,86
25,00	56,67	0,94	0,04	1,99	1044,28	2257,56	1,39	0,00	88,04	402,43	437,01	437,01	402,43
28,33	61,11	0,94	0,04	2,19	1141,34	2486,99	1,53	0,00	97,11	403,92	438,77	438,77	403,92
31,67	65,56	0,95	0,05	2,41	1244,92	2733,38	1,68	0,00	106,98	405,34	440,41	440,41	405,34
35,00	70,00	0,95	0,05	2,64	1355,28	2997,65	1,84	0,00	117,73	406,67	441,92	441,92	406,67
5,00	30,00	0,95	0,02	1,05	584,29	1192,30	0,73	0,00	45,47	397,16	429,94	429,94	397,16
8,33	34,44	0,95	0,02	1,18	647,63	1336,40	0,82	0,00	50,68	398,96	432,35	432,35	398,96
11,67	38,89	0,96	0,03	1,32	715,98	1492,97	0,92	0,00	56,37	400,70	434,65	434,65	400,70
15,00	43,33	0,96	0,03	1,47	789,57	1662,66	1,02	0,00	62,58	402,38	436,85	436,85	402,38
18,33	47,78	0,96	0,03	1,63	868,65	1846,17	1,14	0,00	69,34	404,00	438,92	438,92	404,00



FINAL PROJECT

Date: **19.06.2014**

Page: **44**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

21,67	52,22	0,96	0,04	1,81	953,47	2044,22	1,26	0,00	76,70	405,56	440,89	440,89	405,56
25,00	56,67	0,97	0,04	2,00	1044,28	2257,56	1,39	0,00	84,72	407,04	442,72	442,72	407,04
28,33	61,11	0,97	0,04	2,21	1141,34	2486,99	1,54	0,00	93,44	408,45	444,44	444,44	408,45
31,67	65,56	0,97	0,05	2,42	1244,92	2733,38	1,69	0,00	102,95	409,78	446,02	446,02	409,78
35,00	70,00	0,97	0,05	2,66	1355,28	2997,65	1,85	0,00	113,29	411,02	447,46	447,46	411,02
5,00	30,00	0,98	0,02	1,05	584,29	1192,30	0,73	0,00	43,78	402,23	436,00	436,00	402,23
8,33	34,44	0,98	0,02	1,18	647,63	1336,40	0,82	0,00	48,81	403,96	438,40	438,40	403,96
11,67	38,89	0,98	0,03	1,33	715,98	1492,97	0,92	0,00	54,30	405,63	440,68	440,68	405,63
15,00	43,33	0,98	0,03	1,48	789,57	1662,66	1,03	0,00	60,28	407,23	442,84	442,84	407,23
18,33	47,78	0,99	0,03	1,65	868,65	1846,17	1,15	0,00	66,80	408,78	444,88	444,88	408,78
21,67	52,22	0,99	0,03	1,83	953,47	2044,22	1,27	0,00	73,90	410,25	446,79	446,79	410,25
25,00	56,67	0,99	0,04	2,02	1044,28	2257,56	1,41	0,00	81,63	411,65	448,58	448,58	411,65
28,33	61,11	0,99	0,04	2,23	1141,34	2486,99	1,55	0,00	90,05	412,98	450,23	450,23	412,98
31,67	65,56	1,00	0,05	2,45	1244,92	2733,38	1,71	0,00	99,21	414,22	451,75	451,75	414,22
35,00	70,00	1,00	0,05	2,69	1355,28	2997,65	1,87	0,00	109,18	415,37	453,12	453,12	415,37



FINAL PROJECT

Date: 19.06.2014

Page: 45

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.7.1 Summary R22--- 5000 rpm, 11.4 cc/rev

Table 25-Summary R22- 5000 rpm, 11.4 cc/rev-cycle 1

	mref [g/s]	flow (l/min)	P1 (kPa)	P2	Q (kW)	Qres (kW)	desnsity after resistance	h1	h2	h3	h4
min	21,69	1,04	584,29	1192,30	0,73	0,0000	43,78	356,58	382,06	416,99	356,58
max	63,26	4,03	1355,28	2997,65	2,81	1,1453	139,91	415,37	453,12	453,12	415,37
X1_para minimo	0,98	0,90	0,75	0,75	0,90	0,8687	0,98	0,75	0,75	0,75	0,75
X1_para maximo	0,77	0,77	0,77	0,77	0,77	0,7652	0,77	1,00	1,00	1,00	1,00



FINAL PROJECT

Date: 19.06.2014

Page: 46

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.8 REFRIGERANT R 22 --- 3000 rpm, 7 cc/rev

Table 26- R22- 3000 rpm, 7 cc/rev-cycle 1

T1	T2	X1	mref	flow_l_min	P1	P2	Q	Qres	desnsity after resistance	h1	h2	h3	h4
5,00	30,00	0,75	0,01	0,90	584,29	1192,30	0,63	0,3616	49,71	356,58	382,06	416,99	356,58
8,33	34,44	0,75	0,01	0,97	647,63	1336,40	0,67	0,3780	55,95	358,95	384,91	418,07	358,95
11,67	38,89	0,76	0,01	1,04	715,98	1492,97	0,72	0,3928	62,88	361,28	387,68	419,02	361,28
15,00	43,33	0,76	0,01	1,11	789,57	1662,66	0,77	0,4054	70,56	363,56	390,37	419,83	363,56
18,33	47,78	0,76	0,02	1,18	868,65	1846,17	0,82	0,4151	79,10	365,81	392,96	420,50	365,81
21,67	52,22	0,76	0,02	1,25	953,47	2044,22	0,87	0,4210	88,61	368,00	395,46	420,99	368,00
25,00	56,67	0,77	0,02	1,32	1044,28	2257,56	0,92	0,4219	99,24	370,15	397,86	421,28	370,15
28,33	61,11	0,77	0,02	1,39	1141,34	2486,99	0,97	0,4165	111,17	372,24	400,16	421,35	372,24
31,67	65,56	0,77	0,02	1,44	1244,92	2733,38	1,00	0,4027	124,63	374,27	402,36	421,16	374,27
35,00	70,00	0,77	0,02	1,49	1355,28	2997,65	1,04	0,3781	139,91	376,24	404,44	420,67	376,24
5,00	30,00	0,78	0,01	0,80	584,29	1192,30	0,55	0,2901	49,71	361,65	388,04	416,99	361,65
8,33	34,44	0,78	0,01	0,86	647,63	1336,40	0,60	0,3006	55,95	363,95	390,84	418,07	363,95
11,67	38,89	0,78	0,01	0,92	715,98	1492,97	0,64	0,3092	62,88	366,21	393,55	419,02	366,21
15,00	43,33	0,78	0,01	0,98	789,57	1662,66	0,69	0,3154	70,56	368,42	396,17	419,83	368,42
18,33	47,78	0,79	0,01	1,05	868,65	1846,17	0,73	0,3184	79,10	370,58	398,70	420,50	370,58
21,67	52,22	0,79	0,02	1,11	953,47	2044,22	0,77	0,3175	88,61	372,69	401,12	420,99	372,69



FINAL PROJECT

Date: 19.06.2014

Page: 47

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

25,00	56,67	0,79	0,02	1,17	1044,28	2257,56	0,81	0,3114	99,24	374,76	403,45	421,28	374,76
28,33	61,11	0,79	0,02	1,22	1141,34	2486,99	0,85	0,2989	111,17	376,76	405,67	421,35	376,76
31,67	65,56	0,80	0,02	1,27	1244,92	2733,38	0,88	0,2780	124,63	378,71	407,78	421,16	378,71
35,00	70,00	0,80	0,02	1,30	1355,28	2997,65	0,91	0,2463	139,91	380,59	409,78	420,67	380,59
5,00	30,00	0,80	0,01	0,70	584,29	1192,30	0,49	0,2230	49,71	366,73	394,03	416,99	366,73
8,33	34,44	0,80	0,01	0,75	647,63	1336,40	0,53	0,2279	55,95	368,95	396,77	418,07	368,95
11,67	38,89	0,81	0,01	0,81	715,98	1492,97	0,56	0,2307	62,88	371,13	399,42	419,02	371,13
15,00	43,33	0,81	0,01	0,86	789,57	1662,66	0,60	0,2308	70,56	373,27	401,98	419,83	373,27
18,33	47,78	0,81	0,01	0,92	868,65	1846,17	0,64	0,2276	79,10	375,35	404,44	420,50	375,35
21,67	52,22	0,81	0,02	0,97	953,47	2044,22	0,68	0,2201	88,61	377,39	406,79	420,99	377,39
25,00	56,67	0,82	0,02	1,02	1044,28	2257,56	0,71	0,2075	99,24	379,37	409,04	421,28	379,37
28,33	61,11	0,82	0,02	1,06	1141,34	2486,99	0,74	0,1882	111,17	381,29	411,18	421,35	381,29
31,67	65,56	0,82	0,02	1,10	1244,92	2733,38	0,77	0,1605	124,63	383,15	413,21	421,16	383,15
35,00	70,00	0,82	0,02	1,13	1355,28	2997,65	0,78	0,1220	139,91	384,94	415,11	420,67	384,94
5,00	30,00	0,83	0,01	0,61	584,29	1192,30	0,43	0,1600	49,71	371,80	400,01	416,99	371,80
8,33	34,44	0,83	0,01	0,66	647,63	1336,40	0,46	0,1596	55,95	373,95	402,70	418,07	373,95
11,67	38,89	0,83	0,01	0,70	715,98	1492,97	0,49	0,1568	62,88	376,06	405,29	419,02	376,06
15,00	43,33	0,83	0,01	0,75	789,57	1662,66	0,52	0,1512	70,56	378,12	407,79	419,83	378,12
18,33	47,78	0,84	0,01	0,80	868,65	1846,17	0,56	0,1420	79,10	380,13	410,18	420,50	380,13
21,67	52,22	0,84	0,02	0,84	953,47	2044,22	0,59	0,1284	88,61	382,08	412,46	420,99	382,08
25,00	56,67	0,84	0,02	0,88	1044,28	2257,56	0,61	0,1094	99,24	383,98	414,63	421,28	383,98
28,33	61,11	0,84	0,02	0,92	1141,34	2486,99	0,64	0,0837	111,17	385,82	416,69	421,35	385,82
31,67	65,56	0,85	0,02	0,94	1244,92	2733,38	0,66	0,0496	124,63	387,59	418,63	421,16	387,59



FINAL PROJECT

Date: 19.06.2014

Page: 48

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

35,00	70,00	0,85	0,02	0,96	1355,28	2997,65	0,67	0,0047	139,91	389,29	420,45	420,67	389,29
5,00	30,00	0,85	0,01	0,53	584,29	1192,30	0,37	0,1006	49,71	376,87	406,00	416,99	376,87
8,33	34,44	0,85	0,01	0,57	647,63	1336,40	0,39	0,0952	55,95	378,95	408,63	418,07	378,95
11,67	38,89	0,86	0,01	0,61	715,98	1492,97	0,42	0,0872	62,88	380,99	411,16	419,02	380,99
15,00	43,33	0,86	0,01	0,65	789,57	1662,66	0,45	0,0761	70,56	382,97	413,59	419,83	382,97
18,33	47,78	0,86	0,01	0,68	868,65	1846,17	0,48	0,0612	79,10	384,90	415,92	420,50	384,90
21,67	52,22	0,86	0,01	0,72	953,47	2044,22	0,50	0,0418	88,61	386,78	418,13	420,99	386,78
25,00	56,67	0,87	0,02	0,75	1044,28	2257,56	0,52	0,0169	99,24	388,59	420,23	421,28	388,59
28,33	61,11	0,87	0,02	0,80	1141,34	2486,99	0,56	0,00	110,36	390,34	422,20	422,20	390,34
31,67	65,56	0,87	0,02	0,88	1244,92	2733,38	0,61	0,00	121,51	392,02	424,06	424,06	392,02
35,00	70,00	0,87	0,02	0,96	1355,28	2997,65	0,67	0,00	133,65	393,63	425,79	425,79	393,63
5,00	30,00	0,88	0,01	0,45	584,29	1192,30	0,31	0,0445	49,71	381,94	411,98	416,99	381,94
8,33	34,44	0,88	0,01	0,48	647,63	1336,40	0,33	0,0344	55,95	383,95	414,56	418,07	383,95
11,67	38,89	0,88	0,01	0,51	715,98	1492,97	0,36	0,0214	62,88	385,92	417,04	419,02	385,92
15,00	43,33	0,88	0,01	0,54	789,57	1662,66	0,38	0,0051	70,56	387,82	419,40	419,83	387,82
18,33	47,78	0,89	0,01	0,60	868,65	1846,17	0,42	0,00	78,38	389,68	421,66	421,66	389,68
21,67	52,22	0,89	0,01	0,66	953,47	2044,22	0,46	0,00	86,65	391,47	423,80	423,80	391,47
25,00	56,67	0,89	0,02	0,73	1044,28	2257,56	0,51	0,00	95,65	393,20	425,82	425,82	393,20
28,33	61,11	0,89	0,02	0,80	1141,34	2486,99	0,56	0,00	105,46	394,87	427,72	427,72	394,87
31,67	65,56	0,90	0,02	0,88	1244,92	2733,38	0,61	0,00	116,15	396,46	429,49	429,49	396,46
35,00	70,00	0,90	0,02	0,96	1355,28	2997,65	0,67	0,00	127,80	397,98	431,12	431,12	397,98
5,00	30,00	0,90	0,01	0,38	584,29	1192,30	0,27	0,00	49,35	387,02	417,97	417,97	387,02
8,33	34,44	0,90	0,01	0,43	647,63	1336,40	0,30	0,00	54,96	388,96	420,49	420,49	388,96



FINAL PROJECT

Date: **19.06.2014**

Page: **49**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

11,67	38,89	0,91	0,01	0,48	715,98	1492,97	0,34	0,00	61,08	390,84	422,91	422,91	390,84
15,00	43,33	0,91	0,01	0,54	789,57	1662,66	0,38	0,00	67,77	392,68	425,21	425,21	392,68
18,33	47,78	0,91	0,01	0,60	868,65	1846,17	0,42	0,00	75,05	394,45	427,40	427,40	394,45
21,67	52,22	0,91	0,01	0,66	953,47	2044,22	0,46	0,00	82,99	396,17	429,46	429,46	396,17
25,00	56,67	0,92	0,02	0,73	1044,28	2257,56	0,51	0,00	91,65	397,82	431,41	431,41	397,82
28,33	61,11	0,92	0,02	0,80	1141,34	2486,99	0,56	0,00	101,08	399,40	433,23	433,23	399,40
31,67	65,56	0,92	0,02	0,88	1244,92	2733,38	0,61	0,00	111,36	400,90	434,91	434,91	400,90
35,00	70,00	0,92	0,02	0,97	1355,28	2997,65	0,67	0,00	122,55	402,33	436,47	436,47	402,33
5,00	30,00	0,93	0,01	0,39	584,29	1192,30	0,27	0,00	47,31	392,09	423,95	423,95	392,09
8,33	34,44	0,93	0,01	0,43	647,63	1336,40	0,30	0,00	52,71	393,96	426,42	426,42	393,96
11,67	38,89	0,93	0,01	0,48	715,98	1492,97	0,34	0,00	58,61	395,77	428,78	428,78	395,77
15,00	43,33	0,93	0,01	0,54	789,57	1662,66	0,38	0,00	65,04	397,53	431,02	431,02	397,53
18,33	47,78	0,94	0,01	0,60	868,65	1846,17	0,42	0,00	72,06	399,23	433,14	433,14	399,23
21,67	52,22	0,94	0,01	0,66	953,47	2044,22	0,46	0,00	79,71	400,86	435,13	435,13	400,86
25,00	56,67	0,94	0,01	0,73	1044,28	2257,56	0,51	0,00	88,04	402,43	437,01	437,01	402,43
28,33	61,11	0,94	0,02	0,81	1141,34	2486,99	0,56	0,00	97,11	403,92	438,77	438,77	403,92
31,67	65,56	0,95	0,02	0,89	1244,92	2733,38	0,62	0,00	106,98	405,34	440,41	440,41	405,34
35,00	70,00	0,95	0,02	0,97	1355,28	2997,65	0,68	0,00	117,73	406,67	441,92	441,92	406,67
5,00	30,00	0,95	0,01	0,39	584,29	1192,30	0,27	0,00	45,47	397,16	429,94	429,94	397,16
8,33	34,44	0,95	0,01	0,43	647,63	1336,40	0,30	0,00	50,68	398,96	432,35	432,35	398,96
11,67	38,89	0,96	0,01	0,49	715,98	1492,97	0,34	0,00	56,37	400,70	434,65	434,65	400,70
15,00	43,33	0,96	0,01	0,54	789,57	1662,66	0,38	0,00	62,58	402,38	436,85	436,85	402,38
18,33	47,78	0,96	0,01	0,60	868,65	1846,17	0,42	0,00	69,34	404,00	438,92	438,92	404,00



FINAL PROJECT

Date: **19.06.2014**

Page: **50**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

21,67	52,22	0,96	0,01	0,67	953,47	2044,22	0,46	0,00	76,70	405,56	440,89	440,89	405,56
25,00	56,67	0,97	0,01	0,74	1044,28	2257,56	0,51	0,00	84,72	407,04	442,72	442,72	407,04
28,33	61,11	0,97	0,02	0,81	1141,34	2486,99	0,57	0,00	93,44	408,45	444,44	444,44	408,45
31,67	65,56	0,97	0,02	0,89	1244,92	2733,38	0,62	0,00	102,95	409,78	446,02	446,02	409,78
35,00	70,00	0,97	0,02	0,98	1355,28	2997,65	0,68	0,00	113,29	411,02	447,46	447,46	411,02
5,00	30,00	0,98	0,01	0,39	584,29	1192,30	0,27	0,00	43,78	402,23	436,00	436,00	402,23
8,33	34,44	0,98	0,01	0,44	647,63	1336,40	0,30	0,00	48,81	403,96	438,40	438,40	403,96
11,67	38,89	0,98	0,01	0,49	715,98	1492,97	0,34	0,00	54,30	405,63	440,68	440,68	405,63
15,00	43,33	0,98	0,01	0,55	789,57	1662,66	0,38	0,00	60,28	407,23	442,84	442,84	407,23
18,33	47,78	0,99	0,01	0,61	868,65	1846,17	0,42	0,00	66,80	408,78	444,88	444,88	408,78
21,67	52,22	0,99	0,01	0,67	953,47	2044,22	0,47	0,00	73,90	410,25	446,79	446,79	410,25
25,00	56,67	0,99	0,01	0,74	1044,28	2257,56	0,52	0,00	81,63	411,65	448,58	448,58	411,65
28,33	61,11	0,99	0,02	0,82	1141,34	2486,99	0,57	0,00	90,05	412,98	450,23	450,23	412,98
31,67	65,56	1,00	0,02	0,90	1244,92	2733,38	0,63	0,00	99,21	414,22	451,75	451,75	414,22
35,00	70,00	1,00	0,02	0,99	1355,28	2997,65	0,69	0,00	109,18	415,37	453,12	453,12	415,37



FINAL PROJECT

Date: 19.06.2014

Page: 51

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.8.1 Summary R 22 ---3000 rpm, 7 cc/rev

Table 27-Summary R22- 3000 rpm, 7cc/rev- cycle 1

	mref [g/s]	flow (l/min)	P1 (kPa)	P2	Q (kW)	Qres (kW)	desnsity after resistance	h1	h2	h3	h4
min	7,99	0,38	584,29	1192,30	0,27	0,0000	43,78	356,58	382,06	416,99	356,58
max	23,31	1,49	1355,28	2997,65	1,04	0,4219	139,91	415,37	453,12	453,12	415,37
X1_para minimo	0,98	0,90	0,75	0,75	0,90	0,8687	0,98	0,75	0,75	0,75	0,75
X1_para maximo	0,77	0,77	0,77	0,77	0,77	0,7652	0,77	1,00	1,00	1,00	1,00



FINAL PROJECT

Date: 19.06.2014

Page: 52

PROJECT:
"Compressors test live bench under wet compression conditions"

PLANES:
3

ANNEX II: SECOND STAGE

The search of the equipment had multiple stages, since the thermodynamic cycle changed continuously.

The followings tables represents a part of the

A useful, and well employed website was "RS COMPONENTS" (<http://es.rs-online.com/web/>)

1 PRESSURE SENSORS

Table 28-Pressure sensors

€	Ref. AMI DATA	Fabricant	P. MIN (bar)	P. MAX (bar)	Accuracy	Medium	AO	Power supply	Temp MIN	Temp MAX
111,912 9	455-4646	Gems Sensors	0	25	0,25	--	4 -> 20 mA	10->36 Vdc	-40	120
115,240 4	742-0978	Telemecanique	0	25	--	Aire, Agua,gas, líquido de refrigeración	0 -> 10 V	24 Vac/dc	-30	100
<u>115,240</u> <u>4</u>	<u>742-0969</u>	<u>Telemecanique</u>	<u>0</u>	<u>25</u>	<u>--</u>	<u>Aire,</u> <u>Agua,gas,</u> <u>líquido de</u> <u>refrigeración</u>	<u>4 -> 20</u> <u>mA</u>	<u>24 Vac/dc</u>	<u>-30</u>	<u>100</u>
115,240 4	742-0971	Telemecanique	0	25	--	Aire, Agua,gas, líquido de refrigeración	4 -> 20 mA	24 Vac/dc	-30	100
133,354 1	739-6771	Sick	0	25	0,25%	Líquido, gas	4 -> 20 mA	8->30 Vdc	0	80
225,580 3	455-4567	Gems Sensors	0	25	0,25%	Líquido,gas	4 -> 20 mA	7->35 Vdc	-40	100

"rs-online.com"

The maximum pressure considered at the first stages of the project was 25 bar (it was only considered the R134A refrigerant, and a lower action range was specified).



FINAL PROJECT

Date: 19.06.2014

Page: 53

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2 TEMPERATURE SENSORS

2.1 THERMORESISTANCES

Table 29-Thermoresistances

€	Ref. AMIDATA	Fabricant	TYPE	Temp. MIN	Temp. MAX	Diam. (mm)	Length (mm)	ACCURACY
5,0336	362-9840	RS	PT100	-50	500	--	2,3	CLASE B
5,4813	362-9913	RS	PT1000	-50	500	--	10	CLASE B
7,8771	362-9834	RS	PT100	-50	400	--	2,3	CLASE A
8,2885	181-2012	Correge	PT100	-50	600	2	2,3	--

"es.rs-online.com"

At first, PT100 sensors were considered for their linear response. In the table, the third component is highlighted since the class A is the more accurate (± 0.15 °C).

3 WATER FLUX

Table 30- Water flux

€	Ref. AMIDAT A	Fabricante	Type	Power supply	Q. MIN	Q. MAX	Diameter	P. MAX	Temperature
202,07	725-9969	Cynergy 3	Sensor/ Interruptor sin indicador	7,5->26 Vdc	0,4 l/min	8 l/min	10mm	10	-10 ->85
47,35	616-2693	Gems Sensors	Sensor/interruptor sin indicador	5 → 24 Vdc	0,119 l/min	2,925 l/min	6,35 mm	24 bar	-20-> 100
132,02	395-7173	Gems Sensors	Sensor/interruptor sin indicador	220 V	0 l/min	55 l/min	3/8 pulg	50 bar	90

"es.rs-online.com"



FINAL PROJECT

Date: 19.06.2014

Page: 54

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

4 ELECTRONIC EXPANSION VALVE

According to the first calculations, the maximum pressure to be achieved was 22 bars, so the DANFOSS (ETS 6-25) expansion valve, that could achieve up to 35 bars of pressure difference.

However an offer directly from DANFOSS was not possible so, one of their suppliers was contacted (PEKOMARK).

Table 31-Electronic expansion valve

€	Model	Temperature (fluid)	Temperature (ambient)	kW	Pressure. max (bar)	Diff pressure	Max reverse pressure	Code
	ETS 6 - 25	(-30°C-70°C)	(-30°C-70°C)	15,3	47	35	22	034G5035

4.1 PECOMARK

They have made an offer for the condenser and the expansion valve (drivers and electronic included)).

Table 32- Pekomark

CODE	UDS.	DESCRIPTION	€
428075	1	VALV. EXPAN. ELECTRONICA CAREL E2V05BSF00	81.4
428313	1	TRANSMISOR PRESION CAREL SPKT0013R0	33.04
428544	1	SONDA NTC CAREL NTC030HF01/WF00	5.94
428576	1	TRANSFORMADOR CARRIL DIN TRADRFE240	30.64
428579	1	DRIVER EVO PARA EEV CAREL EVD0000E50	92.41
428670	1	CABLE CONECTOR 2MTS CAREL SPKC002310	5.27
428699	1	CABLE APANTALLADO CAREL E2VCABS600	18.48
SUMA:			€ 515.67



FINAL PROJECT

Date: 19.06.2014

Page: 55

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

5 VARIABLE SPEED PUMP

5.1 EBARA

Since the water flux needed is very low, they suggest the EGO pumps. Those pump are specialized in low fluxes.

Besides, the "EGO ROSCADAS" have an extra version "ER" that include an input of 0-10 V to control the flux created. There are also, the "EGO EASSY" (more complete) that include as well a control input signal.

BUDGET 380-480 € (sin iva)

5.2 PRODEL

A continuous current pump that Works 0-7 V. Its maximum flux is 132L/h and to control it a continuous power supply is needed.

I_{max}=2.2 A T_{max}= 60°C connections 6mm diam connector spacing 50 mm

STE 2/50 579220

PRICE: 157.3€

DELIVERY TIME: 12 SEMANAS

*****If it is more tan 9ud, 5 weeks**

6 CONDENSER

6.1 JOSE NEGREDO

The enterprise "Jose Negredo" has prepared a Budget for the condenser.

PRICE: 255 €.

DELIVERY TIME: 3-4 SEMANAS

BSH ELECTRODOMESTICOS - Sra. Natalia Medina



FINAL PROJECT

Date: 19.06.2014

Page: 56

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

N/REF 140417809 - FECHA 14/03/14

PHE-Type	SL23-BR25-10-TL-COND	Hot side	Cold side
Flowrate	(kg/s) / (m3/h)	0,01	0,17
Inlet temperature	(°C)	40,00	15,00
Outlet Temp. Cond./Fluid	(°C)	40,00 (40)	25,00
Pressure drop / velocity	(bar)	0,01 / 0,64	0,02
Heat exchanged	(kW)	2	
Thermodynamic properties:		R134A	Water
Density	(kg/m ³)		997,71
Specific heat	(kJ/kg*K)		4,19
Thermal conductivity	(W/m*K)		0,60
Mean viscosity	(mPa*s)		1,01
Wall viscosity	(mPa*s)		0,66
Fouling factors	(m ² *K/kW)		0,64
Dimensioning factor	%	213,20	
Inlet branch		F1	F3
Outlet branch		F4	F2

Design of Frame / Plates:

Plate arrangement (passes*channel)		1	x	4	+	0	x	0
Plate arrangement (passes*channel)		1	x	5	+	0	x	0
Number of plates		10						
Effective heat surface	(m ²)	0,19						
Overall K-value Duty/Clean	(W/m ² *K)	528,80		1.656,20				
Plate material		0.4 mm		AISI 316				



FINAL PROJECT

Date: 19.06.2014

Page: 57

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

Gasket material / Max. temp. COPPER/BRAZED / 185

Max. design temperature (°C) 130,00

Max. Working/test pressure (bar) 25,00 32,50

Max. Differential pressure (bar) 25,00

Approval Sondex Standard

Liquid volume (liter) 0

Frame length (mm) 30

Net weight (kg) 2

Frame type BR

Connections HOT side : Ø22.3

Connections COLD side: 0.75 inch. Thread BSP

PRICE

210€ NETO

Cond. de entrega SIN IVA, PORTES INCLUIDOS EN PENINSULA, ENTREGA SOBRE CAMION

Condiciones de pago **30% al pedido, 70% a 60 días fecha de entrega

Plazo de entrega 3 semanas (+1 transporte), a confirmar por fábrica sobre pedido

Validez de la oferta 30 DIAS

Diseñado por: ROGER NEGRE

6.2 PECOMARK

Table 33-Pekomark-condenser

CODE	UDS.	DESCRIPTION	SUPPLIER	PRICE (€)
309010	1	INTERCAMBIADOR DE PLACAS SWEP B 5THX 10	PECOMARK	166.14



FINAL PROJECT

Date: 19.06.2014

Page: 58

PROJECT:
"Compressors test live bench under wet compression conditions"

PLANES:
3

ANNEX III: SOFTWARE SELECTION

1 LABVIEW

1.1 PROS

- *The control process can be done remotely, when both computers are connected to the intranet.*
- *Placing an external card, that is installed on the computer, or connected via USB, it can function as a data logger.*
- *LABVIEW allows the communication by different protocols, such as Ethernet (it is easier to find Pc's compatibles with this protocol).*
- *Depending on the signals to be treated, different external modules must be bought to its correct treatment.*
- *The behavior of the sensor or other components can be linearized, when their response curve is known.*
- *The data can be exported/imported easily using EXCEL.*
- *It has an intuitive and "automatic" HMI. It also dispose of a design option to look like SACADA.*
- *To employ the refrigerant thermodynamic properties, an excel file can be used or a graphic can be created (polyfit) and obtained the data needed.*
- *Technical support for the programming (Upna).*
- *No need to buy any software licenses, because of my student condition. If a modification in the program is needed, then it would have to buy a "debug" license (1800 €).*

1.2 CONS

- *If a modification in the program is required, a debug license is needed (1800 €).*



FINAL PROJECT

Date: 19.06.2014

Page: 59

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

- *Estella staff are not familiar with this software.*

2 SIMATIC- STEP 7

2.1 PROS

- *It is specialized in working in real time.*
- *The process can be controlled remotely, while both computers are connected to the same net.*
- *Depending on the type of signal, different external modules are bought.*
- *At the beginning, it was intended to use the PLC of the carousel (Estella). However, due to the amount of signals to treat it would be necessary two of these PLC (CPU 224), or the disposal of a higher level PLC (S7-300), to be able to control all the stations to be implemented in the test rig bench.*
- *Estella staff are familiar with this software, SIMATIC.*
- *Data can be export to an Excel file easily.*
- *The possibility of use the material present in Estella.*

2.2 CONS

- *There would be no technical support for the programation.*
- *License of WINCC needed.*
- *Programation of the interface human machine (HMI), the tactile panel.*



FINAL PROJECT

Date: 19.06.2014

Page: 60

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.3 WEIGHTED METHODS

Table 34-Software selection procedure

CHARACTERISTICS	WEIGHT	LABVIEW			SUM.	SIMATIC			SUM.
		High (3)	Med. (2)	Few (1)		High (3)	Med. (2)	Few (1)	
Simplicity	1	X			3		X		2
HMI	1	X			3			X	1
Import/ Export	3		X		6		X		6
Licence	2			X	2		X		4
Programation support	1		X		2		X		2
Staff knowledge	5			X	5		X		10
PRICE	4		X		8		X	X	6
SUM					29				31



ANNEX IV: IMPROVEMENTS

1 IMPROVEMENT: SAUNIER DUVAL PROPOSAL

As the chosen option cannot completely assure the pressure after the heating resistance, another expansion valve is added so the water flux don't modified the refrigerant pressure.

Firstly, the refrigerant experiments a raise of its pressure and temperature, once it enters to the compressor. So, the pressure difference achieve by the cycle can be fixed with this component.




Figure 18.-Improvement, S&D cycle



FINAL PROJECT

Date: 19.06.2014

Page: 62

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

The pressure difference achieved by the compressor, must be obtained by the combination of the two electronic expansion valves, so the pressure of the final operating point was the same as the pressure at the beginning of the cycle.

In the Figure 1, the difference between the operating points one and two (besides the pressure difference achieved by the compressor) can be appreciated by studying its abscise distance. This abscise distance represents an enthalpy difference which must be eliminated employing a condenser, in order to complete the cycle and make it stable.

In other words, the condenser will have to get a heat exchange to obtain in point four, the same enthalpy as in point one. This way, the only difference between the first operating point and the last one, would be the pressure difference that would be later corrected by the use of an electronic expansion valve.

1.1.1 OPERATING POINT TWO CALCULATIONS

The pressure and temperature are measured at this operating point (P_{2_EXP} and T_{2_EXP}) will be determined by the operating conditions of the compressor and fixed by the electronic expansion valves. Depending on the compressor type, it would be possible to obtain a bigger pressure ratio.

Temperature Sensor	T_{2_EXP}
Pressure sensor	P_{2_EXP}
Flux sensor	m_{REF} (refrigerant sensor)

For determining the zone in which the refrigerant works (biphasic or overheated steam), the temperature measured (T_{2_EXP}) can be compared with the saturation temperature at the pressure P_{2_EXP} .

With the values of the temperature and pressure, and the knowledge of the zone in which the refrigerant works, the enthalpy of the operating point 2 can be calculated. There are several ways to obtain its value (thermodynamic software programs...) one of them would be:

$$h_{2_EXP} = u_2 + P_{2_EXP} \cdot Y_2$$



FINAL PROJECT

Date: 19.06.2014

Page: 63

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

The specific volume must be calculated in order to use the previous formula. When the refrigerant is in the overheated steam zone, it is obtained using the thermodynamic and the values of pressure and temperature measured.

On the other hand, if the refrigerant is in the biphasic zone to calculate the specific volume the use of a thermodynamic software would be needed.

To avoid its use, some assumptions can be made: The process can be considered as isentropic, so the enthalpy at the operating point two can be calculate with the help of the entropy of the operating point one. This way, the enthalpy "h_{2s}" (enthalpy of the isentropic point two) would be obtained:

1. The operating point 2s and its enthalpy are calculated. To do so, theoretical values of point one must be used.

Knowing the entropy at the point 2s (s₁=s_{2s}), and the vaporization and liquefaction entropies the quality of the operating point it is calculated. Once the quality has been obtained, the enthalpy of the isentropic operating point 2 (h_{2s}) can be calculated.

2. With the isentropic efficiency of the compressor, and the values of the enthalpies of the points one, and the isentropic point two:

$$h_2 = h_1 + \frac{h_{2s} - h_1}{\eta_{iso}}$$

After the compressor, the refrigerant goes through the first electronic expansion valve decreasing its pressure and temperature. There would be another expansion valve, so between both of them the pressure difference generated by the compressor must be equated. Modifying the pressure drop proportion in the first and second valve, the pressure desired in the operating point three can be achieve at the same time that the operating point one and two are properly defined.

In the condenser, the enthalpies difference required to force the operating point four to have the same enthalpy as in the operating point one, it is achieved.

Finally, the second expansion valve recovers the pressure at the starting operating point.

One important aspect of this point is the possible biphasic nature of the refrigerant at the exit of the compressor. This aspect would be specially conditioned by the quality at the entering of the compressor.

The main problem of this biphasic nature is the impossibility (or the unviability) to measure the refrigerant flux. The value of the refrigerant flux, as it would be explained later, will be necessary to obtain the heat exchange between the refrigerant and the water, and therefore the water flux.



FINAL PROJECT

Date: 19.06.2014

Page: 64

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

1.1.2 OPERATING POINT ONE CALCULATIONS

As inputs, the quality and pressures of the compressor would be introduced.

With the stored data of the pressure and temperature of the first operating point, the thermodynamic tables can be employed to obtain the fusion and vaporization enthalpies to calculate the enthalpy at the operating point.

Temperature Sensor	T _{1EXP}
Pressure sensor	P _{1EXP}

$$h_1 = h_{f1} + x_1 \cdot (h_{g1} - h_{f1})$$

This enthalpy value, is the one to be achieved once that the cycle has been stabilized and Works according to the parameters fixed.

This value of enthalpy is also the one that, theoretically should be at the operating point four, since the expansion is considered an isenthalpic process.

1.1.3 CONTROL OF THE OPERATING POINT THREE AND FOUR

With the strangulation ratio of each expansion valve, the pressure of the operating points three and four can be fixed. With the expansion achieve by both valves, the pressure difference obtained by the compressor must be obtained. In other words, if the pressure difference caused by the compressor is 6 bars, then the sum of the pressure difference achieve by each expansion vale must also be 6 bars. However, the pressure drop ratio in each valve is not defined.

The drop pressure ratio can be used to fix the pressure of the operating points three and four. These operating points would have the same enthalpy values as the operating points two and one respectively speaking (due to the isenthalpic nature of the expansion process).

The values of pressure and temperature must be empirically checked so they reach the adequate values, to obtain the calculated enthalpies. Furthermore, thanks to the previous expansion of the condensation and the behavior of the refrigerant, there is a possibility to make the operating point three be in the overheated steam zone.



FINAL PROJECT

Date: 19.06.2014

Page: 65

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

Temperature Sensor	T _{3EXP} , T _{4EXP}
--------------------	---------------------------------------

Pressure sensor	P _{3EXP} , P _{4EXP}
-----------------	---------------------------------------

1.1.4 CONDENSER

Once that the operating points three and four have been fixed, with its enthalpy difference the necessary heat that must be exchanged (to reach the point 4) is calculated.

1. The difference of enthalpies that must be achieved by the cooling effect of the condenser in the refrigerant is known.

$$\Delta h = h_3 - h_4$$

2. This cooling effect will be conditioned by the water input temperature ($T_{w_{IN}}$) and by its flux. Studying the formulas, the heat exchanged between the refrigerant and the condenser water is:

$$\begin{aligned}\dot{Q} &= \dot{m}_{R134a} \cdot (h_3 - h_2) \\ \dot{Q} &= -\dot{m}_W \cdot C_p \cdot (T_{OUT_W} - T_{IN_W})\end{aligned}$$

To control the heat exchanged needed between the refrigerant and the water, two magnitudes can be used (according to the equations studied): The water input temperature of the condenser and the water flux.

Temperature Sensor	T _{w_{IN}} , T _{w_{OUT}}
--------------------	--

Flux sensor	m _w
-------------	----------------

As the thermodynamic magnitudes have an important thermal inertia, to control the heat exchanged it is better to modify the water flux instead its input temperature, because it would occasioned a faster response. For being able to change the water flux, a variable speed pump would have to be chosen.



FINAL PROJECT

Date: 19.06.2014

Page: 66

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

1.1.5 SECOND EXPANSION AND FINAL PROCESS

It has been achieved to obtain the same enthalpy value at the operating point four as the value in the first operating point. Therefore, to complete the cycle there is only one more process needed, an expansion to return to the first pressure value.

1.1.6 ADVANTAGES AND DISADVANTAGES

Developing this cycle, the pressures at the exit of the compressor and condenser are completely fixed and stabilized.

Other important aspect, is that with the first expansion process, the refrigerant could be displaced to the overheated steam zone so the measure of its flux refrigerant can be done. However it is not guarantee and could be useful to employ a heating resistance, as it was employed in the chosen cycle.

2 MODIFICATION




Figure 19-Thermodynamic components cycle



FINAL PROJECT

Date: 19.06.2014

Page: 67

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

Base on "Saunier & Duval cycle" it is added a heating resistance at the compressor outlet, so the refrigerant flux can be measured without any problems.

This would be a better option to be implemented, an in fact, is the one that would be developed during the followings months.

3 CALCULATIONS

3.1 "EES" CODE

"Functions"

"Enthalpy 2"

```
Function f_h2 (rend_iso; h1; h2s)
h2=h1+((h2s-h1)/rend_iso)
f_h2=h2
end
```

"Refrigerant flux"

```
function f_m_ref(rho_ref ; rend_vol ; rps ; displ)
m_ref=(rho_ref*displ*rps*rend_vol)/(1000000)
f_m_ref=m_ref
end
```

"Water flux"

```
function f_m_w(Q; Cp ;delta_T)
m_w=(Q/( Cp *delta_T))
f_m_w=m_w
end
```

"Compressor data"

```
displ=7 "cc"
rpm=3000

rps=rpm/60
rend_vol=0,9
```

" Displacement of the compressor"
" Revolutions per minute of the
compressor"
" Rev. per second"
" Assumption of constant volumetric
efficiency"



FINAL PROJECT

Date: 19.06.2014

Page: 68

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

rend_iso=0,5

" Assumption of constant isentropic efficiency"

"Water circuit data"

Cp=Cp(Water;T=Tout;P=P_atm) "kJ/kg-K"

" Cp of the water at a given temperature, Tout"

Tin=15 "°C"

" Input temperature of the water at the entering of the condenser"

Tout=25 "°C"

" Outout temperature of the water, at the exit of the condenser, after the heat exchange had taken place"

delta_T=(Tout-Tin) "K"

P_atm=101,3 "kPa"

"REFRIGERANT"

R\$='R134a'

"Refrigerant"

"INPUTS"

{T[1]=5 "°C"

" Temperature at the charging point of the

compressor"

x1=0,8

" Quality of the refrigerant at the entering of the

compressor"

T[2]= 70 "°C"

p=0,5

T[3]= p*(T[2]-T[1])+T[1]

" Temperature at the discharge point of the compressor"

P1sat=pressure(R\$;T=T[1]; x=1)

P2sat=pressure(R\$;T=T[2];x=1)

P3=pressure(R\$;T=T[3]; x=1)

"*****POINT 1*****"

h1=ENTHALPY(R\$; P=P1sat; x=x1)

s1=ENTROPY(R\$;P=P1sat ;x=x1)



FINAL PROJECT

Date: 19.06.2014

Page: 69

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

*****POINT 2 ISENTROPIC*****

s2s=s1
h2s=enthalpy(R\$,P=P2sat;s=s2s)

*****POINT 2***** DISCHARGE OF THE COMPRESSOR"

h2=f_h2 (rend_iso; h1; h2s)
T2_real=temperature(R\$;h=h2;P=P2sat)

*****POINT 2***** AFTER RESISTENCE"

T2_resist=T[2]+3
h2_resist=enthalpy(R\$;T=T2_resist;P=P2sat)

*****PUNTO 3*****AFTER THE EEV "

h3= h2_resist
{P3comp=pressure(R\$;T=T[3];h=h3)}

*****POINT 4***** AFTER THE CONDENSER"

h4=h1
T[4]=T[3]

*****HEAT EXCHANGE*****

delta_enthalpy=h3-h4

"Difference of enthalpies that must be obtained with the condenser, in order to return to the enthalpy state in POINT 1"

rho_ref=density(R\$; h=h1; P=P1sat)

"Density at the entering of the compressor, to calculate the flux"

rho_ref_after_resistance=density(R\$; h=h3; P=P2sat)"Density of the refrigerant gas, after the heating resistance, to dimensionate the refrigerant flux sensor"

m_ref=f_m_ref(rho_ref ; rend_vol ; rps ; displ)

"Call the function 'refrigerant flux' "



FINAL PROJECT

Date: 19.06.2014

Page: 70

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

$Q = m_{ref} * \Delta_{enthalpy}$ "kW"

"Heat exchange in the condenser"

$m_w = f_m_w(Q; C_p; \Delta_T)$
calculated heat"

"Water flux needed to exchange the

$\rho_{water} = \text{Density}(\text{Water}; T = T_{in}; P = P_{atm})$ "kg/m³" "Density of the water at a given , T_{in} ,
Temperature"

$flow_w_lit_min = m_w / \rho_{water} * 60000$
{ $flow_w_lit_h = flow_w_lit_min * 60$

"Water flux in liters per minute"

"Water flux in liters per hour"}"

*****CALOR RESISTENCIA*****

$\Delta_{h_res} = h_3 - h_2$

"Difference of enthalpies that must be
obtained with the heating resistance"

$Q_{res} = \Delta_{h_res} * m_{ref}$

" Heat flux that must be exchange
within the resistance and the refrigerant
flux, to fully evaporate the refrigerant"



FINAL PROJECT

Date: 19.06.2014

Page: 71

PROJECT:
"Compressors test live bench under wet compression conditions"

PLANES:
3

3.2 REFRIGERANT R134 A--> 5000 rpm, 11 cc/rev

Table 35-R134 A- 5000rpm, 11.4 cc/rev- improvement

T1	T2	T3	T4	X1	mref	flow_l_min	P1	P2	Q	Qres	h1	h2	h3	h4
5,00	30,00	17,50	17,50	0,75	0,02	1,82	349,90	770,64	1,27	0,80	204,66	228,59	269,83	204,66
8,33	34,44	21,39	21,39	0,75	0,02	2,00	392,28	873,87	1,39	0,87	207,69	232,05	272,04	207,69
11,67	38,89	25,28	25,28	0,76	0,02	2,19	438,48	987,17	1,53	0,93	210,71	235,43	274,15	210,71
15,00	43,33	29,17	29,17	0,76	0,03	2,39	488,70	1111,16	1,67	1,00	213,69	238,73	276,16	213,69
18,33	47,78	33,06	33,06	0,76	0,03	2,60	543,17	1246,48	1,81	1,07	216,63	241,95	278,06	216,63
21,67	52,22	36,94	36,94	0,76	0,03	2,82	602,12	1393,83	1,96	1,13	219,55	245,10	279,82	219,55
25,00	56,67	40,83	40,83	0,77	0,04	3,04	665,78	1553,90	2,12	1,19	222,43	248,17	281,43	222,43
28,33	61,11	44,72	44,72	0,77	0,04	3,26	734,40	1727,45	2,27	1,25	225,26	251,15	282,87	225,26
31,67	65,56	48,61	48,61	0,77	0,04	3,49	808,21	1915,28	2,43	1,30	228,06	254,04	284,11	228,06
35,00	70,00	52,50	52,50	0,77	0,05	3,71	887,47	2118,24	2,58	1,34	230,81	256,84	285,12	230,81
5,00	30,00	17,50	17,50	0,78	0,02	1,63	349,90	770,64	1,13	0,67	209,57	234,40	269,83	209,57
8,33	34,44	21,39	21,39	0,78	0,02	1,79	392,28	873,87	1,25	0,72	212,55	237,80	272,04	212,55
11,67	38,89	25,28	25,28	0,78	0,02	1,96	438,48	987,17	1,37	0,77	215,49	241,12	274,15	215,49
15,00	43,33	29,17	29,17	0,78	0,03	2,14	488,70	1111,16	1,49	0,82	218,40	244,37	276,16	218,40
18,33	47,78	33,06	33,06	0,79	0,03	2,33	543,17	1246,48	1,62	0,87	221,27	247,53	278,06	221,27
21,67	52,22	36,94	36,94	0,79	0,03	2,52	602,12	1393,83	1,76	0,92	224,11	250,61	279,82	224,11
25,00	56,67	40,83	40,83	0,79	0,03	2,72	665,78	1553,90	1,90	0,97	226,92	253,61	281,43	226,92



FINAL PROJECT

Date: 19.06.2014

Page: 72

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

28,33	61,11	44,72	44,72	0,79	0,04	2,92	734,40	1727,45	2,04	1,01	229,68	256,52	282,87	229,68
31,67	65,56	48,61	48,61	0,80	0,04	3,12	808,21	1915,28	2,17	1,04	232,39	259,33	284,11	232,39
35,00	70,00	52,50	52,50	0,80	0,05	3,31	887,47	2118,24	2,31	1,06	235,06	262,05	285,12	235,06
5,00	30,00	17,50	17,50	0,80	0,02	1,45	349,90	770,64	1,01	0,54	214,49	240,20	269,83	214,49
8,33	34,44	21,39	21,39	0,80	0,02	1,59	392,28	873,87	1,11	0,58	217,40	243,55	272,04	217,40
11,67	38,89	25,28	25,28	0,81	0,02	1,75	438,48	987,17	1,22	0,62	220,27	246,82	274,15	220,27
15,00	43,33	29,17	29,17	0,81	0,03	1,91	488,70	1111,16	1,33	0,66	223,11	250,00	276,16	223,11
18,33	47,78	33,06	33,06	0,81	0,03	2,07	543,17	1246,48	1,44	0,69	225,91	253,11	278,06	225,91
21,67	52,22	36,94	36,94	0,81	0,03	2,25	602,12	1393,83	1,56	0,73	228,68	256,12	279,82	228,68
25,00	56,67	40,83	40,83	0,82	0,03	2,42	665,78	1553,90	1,69	0,75	231,40	259,05	281,43	231,40
28,33	61,11	44,72	44,72	0,82	0,04	2,60	734,40	1727,45	1,81	0,78	234,09	261,89	282,87	234,09
31,67	65,56	48,61	48,61	0,82	0,04	2,78	808,21	1915,28	1,93	0,80	236,72	264,62	284,11	236,72
35,00	70,00	52,50	52,50	0,82	0,04	2,94	887,47	2118,24	2,05	0,80	239,30	267,26	285,12	239,30
5,00	30,00	17,50	17,50	0,83	0,02	1,28	349,90	770,64	0,89	0,42	219,41	246,00	269,83	219,41
8,33	34,44	21,39	21,39	0,83	0,02	1,41	392,28	873,87	0,98	0,45	222,25	249,30	272,04	222,25
11,67	38,89	25,28	25,28	0,83	0,02	1,54	438,48	987,17	1,08	0,47	225,05	252,51	274,15	225,05
15,00	43,33	29,17	29,17	0,83	0,02	1,69	488,70	1111,16	1,17	0,50	227,82	255,64	276,16	227,82
18,33	47,78	33,06	33,06	0,84	0,03	1,83	543,17	1246,48	1,28	0,52	230,55	258,68	278,06	230,55
21,67	52,22	36,94	36,94	0,84	0,03	1,99	602,12	1393,83	1,38	0,54	233,25	261,64	279,82	233,25
25,00	56,67	40,83	40,83	0,84	0,03	2,14	665,78	1553,90	1,49	0,55	235,89	264,49	281,43	235,89
28,33	61,11	44,72	44,72	0,84	0,04	2,30	734,40	1727,45	1,60	0,56	238,50	267,26	282,87	238,50
31,67	65,56	48,61	48,61	0,85	0,04	2,45	808,21	1915,28	1,71	0,56	241,05	269,92	284,11	241,05
35,00	70,00	52,50	52,50	0,85	0,04	2,60	887,47	2118,24	1,81	0,55	243,55	272,47	285,12	243,55



FINAL PROJECT

Date: 19.06.2014

Page: 73

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

5,00	30,00	17,50	17,50	0,85	0,02	1,12	349,90	770,64	0,78	0,31	224,33	251,80	269,83	224,33
8,33	34,44	21,39	21,39	0,85	0,02	1,24	392,28	873,87	0,86	0,33	227,10	255,05	272,04	227,10
11,67	38,89	25,28	25,28	0,86	0,02	1,35	438,48	987,17	0,94	0,34	229,83	258,21	274,15	229,83
15,00	43,33	29,17	29,17	0,86	0,02	1,48	488,70	1111,16	1,03	0,35	232,53	261,28	276,16	232,53
18,33	47,78	33,06	33,06	0,86	0,03	1,61	543,17	1246,48	1,12	0,36	235,19	264,26	278,06	235,19
21,67	52,22	36,94	36,94	0,86	0,03	1,74	602,12	1393,83	1,21	0,37	237,81	267,15	279,82	237,81
25,00	56,67	40,83	40,83	0,87	0,03	1,88	665,78	1553,90	1,31	0,37	240,38	269,94	281,43	240,38
28,33	61,11	44,72	44,72	0,87	0,04	2,01	734,40	1727,45	1,40	0,36	242,91	272,63	282,87	242,91
31,67	65,56	48,61	48,61	0,87	0,04	2,14	808,21	1915,28	1,49	0,34	245,38	275,21	284,11	245,38
35,00	70,00	52,50	52,50	0,87	0,04	2,27	887,47	2118,24	1,58	0,31	247,80	277,68	285,12	247,80
5,00	30,00	17,50	17,50	0,88	0,02	0,97	349,90	770,64	0,68	0,20	229,24	257,60	269,83	229,24
8,33	34,44	21,39	21,39	0,88	0,02	1,07	392,28	873,87	0,75	0,21	231,95	260,80	272,04	231,95
11,67	38,89	25,28	25,28	0,88	0,02	1,17	438,48	987,17	0,82	0,21	234,61	263,91	274,15	234,61
15,00	43,33	29,17	29,17	0,88	0,02	1,28	488,70	1111,16	0,89	0,21	237,24	266,92	276,16	237,24
18,33	47,78	33,06	33,06	0,89	0,03	1,39	543,17	1246,48	0,97	0,21	239,83	269,84	278,06	239,83
21,67	52,22	36,94	36,94	0,89	0,03	1,51	602,12	1393,83	1,05	0,20	242,38	272,66	279,82	242,38
25,00	56,67	40,83	40,83	0,89	0,03	1,62	665,78	1553,90	1,13	0,19	244,87	275,38	281,43	244,87
28,33	61,11	44,72	44,72	0,89	0,03	1,74	734,40	1727,45	1,21	0,17	247,32	278,00	282,87	247,32
31,67	65,56	48,61	48,61	0,90	0,04	1,85	808,21	1915,28	1,29	0,14	249,71	280,50	284,11	249,71
35,00	70,00	52,50	52,50	0,90	0,04	1,95	887,47	2118,24	1,36	0,09	252,04	282,89	285,12	252,04
5,00	30,00	17,50	17,50	0,90	0,02	0,83	349,90	770,64	0,58	0,10	234,16	263,40	269,83	234,16
8,33	34,44	21,39	21,39	0,90	0,02	0,92	392,28	873,87	0,64	0,10	236,80	266,55	272,04	236,80
11,67	38,89	25,28	25,28	0,91	0,02	1,00	438,48	987,17	0,70	0,09	239,40	269,60	274,15	239,40



FINAL PROJECT

Date: 19.06.2014

Page: 74

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

15,00	43,33	29,17	29,17	0,91	0,02	1,10	488,70	1111,16	0,76	0,08	241,96	272,56	276,16	241,96
18,33	47,78	33,06	33,06	0,91	0,02	1,19	543,17	1246,48	0,83	0,07	244,47	275,42	278,06	244,47
21,67	52,22	36,94	36,94	0,91	0,03	1,29	602,12	1393,83	0,90	0,05	246,94	278,17	279,82	246,94
25,00	56,67	40,83	40,83	0,92	0,03	1,39	665,78	1553,90	0,97	0,02	249,36	280,82	281,43	249,36
28,33	61,11	44,72	44,72	0,92	0,03	1,48	734,40	1727,45	1,03	-0,02	251,73	283,37	282,87	251,73
31,67	65,56	48,61	48,61	0,92	0,04	1,58	808,21	1915,28	1,10	-0,06	254,04	285,80	284,11	254,04
35,00	70,00	52,50	52,50	0,92	0,04	1,66	887,47	2118,24	1,16	-0,12	256,29	288,11	285,12	256,29
5,00	30,00	17,50	17,50	0,93	0,02	0,70	349,90	770,64	0,49	0,01	239,08	269,20	269,83	239,08
8,33	34,44	21,39	21,39	0,93	0,02	0,77	392,28	873,87	0,54	0,00	241,65	272,30	272,04	241,65
11,67	38,89	25,28	25,28	0,93	0,02	0,84	438,48	987,17	0,59	-0,02	244,18	275,30	274,15	244,18
15,00	43,33	29,17	29,17	0,93	0,02	0,92	488,70	1111,16	0,64	-0,04	246,67	278,20	276,16	246,67
18,33	47,78	33,06	33,06	0,94	0,02	1,00	543,17	1246,48	0,70	-0,07	249,11	280,99	278,06	249,11
21,67	52,22	36,94	36,94	0,94	0,03	1,08	602,12	1393,83	0,75	-0,10	251,51	283,68	279,82	251,51
25,00	56,67	40,83	40,83	0,94	0,03	1,16	665,78	1553,90	0,81	-0,14	253,85	286,27	281,43	253,85
28,33	61,11	44,72	44,72	0,94	0,03	1,24	734,40	1727,45	0,86	-0,19	256,14	288,74	282,87	256,14
31,67	65,56	48,61	48,61	0,95	0,04	1,31	808,21	1915,28	0,92	-0,25	258,37	291,09	284,11	258,37
35,00	70,00	52,50	52,50	0,95	0,04	1,38	887,47	2118,24	0,96	-0,32	260,54	293,32	285,12	260,54
5,00	30,00	17,50	17,50	0,95	0,02	0,57	349,90	770,64	0,40	-0,08	244,00	275,01	269,83	244,00
8,33	34,44	21,39	21,39	0,95	0,02	0,63	392,28	873,87	0,44	-0,10	246,50	278,05	272,04	246,50
11,67	38,89	25,28	25,28	0,96	0,02	0,69	438,48	987,17	0,48	-0,13	248,96	280,99	274,15	248,96
15,00	43,33	29,17	29,17	0,96	0,02	0,75	488,70	1111,16	0,52	-0,16	251,38	283,83	276,16	251,38
18,33	47,78	33,06	33,06	0,96	0,02	0,82	543,17	1246,48	0,57	-0,20	253,75	286,57	278,06	253,75
21,67	52,22	36,94	36,94	0,96	0,03	0,88	602,12	1393,83	0,62	-0,24	256,07	289,20	279,82	256,07



FINAL PROJECT

Date: 19.06.2014

Page: 75

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

25,00	56,67	40,83	40,83	0,97	0,03	0,95	665,78	1553,90	0,66	-0,29	258,34	291,71	281,43	258,34
28,33	61,11	44,72	44,72	0,97	0,03	1,01	734,40	1727,45	0,70	-0,35	260,55	294,11	282,87	260,55
31,67	65,56	48,61	48,61	0,97	0,03	1,07	808,21	1915,28	0,74	-0,43	262,70	296,38	284,11	262,70
35,00	70,00	52,50	52,50	0,97	0,04	1,11	887,47	2118,24	0,77	-0,51	264,78	298,53	285,12	264,78
5,00	30,00	17,50	17,50	0,98	0,01	0,45	349,90	770,64	0,31	-0,16	248,91	280,81	269,83	248,91
8,33	34,44	21,39	21,39	0,98	0,02	0,50	392,28	873,87	0,35	-0,20	251,35	283,80	272,04	251,35
11,67	38,89	25,28	25,28	0,98	0,02	0,54	438,48	987,17	0,38	-0,23	253,74	286,69	274,15	253,74
15,00	43,33	29,17	29,17	0,98	0,02	0,59	488,70	1111,16	0,41	-0,27	256,09	289,47	276,16	256,09
18,33	47,78	33,06	33,06	0,99	0,02	0,65	543,17	1246,48	0,45	-0,32	258,39	292,15	278,06	258,39
21,67	52,22	36,94	36,94	0,99	0,03	0,70	602,12	1393,83	0,48	-0,38	260,64	294,71	279,82	260,64
25,00	56,67	40,83	40,83	0,99	0,03	0,74	665,78	1553,90	0,52	-0,44	262,83	297,17	281,43	262,83
28,33	61,11	44,72	44,72	0,99	0,03	0,79	734,40	1727,45	0,55	-0,51	264,96	299,50	282,87	264,96
31,67	65,56	48,61	48,61	1,00	0,03	0,83	808,21	1915,28	0,58	-0,60	267,03	301,72	284,11	267,03
35,00	70,00	52,50	52,50	1,00	0,04	0,86	887,47	2118,24	0,60	-0,69	269,03	303,81	285,12	269,03



FINAL PROJECT

Date: 19.06.2014

Page: 76

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3.2.1 Summary R134 A--- 5000 rpm, 11.4 cc/rev

Table 36-Summary R134 A-5000rpm, 11.4 cc/rev- improvement

	mref [g/s]	flow (l/min)	P1 (kPa)	P2	P3	Q (kW)	Qres (kW)	h1	h2	h3	h4
min	14,99	0,45	349,90	770,64	560,271414	0,31	-0,69	204,66	228,59	269,83	204,66
max	47,55	3,71	887,47	2118,24	1502,85679	2,58	1,34	269,03	303,81	285,12	269,03
X1_para minimo	0,98	0,98	0,75	0,75	0,75	0,98	1,00	0,75	0,75	0,75	0,75
X1_para maximo	0,77	0,77	0,77	0,77	0,77	0,77	0,77	1,00	1,00	0,77	1,00



FINAL PROJECT

Date: 19.06.2014

Page: 77

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3.3 REFRIGERANT R 134A --> 3000rpm, 7 cc/rev

Table 37-R134 A- 3000rpm, 7 cc/rev- improvement

T1	T2	T3	T4	X1	mref	flow_l_min	P1	P2	Q	Qres	h1	h2	h3	h4
5,00	30,00	17,50	17,50	0,75	0,01	0,67	349,90	770,64	0,47	0,30	204,66	228,59	269,83	204,66
8,33	34,44	21,39	21,39	0,75	0,01	0,74	392,28	873,87	0,51	0,32	207,69	232,05	272,04	207,69
11,67	38,89	25,28	25,28	0,76	0,01	0,81	438,48	987,17	0,56	0,34	210,71	235,43	274,15	210,71
15,00	43,33	29,17	29,17	0,76	0,01	0,88	488,70	1111,16	0,61	0,37	213,69	238,73	276,16	213,69
18,33	47,78	33,06	33,06	0,76	0,01	0,96	543,17	1246,48	0,67	0,39	216,63	241,95	278,06	216,63
21,67	52,22	36,94	36,94	0,76	0,01	1,04	602,12	1393,83	0,72	0,42	219,55	245,10	279,82	219,55
25,00	56,67	40,83	40,83	0,77	0,01	1,12	665,78	1553,90	0,78	0,44	222,43	248,17	281,43	222,43
28,33	61,11	44,72	44,72	0,77	0,01	1,20	734,40	1727,45	0,84	0,46	225,26	251,15	282,87	225,26
31,67	65,56	48,61	48,61	0,77	0,02	1,29	808,21	1915,28	0,90	0,48	228,06	254,04	284,11	228,06
35,00	70,00	52,50	52,50	0,77	0,02	1,37	887,47	2118,24	0,95	0,50	230,81	256,84	285,12	230,81
5,00	30,00	17,50	17,50	0,78	0,01	0,60	349,90	770,64	0,42	0,25	209,57	234,40	269,83	209,57
8,33	34,44	21,39	21,39	0,78	0,01	0,66	392,28	873,87	0,46	0,26	212,55	237,80	272,04	212,55
11,67	38,89	25,28	25,28	0,78	0,01	0,72	438,48	987,17	0,50	0,28	215,49	241,12	274,15	215,49
15,00	43,33	29,17	29,17	0,78	0,01	0,79	488,70	1111,16	0,55	0,30	218,40	244,37	276,16	218,40
18,33	47,78	33,06	33,06	0,79	0,01	0,86	543,17	1246,48	0,60	0,32	221,27	247,53	278,06	221,27
21,67	52,22	36,94	36,94	0,79	0,01	0,93	602,12	1393,83	0,65	0,34	224,11	250,61	279,82	224,11



FINAL PROJECT

Date: 19.06.2014

Page: 78

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

25,00	56,67	40,83	40,83	0,79	0,01	1,00	665,78	1553,90	0,70	0,36	226,92	253,61	281,43	226,92
28,33	61,11	44,72	44,72	0,79	0,01	1,08	734,40	1727,45	0,75	0,37	229,68	256,52	282,87	229,68
31,67	65,56	48,61	48,61	0,80	0,02	1,15	808,21	1915,28	0,80	0,38	232,39	259,33	284,11	232,39
35,00	70,00	52,50	52,50	0,80	0,02	1,22	887,47	2118,24	0,85	0,39	235,06	262,05	285,12	235,06
5,00	30,00	17,50	17,50	0,80	0,01	0,53	349,90	770,64	0,37	0,20	214,49	240,20	269,83	214,49
8,33	34,44	21,39	21,39	0,80	0,01	0,59	392,28	873,87	0,41	0,21	217,40	243,55	272,04	217,40
11,67	38,89	25,28	25,28	0,81	0,01	0,64	438,48	987,17	0,45	0,23	220,27	246,82	274,15	220,27
15,00	43,33	29,17	29,17	0,81	0,01	0,70	488,70	1111,16	0,49	0,24	223,11	250,00	276,16	223,11
18,33	47,78	33,06	33,06	0,81	0,01	0,76	543,17	1246,48	0,53	0,25	225,91	253,11	278,06	225,91
21,67	52,22	36,94	36,94	0,81	0,01	0,83	602,12	1393,83	0,58	0,27	228,68	256,12	279,82	228,68
25,00	56,67	40,83	40,83	0,82	0,01	0,89	665,78	1553,90	0,62	0,28	231,40	259,05	281,43	231,40
28,33	61,11	44,72	44,72	0,82	0,01	0,96	734,40	1727,45	0,67	0,29	234,09	261,89	282,87	234,09
31,67	65,56	48,61	48,61	0,82	0,02	1,02	808,21	1915,28	0,71	0,29	236,72	264,62	284,11	236,72
35,00	70,00	52,50	52,50	0,82	0,02	1,08	887,47	2118,24	0,76	0,29	239,30	267,26	285,12	239,30
5,00	30,00	17,50	17,50	0,83	0,01	0,47	349,90	770,64	0,33	0,16	219,41	246,00	269,83	219,41
8,33	34,44	21,39	21,39	0,83	0,01	0,52	392,28	873,87	0,36	0,17	222,25	249,30	272,04	222,25
11,67	38,89	25,28	25,28	0,83	0,01	0,57	438,48	987,17	0,40	0,17	225,05	252,51	274,15	225,05
15,00	43,33	29,17	29,17	0,83	0,01	0,62	488,70	1111,16	0,43	0,18	227,82	255,64	276,16	227,82
18,33	47,78	33,06	33,06	0,84	0,01	0,68	543,17	1246,48	0,47	0,19	230,55	258,68	278,06	230,55
21,67	52,22	36,94	36,94	0,84	0,01	0,73	602,12	1393,83	0,51	0,20	233,25	261,64	279,82	233,25
25,00	56,67	40,83	40,83	0,84	0,01	0,79	665,78	1553,90	0,55	0,20	235,89	264,49	281,43	235,89
28,33	61,11	44,72	44,72	0,84	0,01	0,85	734,40	1727,45	0,59	0,21	238,50	267,26	282,87	238,50
31,67	65,56	48,61	48,61	0,85	0,01	0,90	808,21	1915,28	0,63	0,21	241,05	269,92	284,11	241,05



FINAL PROJECT

Date: 19.06.2014

Page: 79

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

35,00	70,00	52,50	52,50	0,85	0,02	0,96	887,47	2118,24	0,67	0,20	243,55	272,47	285,12	243,55
5,00	30,00	17,50	17,50	0,85	0,01	0,41	349,90	770,64	0,29	0,11	224,33	251,80	269,83	224,33
8,33	34,44	21,39	21,39	0,85	0,01	0,46	392,28	873,87	0,32	0,12	227,10	255,05	272,04	227,10
11,67	38,89	25,28	25,28	0,86	0,01	0,50	438,48	987,17	0,35	0,13	229,83	258,21	274,15	229,83
15,00	43,33	29,17	29,17	0,86	0,01	0,54	488,70	1111,16	0,38	0,13	232,53	261,28	276,16	232,53
18,33	47,78	33,06	33,06	0,86	0,01	0,59	543,17	1246,48	0,41	0,13	235,19	264,26	278,06	235,19
21,67	52,22	36,94	36,94	0,86	0,01	0,64	602,12	1393,83	0,45	0,13	237,81	267,15	279,82	237,81
25,00	56,67	40,83	40,83	0,87	0,01	0,69	665,78	1553,90	0,48	0,13	240,38	269,94	281,43	240,38
28,33	61,11	44,72	44,72	0,87	0,01	0,74	734,40	1727,45	0,52	0,13	242,91	272,63	282,87	242,91
31,67	65,56	48,61	48,61	0,87	0,01	0,79	808,21	1915,28	0,55	0,13	245,38	275,21	284,11	245,38
35,00	70,00	52,50	52,50	0,87	0,02	0,83	887,47	2118,24	0,58	0,12	247,80	277,68	285,12	247,80
5,00	30,00	17,50	17,50	0,88	0,01	0,36	349,90	770,64	0,25	0,08	229,24	257,60	269,83	229,24
8,33	34,44	21,39	21,39	0,88	0,01	0,39	392,28	873,87	0,27	0,08	231,95	260,80	272,04	231,95
11,67	38,89	25,28	25,28	0,88	0,01	0,43	438,48	987,17	0,30	0,08	234,61	263,91	274,15	234,61
15,00	43,33	29,17	29,17	0,88	0,01	0,47	488,70	1111,16	0,33	0,08	237,24	266,92	276,16	237,24
18,33	47,78	33,06	33,06	0,89	0,01	0,51	543,17	1246,48	0,36	0,08	239,83	269,84	278,06	239,83
21,67	52,22	36,94	36,94	0,89	0,01	0,56	602,12	1393,83	0,39	0,07	242,38	272,66	279,82	242,38
25,00	56,67	40,83	40,83	0,89	0,01	0,60	665,78	1553,90	0,42	0,07	244,87	275,38	281,43	244,87
28,33	61,11	44,72	44,72	0,89	0,01	0,64	734,40	1727,45	0,45	0,06	247,32	278,00	282,87	247,32
31,67	65,56	48,61	48,61	0,90	0,01	0,68	808,21	1915,28	0,47	0,05	249,71	280,50	284,11	249,71
35,00	70,00	52,50	52,50	0,90	0,02	0,72	887,47	2118,24	0,50	0,03	252,04	282,89	285,12	252,04
5,00	30,00	17,50	17,50	0,90	0,01	0,31	349,90	770,64	0,21	0,04	234,16	263,40	269,83	234,16
8,33	34,44	21,39	21,39	0,90	0,01	0,34	392,28	873,87	0,23	0,04	236,80	266,55	272,04	236,80



FINAL PROJECT

Date: 19.06.2014

Page: 80

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

11,67	38,89	25,28	25,28	0,91	0,01	0,37	438,48	987,17	0,26	0,03	239,40	269,60	274,15	239,40
15,00	43,33	29,17	29,17	0,91	0,01	0,40	488,70	1111,16	0,28	0,03	241,96	272,56	276,16	241,96
18,33	47,78	33,06	33,06	0,91	0,01	0,44	543,17	1246,48	0,31	0,02	244,47	275,42	278,06	244,47
21,67	52,22	36,94	36,94	0,91	0,01	0,47	602,12	1393,83	0,33	0,02	246,94	278,17	279,82	246,94
25,00	56,67	40,83	40,83	0,92	0,01	0,51	665,78	1553,90	0,36	0,01	249,36	280,82	281,43	249,36
28,33	61,11	44,72	44,72	0,92	0,01	0,55	734,40	1727,45	0,38	-0,01	251,73	283,37	282,87	251,73
31,67	65,56	48,61	48,61	0,92	0,01	0,58	808,21	1915,28	0,40	-0,02	254,04	285,80	284,11	254,04
35,00	70,00	52,50	52,50	0,92	0,01	0,61	887,47	2118,24	0,43	-0,04	256,29	288,11	285,12	256,29
5,00	30,00	17,50	17,50	0,93	0,01	0,26	349,90	770,64	0,18	0,00	239,08	269,20	269,83	239,08
8,33	34,44	21,39	21,39	0,93	0,01	0,28	392,28	873,87	0,20	0,00	241,65	272,30	272,04	241,65
11,67	38,89	25,28	25,28	0,93	0,01	0,31	438,48	987,17	0,22	-0,01	244,18	275,30	274,15	244,18
15,00	43,33	29,17	29,17	0,93	0,01	0,34	488,70	1111,16	0,24	-0,02	246,67	278,20	276,16	246,67
18,33	47,78	33,06	33,06	0,94	0,01	0,37	543,17	1246,48	0,26	-0,03	249,11	280,99	278,06	249,11
21,67	52,22	36,94	36,94	0,94	0,01	0,40	602,12	1393,83	0,28	-0,04	251,51	283,68	279,82	251,51
25,00	56,67	40,83	40,83	0,94	0,01	0,43	665,78	1553,90	0,30	-0,05	253,85	286,27	281,43	253,85
28,33	61,11	44,72	44,72	0,94	0,01	0,46	734,40	1727,45	0,32	-0,07	256,14	288,74	282,87	256,14
31,67	65,56	48,61	48,61	0,95	0,01	0,48	808,21	1915,28	0,34	-0,09	258,37	291,09	284,11	258,37
35,00	70,00	52,50	52,50	0,95	0,01	0,51	887,47	2118,24	0,35	-0,12	260,54	293,32	285,12	260,54
5,00	30,00	17,50	17,50	0,00	0,40	122,08	349,90	770,64	85,04	84,77	58,61	59,27	269,83	58,61
8,33	34,44	21,39	21,39	0,95	0,01	0,23	392,28	873,87	0,16	-0,04	246,50	278,05	272,04	246,50
11,67	38,89	25,28	25,28	0,96	0,01	0,25	438,48	987,17	0,18	-0,05	248,96	280,99	274,15	248,96
15,00	43,33	29,17	29,17	0,96	0,01	0,28	488,70	1111,16	0,19	-0,06	251,38	283,83	276,16	251,38
18,33	47,78	33,06	33,06	0,96	0,01	0,30	543,17	1246,48	0,21	-0,07	253,75	286,57	278,06	253,75



FINAL PROJECT

Date: 19.06.2014

Page: 81

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

21,67	52,22	36,94	36,94	0,96	0,01	0,33	602,12	1393,83	0,23	-0,09	256,07	289,20	279,82	256,07
25,00	56,67	40,83	40,83	0,97	0,01	0,35	665,78	1553,90	0,24	-0,11	258,34	291,71	281,43	258,34
28,33	61,11	44,72	44,72	0,97	0,01	0,37	734,40	1727,45	0,26	-0,13	260,55	294,11	282,87	260,55
31,67	65,56	48,61	48,61	0,97	0,01	0,39	808,21	1915,28	0,27	-0,16	262,70	296,38	284,11	262,70
35,00	70,00	52,50	52,50	0,97	0,01	0,41	887,47	2118,24	0,29	-0,19	264,78	298,53	285,12	264,78
5,00	30,00	17,50	17,50	0,98	0,01	0,17	349,90	770,64	0,12	-0,06	248,91	280,81	269,83	248,91
8,33	34,44	21,39	21,39	0,98	0,01	0,18	392,28	873,87	0,13	-0,07	251,35	283,80	272,04	251,35
11,67	38,89	25,28	25,28	0,98	0,01	0,20	438,48	987,17	0,14	-0,09	253,74	286,69	274,15	253,74
15,00	43,33	29,17	29,17	0,98	0,01	0,22	488,70	1111,16	0,15	-0,10	256,09	289,47	276,16	256,09
18,33	47,78	33,06	33,06	0,99	0,01	0,24	543,17	1246,48	0,17	-0,12	258,39	292,15	278,06	258,39
21,67	52,22	36,94	36,94	0,99	0,01	0,26	602,12	1393,83	0,18	-0,14	260,64	294,71	279,82	260,64
25,00	56,67	40,83	40,83	0,99	0,01	0,27	665,78	1553,90	0,19	-0,16	262,83	297,17	281,43	262,83
28,33	61,11	44,72	44,72	0,99	0,01	0,29	734,40	1727,45	0,20	-0,19	264,96	299,50	282,87	264,96
31,67	65,56	48,61	48,61	1,00	0,01	0,31	808,21	1915,28	0,21	-0,22	267,03	301,72	284,11	267,03
35,00	70,00	52,50	52,50	1,00	0,01	0,32	887,47	2118,24	0,22	-0,26	269,03	303,81	285,12	269,03



FINAL PROJECT

Date: 19.06.2014

Page: 82

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3.3.1 Summary R 134 A--- 3000 rpm, 7 cc/rev

Table 38- Summary R134A- 3000rpm, 7 cc/rev - improvement

	mref [g/s]	flow (l/min)	P1 (kPa)	P2	P3	Q (kW)	Qres (kW)	h1	h2	h3	h4
min	5,52	0,17	349,90	770,64	560,271414	0,12	-0,26	58,61	59,27	269,83	58,61
max	402,59	122,08	887,47	2118,24	1502,85679	85,04	84,77	269,03	303,81	285,12	269,03
X1_para minimo	0,98	0,98	0,75	0,75	0,75	0,98	1,00	0,00	0,00	0,75	0,00
X1_para maximo	0,00	0,00	0,77	0,77	0,77	0,00	0,00	1,00	1,00	0,77	1,00



FINAL PROJECT

Date: 19.06.2014

Page: 83

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3.4 REFRIGERANT R410 A --> 5000 rpm, 11.4 cc/rev

Table 39-R410 A-5000 rpm, 11.4 cc/rev- improvement

T1	T2	T3	T4	X1	mref	flow_l_min	P1	P2	Q	Qres	h1	h2	h3	h4
5,00	30,00	17,50	17,50	0,75	0,04	3,60	933,18	1883,41	2,51	1,40	369,01	396,38	430,96	369,01
8,33	34,44	21,39	21,39	0,75	0,04	3,82	1032,35	2108,78	2,66	1,42	371,47	399,22	431,06	371,47
11,67	38,89	25,28	25,28	0,76	0,05	4,04	1139,26	2354,04	2,81	1,43	373,85	401,91	430,84	373,85
15,00	43,33	29,17	29,17	0,76	0,05	4,22	1254,29	2620,47	2,94	1,40	376,15	404,46	430,26	376,15
18,33	47,78	33,06	33,06	0,76	0,06	4,37	1377,83	2909,51	3,05	1,34	378,36	406,85	429,26	378,36
21,67	52,22	36,94	36,94	0,76	0,07	4,47	1510,31	3222,74	3,11	1,23	380,48	409,08	427,74	380,48
25,00	56,67	40,83	40,83	0,77	0,07	4,47	1652,14	3562,00	3,12	1,05	382,49	411,13	425,60	382,49
28,33	61,11	44,72	44,72	0,77	0,08	4,36	1803,77	3929,48	3,04	0,77	384,38	413,00	422,66	384,38
31,67	65,56	48,61	48,61	0,77	0,09	4,08	1965,67	4327,98	2,84	0,35	386,14	414,66	418,71	386,14
35,00	70,00	52,50	52,50	0,77	0,10	3,54	2138,33	4761,73	2,46	-0,25	387,76	416,13	413,50	387,76
5,00	30,00	17,50	17,50	0,78	0,04	3,18	933,18	1883,41	2,22	1,10	374,45	402,79	430,96	374,45
8,33	34,44	21,39	21,39	0,78	0,04	3,37	1032,35	2108,78	2,35	1,11	376,79	405,53	431,06	376,79
11,67	38,89	25,28	25,28	0,78	0,05	3,55	1139,26	2354,04	2,48	1,09	379,06	408,12	430,84	379,06
15,00	43,33	29,17	29,17	0,78	0,05	3,71	1254,29	2620,47	2,58	1,04	381,24	410,55	430,26	381,24
18,33	47,78	33,06	33,06	0,79	0,06	3,83	1377,83	2909,51	2,67	0,95	383,33	412,83	429,26	383,33
21,67	52,22	36,94	36,94	0,79	0,06	3,89	1510,31	3222,74	2,71	0,82	385,32	414,93	427,74	385,32



FINAL PROJECT

Date: 19.06.2014

Page: 84

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

25,00	56,67	40,83	40,83	0,79	0,07	3,87	1652,14	3562,00	2,69	0,61	387,20	416,85	425,60	387,20
28,33	61,11	44,72	44,72	0,79	0,08	3,73	1803,77	3929,48	2,60	0,32	388,95	418,57	422,66	388,95
31,67	65,56	48,61	48,61	0,80	0,08	3,42	1965,67	4327,98	2,38	-0,12	390,57	420,07	418,71	390,57
35,00	70,00	52,50	52,50	0,80	0,09	2,87	2138,33	4761,73	2,00	-0,74	392,03	421,41	413,50	392,03
5,00	30,00	17,50	17,50	0,80	0,04	2,79	933,18	1883,41	1,94	0,83	379,88	409,20	430,96	379,88
8,33	34,44	21,39	21,39	0,80	0,04	2,95	1032,35	2108,78	2,06	0,81	382,12	411,84	431,06	382,12
11,67	38,89	25,28	25,28	0,81	0,05	3,10	1139,26	2354,04	2,16	0,77	384,28	414,32	430,84	384,28
15,00	43,33	29,17	29,17	0,81	0,05	3,23	1254,29	2620,47	2,25	0,70	386,34	416,65	430,26	386,34
18,33	47,78	33,06	33,06	0,81	0,06	3,31	1377,83	2909,51	2,31	0,59	388,31	418,80	429,26	388,31
21,67	52,22	36,94	36,94	0,81	0,06	3,34	1510,31	3222,74	2,33	0,43	390,17	420,78	427,74	390,17
25,00	56,67	40,83	40,83	0,82	0,07	3,30	1652,14	3562,00	2,30	0,21	391,91	422,56	425,60	391,91
28,33	61,11	44,72	44,72	0,82	0,07	3,13	1803,77	3929,48	2,18	-0,11	393,53	424,13	422,66	393,53
31,67	65,56	48,61	48,61	0,82	0,08	2,80	1965,67	4327,98	1,95	-0,56	395,00	425,50	418,71	395,00
35,00	70,00	52,50	52,50	0,82	0,09	2,23	2138,33	4761,73	1,56	-1,20	396,31	426,71	413,50	396,31
5,00	30,00	17,50	17,50	0,83	0,04	2,42	933,18	1883,41	1,68	0,57	385,32	415,61	430,96	385,32
8,33	34,44	21,39	21,39	0,83	0,04	2,55	1032,35	2108,78	1,78	0,53	387,45	418,15	431,06	387,45
11,67	38,89	25,28	25,28	0,83	0,05	2,67	1139,26	2354,04	1,86	0,46	389,49	420,53	430,84	389,49
15,00	43,33	29,17	29,17	0,83	0,05	2,77	1254,29	2620,47	1,93	0,37	391,44	422,74	430,26	391,44
18,33	47,78	33,06	33,06	0,84	0,05	2,83	1377,83	2909,51	1,97	0,25	393,28	424,78	429,26	393,28
21,67	52,22	36,94	36,94	0,84	0,06	2,83	1510,31	3222,74	1,97	0,07	395,01	426,62	427,74	395,01
25,00	56,67	40,83	40,83	0,84	0,07	2,76	1652,14	3562,00	1,92	-0,18	396,63	428,27	425,60	396,63
28,33	61,11	44,72	44,72	0,84	0,07	2,57	1803,77	3929,48	1,79	-0,51	398,10	429,70	422,66	398,10
31,67	65,56	48,61	48,61	0,85	0,08	2,22	1965,67	4327,98	1,54	-0,98	399,43	430,95	418,71	399,43



FINAL PROJECT

Date: 19.06.2014

Page: 85

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

35,00	70,00	52,50	52,50	0,85	0,09	1,63	2138,33	4761,73	1,14	-1,63	400,58	432,03	413,50	400,58
5,00	30,00	17,50	17,50	0,85	0,04	2,07	933,18	1883,41	1,44	0,32	390,75	422,02	430,96	390,75
8,33	34,44	21,39	21,39	0,85	0,04	2,18	1032,35	2108,78	1,52	0,26	392,77	424,46	431,06	392,77
11,67	38,89	25,28	25,28	0,86	0,04	2,27	1139,26	2354,04	1,58	0,18	394,70	426,74	430,84	394,70
15,00	43,33	29,17	29,17	0,86	0,05	2,34	1254,29	2620,47	1,63	0,07	396,53	428,84	430,26	396,53
18,33	47,78	33,06	33,06	0,86	0,05	2,37	1377,83	2909,51	1,65	-0,08	398,25	430,75	429,26	398,25
21,67	52,22	36,94	36,94	0,86	0,06	2,35	1510,31	3222,74	1,63	-0,28	399,86	432,47	427,74	399,86
25,00	56,67	40,83	40,83	0,87	0,06	2,25	1652,14	3562,00	1,56	-0,54	401,34	433,98	425,60	401,34
28,33	61,11	44,72	44,72	0,87	0,07	2,03	1803,77	3929,48	1,42	-0,90	402,67	435,30	422,66	402,67
31,67	65,56	48,61	48,61	0,87	0,08	1,66	1965,67	4327,98	1,16	-1,38	403,85	436,44	418,71	403,85
35,00	70,00	52,50	52,50	0,87	0,09	1,06	2138,33	4761,73	0,74	-2,05	404,85	437,39	413,50	404,85
5,00	30,00	17,50	17,50	0,88	0,03	1,74	933,18	1883,41	1,21	0,09	396,19	428,43	430,96	396,19
8,33	34,44	21,39	21,39	0,88	0,04	1,82	1032,35	2108,78	1,27	0,01	398,10	430,77	431,06	398,10
11,67	38,89	25,28	25,28	0,88	0,04	1,89	1139,26	2354,04	1,32	-0,09	399,91	432,94	430,84	399,91
15,00	43,33	29,17	29,17	0,88	0,05	1,93	1254,29	2620,47	1,35	-0,22	401,63	434,93	430,26	401,63
18,33	47,78	33,06	33,06	0,89	0,05	1,94	1377,83	2909,51	1,35	-0,39	403,23	436,73	429,26	403,23
21,67	52,22	36,94	36,94	0,89	0,06	1,89	1510,31	3222,74	1,31	-0,60	404,71	438,32	427,74	404,71
25,00	56,67	40,83	40,83	0,89	0,06	1,76	1652,14	3562,00	1,23	-0,89	406,05	439,72	425,60	406,05
28,33	61,11	44,72	44,72	0,89	0,07	1,53	1803,77	3929,48	1,06	-1,26	407,25	440,94	422,66	407,25
31,67	65,56	48,61	48,61	0,90	0,08	1,14	1965,67	4327,98	0,79	-1,77	408,28	441,97	418,71	408,28
35,00	70,00	52,50	52,50	0,90	0,08	0,52	2138,33	4761,73	0,37	-2,45	409,12	442,79	413,50	409,12
5,00	30,00	17,50	17,50	0,90	0,03	1,43	933,18	1883,41	0,99	-0,13	401,62	434,83	430,96	401,62
8,33	34,44	21,39	21,39	0,90	0,04	1,49	1032,35	2108,78	1,04	-0,23	403,42	437,08	431,06	403,42



FINAL PROJECT

Date: 19.06.2014

Page: 86

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

11,67	38,89	25,28	25,28	0,91	0,04	1,53	1139,26	2354,04	1,07	-0,34	405,12	439,15	430,84	405,12
15,00	43,33	29,17	29,17	0,91	0,05	1,55	1254,29	2620,47	1,08	-0,49	406,72	441,02	430,26	406,72
18,33	47,78	33,06	33,06	0,91	0,05	1,52	1377,83	2909,51	1,06	-0,68	408,20	442,71	429,26	408,20
21,67	52,22	36,94	36,94	0,91	0,06	1,45	1510,31	3222,74	1,01	-0,92	409,55	444,21	427,74	409,55
25,00	56,67	40,83	40,83	0,92	0,06	1,30	1652,14	3562,00	0,91	-1,22	410,76	445,53	425,60	410,76
28,33	61,11	44,72	44,72	0,92	0,07	1,05	1803,77	3929,48	0,73	-1,62	411,82	446,65	422,66	411,82
31,67	65,56	48,61	48,61	0,92	0,07	0,64	1965,67	4327,98	0,44	-2,14	412,71	447,55	418,71	412,71
35,00	70,00			0,92										
5,00	30,00	17,50	17,50	0,93	0,03	1,13	933,18	1883,41	0,79	-0,34	407,05	441,24	430,96	407,05
8,33	34,44	21,39	21,39	0,93	0,04	1,17	1032,35	2108,78	0,81	-0,45	408,75	443,39	431,06	408,75
11,67	38,89	25,28	25,28	0,93	0,04	1,19	1139,26	2354,04	0,83	-0,59	410,34	445,36	430,84	410,34
15,00	43,33	29,17	29,17	0,93	0,04	1,18	1254,29	2620,47	0,82	-0,75	411,81	447,15	430,26	411,81
18,33	47,78	33,06	33,06	0,94	0,05	1,14	1377,83	2909,51	0,79	-0,96	413,17	448,77	429,26	413,17
21,67	52,22	36,94	36,94	0,94	0,05	1,04	1510,31	3222,74	0,72	-1,22	414,40	450,19	427,74	414,40
25,00	56,67	40,83	40,83	0,94	0,06	0,87	1652,14	3562,00	0,60	-1,54	415,47	451,41	425,60	415,47
28,33	61,11	44,72	44,72	0,94	0,07	0,59	1803,77	3929,48	0,41	-1,95	416,39	452,41	422,66	416,39
31,67	65,56	48,61	48,61	0,95	0,07	0,16	1965,67	4327,98	0,11	-2,49	417,13	453,19	418,71	417,13
35,00	70,00	52,50	52,50	0,95	0,08	-0,48	2138,33	4761,73	-0,33	-3,20	417,67	453,73	413,50	417,67
5,00	30,00	17,50	17,50	0,95	0,03	0,85	933,18	1883,41	0,59	-0,54	412,49	447,68	430,96	412,49
8,33	34,44	21,39	21,39	0,95	0,04	0,87	1032,35	2108,78	0,60	-0,67	414,07	449,76	431,06	414,07
11,67	38,89	25,28	25,28	0,96	0,04	0,86	1139,26	2354,04	0,60	-0,82	415,55	451,67	430,84	415,55
15,00	43,33	29,17	29,17	0,96	0,04	0,83	1254,29	2620,47	0,58	-1,01	416,91	453,40	430,26	416,91
18,33	47,78	33,06	33,06	0,96	0,05	0,76	1377,83	2909,51	0,53	-1,23	418,14	454,93	429,26	418,14



FINAL PROJECT

Date: 19.06.2014

Page: 87

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

21,67	52,22	36,94	36,94	0,96	0,05	0,64	1510,31	3222,74	0,45	-1,51	419,24	456,25	427,74	419,24
25,00	56,67	40,83	40,83	0,97	0,06	0,45	1652,14	3562,00	0,31	-1,85	420,19	457,36	425,60	420,19
28,33	61,11	44,72	44,72	0,97	0,06	0,16	1803,77	3929,48	0,11	-2,28	420,96	458,25	422,66	420,96
31,67	65,56	48,61	48,61	0,97	0,07	-0,29	1965,67	4327,98	-0,20	-2,83	421,56	458,89	418,71	421,56
35,00	70,00	52,50	52,50	0,97	0,08	-0,94	2138,33	4761,73	-0,66	-3,56	421,94	459,28	413,50	421,94
5,00	30,00	17,50	17,50	0,98	0,03	0,59	933,18	1883,41	0,41	-0,73	417,92	454,26	430,96	417,92
8,33	34,44	21,39	21,39	0,98	0,03	0,58	1032,35	2108,78	0,40	-0,88	419,40	456,28	431,06	419,40
11,67	38,89	25,28	25,28	0,98	0,04	0,56	1139,26	2354,04	0,39	-1,05	420,76	458,12	430,84	420,76
15,00	43,33	29,17	29,17	0,98	0,04	0,50	1254,29	2620,47	0,35	-1,25	422,00	459,76	430,26	422,00
18,33	47,78	33,06	33,06	0,99	0,05	0,41	1377,83	2909,51	0,29	-1,49	423,12	461,19	429,26	423,12
21,67	52,22	36,94	36,94	0,99	0,05	0,27	1510,31	3222,74	0,19	-1,79	424,09	462,41	427,74	424,09
25,00	56,67	40,83	40,83	0,99	0,06	0,06	1652,14	3562,00	0,04	-2,15	424,90	463,41	425,60	424,90
28,33	61,11	44,72	44,72	0,99	0,06	-0,26	1803,77	3929,48	-0,18	-2,60	425,54	464,16	422,66	425,54
31,67	65,56	48,61	48,61	1,00	0,07	-0,72	1965,67	4327,98	-0,50	-3,17	425,98	464,66	418,71	425,98
35,00	70,00	52,50	52,50	1,00	0,08	-1,39	2138,33	4761,73	-0,97	-3,90	426,21	464,89	413,50	426,21



FINAL PROJECT

Date: 19.06.2014

Page: 88

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3.4.1 Summary R410 A--- 5000 rpm, 11.4 cc/rev

Table 40-Summary R410 -5000rpm, 11.4 cc/rev- improvement

	mref [g/s]	flow (l/min)	P1 (kPa)	P2	P3	Q (kW)	Qres (kW)	h1	h2	h3	h4
min	31,35	-1,39	933,18	1883,41	1408,29229	-0,97	-3,90	369,01	396,38	413,50	369,01
max	95,75	4,47	2138,33	4761,73	3450,02858	3,12	1,43	426,21	464,89	431,06	426,21
X1_para minimo	0,98	1,00	0,75	0,75	0,75	1,00	1,00	0,75	0,75	0,77	0,75
X1_para maximo	0,77	0,77	0,77	0,77	0,77	0,77	0,76	1,00	1,00	0,75	1,00



FINAL PROJECT

Date: 19.06.2014

Page: 89

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3.5 REFRIGERANT R410 A--> 3000 rpm, 7 cc/rev

Table 41-R410 A- 3000 rpm, 7 cc/rev- improvement

T1	T2	T3	T4	X1	mref	flow_l_min	P1	P2	Q	Qres	h1	h2	h3	h4
5,00	30,00	17,50	17,50	0,75	0,02	1,82	349,90	770,64	1,27	0,80	204,66	228,59	269,83	204,66
8,33	34,44	21,39	21,39	0,75	0,02	2,00	392,28	873,87	1,39	0,87	207,69	232,05	272,04	207,69
11,67	38,89	25,28	25,28	0,76	0,02	2,19	438,48	987,17	1,53	0,93	210,71	235,43	274,15	210,71
15,00	43,33	29,17	29,17	0,76	0,03	2,39	488,70	1111,16	1,67	1,00	213,69	238,73	276,16	213,69
18,33	47,78	33,06	33,06	0,76	0,03	2,60	543,17	1246,48	1,81	1,07	216,63	241,95	278,06	216,63
21,67	52,22	36,94	36,94	0,76	0,03	2,82	602,12	1393,83	1,96	1,13	219,55	245,10	279,82	219,55
25,00	56,67	40,83	40,83	0,77	0,04	3,04	665,78	1553,90	2,12	1,19	222,43	248,17	281,43	222,43
28,33	61,11	44,72	44,72	0,77	0,04	3,26	734,40	1727,45	2,27	1,25	225,26	251,15	282,87	225,26
31,67	65,56	48,61	48,61	0,77	0,04	3,49	808,21	1915,28	2,43	1,30	228,06	254,04	284,11	228,06
35,00	70,00	52,50	52,50	0,77	0,05	3,71	887,47	2118,24	2,58	1,34	230,81	256,84	285,12	230,81
5,00	30,00	17,50	17,50	0,78	0,02	1,63	349,90	770,64	1,13	0,67	209,57	234,40	269,83	209,57
8,33	34,44	21,39	21,39	0,78	0,02	1,79	392,28	873,87	1,25	0,72	212,55	237,80	272,04	212,55
11,67	38,89	25,28	25,28	0,78	0,02	1,96	438,48	987,17	1,37	0,77	215,49	241,12	274,15	215,49
15,00	43,33	29,17	29,17	0,78	0,03	2,14	488,70	1111,16	1,49	0,82	218,40	244,37	276,16	218,40
18,33	47,78	33,06	33,06	0,79	0,03	2,33	543,17	1246,48	1,62	0,87	221,27	247,53	278,06	221,27
21,67	52,22	36,94	36,94	0,79	0,03	2,52	602,12	1393,83	1,76	0,92	224,11	250,61	279,82	224,11



FINAL PROJECT

Date: 19.06.2014

Page: 90

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

25,00	56,67	40,83	40,83	0,79	0,03	2,72	665,78	1553,90	1,90	0,97	226,92	253,61	281,43	226,92
28,33	61,11	44,72	44,72	0,79	0,04	2,92	734,40	1727,45	2,04	1,01	229,68	256,52	282,87	229,68
31,67	65,56	48,61	48,61	0,80	0,04	3,12	808,21	1915,28	2,17	1,04	232,39	259,33	284,11	232,39
35,00	70,00	52,50	52,50	0,80	0,05	3,31	887,47	2118,24	2,31	1,06	235,06	262,05	285,12	235,06
5,00	30,00	17,50	17,50	0,80	0,02	1,45	349,90	770,64	1,01	0,54	214,49	240,20	269,83	214,49
8,33	34,44	21,39	21,39	0,80	0,02	1,59	392,28	873,87	1,11	0,58	217,40	243,55	272,04	217,40
11,67	38,89	25,28	25,28	0,81	0,02	1,75	438,48	987,17	1,22	0,62	220,27	246,82	274,15	220,27
15,00	43,33	29,17	29,17	0,81	0,03	1,91	488,70	1111,16	1,33	0,66	223,11	250,00	276,16	223,11
18,33	47,78	33,06	33,06	0,81	0,03	2,07	543,17	1246,48	1,44	0,69	225,91	253,11	278,06	225,91
21,67	52,22	36,94	36,94	0,81	0,03	2,25	602,12	1393,83	1,56	0,73	228,68	256,12	279,82	228,68
25,00	56,67	40,83	40,83	0,82	0,03	2,42	665,78	1553,90	1,69	0,75	231,40	259,05	281,43	231,40
28,33	61,11	44,72	44,72	0,82	0,04	2,60	734,40	1727,45	1,81	0,78	234,09	261,89	282,87	234,09
31,67	65,56	48,61	48,61	0,82	0,04	2,78	808,21	1915,28	1,93	0,80	236,72	264,62	284,11	236,72
35,00	70,00	52,50	52,50	0,82	0,04	2,94	887,47	2118,24	2,05	0,80	239,30	267,26	285,12	239,30
5,00	30,00	17,50	17,50	0,83	0,02	1,28	349,90	770,64	0,89	0,42	219,41	246,00	269,83	219,41
8,33	34,44	21,39	21,39	0,83	0,02	1,41	392,28	873,87	0,98	0,45	222,25	249,30	272,04	222,25
11,67	38,89	25,28	25,28	0,83	0,02	1,54	438,48	987,17	1,08	0,47	225,05	252,51	274,15	225,05
15,00	43,33	29,17	29,17	0,83	0,02	1,69	488,70	1111,16	1,17	0,50	227,82	255,64	276,16	227,82
18,33	47,78	33,06	33,06	0,84	0,03	1,83	543,17	1246,48	1,28	0,52	230,55	258,68	278,06	230,55
21,67	52,22	36,94	36,94	0,84	0,03	1,99	602,12	1393,83	1,38	0,54	233,25	261,64	279,82	233,25
25,00	56,67	40,83	40,83	0,84	0,03	2,14	665,78	1553,90	1,49	0,55	235,89	264,49	281,43	235,89
28,33	61,11	44,72	44,72	0,84	0,04	2,30	734,40	1727,45	1,60	0,56	238,50	267,26	282,87	238,50
31,67	65,56	48,61	48,61	0,85	0,04	2,45	808,21	1915,28	1,71	0,56	241,05	269,92	284,11	241,05



FINAL PROJECT

Date: 19.06.2014

Page: 91

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

35,00	70,00	52,50	52,50	0,85	0,04	2,60	887,47	2118,24	1,81	0,55	243,55	272,47	285,12	243,55
5,00	30,00	17,50	17,50	0,85	0,02	1,12	349,90	770,64	0,78	0,31	224,33	251,80	269,83	224,33
8,33	34,44	21,39	21,39	0,85	0,02	1,24	392,28	873,87	0,86	0,33	227,10	255,05	272,04	227,10
11,67	38,89	25,28	25,28	0,86	0,02	1,35	438,48	987,17	0,94	0,34	229,83	258,21	274,15	229,83
15,00	43,33	29,17	29,17	0,86	0,02	1,48	488,70	1111,16	1,03	0,35	232,53	261,28	276,16	232,53
18,33	47,78	33,06	33,06	0,86	0,03	1,61	543,17	1246,48	1,12	0,36	235,19	264,26	278,06	235,19
21,67	52,22	36,94	36,94	0,86	0,03	1,74	602,12	1393,83	1,21	0,37	237,81	267,15	279,82	237,81
25,00	56,67	40,83	40,83	0,87	0,03	1,88	665,78	1553,90	1,31	0,37	240,38	269,94	281,43	240,38
28,33	61,11	44,72	44,72	0,87	0,04	2,01	734,40	1727,45	1,40	0,36	242,91	272,63	282,87	242,91
31,67	65,56	48,61	48,61	0,87	0,04	2,14	808,21	1915,28	1,49	0,34	245,38	275,21	284,11	245,38
35,00	70,00	52,50	52,50	0,87	0,04	2,27	887,47	2118,24	1,58	0,31	247,80	277,68	285,12	247,80
5,00	30,00	17,50	17,50	0,88	0,02	0,97	349,90	770,64	0,68	0,20	229,24	257,60	269,83	229,24
8,33	34,44	21,39	21,39	0,88	0,02	1,07	392,28	873,87	0,75	0,21	231,95	260,80	272,04	231,95
11,67	38,89	25,28	25,28	0,88	0,02	1,17	438,48	987,17	0,82	0,21	234,61	263,91	274,15	234,61
15,00	43,33	29,17	29,17	0,88	0,02	1,28	488,70	1111,16	0,89	0,21	237,24	266,92	276,16	237,24
18,33	47,78	33,06	33,06	0,89	0,03	1,39	543,17	1246,48	0,97	0,21	239,83	269,84	278,06	239,83
21,67	52,22	36,94	36,94	0,89	0,03	1,51	602,12	1393,83	1,05	0,20	242,38	272,66	279,82	242,38
25,00	56,67	40,83	40,83	0,89	0,03	1,62	665,78	1553,90	1,13	0,19	244,87	275,38	281,43	244,87
28,33	61,11	44,72	44,72	0,89	0,03	1,74	734,40	1727,45	1,21	0,17	247,32	278,00	282,87	247,32
31,67	65,56	48,61	48,61	0,90	0,04	1,85	808,21	1915,28	1,29	0,14	249,71	280,50	284,11	249,71
35,00	70,00	52,50	52,50	0,90	0,04	1,95	887,47	2118,24	1,36	0,09	252,04	282,89	285,12	252,04
5,00	30,00	17,50	17,50	0,90	0,02	0,83	349,90	770,64	0,58	0,10	234,16	263,40	269,83	234,16
8,33	34,44	21,39	21,39	0,90	0,02	0,92	392,28	873,87	0,64	0,10	236,80	266,55	272,04	236,80



FINAL PROJECT

Date: 19.06.2014

Page: 92

PROJECT:
“Compressors test live bench under wet compression conditions”

ANNEX:
2

11,67	38,89	25,28	25,28	0,91	0,02	1,00	438,48	987,17	0,70	0,09	239,40	269,60	274,15	239,40
15,00	43,33	29,17	29,17	0,91	0,02	1,10	488,70	1111,16	0,76	0,08	241,96	272,56	276,16	241,96
18,33	47,78	33,06	33,06	0,91	0,02	1,19	543,17	1246,48	0,83	0,07	244,47	275,42	278,06	244,47
21,67	52,22	36,94	36,94	0,91	0,03	1,29	602,12	1393,83	0,90	0,05	246,94	278,17	279,82	246,94
25,00	56,67	40,83	40,83	0,92	0,03	1,39	665,78	1553,90	0,97	0,02	249,36	280,82	281,43	249,36
28,33	61,11	44,72	44,72	0,92	0,03	1,48	734,40	1727,45	1,03	-0,02	251,73	283,37	282,87	251,73
31,67	65,56	48,61	48,61	0,92	0,04	1,58	808,21	1915,28	1,10	-0,06	254,04	285,80	284,11	254,04
35,00	70,00	52,50	52,50	0,92	0,04	1,66	887,47	2118,24	1,16	-0,12	256,29	288,11	285,12	256,29
5,00	30,00	17,50	17,50	0,93	0,02	0,70	349,90	770,64	0,49	0,01	239,08	269,20	269,83	239,08
8,33	34,44	21,39	21,39	0,93	0,02	0,77	392,28	873,87	0,54	0,00	241,65	272,30	272,04	241,65
11,67	38,89	25,28	25,28	0,93	0,02	0,84	438,48	987,17	0,59	-0,02	244,18	275,30	274,15	244,18
15,00	43,33	29,17	29,17	0,93	0,02	0,92	488,70	1111,16	0,64	-0,04	246,67	278,20	276,16	246,67
18,33	47,78	33,06	33,06	0,94	0,02	1,00	543,17	1246,48	0,70	-0,07	249,11	280,99	278,06	249,11
21,67	52,22	36,94	36,94	0,94	0,03	1,08	602,12	1393,83	0,75	-0,10	251,51	283,68	279,82	251,51
25,00	56,67	40,83	40,83	0,94	0,03	1,16	665,78	1553,90	0,81	-0,14	253,85	286,27	281,43	253,85
28,33	61,11	44,72	44,72	0,94	0,03	1,24	734,40	1727,45	0,86	-0,19	256,14	288,74	282,87	256,14
31,67	65,56	48,61	48,61	0,95	0,04	1,31	808,21	1915,28	0,92	-0,25	258,37	291,09	284,11	258,37
35,00	70,00	52,50	52,50	0,95	0,04	1,38	887,47	2118,24	0,96	-0,32	260,54	293,32	285,12	260,54
5,00	30,00			0,00										
8,33	34,44	21,39	21,39	0,95	0,02	0,63	392,28	873,87	0,44	-0,10	246,50	278,05	272,04	246,50
11,67	38,89	25,28	25,28	0,96	0,02	0,69	438,48	987,17	0,48	-0,13	248,96	280,99	274,15	248,96
15,00	43,33	29,17	29,17	0,96	0,02	0,75	488,70	1111,16	0,52	-0,16	251,38	283,83	276,16	251,38
18,33	47,78	33,06	33,06	0,96	0,02	0,82	543,17	1246,48	0,57	-0,20	253,75	286,57	278,06	253,75



FINAL PROJECT

Date: 19.06.2014

Page: 93

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

21,67	52,22	36,94	36,94	0,96	0,03	0,88	602,12	1393,83	0,62	-0,24	256,07	289,20	279,82	256,07
25,00	56,67	40,83	40,83	0,97	0,03	0,95	665,78	1553,90	0,66	-0,29	258,34	291,71	281,43	258,34
28,33	61,11	44,72	44,72	0,97	0,03	1,01	734,40	1727,45	0,70	-0,35	260,55	294,11	282,87	260,55
31,67	65,56	48,61	48,61	0,97	0,03	1,07	808,21	1915,28	0,74	-0,43	262,70	296,38	284,11	262,70
35,00	70,00	52,50	52,50	0,97	0,04	1,11	887,47	2118,24	0,77	-0,51	264,78	298,53	285,12	264,78
5,00	30,00	17,50	17,50	0,98	0,01	0,45	349,90	770,64	0,31	-0,16	248,91	280,81	269,83	248,91
8,33	34,44	21,39	21,39	0,98	0,02	0,50	392,28	873,87	0,35	-0,20	251,35	283,80	272,04	251,35
11,67	38,89	25,28	25,28	0,98	0,02	0,54	438,48	987,17	0,38	-0,23	253,74	286,69	274,15	253,74
15,00	43,33	29,17	29,17	0,98	0,02	0,59	488,70	1111,16	0,41	-0,27	256,09	289,47	276,16	256,09
18,33	47,78	33,06	33,06	0,99	0,02	0,65	543,17	1246,48	0,45	-0,32	258,39	292,15	278,06	258,39
21,67	52,22	36,94	36,94	0,99	0,03	0,70	602,12	1393,83	0,48	-0,38	260,64	294,71	279,82	260,64
25,00	56,67	40,83	40,83	0,99	0,03	0,74	665,78	1553,90	0,52	-0,44	262,83	297,17	281,43	262,83
28,33	61,11	44,72	44,72	0,99	0,03	0,79	734,40	1727,45	0,55	-0,51	264,96	299,50	282,87	264,96
31,67	65,56	48,61	48,61	1,00	0,03	0,83	808,21	1915,28	0,58	-0,60	267,03	301,72	284,11	267,03
35,00	70,00	52,50	52,50	1,00	0,04	0,86	887,47	2118,24	0,60	-0,69	269,03	303,81	285,12	269,03



FINAL PROJECT

Date: 19.06.2014

Page: 94

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3.5.1 Summary R410 A--- 3000rpm, 7cc/rev

Table 42-Summary R410 A- 3000 rpm, 7 cc/rev- improvement

	mref [g/s]	flow (l/min)	P1 (kPa)	P2	P3	Q (kW)	Qres (kW)	h1	h2	h3	h4
Min	14,99	0,45	349,90	770,64	560,271414	0,31	-0,69	204,66	228,59	269,83	204,66
Max	47,55	3,71	887,47	2118,24	1502,85679	2,58	1,34	269,03	303,81	285,12	269,03
X1_para minimo	0,98	0,98	0,75	0,75	0,75	0,98	1,00	0,75	0,75	0,75	0,75
X1_para maximo	0,77	0,77	0,77	0,77	0,77	0,77	0,77	1,00	1,00	0,77	1,00



FINAL PROJECT

Date: 19.06.2014

Page: 95

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3.6 REFRIGERANT R407 C -->5000 rpm, 11.4 cc/rev

Table 43-R407C-5000 rpm, 11.4 cc/rev- improvement

T1	T2	T3	T4	X1	mref	flow_l_min	P1	P2	Q	Qres	h1	h2	h3	h4
5,00	30,00	17,50	17,50	0,75	0,03	2,47	546,52	1175,14	1,72	0,97	359,51	388,30	425,23	359,51
8,33	34,44	21,39	21,39	0,75	0,03	2,69	610,42	1328,23	1,87	1,02	362,40	391,55	426,69	362,40
11,67	38,89	25,28	25,28	0,76	0,03	2,91	679,86	1496,04	2,02	1,07	365,25	394,71	427,99	365,25
15,00	43,33	29,17	29,17	0,76	0,04	3,13	755,15	1679,57	2,18	1,12	368,06	397,76	429,11	368,06
18,33	47,78	33,06	33,06	0,76	0,04	3,35	836,60	1879,91	2,34	1,16	370,81	400,71	430,02	370,81
21,67	52,22	36,94	36,94	0,76	0,04	3,57	924,55	2098,22	2,49	1,18	373,50	403,55	430,67	373,50
25,00	56,67	40,83	40,83	0,77	0,05	3,78	1019,34	2335,84	2,63	1,19	376,14	406,29	431,04	376,14
28,33	61,11	44,72	44,72	0,77	0,05	3,96	1121,33	2594,27	2,76	1,17	378,71	408,90	431,06	378,71
31,67	65,56	48,61	48,61	0,77	0,06	4,11	1230,88	2875,31	2,87	1,12	381,21	411,40	430,65	381,21
35,00	70,00	52,50	52,50	0,77	0,06	4,21	1348,38	3181,21	2,93	1,01	383,63	413,78	429,70	383,63
5,00	30,00	17,50	17,50	0,78	0,03	2,20	546,52	1175,14	1,53	0,78	364,82	394,45	425,23	364,82
8,33	34,44	21,39	21,39	0,78	0,03	2,39	610,42	1328,23	1,67	0,82	367,63	397,64	426,69	367,63
11,67	38,89	25,28	25,28	0,78	0,03	2,59	679,86	1496,04	1,80	0,85	370,40	400,72	427,99	370,40
15,00	43,33	29,17	29,17	0,78	0,03	2,78	755,15	1679,57	1,94	0,88	373,11	403,70	429,11	373,11
18,33	47,78	33,06	33,06	0,79	0,04	2,98	836,60	1879,91	2,08	0,90	375,76	406,57	430,02	375,76
21,67	52,22	36,94	36,94	0,79	0,04	3,17	924,55	2098,22	2,21	0,90	378,36	409,33	430,67	378,36



FINAL PROJECT

Date: 19.06.2014

Page: 96

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

25,00	56,67	40,83	40,83	0,79	0,05	3,35	1019,34	2335,84	2,33	0,89	380,89	411,97	431,04	380,89
28,33	61,11	44,72	44,72	0,79	0,05	3,50	1121,33	2594,27	2,44	0,85	383,36	414,49	431,06	383,36
31,67	65,56	48,61	48,61	0,80	0,06	3,63	1230,88	2875,31	2,53	0,77	385,75	416,88	430,65	385,75
35,00	70,00	52,50	52,50	0,80	0,06	3,69	1348,38	3181,21	2,57	0,65	388,06	419,15	429,70	388,06
5,00	30,00	17,50	17,50	0,80	0,02	1,95	546,52	1175,14	1,36	0,61	370,13	400,58	425,23	370,13
8,33	34,44	21,39	21,39	0,80	0,03	2,11	610,42	1328,23	1,47	0,63	372,86	403,70	426,69	372,86
11,67	38,89	25,28	25,28	0,81	0,03	2,29	679,86	1496,04	1,59	0,65	375,53	406,71	427,99	375,53
15,00	43,33	29,17	29,17	0,81	0,03	2,46	755,15	1679,57	1,71	0,66	378,15	409,62	429,11	378,15
18,33	47,78	33,06	33,06	0,81	0,04	2,63	836,60	1879,91	1,83	0,65	380,71	412,41	430,02	380,71
21,67	52,22	36,94	36,94	0,81	0,04	2,79	924,55	2098,22	1,95	0,64	383,21	415,08	430,67	383,21
25,00	56,67	40,83	40,83	0,82	0,05	2,94	1019,34	2335,84	2,05	0,61	385,64	417,63	431,04	385,64
28,33	61,11	44,72	44,72	0,82	0,05	3,07	1121,33	2594,27	2,14	0,55	388,00	420,05	431,06	388,00
31,67	65,56	48,61	48,61	0,82	0,05	3,17	1230,88	2875,31	2,21	0,45	390,29	422,35	430,65	390,29
35,00	70,00	52,50	52,50	0,82	0,06	3,21	1348,38	3181,21	2,23	0,31	392,49	424,50	429,70	392,49
5,00	30,00	17,50	17,50	0,83	0,02	1,71	546,52	1175,14	1,19	0,44	375,43	406,69	425,23	375,43
8,33	34,44	21,39	21,39	0,83	0,03	1,85	610,42	1328,23	1,29	0,45	378,07	409,74	426,69	378,07
11,67	38,89	25,28	25,28	0,83	0,03	2,00	679,86	1496,04	1,40	0,45	380,65	412,68	427,99	380,65
15,00	43,33	29,17	29,17	0,83	0,03	2,15	755,15	1679,57	1,50	0,44	383,18	415,51	429,11	383,18
18,33	47,78	33,06	33,06	0,84	0,04	2,30	836,60	1879,91	1,60	0,43	385,65	418,22	430,02	385,65
21,67	52,22	36,94	36,94	0,84	0,04	2,44	924,55	2098,22	1,70	0,39	388,05	420,81	430,67	388,05
25,00	56,67	40,83	40,83	0,84	0,04	2,56	1019,34	2335,84	1,79	0,34	390,38	423,27	431,04	390,38
28,33	61,11	44,72	44,72	0,84	0,05	2,67	1121,33	2594,27	1,86	0,26	392,64	425,60	431,06	392,64
31,67	65,56	48,61	48,61	0,85	0,05	2,74	1230,88	2875,31	1,91	0,15	394,82	427,79	430,65	394,82



FINAL PROJECT

Date: 19.06.2014

Page: 97

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

35,00	70,00	52,50	52,50	0,85	0,06	2,75	1348,38	3181,21	1,92	-0,01	396,90	429,83	429,70	396,90
5,00	30,00	17,50	17,50	0,85	0,02	1,48	546,52	1175,14	1,03	0,29	380,72	412,77	425,23	380,72
8,33	34,44	21,39	21,39	0,85	0,03	1,61	610,42	1328,23	1,12	0,28	383,28	415,76	426,69	383,28
11,67	38,89	25,28	25,28	0,86	0,03	1,74	679,86	1496,04	1,21	0,27	385,77	418,63	427,99	385,77
15,00	43,33	29,17	29,17	0,86	0,03	1,86	755,15	1679,57	1,30	0,25	388,21	421,39	429,11	388,21
18,33	47,78	33,06	33,06	0,86	0,04	1,99	836,60	1879,91	1,38	0,21	390,58	424,02	430,02	390,58
21,67	52,22	36,94	36,94	0,86	0,04	2,10	924,55	2098,22	1,46	0,16	392,89	426,52	430,67	392,89
25,00	56,67	40,83	40,83	0,87	0,04	2,20	1019,34	2335,84	1,53	0,09	395,12	428,89	431,04	395,12
28,33	61,11	44,72	44,72	0,87	0,05	2,28	1121,33	2594,27	1,59	0,00	397,27	431,12	431,06	397,27
31,67	65,56	48,61	48,61	0,87	0,05	2,33	1230,88	2875,31	1,62	-0,13	399,34	433,21	430,65	399,34
35,00	70,00	52,50	52,50	0,87	0,06	2,32	1348,38	3181,21	1,62	-0,31	401,31	435,15	429,70	401,31
5,00	30,00	17,50	17,50	0,88	0,02	1,27	546,52	1175,14	0,89	0,14	386,01	418,83	425,23	386,01
8,33	34,44	21,39	21,39	0,88	0,03	1,38	610,42	1328,23	0,96	0,12	388,48	421,75	426,69	388,48
11,67	38,89	25,28	25,28	0,88	0,03	1,48	679,86	1496,04	1,03	0,10	390,88	424,56	427,99	390,88
15,00	43,33	29,17	29,17	0,88	0,03	1,59	755,15	1679,57	1,11	0,06	393,23	427,24	429,11	393,23
18,33	47,78	33,06	33,06	0,89	0,03	1,69	836,60	1879,91	1,18	0,01	395,51	429,79	430,02	395,51
21,67	52,22	36,94	36,94	0,89	0,04	1,78	924,55	2098,22	1,24	-0,06	397,71	432,21	430,67	397,71
25,00	56,67	40,83	40,83	0,89	0,04	1,86	1019,34	2335,84	1,30	-0,14	399,84	434,49	431,04	399,84
28,33	61,11	44,72	44,72	0,89	0,05	1,92	1121,33	2594,27	1,34	-0,25	401,89	436,63	431,06	401,89
31,67	65,56	48,61	48,61	0,90	0,05	1,94	1230,88	2875,31	1,35	-0,40	403,85	438,61	430,65	403,85
35,00	70,00	52,50	52,50	0,90	0,06	1,91	1348,38	3181,21	1,33	-0,60	405,71	440,44	429,70	405,71
5,00	30,00	17,50	17,50	0,90	0,02	1,07	546,52	1175,14	0,75	0,01	391,29	424,87	425,23	391,29
8,33	34,44	21,39	21,39	0,90	0,02	1,16	610,42	1328,23	0,81	-0,03	393,67	427,73	426,69	393,67



FINAL PROJECT

Date: 19.06.2014

Page: 98

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

11,67	38,89	25,28	25,28	0,91	0,03	1,25	679,86	1496,04	0,87	-0,07	395,98	430,46	427,99	395,98
15,00	43,33	29,17	29,17	0,91	0,03	1,33	755,15	1679,57	0,93	-0,12	398,24	433,07	429,11	398,24
18,33	47,78	33,06	33,06	0,91	0,03	1,41	836,60	1879,91	0,98	-0,18	400,42	435,54	430,02	400,42
21,67	52,22	36,94	36,94	0,91	0,04	1,48	924,55	2098,22	1,03	-0,26	402,53	437,88	430,67	402,53
25,00	56,67	40,83	40,83	0,92	0,04	1,54	1019,34	2335,84	1,07	-0,37	404,56	440,07	431,04	404,56
28,33	61,11	44,72	44,72	0,92	0,04	1,57	1121,33	2594,27	1,10	-0,49	406,50	442,11	431,06	406,50
31,67	65,56			0,92										
35,00	70,00			0,92										
5,00	30,00	17,50	17,50	0,93	0,02	0,88	546,52	1175,14	0,61	-0,12	396,56	430,88	425,23	396,56
8,33	34,44	21,39	21,39	0,93	0,02	0,95	610,42	1328,23	0,66	-0,17	398,85	433,68	426,69	398,85
11,67	38,89	25,28	25,28	0,93	0,03	1,02	679,86	1496,04	0,71	-0,22	401,08	436,34	427,99	401,08
15,00	43,33	29,17	29,17	0,93	0,03	1,09	755,15	1679,57	0,76	-0,29	403,24	438,88	429,11	403,24
18,33	47,78	33,06	33,06	0,94	0,03	1,15	836,60	1879,91	0,80	-0,36	405,33	441,27	430,02	405,33
21,67	52,22	36,94	36,94	0,94	0,04	1,20	924,55	2098,22	0,84	-0,46	407,34	443,52	430,67	407,34
25,00	56,67			0,94										
28,33	61,11			0,94										
31,67	65,56			0,95										
35,00	70,00			0,95										
5,00	30,00	17,50	17,50	0,95	0,02	0,70	546,52	1175,14	0,49	-0,24	401,82	436,87	425,23	401,82
8,33	34,44	21,39	21,39	0,95	0,02	0,75	610,42	1328,23	0,53	-0,30	404,02	439,60	426,69	404,02
11,67	38,89	25,28	25,28	0,96	0,03	0,81	679,86	1496,04	0,56	-0,37	406,16	442,20	427,99	406,16
15,00	43,33			0,96										
18,33	47,78			0,96										



FINAL PROJECT

Date: 19.06.2014

Page: 99

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

21,67	52,22			0,96											
25,00	56,67			0,97											
28,33	61,11	44,72	44,72	0,97	0,04	0,94	1121,33	2594,27	0,65	-0,94	415,70	453,25	431,06	415,70	
31,67	65,56	48,61	48,61	0,97	0,05	0,90	1230,88	2875,31	0,62	-1,14	417,32	455,02	430,65	417,32	
35,00	70,00	52,50	52,50	0,97	0,05	0,80	1348,38	3181,21	0,56	-1,39	418,84	456,64	429,70	418,84	
5,00	30,00	17,50	17,50	0,98	0,02	0,53	546,52	1175,14	0,37	-0,36	407,07	442,93	425,23	407,07	
8,33	34,44	21,39	21,39	0,98	0,02	0,57	610,42	1328,23	0,40	-0,43	409,19	445,63	426,69	409,19	
11,67	38,89	25,28	25,28	0,98	0,03	0,60	679,86	1496,04	0,42	-0,51	411,24	448,21	427,99	411,24	
15,00	43,33	29,17	29,17	0,98	0,03	0,64	755,15	1679,57	0,44	-0,60	413,22	450,64	429,11	413,22	
18,33	47,78	33,06	33,06	0,99	0,03	0,66	836,60	1879,91	0,46	-0,71	415,12	452,94	430,02	415,12	
21,67	52,22	36,94	36,94	0,99	0,03	0,67	924,55	2098,22	0,47	-0,83	416,93	455,09	430,67	416,93	
25,00	56,67	40,83	40,83	0,99	0,04	0,67	1019,34	2335,84	0,47	-0,98	418,65	457,09	431,04	418,65	
28,33	61,11	44,72	44,72	0,99	0,04	0,64	1121,33	2594,27	0,45	-1,16	420,28	458,94	431,06	420,28	
31,67	65,56	48,61	48,61	1,00	0,05	0,58	1230,88	2875,31	0,40	-1,37	421,80	460,62	430,65	421,80	
35,00	70,00	52,50	52,50	1,00	0,05	0,47	1348,38	3181,21	0,33	-1,63	423,20	462,15	429,70	423,20	



FINAL PROJECT

Date: 19.06.2014

Page: 100

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3.6.1 Summary R407 C---5000 rpm, 11.4 cc/rev

Table 44-Summary R407C-5000 rpm, 11.4 cc/rev- improvement

	mref [g/s]	flow (l/min)	P1 (kPa)	P2	P3	Q (kW)	Qres (kW)	h1	h2	h3	h4
Min	20,33	0,47	546,52	1175,14	860,82716	0,33	-1,63	359,51	388,30	425,23	359,51
Max	63,61	4,21	1348,38	3181,21	2264,79558	2,93	1,19	423,20	462,15	431,06	423,20
X1_para minimo	0,98	1,00	0,75	0,75	0,75	1,00	1,00	0,75	0,75	0,75	0,75
X1_para maximo	0,77	0,77	0,77	0,77	0,77	0,77	0,77	1,00	1,00	0,77	1,00



FINAL PROJECT

Date: 19.06.2014

Page: 101

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3.7 REFRIGERANT R407 C --> 3000 rpm, 7cc/rev

Table 45-R407C- 3000 rpm, 7cc/rev- improvement

T1	T2	T3	T4	X1	mref	flow_l_min	P1	P2	Q	Qres	h1	h2	h3	h4
5,00	30,00	17,50	17,50	0,75	0,01	0,91	546,52	1175,14	0,63	0,36	359,51	388,30	425,23	359,51
8,33	34,44	21,39	21,39	0,75	0,01	0,99	610,42	1328,23	0,69	0,38	362,40	391,55	426,69	362,40
11,67	38,89	25,28	25,28	0,76	0,01	1,07	679,86	1496,04	0,75	0,40	365,25	394,71	427,99	365,25
15,00	43,33	29,17	29,17	0,76	0,01	1,15	755,15	1679,57	0,80	0,41	368,06	397,76	429,11	368,06
18,33	47,78	33,06	33,06	0,76	0,01	1,24	836,60	1879,91	0,86	0,43	370,81	400,71	430,02	370,81
21,67	52,22	36,94	36,94	0,76	0,02	1,32	924,55	2098,22	0,92	0,43	373,50	403,55	430,67	373,50
25,00	56,67	40,83	40,83	0,77	0,02	1,39	1019,34	2335,84	0,97	0,44	376,14	406,29	431,04	376,14
28,33	61,11	44,72	44,72	0,77	0,02	1,46	1121,33	2594,27	1,02	0,43	378,71	408,90	431,06	378,71
31,67	65,56	48,61	48,61	0,77	0,02	1,52	1230,88	2875,31	1,06	0,41	381,21	411,40	430,65	381,21
35,00	70,00	52,50	52,50	0,77	0,02	1,55	1348,38	3181,21	1,08	0,37	383,63	413,78	429,70	383,63
5,00	30,00	17,50	17,50	0,78	0,01	0,81	546,52	1175,14	0,56	0,29	364,82	394,45	425,23	364,82
8,33	34,44	21,39	21,39	0,78	0,01	0,88	610,42	1328,23	0,61	0,30	367,63	397,64	426,69	367,63
11,67	38,89	25,28	25,28	0,78	0,01	0,95	679,86	1496,04	0,66	0,31	370,40	400,72	427,99	370,40
15,00	43,33	29,17	29,17	0,78	0,01	1,03	755,15	1679,57	0,71	0,32	373,11	403,70	429,11	373,11
18,33	47,78	33,06	33,06	0,79	0,01	1,10	836,60	1879,91	0,76	0,33	375,76	406,57	430,02	375,76
21,67	52,22	36,94	36,94	0,79	0,02	1,17	924,55	2098,22	0,81	0,33	378,36	409,33	430,67	378,36



FINAL PROJECT

Date: 19.06.2014

Page: 102

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

25,00	56,67	40,83	40,83	0,79	0,02	1,23	1019,34	2335,84	0,86	0,33	380,89	411,97	431,04	380,89
28,33	61,11	44,72	44,72	0,79	0,02	1,29	1121,33	2594,27	0,90	0,31	383,36	414,49	431,06	383,36
31,67	65,56	48,61	48,61	0,80	0,02	1,34	1230,88	2875,31	0,93	0,29	385,75	416,88	430,65	385,75
35,00	70,00	52,50	52,50	0,80	0,02	1,36	1348,38	3181,21	0,95	0,24	388,06	419,15	429,70	388,06
5,00	30,00	17,50	17,50	0,80	0,01	0,72	546,52	1175,14	0,50	0,22	370,13	400,58	425,23	370,13
8,33	34,44	21,39	21,39	0,80	0,01	0,78	610,42	1328,23	0,54	0,23	372,86	403,70	426,69	372,86
11,67	38,89	25,28	25,28	0,81	0,01	0,84	679,86	1496,04	0,59	0,24	375,53	406,71	427,99	375,53
15,00	43,33	29,17	29,17	0,81	0,01	0,91	755,15	1679,57	0,63	0,24	378,15	409,62	429,11	378,15
18,33	47,78	33,06	33,06	0,81	0,01	0,97	836,60	1879,91	0,67	0,24	380,71	412,41	430,02	380,71
21,67	52,22	36,94	36,94	0,81	0,02	1,03	924,55	2098,22	0,72	0,24	383,21	415,08	430,67	383,21
25,00	56,67	40,83	40,83	0,82	0,02	1,08	1019,34	2335,84	0,76	0,22	385,64	417,63	431,04	385,64
28,33	61,11	44,72	44,72	0,82	0,02	1,13	1121,33	2594,27	0,79	0,20	388,00	420,05	431,06	388,00
31,67	65,56	48,61	48,61	0,82	0,02	1,17	1230,88	2875,31	0,81	0,17	390,29	422,35	430,65	390,29
35,00	70,00	52,50	52,50	0,82	0,02	1,18	1348,38	3181,21	0,82	0,12	392,49	424,50	429,70	392,49
5,00	30,00	17,50	17,50	0,83	0,01	0,63	546,52	1175,14	0,44	0,16	375,43	406,69	425,23	375,43
8,33	34,44	21,39	21,39	0,83	0,01	0,68	610,42	1328,23	0,48	0,17	378,07	409,74	426,69	378,07
11,67	38,89	25,28	25,28	0,83	0,01	0,74	679,86	1496,04	0,51	0,17	380,65	412,68	427,99	380,65
15,00	43,33	29,17	29,17	0,83	0,01	0,79	755,15	1679,57	0,55	0,16	383,18	415,51	429,11	383,18
18,33	47,78	33,06	33,06	0,84	0,01	0,85	836,60	1879,91	0,59	0,16	385,65	418,22	430,02	385,65
21,67	52,22	36,94	36,94	0,84	0,01	0,90	924,55	2098,22	0,63	0,14	388,05	420,81	430,67	388,05
25,00	56,67	40,83	40,83	0,84	0,02	0,94	1019,34	2335,84	0,66	0,13	390,38	423,27	431,04	390,38
28,33	61,11	44,72	44,72	0,84	0,02	0,98	1121,33	2594,27	0,68	0,10	392,64	425,60	431,06	392,64
31,67	65,56	48,61	48,61	0,85	0,02	1,01	1230,88	2875,31	0,70	0,06	394,82	427,79	430,65	394,82



FINAL PROJECT

Date: 19.06.2014

Page: 103

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

35,00	70,00	52,50	52,50	0,85	0,02	1,01	1348,38	3181,21	0,71	0,00	396,90	429,83	429,70	396,90
5,00	30,00	17,50	17,50	0,85	0,01	0,55	546,52	1175,14	0,38	0,11	380,72	412,77	425,23	380,72
8,33	34,44	21,39	21,39	0,85	0,01	0,59	610,42	1328,23	0,41	0,10	383,28	415,76	426,69	383,28
11,67	38,89	25,28	25,28	0,86	0,01	0,64	679,86	1496,04	0,45	0,10	385,77	418,63	427,99	385,77
15,00	43,33	29,17	29,17	0,86	0,01	0,69	755,15	1679,57	0,48	0,09	388,21	421,39	429,11	388,21
18,33	47,78	33,06	33,06	0,86	0,01	0,73	836,60	1879,91	0,51	0,08	390,58	424,02	430,02	390,58
21,67	52,22	36,94	36,94	0,86	0,01	0,77	924,55	2098,22	0,54	0,06	392,89	426,52	430,67	392,89
25,00	56,67	40,83	40,83	0,87	0,02	0,81	1019,34	2335,84	0,57	0,03	395,12	428,89	431,04	395,12
28,33	61,11	44,72	44,72	0,87	0,02	0,84	1121,33	2594,27	0,59	0,00	397,27	431,12	431,06	397,27
31,67	65,56	48,61	48,61	0,87	0,02	0,86	1230,88	2875,31	0,60	-0,05	399,34	433,21	430,65	399,34
35,00	70,00	52,50	52,50	0,87	0,02	0,85	1348,38	3181,21	0,60	-0,11	401,31	435,15	429,70	401,31
5,00	30,00	17,50	17,50	0,88	0,01	0,47	546,52	1175,14	0,33	0,05	386,01	418,83	425,23	386,01
8,33	34,44	21,39	21,39	0,88	0,01	0,51	610,42	1328,23	0,35	0,05	388,48	421,75	426,69	388,48
11,67	38,89	25,28	25,28	0,88	0,01	0,55	679,86	1496,04	0,38	0,04	390,88	424,56	427,99	390,88
15,00	43,33	29,17	29,17	0,88	0,01	0,59	755,15	1679,57	0,41	0,02	393,23	427,24	429,11	393,23
18,33	47,78	33,06	33,06	0,89	0,01	0,62	836,60	1879,91	0,43	0,00	395,51	429,79	430,02	395,51
21,67	52,22	36,94	36,94	0,89	0,01	0,66	924,55	2098,22	0,46	-0,02	397,71	432,21	430,67	397,71
25,00	56,67	40,83	40,83	0,89	0,02	0,69	1019,34	2335,84	0,48	-0,05	399,84	434,49	431,04	399,84
28,33	61,11	44,72	44,72	0,89	0,02	0,71	1121,33	2594,27	0,49	-0,09	401,89	436,63	431,06	401,89
31,67	65,56	48,61	48,61	0,90	0,02	0,71	1230,88	2875,31	0,50	-0,15	403,85	438,61	430,65	403,85
35,00	70,00	52,50	52,50	0,90	0,02	0,70	1348,38	3181,21	0,49	-0,22	405,71	440,44	429,70	405,71
5,00	30,00	17,50	17,50	0,90	0,01	0,39	546,52	1175,14	0,27	0,00	391,29	424,87	425,23	391,29
8,33	34,44	21,39	21,39	0,90	0,01	0,43	610,42	1328,23	0,30	-0,01	393,67	427,73	426,69	393,67



FINAL PROJECT

Date: 19.06.2014

Page: 104

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

11,67	38,89	25,28	25,28	0,91	0,01	0,46	679,86	1496,04	0,32	-0,02	395,98	430,46	427,99	395,98
15,00	43,33	29,17	29,17	0,91	0,01	0,49	755,15	1679,57	0,34	-0,04	398,24	433,07	429,11	398,24
18,33	47,78	33,06	33,06	0,91	0,01	0,52	836,60	1879,91	0,36	-0,07	400,42	435,54	430,02	400,42
21,67	52,22	36,94	36,94	0,91	0,01	0,55	924,55	2098,22	0,38	-0,10	402,53	437,88	430,67	402,53
25,00	56,67	40,83	40,83	0,92	0,01	0,57	1019,34	2335,84	0,40	-0,13	404,56	440,07	431,04	404,56
28,33	61,11	44,72	44,72	0,92	0,02	0,58	1121,33	2594,27	0,40	-0,18	406,50	442,11	431,06	406,50
31,67	65,56			0,92										
35,00	70,00			0,92										
5,00	30,00	17,50	17,50	0,93	0,01	0,32	546,52	1175,14	0,23	-0,04	396,56	430,88	425,23	396,56
8,33	34,44	21,39	21,39	0,93	0,01	0,35	610,42	1328,23	0,24	-0,06	398,85	433,68	426,69	398,85
11,67	38,89	25,28	25,28	0,93	0,01	0,38	679,86	1496,04	0,26	-0,08	401,08	436,34	427,99	401,08
15,00	43,33	29,17	29,17	0,93	0,01	0,40	755,15	1679,57	0,28	-0,11	403,24	438,88	429,11	403,24
18,33	47,78	33,06	33,06	0,94	0,01	0,42	836,60	1879,91	0,29	-0,13	405,33	441,27	430,02	405,33
21,67	52,22	36,94	36,94	0,94	0,01	0,44	924,55	2098,22	0,31	-0,17	407,34	443,52	430,67	407,34
25,00	56,67			0,94										
28,33	61,11			0,94										
31,67	65,56			0,95										
35,00	70,00			0,95										
5,00	30,00	17,50	17,50	0,95	0,01	0,26	546,52	1175,14	0,18	-0,09	401,82	436,87	425,23	401,82
8,33	34,44	21,39	21,39	0,95	0,01	0,28	610,42	1328,23	0,19	-0,11	404,02	439,60	426,69	404,02
11,67	38,89	25,28	25,28	0,96	0,01	0,30	679,86	1496,04	0,21	-0,13	406,16	442,20	427,99	406,16
15,00	43,33			0,96										
18,33	47,78			0,96										



FINAL PROJECT

Date: 19.06.2014

Page: 105

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

21,67	52,22			0,96											
25,00	56,67			0,97											
28,33	61,11	44,72	44,72	0,97	0,02	0,35	1121,33	2594,27	0,24	-0,35	415,70	453,25	431,06	415,70	
31,67	65,56	48,61	48,61	0,97	0,02	0,33	1230,88	2875,31	0,23	-0,42	417,32	455,02	430,65	417,32	
35,00	70,00	52,50	52,50	0,97	0,02	0,30	1348,38	3181,21	0,21	-0,51	418,84	456,64	429,70	418,84	
5,00	30,00	17,50	17,50	0,98	0,01	0,20	546,52	1175,14	0,14	-0,13	407,07	442,93	425,23	407,07	
8,33	34,44	21,39	21,39	0,98	0,01	0,21	610,42	1328,23	0,15	-0,16	409,19	445,63	426,69	409,19	
11,67	38,89	25,28	25,28	0,98	0,01	0,22	679,86	1496,04	0,16	-0,19	411,24	448,21	427,99	411,24	
15,00	43,33	29,17	29,17	0,98	0,01	0,23	755,15	1679,57	0,16	-0,22	413,22	450,64	429,11	413,22	
18,33	47,78	33,06	33,06	0,99	0,01	0,24	836,60	1879,91	0,17	-0,26	415,12	452,94	430,02	415,12	
21,67	52,22	36,94	36,94	0,99	0,01	0,25	924,55	2098,22	0,17	-0,31	416,93	455,09	430,67	416,93	
25,00	56,67	40,83	40,83	0,99	0,01	0,25	1019,34	2335,84	0,17	-0,36	418,65	457,09	431,04	418,65	
28,33	61,11	44,72	44,72	0,99	0,02	0,24	1121,33	2594,27	0,16	-0,43	420,28	458,94	431,06	420,28	
31,67	65,56	48,61	48,61	1,00	0,02	0,21	1230,88	2875,31	0,15	-0,50	421,80	460,62	430,65	421,80	
35,00	70,00	52,50	52,50	1,00	0,02	0,17	1348,38	3181,21	0,12	-0,60	423,20	462,15	429,70	423,20	



FINAL PROJECT

Date: 19.06.2014

Page: 106

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3.7.1 Summary R407 C--- 3000 rpm, 7 cc/rev

Table 46-Summary R407C-3000rpm, 7cc/rev- improvement

	mref [g/s]	flow (l/min)	P1 (kPa)	P2	P3	Q (kW)	Qres (kW)	h1	h2	h3	h4
min	7,49	0,17	546,52	1175,14	860,82716	0,12	-0,60	359,51	388,30	425,23	359,51
max	23,43	1,55	1348,38	3181,21	2264,79558	1,08	0,44	423,20	462,15	431,06	423,20
X1_para minimo	0,98	1,00	0,75	0,75	0,75	1,00	1,00	0,75	0,75	0,75	0,75
X1_para maximo	0,77	0,77	0,77	0,77	0,77	0,77	0,77	1,00	1,00	0,77	1,00



FINAL PROJECT

Date: 19.06.2014

Page: 107

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3.8 REFRIGERANT R 22--> 5000 rpm, 11.4cc/rev

Table 47- R22- 5000rpm, 11.4 cc/rev- improvement

T1	T2	T3	T4	X1	mref	flow_l_min	P1	P2	Q	Qres	h1	h2	h3	h4
5,00	30,00	17,50	17,50	0,75	0,03	2,44	584,29	1192,30	1,70	0,98	356,58	382,06	416,99	356,58
8,33	34,44	21,39	21,39	0,75	0,03	2,63	647,63	1336,40	1,83	1,03	358,95	384,91	418,07	358,95
11,67	38,89	25,28	25,28	0,76	0,03	2,82	715,98	1492,97	1,96	1,07	361,28	387,68	419,02	361,28
15,00	43,33	29,17	29,17	0,76	0,04	3,02	789,57	1662,66	2,10	1,10	363,56	390,37	419,83	363,56
18,33	47,78	33,06	33,06	0,76	0,04	3,21	868,65	1846,17	2,24	1,13	365,81	392,96	420,50	365,81
21,67	52,22	36,94	36,94	0,76	0,04	3,40	953,47	2044,22	2,37	1,14	368,00	395,46	420,99	368,00
25,00	56,67	40,83	40,83	0,77	0,05	3,59	1044,28	2257,56	2,50	1,15	370,15	397,86	421,28	370,15
28,33	61,11	44,72	44,72	0,77	0,05	3,76	1141,34	2486,99	2,62	1,13	372,24	400,16	421,35	372,24
31,67	65,56	48,61	48,61	0,77	0,06	3,91	1244,92	2733,38	2,73	1,09	374,27	402,36	421,16	374,27
35,00	70,00	52,50	52,50	0,77	0,06	4,03	1355,28	2997,65	2,81	1,03	376,24	404,44	420,67	376,24
5,00	30,00	17,50	17,50	0,78	0,03	2,16	584,29	1192,30	1,51	0,79	361,65	388,04	416,99	361,65
8,33	34,44	21,39	21,39	0,78	0,03	2,33	647,63	1336,40	1,62	0,82	363,95	390,84	418,07	363,95
11,67	38,89	25,28	25,28	0,78	0,03	2,50	715,98	1492,97	1,74	0,84	366,21	393,55	419,02	366,21
15,00	43,33	29,17	29,17	0,78	0,04	2,67	789,57	1662,66	1,86	0,86	368,42	396,17	419,83	368,42
18,33	47,78	33,06	33,06	0,79	0,04	2,84	868,65	1846,17	1,98	0,86	370,58	398,70	420,50	370,58
21,67	52,22	36,94	36,94	0,79	0,04	3,01	953,47	2044,22	2,10	0,86	372,69	401,12	420,99	372,69



FINAL PROJECT

Date: 19.06.2014

Page: 108

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

25,00	56,67	40,83	40,83	0,79	0,05	3,17	1044,28	2257,56	2,21	0,85	374,76	403,45	421,28	374,76
28,33	61,11	44,72	44,72	0,79	0,05	3,31	1141,34	2486,99	2,31	0,81	376,76	405,67	421,35	376,76
31,67	65,56	48,61	48,61	0,80	0,06	3,44	1244,92	2733,38	2,39	0,75	378,71	407,78	421,16	378,71
35,00	70,00	52,50	52,50	0,80	0,06	3,53	1355,28	2997,65	2,46	0,67	380,59	409,78	420,67	380,59
5,00	30,00	17,50	17,50	0,80	0,03	1,90	584,29	1192,30	1,33	0,61	366,73	394,03	416,99	366,73
8,33	34,44	21,39	21,39	0,80	0,03	2,05	647,63	1336,40	1,43	0,62	368,95	396,77	418,07	368,95
11,67	38,89	25,28	25,28	0,81	0,03	2,20	715,98	1492,97	1,53	0,63	371,13	399,42	419,02	371,13
15,00	43,33	29,17	29,17	0,81	0,04	2,35	789,57	1662,66	1,63	0,63	373,27	401,98	419,83	373,27
18,33	47,78	33,06	33,06	0,81	0,04	2,49	868,65	1846,17	1,74	0,62	375,35	404,44	420,50	375,35
21,67	52,22	36,94	36,94	0,81	0,04	2,63	953,47	2044,22	1,84	0,60	377,39	406,79	420,99	377,39
25,00	56,67	40,83	40,83	0,82	0,05	2,77	1044,28	2257,56	1,93	0,56	379,37	409,04	421,28	379,37
28,33	61,11	44,72	44,72	0,82	0,05	2,89	1141,34	2486,99	2,01	0,51	381,29	411,18	421,35	381,29
31,67	65,56	48,61	48,61	0,82	0,05	2,99	1244,92	2733,38	2,08	0,44	383,15	413,21	421,16	383,15
35,00	70,00	52,50	52,50	0,82	0,06	3,06	1355,28	2997,65	2,13	0,33	384,94	415,11	420,67	384,94
5,00	30,00	17,50	17,50	0,83	0,03	1,66	584,29	1192,30	1,16	0,43	371,80	400,01	416,99	371,80
8,33	34,44	21,39	21,39	0,83	0,03	1,79	647,63	1336,40	1,24	0,43	373,95	402,70	418,07	373,95
11,67	38,89	25,28	25,28	0,83	0,03	1,91	715,98	1492,97	1,33	0,43	376,06	405,29	419,02	376,06
15,00	43,33	29,17	29,17	0,83	0,03	2,04	789,57	1662,66	1,42	0,41	378,12	407,79	419,83	378,12
18,33	47,78	33,06	33,06	0,84	0,04	2,16	868,65	1846,17	1,51	0,39	380,13	410,18	420,50	380,13
21,67	52,22	36,94	36,94	0,84	0,04	2,28	953,47	2044,22	1,59	0,35	382,08	412,46	420,99	382,08
25,00	56,67	40,83	40,83	0,84	0,04	2,39	1044,28	2257,56	1,67	0,30	383,98	414,63	421,28	383,98
28,33	61,11	44,72	44,72	0,84	0,05	2,49	1141,34	2486,99	1,73	0,23	385,82	416,69	421,35	385,82
31,67	65,56	48,61	48,61	0,85	0,05	2,56	1244,92	2733,38	1,79	0,13	387,59	418,63	421,16	387,59



FINAL PROJECT

Date: 19.06.2014

Page: 109

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

35,00	70,00	52,50	52,50	0,85	0,06	2,61	1355,28	2997,65	1,82	0,01	389,29	420,45	420,67	389,29
5,00	30,00	17,50	17,50	0,85	0,02	1,43	584,29	1192,30	1,00	0,27	376,87	406,00	416,99	376,87
8,33	34,44	21,39	21,39	0,85	0,03	1,54	647,63	1336,40	1,07	0,26	378,95	408,63	418,07	378,95
11,67	38,89	25,28	25,28	0,86	0,03	1,64	715,98	1492,97	1,15	0,24	380,99	411,16	419,02	380,99
15,00	43,33	29,17	29,17	0,86	0,03	1,75	789,57	1662,66	1,22	0,21	382,97	413,59	419,83	382,97
18,33	47,78	33,06	33,06	0,86	0,04	1,85	868,65	1846,17	1,29	0,17	384,90	415,92	420,50	384,90
21,67	52,22	36,94	36,94	0,86	0,04	1,95	953,47	2044,22	1,36	0,11	386,78	418,13	420,99	386,78
25,00	56,67	40,83	40,83	0,87	0,04	2,04	1044,28	2257,56	1,42	0,05	388,59	420,23	421,28	388,59
28,33	61,11	44,72	44,72	0,87	0,05	2,11	1141,34	2486,99	1,47	-0,04	390,34	422,20	421,35	390,34
31,67	65,56	48,61	48,61	0,87	0,05	2,16	1244,92	2733,38	1,51	-0,15	392,02	424,06	421,16	392,02
35,00	70,00	52,50	52,50	0,87	0,06	2,19	1355,28	2997,65	1,52	-0,29	393,63	425,79	420,67	393,63
5,00	30,00	17,50	17,50	0,88	0,02	1,21	584,29	1192,30	0,85	0,12	381,94	411,98	416,99	381,94
8,33	34,44	21,39	21,39	0,88	0,03	1,30	647,63	1336,40	0,91	0,09	383,95	414,56	418,07	383,95
11,67	38,89	25,28	25,28	0,88	0,03	1,39	715,98	1492,97	0,97	0,06	385,92	417,04	419,02	385,92
15,00	43,33	29,17	29,17	0,88	0,03	1,48	789,57	1662,66	1,03	0,01	387,82	419,40	419,83	387,82
18,33	47,78	33,06	33,06	0,89	0,04	1,56	868,65	1846,17	1,09	-0,04	389,68	421,66	420,50	389,68
21,67	52,22	36,94	36,94	0,89	0,04	1,64	953,47	2044,22	1,14	-0,11	391,47	423,80	420,99	391,47
25,00	56,67	40,83	40,83	0,89	0,04	1,70	1044,28	2257,56	1,19	-0,19	393,20	425,82	421,28	393,20
28,33	61,11	44,72	44,72	0,89	0,05	1,75	1141,34	2486,99	1,22	-0,29	394,87	427,72	421,35	394,87
31,67	65,56	48,61	48,61	0,90	0,05	1,79	1244,92	2733,38	1,24	-0,42	396,46	429,49	421,16	396,46
35,00	70,00	52,50	52,50	0,90	0,05	1,79	1355,28	2997,65	1,24	-0,57	397,98	431,12	420,67	397,98
5,00	30,00	17,50	17,50	0,90	0,02	1,01	584,29	1192,30	0,70	-0,02	387,02	417,97	416,99	387,02
8,33	34,44	21,39	21,39	0,90	0,03	1,08	647,63	1336,40	0,75	-0,06	388,96	420,49	418,07	388,96



FINAL PROJECT

Date: 19.06.2014

Page: 110

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

11,67	38,89	25,28	25,28	0,91	0,03	1,15	715,98	1492,97	0,80	-0,11	390,84	422,91	419,02	390,84
15,00	43,33	29,17	29,17	0,91	0,03	1,22	789,57	1662,66	0,85	-0,17	392,68	425,21	419,83	392,68
18,33	47,78	33,06	33,06	0,91	0,03	1,28	868,65	1846,17	0,89	-0,24	394,45	427,40	420,50	394,45
21,67	52,22	36,94	36,94	0,91	0,04	1,34	953,47	2044,22	0,93	-0,32	396,17	429,46	420,99	396,17
25,00	56,67	40,83	40,83	0,92	0,04	1,39	1044,28	2257,56	0,97	-0,42	397,82	431,41	421,28	397,82
28,33	61,11	44,72	44,72	0,92	0,04	1,42	1141,34	2486,99	0,99	-0,53	399,40	433,23	421,35	399,40
31,67	65,56	48,61	48,61	0,92	0,05	1,43	1244,92	2733,38	0,99	-0,67	400,90	434,91	421,16	400,90
35,00	70,00	52,50	52,50	0,92	0,05	1,41	1355,28	2997,65	0,98	-0,84	402,33	436,47	420,67	402,33
5,00	30,00	17,50	17,50	0,93	0,02	0,82	584,29	1192,30	0,57	-0,16	392,09	423,95	416,99	392,09
8,33	34,44	21,39	21,39	0,93	0,03	0,87	647,63	1336,40	0,61	-0,21	393,96	426,42	418,07	393,96
11,67	38,89	25,28	25,28	0,93	0,03	0,93	715,98	1492,97	0,64	-0,27	395,77	428,78	419,02	395,77
15,00	43,33	29,17	29,17	0,93	0,03	0,98	789,57	1662,66	0,68	-0,34	397,53	431,02	419,83	397,53
18,33	47,78	33,06	33,06	0,94	0,03	1,02	868,65	1846,17	0,71	-0,42	399,23	433,14	420,50	399,23
21,67	52,22	36,94	36,94	0,94	0,04	1,06	953,47	2044,22	0,74	-0,52	400,86	435,13	420,99	400,86
25,00	56,67	40,83	40,83	0,94	0,04	1,08	1044,28	2257,56	0,76	-0,63	402,43	437,01	421,28	402,43
28,33	61,11	44,72	44,72	0,94	0,04	1,10	1141,34	2486,99	0,76	-0,76	403,92	438,77	421,35	403,92
31,67	65,56	48,61	48,61	0,95	0,05	1,09	1244,92	2733,38	0,76	-0,92	405,34	440,41	421,16	405,34
35,00	70,00	52,50	52,50	0,95	0,05	1,05	1355,28	2997,65	0,73	-1,11	406,67	441,92	420,67	406,67
5,00	30,00	17,50	17,50	0,95	0,02	0,63	584,29	1192,30	0,44	-0,29	397,16	429,94	416,99	397,16
8,33	34,44	21,39	21,39	0,95	0,02	0,67	647,63	1336,40	0,47	-0,35	398,96	432,35	418,07	398,96
11,67	38,89	25,28	25,28	0,96	0,03	0,71	715,98	1492,97	0,50	-0,42	400,70	434,65	419,02	400,70
15,00	43,33	29,17	29,17	0,96	0,03	0,74	789,57	1662,66	0,52	-0,51	402,38	436,85	419,83	402,38
18,33	47,78	33,06	33,06	0,96	0,03	0,77	868,65	1846,17	0,54	-0,60	404,00	438,92	420,50	404,00



FINAL PROJECT

Date: **19.06.2014**

Page: **111**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

21,67	52,22	36,94	36,94	0,96	0,04	0,79	953,47	2044,22	0,55	-0,71	405,56	440,89	420,99	405,56
25,00	56,67	40,83	40,83	0,97	0,04	0,80	1044,28	2257,56	0,56	-0,84	407,04	442,72	421,28	407,04
28,33	61,11	44,72	44,72	0,97	0,04	0,79	1141,34	2486,99	0,55	-0,99	408,45	444,44	421,35	408,45
31,67	65,56	48,61	48,61	0,97	0,05	0,76	1244,92	2733,38	0,53	-1,16	409,78	446,02	421,16	409,78
35,00	70,00	52,50	52,50	0,97	0,05	0,70	1355,28	2997,65	0,49	-1,36	411,02	447,46	420,67	411,02
5,00	30,00	17,50	17,50	0,98	0,02	0,46	584,29	1192,30	0,32	-0,41	402,23	436,00	416,99	402,23
8,33	34,44	21,39	21,39	0,98	0,02	0,48	647,63	1336,40	0,34	-0,49	403,96	438,40	418,07	403,96
11,67	38,89	25,28	25,28	0,98	0,03	0,51	715,98	1492,97	0,35	-0,57	405,63	440,68	419,02	405,63
15,00	43,33	29,17	29,17	0,98	0,03	0,52	789,57	1662,66	0,36	-0,67	407,23	442,84	419,83	407,23
18,33	47,78	33,06	33,06	0,99	0,03	0,53	868,65	1846,17	0,37	-0,77	408,78	444,88	420,50	408,78
21,67	52,22	36,94	36,94	0,99	0,03	0,54	953,47	2044,22	0,37	-0,90	410,25	446,79	420,99	410,25
25,00	56,67	40,83	40,83	0,99	0,04	0,53	1044,28	2257,56	0,37	-1,04	411,65	448,58	421,28	411,65
28,33	61,11	44,72	44,72	0,99	0,04	0,50	1141,34	2486,99	0,35	-1,20	412,98	450,23	421,35	412,98
31,67	65,56	48,61	48,61	1,00	0,05	0,45	1244,92	2733,38	0,32	-1,39	414,22	451,75	421,16	414,22
35,00	70,00	52,50	52,50	1,00	0,05	0,38	1355,28	2997,65	0,26	-1,61	415,37	453,12	420,67	415,37



FINAL PROJECT

Date: 19.06.2014

Page: 112

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3.8.1 Summary R 22--- 5000 rpm, 11.4 cc/rev

Table 48-Summary R22- 5000rpm, 11.4 cc/rev- improvement

	mref [g/s]	flow (l/min)	P1 (kPa)	P2	P3	Q (kW)	Qres (kW)	h1	h2	h3	h4
min	21,69	0,38	584,29	1192,30	888,295375	0,26	-1,61	356,58	382,06	416,99	356,58
max	63,26	4,03	1355,28	2997,65	2176,46532	2,81	1,15	415,37	453,12	421,35	415,37
X1_para minimo	0,98	1,00	0,75	0,75	0,75	1,00	1,00	0,75	0,75	0,75	0,75
X1_para maximo	0,77	0,77	0,77	0,77	0,77	0,77	0,77	1,00	1,00	0,77	1,00



FINAL PROJECT

Date: 19.06.2014

Page: 113

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3.9 REFRIGERANT R 22--> 3000 rpm, 7cc/rev

Table 49-R22- 3000 rpm, 7 cc/rev- improvement

T1	T2	T3	T4	X1	mref	flow_l_min	P1	P2	Q	Qres	h1	h2	h3	h4
5,00	30,00	17,50	17,50	0,75	0,01	0,90	584,29	1192,30	0,63	0,36	356,58	382,06	416,99	356,58
8,33	34,44	21,39	21,39	0,75	0,01	0,97	647,63	1336,40	0,67	0,38	358,95	384,91	418,07	358,95
11,67	38,89	25,28	25,28	0,76	0,01	1,04	715,98	1492,97	0,72	0,39	361,28	387,68	419,02	361,28
15,00	43,33	29,17	29,17	0,76	0,01	1,11	789,57	1662,66	0,77	0,41	363,56	390,37	419,83	363,56
18,33	47,78	33,06	33,06	0,76	0,02	1,18	868,65	1846,17	0,82	0,42	365,81	392,96	420,50	365,81
21,67	52,22	36,94	36,94	0,76	0,02	1,25	953,47	2044,22	0,87	0,42	368,00	395,46	420,99	368,00
25,00	56,67	40,83	40,83	0,77	0,02	1,32	1044,28	2257,56	0,92	0,42	370,15	397,86	421,28	370,15
28,33	61,11	44,72	44,72	0,77	0,02	1,39	1141,34	2486,99	0,97	0,42	372,24	400,16	421,35	372,24
31,67	65,56	48,61	48,61	0,77	0,02	1,44	1244,92	2733,38	1,00	0,40	374,27	402,36	421,16	374,27
35,00	70,00	52,50	52,50	0,77	0,02	1,49	1355,28	2997,65	1,04	0,38	376,24	404,44	420,67	376,24
5,00	30,00	17,50	17,50	0,78	0,01	0,80	584,29	1192,30	0,55	0,29	361,65	388,04	416,99	361,65
8,33	34,44	21,39	21,39	0,78	0,01	0,86	647,63	1336,40	0,60	0,30	363,95	390,84	418,07	363,95
11,67	38,89	25,28	25,28	0,78	0,01	0,92	715,98	1492,97	0,64	0,31	366,21	393,55	419,02	366,21
15,00	43,33	29,17	29,17	0,78	0,01	0,98	789,57	1662,66	0,69	0,32	368,42	396,17	419,83	368,42
18,33	47,78	33,06	33,06	0,79	0,01	1,05	868,65	1846,17	0,73	0,32	370,58	398,70	420,50	370,58
21,67	52,22	36,94	36,94	0,79	0,02	1,11	953,47	2044,22	0,77	0,32	372,69	401,12	420,99	372,69



FINAL PROJECT

Date: 19.06.2014

Page: 114

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

25,00	56,67	40,83	40,83	0,79	0,02	1,17	1044,28	2257,56	0,81	0,31	374,76	403,45	421,28	374,76
28,33	61,11	44,72	44,72	0,79	0,02	1,22	1141,34	2486,99	0,85	0,30	376,76	405,67	421,35	376,76
31,67	65,56	48,61	48,61	0,80	0,02	1,27	1244,92	2733,38	0,88	0,28	378,71	407,78	421,16	378,71
35,00	70,00	52,50	52,50	0,80	0,02	1,30	1355,28	2997,65	0,91	0,25	380,59	409,78	420,67	380,59
5,00	30,00	17,50	17,50	0,80	0,01	0,70	584,29	1192,30	0,49	0,22	366,73	394,03	416,99	366,73
8,33	34,44	21,39	21,39	0,80	0,01	0,75	647,63	1336,40	0,53	0,23	368,95	396,77	418,07	368,95
11,67	38,89	25,28	25,28	0,81	0,01	0,81	715,98	1492,97	0,56	0,23	371,13	399,42	419,02	371,13
15,00	43,33	29,17	29,17	0,81	0,01	0,86	789,57	1662,66	0,60	0,23	373,27	401,98	419,83	373,27
18,33	47,78	33,06	33,06	0,81	0,01	0,92	868,65	1846,17	0,64	0,23	375,35	404,44	420,50	375,35
21,67	52,22	36,94	36,94	0,81	0,02	0,97	953,47	2044,22	0,68	0,22	377,39	406,79	420,99	377,39
25,00	56,67	40,83	40,83	0,82	0,02	1,02	1044,28	2257,56	0,71	0,21	379,37	409,04	421,28	379,37
28,33	61,11	44,72	44,72	0,82	0,02	1,06	1141,34	2486,99	0,74	0,19	381,29	411,18	421,35	381,29
31,67	65,56	48,61	48,61	0,82	0,02	1,10	1244,92	2733,38	0,77	0,16	383,15	413,21	421,16	383,15
35,00	70,00	52,50	52,50	0,82	0,02	1,13	1355,28	2997,65	0,78	0,12	384,94	415,11	420,67	384,94
5,00	30,00	17,50	17,50	0,83	0,01	0,61	584,29	1192,30	0,43	0,16	371,80	400,01	416,99	371,80
8,33	34,44	21,39	21,39	0,83	0,01	0,66	647,63	1336,40	0,46	0,16	373,95	402,70	418,07	373,95
11,67	38,89	25,28	25,28	0,83	0,01	0,70	715,98	1492,97	0,49	0,16	376,06	405,29	419,02	376,06
15,00	43,33	29,17	29,17	0,83	0,01	0,75	789,57	1662,66	0,52	0,15	378,12	407,79	419,83	378,12
18,33	47,78	33,06	33,06	0,84	0,01	0,80	868,65	1846,17	0,56	0,14	380,13	410,18	420,50	380,13
21,67	52,22	36,94	36,94	0,84	0,02	0,84	953,47	2044,22	0,59	0,13	382,08	412,46	420,99	382,08
25,00	56,67	40,83	40,83	0,84	0,02	0,88	1044,28	2257,56	0,61	0,11	383,98	414,63	421,28	383,98
28,33	61,11	44,72	44,72	0,84	0,02	0,92	1141,34	2486,99	0,64	0,08	385,82	416,69	421,35	385,82
31,67	65,56	48,61	48,61	0,85	0,02	0,94	1244,92	2733,38	0,66	0,05	387,59	418,63	421,16	387,59



FINAL PROJECT

Date: 19.06.2014

Page: 115

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

35,00	70,00	52,50	52,50	0,85	0,02	0,96	1355,28	2997,65	0,67	0,00	389,29	420,45	420,67	389,29
5,00	30,00	17,50	17,50	0,85	0,01	0,53	584,29	1192,30	0,37	0,10	376,87	406,00	416,99	376,87
8,33	34,44	21,39	21,39	0,85	0,01	0,57	647,63	1336,40	0,39	0,10	378,95	408,63	418,07	378,95
11,67	38,89	25,28	25,28	0,86	0,01	0,61	715,98	1492,97	0,42	0,09	380,99	411,16	419,02	380,99
15,00	43,33	29,17	29,17	0,86	0,01	0,65	789,57	1662,66	0,45	0,08	382,97	413,59	419,83	382,97
18,33	47,78	33,06	33,06	0,86	0,01	0,68	868,65	1846,17	0,48	0,06	384,90	415,92	420,50	384,90
21,67	52,22	36,94	36,94	0,86	0,01	0,72	953,47	2044,22	0,50	0,04	386,78	418,13	420,99	386,78
25,00	56,67	40,83	40,83	0,87	0,02	0,75	1044,28	2257,56	0,52	0,02	388,59	420,23	421,28	388,59
28,33	61,11	44,72	44,72	0,87	0,02	0,78	1141,34	2486,99	0,54	-0,01	390,34	422,20	421,35	390,34
31,67	65,56	48,61	48,61	0,87	0,02	0,80	1244,92	2733,38	0,56	-0,06	392,02	424,06	421,16	392,02
35,00	70,00	52,50	52,50	0,87	0,02	0,81	1355,28	2997,65	0,56	-0,11	393,63	425,79	420,67	393,63
5,00	30,00	17,50	17,50	0,88	0,01	0,45	584,29	1192,30	0,31	0,04	381,94	411,98	416,99	381,94
8,33	34,44	21,39	21,39	0,88	0,01	0,48	647,63	1336,40	0,33	0,03	383,95	414,56	418,07	383,95
11,67	38,89	25,28	25,28	0,88	0,01	0,51	715,98	1492,97	0,36	0,02	385,92	417,04	419,02	385,92
15,00	43,33	29,17	29,17	0,88	0,01	0,54	789,57	1662,66	0,38	0,01	387,82	419,40	419,83	387,82
18,33	47,78	33,06	33,06	0,89	0,01	0,58	868,65	1846,17	0,40	-0,02	389,68	421,66	420,50	389,68
21,67	52,22	36,94	36,94	0,89	0,01	0,60	953,47	2044,22	0,42	-0,04	391,47	423,80	420,99	391,47
25,00	56,67	40,83	40,83	0,89	0,02	0,63	1044,28	2257,56	0,44	-0,07	393,20	425,82	421,28	393,20
28,33	61,11	44,72	44,72	0,89	0,02	0,65	1141,34	2486,99	0,45	-0,11	394,87	427,72	421,35	394,87
31,67	65,56	48,61	48,61	0,90	0,02	0,66	1244,92	2733,38	0,46	-0,15	396,46	429,49	421,16	396,46
35,00	70,00	52,50	52,50	0,90	0,02	0,66	1355,28	2997,65	0,46	-0,21	397,98	431,12	420,67	397,98
5,00	30,00	17,50	17,50	0,90	0,01	0,37	584,29	1192,30	0,26	-0,01	387,02	417,97	416,99	387,02
8,33	34,44	21,39	21,39	0,90	0,01	0,40	647,63	1336,40	0,28	-0,02	388,96	420,49	418,07	388,96



FINAL PROJECT

Date: 19.06.2014

Page: 116

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

11,67	38,89	25,28	25,28	0,91	0,01	0,42	715,98	1492,97	0,30	-0,04	390,84	422,91	419,02	390,84
15,00	43,33	29,17	29,17	0,91	0,01	0,45	789,57	1662,66	0,31	-0,06	392,68	425,21	419,83	392,68
18,33	47,78	33,06	33,06	0,91	0,01	0,47	868,65	1846,17	0,33	-0,09	394,45	427,40	420,50	394,45
21,67	52,22	36,94	36,94	0,91	0,01	0,49	953,47	2044,22	0,34	-0,12	396,17	429,46	420,99	396,17
25,00	56,67	40,83	40,83	0,92	0,02	0,51	1044,28	2257,56	0,36	-0,15	397,82	431,41	421,28	397,82
28,33	61,11	44,72	44,72	0,92	0,02	0,52	1141,34	2486,99	0,36	-0,20	399,40	433,23	421,35	399,40
31,67	65,56	48,61	48,61	0,92	0,02	0,53	1244,92	2733,38	0,37	-0,25	400,90	434,91	421,16	400,90
35,00	70,00	52,50	52,50	0,92	0,02	0,52	1355,28	2997,65	0,36	-0,31	402,33	436,47	420,67	402,33
5,00	30,00	17,50	17,50	0,93	0,01	0,30	584,29	1192,30	0,21	-0,06	392,09	423,95	416,99	392,09
8,33	34,44	21,39	21,39	0,93	0,01	0,32	647,63	1336,40	0,22	-0,08	393,96	426,42	418,07	393,96
11,67	38,89	25,28	25,28	0,93	0,01	0,34	715,98	1492,97	0,24	-0,10	395,77	428,78	419,02	395,77
15,00	43,33	29,17	29,17	0,93	0,01	0,36	789,57	1662,66	0,25	-0,13	397,53	431,02	419,83	397,53
18,33	47,78	33,06	33,06	0,94	0,01	0,38	868,65	1846,17	0,26	-0,16	399,23	433,14	420,50	399,23
21,67	52,22	36,94	36,94	0,94	0,01	0,39	953,47	2044,22	0,27	-0,19	400,86	435,13	420,99	400,86
25,00	56,67	40,83	40,83	0,94	0,01	0,40	1044,28	2257,56	0,28	-0,23	402,43	437,01	421,28	402,43
28,33	61,11	44,72	44,72	0,94	0,02	0,40	1141,34	2486,99	0,28	-0,28	403,92	438,77	421,35	403,92
31,67	65,56	48,61	48,61	0,95	0,02	0,40	1244,92	2733,38	0,28	-0,34	405,34	440,41	421,16	405,34
35,00	70,00	52,50	52,50	0,95	0,02	0,39	1355,28	2997,65	0,27	-0,41	406,67	441,92	420,67	406,67
5,00	30,00	17,50	17,50	0,95	0,01	0,23	584,29	1192,30	0,16	-0,11	397,16	429,94	416,99	397,16
8,33	34,44	21,39	21,39	0,95	0,01	0,25	647,63	1336,40	0,17	-0,13	398,96	432,35	418,07	398,96
11,67	38,89	25,28	25,28	0,96	0,01	0,26	715,98	1492,97	0,18	-0,16	400,70	434,65	419,02	400,70
15,00	43,33	29,17	29,17	0,96	0,01	0,27	789,57	1662,66	0,19	-0,19	402,38	436,85	419,83	402,38
18,33	47,78	33,06	33,06	0,96	0,01	0,28	868,65	1846,17	0,20	-0,22	404,00	438,92	420,50	404,00



FINAL PROJECT

Date: 19.06.2014

Page: 117

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

21,67	52,22	36,94	36,94	0,96	0,01	0,29	953,47	2044,22	0,20	-0,26	405,56	440,89	420,99	405,56
25,00	56,67	40,83	40,83	0,97	0,01	0,29	1044,28	2257,56	0,21	-0,31	407,04	442,72	421,28	407,04
28,33	61,11	44,72	44,72	0,97	0,02	0,29	1141,34	2486,99	0,20	-0,36	408,45	444,44	421,35	408,45
31,67	65,56	48,61	48,61	0,97	0,02	0,28	1244,92	2733,38	0,20	-0,43	409,78	446,02	421,16	409,78
35,00	70,00	52,50	52,50	0,97	0,02	0,26	1355,28	2997,65	0,18	-0,50	411,02	447,46	420,67	411,02
5,00	30,00	17,50	17,50	0,98	0,01	0,17	584,29	1192,30	0,12	-0,15	402,23	436,00	416,99	402,23
8,33	34,44	21,39	21,39	0,98	0,01	0,18	647,63	1336,40	0,12	-0,18	403,96	438,40	418,07	403,96
11,67	38,89	25,28	25,28	0,98	0,01	0,19	715,98	1492,97	0,13	-0,21	405,63	440,68	419,02	405,63
15,00	43,33	29,17	29,17	0,98	0,01	0,19	789,57	1662,66	0,13	-0,25	407,23	442,84	419,83	407,23
18,33	47,78	33,06	33,06	0,99	0,01	0,20	868,65	1846,17	0,14	-0,29	408,78	444,88	420,50	408,78
21,67	52,22	36,94	36,94	0,99	0,01	0,20	953,47	2044,22	0,14	-0,33	410,25	446,79	420,99	410,25
25,00	56,67	40,83	40,83	0,99	0,01	0,19	1044,28	2257,56	0,14	-0,38	411,65	448,58	421,28	411,65
28,33	61,11	44,72	44,72	0,99	0,02	0,18	1141,34	2486,99	0,13	-0,44	412,98	450,23	421,35	412,98
31,67	65,56	48,61	48,61	1,00	0,02	0,17	1244,92	2733,38	0,12	-0,51	414,22	451,75	421,16	414,22
35,00	70,00	52,50	52,50	1,00	0,02	0,14	1355,28	2997,65	0,10	-0,59	415,37	453,12	420,67	415,37



FINAL PROJECT

Date: 19.06.2014

Page: 118

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3.9.1 Summary R 22-->3000 rpm, 7 cc/rev

Table 50- Summary R22- 3000rpm, 7 cc/rev- improvement

	mref [g/s]	flow (l/min)	P1 (kPa)	P2	P3	Q (kW)	Qres (kW)	h1	h2	h3	h4
min	7,99	0,14	584,29	1192,30	888,295375	0,10	-0,59	356,58	382,06	416,99	356,58
max	23,31	1,49	1355,28	2997,65	2176,46532	1,04	0,42	415,37	453,12	421,35	415,37
X1_para minimo	0,98	1,00	0,75	0,75	0,75	1,00	1,00	0,75	0,75	0,75	0,75
X1_para maximo	0,77	0,77	0,77	0,77	0,77	0,77	0,77	1,00	1,00	0,77	1,00



FINAL PROJECT

Date: 19.06.2014

Page: 119

PROJECT:
"Compressors test live bench under wet compression conditions"

PLANES:
3

ANNEX V: WINCC

1. SCADA STRUCTURE




Figure 20-WINCC structure

The process has been defined when the T1,T3 or m_ref sensors haven' t been connected.

Instead to store the value of the sensor (to be used later), the program store its theoretical value, this way it can continue with the rest of the calculations.



FINAL PROJECT

Date: 19.06.2014

Page: 120

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2


2 SCREENS

2.1 HOME SCREEN



Figure 21-Home screen

Although a picture of a dryer machine have seen selected, although other options are available.



	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 121
PROJECT: “Compressors test live bench under wet compression conditions”		ANNEX: 2

2.2 MAIN MENU




Figure 22-Main menu

The order of the buttons has been defined following a logical development, although it can be done differently. The only order that must be respected is the first one.

The “STATIONS EQUIPMENT”, “STATIONS SETTINGS” and “STATIONS MENU” would only give the user the possibility of access, to those stations that were implemented in the first point: “STATIONS HABILITATION”.



FINAL PROJECT

Date: 19.06.2014

Page: 122

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.3 STATIONS HABILITATION




Figure 23-Stations habilitation

1	It varies the number of stations shown in the screen that could be habilitated
2	Once that the station has been habilitated, this access guide the user directly to the settings screen of the station. It changes its color once that has been pressed.
3	Pressing the button, the habilitation of the station is completed
4	Once that the station has been habilitated, this access guide the user directly to the equipment screen of the station. It changes its color once that has been pressed.
EQUIPMENT	It guides the user
SUP. FOLDER	It guides the user to the superior folder, in this case : MAIN MENU
BACK	Goes to the previous screen
MAIN MENU	This button is at the same place in all the project. It guides the user to the MAIN MENU

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 123
PROJECT: “Compressors test live bench under wet compression conditions”		ANNEX: 2

2.4 STATIONS EQUIPMENT




Figure 24-Stations equipment

The stations that have been habilitated appear in the STATIONS MENU. “Clicking” in the stations buttons the specific equipments screen of each station would appear.

STATIONS SETTINGS	It guides the user to the “STATIONS SETTINGS” screen
SUP. FOLDER	It guides the user to the superior folder, in this case : MAIN MENU
BACK	Goes to the previous screen
MAIN MENU	This button is at the same place in all the project. It guides the user to the MAIN MENU

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 124
PROJECT: “Compressors test live bench under wet compression conditions”		ANNEX: 2

2.5 STATIONS SETTINGS




Figure 25-Stations settings

The stations that have been habilitated appear in the STATIONS MENU. “Clicking” in the stations buttons the specific settings screen of each station would appear.

STATIONS MENU	It guides the user to the “STATIONS MENU” screen
SUP. FOLDER	It guides the user to the superior folder, in this case : MAIN MENU
BACK	Goes to the previous screen
MAIN MENU	This button is at the same place in all the project. It guides the user to the MAIN MENU

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 125
PROJECT: “Compressors test live bench under wet compression conditions”		ANNEX: 2

2.6 STATIONS MENU




Figure 26-Stations menu

The stations that have been habilitated appear in the STATIONS MENU. “Clicking” in the stations buttons the specific menu of each station would appear.

EQUIPMENT	It guides the user to the “STATIONS EQUIPMENT” screen
SUP. FOLDER	It guides the user to the superior folder, in this case : MAIN MENU
BACK	Goes to the previous screen
MAIN MENU	This button is at the same place in all the project. It guides the user to the MAIN MENU



FINAL PROJECT

Date: 19.06.2014

Page: 126

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.7 MENU 1




Figure 27-Station 1 Menu

The buttons in this screen guides the user to the specific screens of its station.

EQUIPMENT STATION 1	To determine the equipment used in this station
SETTINGS STATION 1	To configure the station 1 (Refrigerant, alarms, set points..)
DATA STATION 1	Access to the measured data of the station
COMPARATIONS	Comparison between the measured values and the Set/ Calculated values
DIAGRAM STATION 1	Diagram of the functioning with the measured and set values
GRAPHIC STATION 1	Access to the magnitudes graphics

EQUIPMENT	It guides the user to the "STATIONS EQUIPMENT" screen
SUP. FOLDER	It guides the user to the superior folder, in this case : STATIONS MENU
BACK	Goes to the previous screen
MAIN MENU	This button is at the same place in all the project. It guides the user to the MAIN MENU



FINAL PROJECT

Date: 19.06.2014

Page: 127

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.8 EQUIPMENT 1




Figure 28-Station 1 Equipment

It is divided in two parts: the refrigerant circuit, and the water circuit. In both of them the user must select the sensors/ equipment that have been implemented in the station. For both cases, there is a "SELEC ALL" button, which "connect" all the sensor/ equipment (of the corresponding circuit) to configure the station faster.

As it is shown, some sensors MUST BE CONNECTED, and so is shown in the HMI.

SETTINGS 1	It guides the user to the "SETTINGS 1" screen
STATION 1	It guides the user to the STATION 1 MENU
BACK	Goes to the previous screen
MAIN MENU	This button is at the same place in all the project. It guides the user to the MAIN MENU

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014
		Page: 128
PROJECT: "Compressors test live bench under wet compression conditions"		ANNEX: 2

2.9 SETTING AUTOMATIC




Figure 29-Settings station 1, automatic

In this screen the user can choose between the automatic or manual mode. When the automatic mode is set, the desired value of the pressure and the quality at the operating point 1 have to be fixed. At this point, the user must also fix the parameters of the compressor (used to calculate the refrigerant flux). For the efficiencies, the parameters of the second degree equation that compute the efficiencies must be introduced.

DATA 1	It guides the user to the "DATA 1" screen
STATION 1	It guides the user to the STATION 1 MENU
BACK	Goes to the previous screen
MAIN MENU	This button is at the same place in all the project. It guides the user to the MAIN MENU

The "Alarm block" has been implemented to assure the correct functioning of the test bench as well as for safety reasons. The thermodynamic components, the circuit in general, have been chosen for a maximum pressure and temperature.

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 129
PROJECT: "Compressors test live bench under wet compression conditions"		ANNEX: 2

DEVIATION P1 [%]	Indicates the percentage over the P1_set, that the measured value can be bellow or above the pressure desired.
DEVIATION T1 [%]	Indicates the percentage over the T1sat, that the measured value can be bellow or above the temperature desired.
P2 [bar] greater >	Maximum value that the pressure can achieve
T2 [°C] greater >	Maximum value that the temperature can achieve

When the "Tin" sensor (water input temperature sensor) has not been connected, it can be fixed theoretically assuming that the temperature fixed in the chiller would be the same.




Figure 30-Settings station1, automatic (No Tin sensor)



FINAL PROJECT

Date: 19.06.2014

Page: 130

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.10 SETTING MANUAL




Figure 31-Settings station 1, manual

The manual mode, has been defined so the individual components could be tested. Once the user press a button it change its color and; either an "ON" statement appears, slide control does.

DATA 1	It guides the user to the "DATA 1" screen
STATION 1	It guides the user to the STATION 1 MENU
BACK	Goes to the previous screen
MAIN MENU	This button is at the same place in all the project. It guides the user to the MAIN MENU

The resistance control is with the difference of temperature to be achieved. The pump, with the water flux. And the EEV control is with the pressure ratio ($P2/P1 \sim P3/P1$) to be achieved.

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014
PROJECT: "Compressors test live bench under wet compression conditions"		Page: 131
		ANNEX: 2

2.11 DATA 1




Figure 32-Data station 1

The measured values of the station are shown separately (depending on if it's a refrigerant measurement, or a water circuit one) in this screen. There are some values such as the point 2 calculates, or the quality at point 1, that are not measured.

COMPARATION 1	It guides the user to the "COMPARATION 1" screen
STATION 1	It guides the user to the STATION 1 MENU
BACK	Goes to the previous screen
MAIN MENU	This button is at the same place in all the project. It guides the user to the MAIN MENU

When the values of T1, P1, T2 or P2 don't fulfil the "ALARM" specifications, the red indicator is only visible when the error has occurred, furthermore, it blinks.

When a sensor is not connected, it doesn't appear in this screen. Eg: P3,T3, m_ref not connected.



FINAL PROJECT

Date: 19.06.2014

Page: 132

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2




Figure 33-Data station 1, alarms



FINAL PROJECT

Date: 19.06.2014

Page: 133

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.12 COMPARATIONS 1




Figure 34-Comparison 1

At this screen the comparisons between the measured values and the set / calculated ones are compared. This way it can be shown, the "ideality" of the station.

DIAGRAM 1	It guides the user to the "DIAGRAM 1" screen
STATION 1	It guides the user to the STATION 1 MENU
BACK	Goes to the previous screen
MAIN MENU	This button is at the same place in all the project. It guides the user to the MAIN MENU

If a sensor is not connected, its name would be gray and there would be no "measured value".

When the values of T1, P1, T2 or P2 don't fulfil the "ALARM" specifications:



FINAL PROJECT

Date: 19.06.2014

Page: 134

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

The red indicator is only visible when the error has occurred, furthermore, it blinks. When a sensor is not connected, it doesn't appear in this screen. Eg: P3, T3, m_ref not connected.




Figure 35-Comparison 1, alarms



FINAL PROJECT

Date: 19.06.2014

Page: 135

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.13 DIAGRAM 1




Figure 36- Diagram station 1

The measured values are situated next to the operating point in which they were measured. The set values "x1" and "P1 set" are also shown next to the operating point 1.

GRAPHICS 1	It guides the user to the "GRAPHICS 1" screen
STATION 1	It guides the user to the STATION 1 MENU
BACK	Goes to the previous screen
MAIN MENU	This button is at the same place in all the project. It guides the user to the MAIN MENU



FINAL PROJECT

Date: 19.06.2014

Page: 136

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

When the values of T1, P1, T2 or P2 don't fulfil the "ALARM" specifications. When a sensor is not connected, it doesn't appear in this screen. Eg: P3, T3, m_ref not connected.




Figure 37-Diagram station 1, alarms



FINAL PROJECT

Date: 19.06.2014

Page: 137

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.14 GRAPHICS 1




Figure 38-Graphics station 1

In this screen, the user can visualize one minute of the variables values shown in the legends (values registered every 2 seconds). If there is an interest to see more time or bigger, the corresponding buttons must be pressed; "Pressures and temperatures" or "Water and refrigerant flux".

GRAPHICS 1	It guides the user to the "GRAPHICS 1" screen
STATION 1	It guides the user to the STATION 1 MENU
BACK	Goes to the previous screen
MAIN MENU	This button is at the same place in all the project. It guides the user to the MAIN MENU

When a sensor has not been connected, its theoretical value would appear in the graphic. However, it would be shown a "Th" (stand for theoretical) to indicate that the value shown is not a measured value. Eg: P3, T3 and m_ref haven't been connected



FINAL PROJECT

Date: 19.06.2014

Page: 138

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2




Figure 39-Graphic station 1, no sensors connected

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 139
PROJECT: “Compressors test live bench under wet compression conditions”		ANNEX: 2

2.15 GRAPHIC P&T




Figure 40-T&P graphic

This screens shows the graphic of pressures and temperatures maximize. It can show up to an hour of the variables values (values registered every 5 seconds).

STATION 1	It guides the user to the STATION 1 MENU
BACK	Goes to the previous screen: GRAPHICS 1

When a sensor has not been connected, its theoretical value would appear in the graphic. However, it would be shown a “Th” (stand for theoretical) to indicate that the value shown is not a measured value. Eg: P3, T3 and m_ref haven’t been connected



FINAL PROJECT

Date: 19.06.2014

Page: 140

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2




Figure 41- T&P graphic, no sensors connected



FINAL PROJECT

Date: 19.06.2014

Page: 141

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2.16 GRAPHIC FLUX




Figure 42- Flux graphic

It shows the refrigerant and water flux graphic maximize. As the other graphic, it can show up to an hour of the variables values (values registered every 5 seconds).

STATION 1	It guides the user to the STATION 1 MENU
BACK	Goes to the previous screen: GRAPHICS 1

When a sensor has not been connected, its theoretical value would appear in the graphic. However, it would be shown a "Th" (stand for theoretical) to indicate that the value shown is not a measured value. Eg: P3, T3 and m_ref haven't been connected

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 142
PROJECT: “Compressors test live bench under wet compression conditions”		ANNEX: 2




Figure 43-Flux graphic, no sensors connected

3 CONNECTIVITY & VARIABLES & TEXT LISTS

3.1 CONNECTIVITY

As an interface between the PLC and excel is needed to compute the calculations, WINCC would be used as an intermediate.

Besides the variables that must be defined and import, for the proper visualization of the data, as well as for the graphic events that have been programed (blinks...), the variables to be exported to an excel file would have to be also defined.

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 143
PROJECT: “Compressors test live bench under wet compression conditions”		ANNEX: 2




Figure 44-Connectivity

To enable the communication, and the exportation, those options must be selected.

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 144
PROJECT: “Compressors test live bench under wet compression conditions”		ANNEX: 2




Figure 45-IP Adress. Connection between PLC and the HMI

3.2 VARIABLES

The variables for the 12 stations have been included in WINCC to leave everything ready for their implementation.

When defining the variables, the programmer must define the connection. In this case is the "conexion_1", besides, the direction of the variable must be introduce along with its data type.



FINAL PROJECT

Date: 19.06.2014

Page: 145

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

Nombre	Conexión	Dirección	Tipo d...	Símbolo	Cic...	Comentario
Puesto10.UDT1_10.m_ref_m	Conexión_1	DB 100 DBD 36	Real	m_ref_m	1 s	Refrigerant flux
Puesto10.UDT1_10.m_w_m	Conexión_1	DB 100 DBD 40	Real	m_w_m	1 s	Water flux
Puesto10.UDT1_10.P1_m	Conexión_1	DB 100 DBD 24	Real	P1_m	1 s	Input pressure of the compressor
Puesto10.UDT1_10.P1_set	Conexión_1	DB 100 DBD 44	Real	P1_set	1 s	Pressure desired at point one
Puesto10.UDT1_10.P2_m	Conexión_1	DB 100 DBD 28	Real	P2_m	1 s	input pressure of the condenser
Puesto10.UDT1_10.P3_m	Conexión_1	DB 100 DBD 32	Real	P3_m	1 s	Output pressure of the condenser
Puesto10.UDT1_10.Ref_number	Conexión_1	DB 100 DBW 52	Int	Ref_number	1 s	0->R134A , 1->R410A, 2->R407C, 3->R22
Puesto10.UDT1_10.T1_m	Conexión_1	DB 100 DBD 4	Real	T1_m	1 s	Input temperature of the compressors refrigerant
Puesto10.UDT1_10.T2_m	Conexión_1	DB 100 DBD 8	Real	T2_m	1..	Input temperature of the condenser
Puesto10.UDT1_10.T3_m	Conexión_1	DB 100 DBD 12	Real	T3_m	1 s	Output temperature of the condenser
Puesto10.UDT1_10.Tin_chiller	Conexión_1	DB 100 DBD 48	Real	Tin_chiller	1 s	Tin temperature fixed with the chiller
Puesto10.UDT1_10.Tin_m	Conexión_1	DB 100 DBD 16	Real	Tin_m	1 s	Water input temperature
Puesto10.UDT1_10.Tout_m	Conexión_1	DB 100 DBD 20	Real	Tout_m	1 s	Water output temperature
Puesto10.UDT1_10.x1	Conexión_1	DB 100 DBD 0	Real	x1	1 s	Quality
Puesto10.UDT1_10.DeviationP1	Conexión_1	DB 100 DBD 372	Real	DeviationP1	1 s	Maximum deviation of P1 allowed

Puesto10.UDT1_10.T2_m (Variable)

General

Propiedades

Eventos

General

Nombre: o10.UDT1_10.T2_m

Nombre a visualizar:

Conexión: Conexión_1

Tipo de datos: Real

Modo de adquisición: Uso cíclico

Configuración

Longitud: 4

Figure 46-WINCC Variables

3.3 TEXT LISTS

WINCC offers the possibility to create text lists (and graphic lists). E.g: To develop the displayable multiple-choice menu for the refrigerant, a text list was created.



FINAL PROJECT

Date: 19.06.2014

Page: 146

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

Pantalla_Inicio Conexiones Variables **Listas de texto**

Listas de texto		
Nombre	Selección	Comentario
Conected&Not_connected	Bit (0, 1)	
OK_Error	Bit (0, 1)	
ON_OFF	Bit (0, 1)	
Refrigerant	Rango (... - ...)	

Entradas en la lista

Por defecto	Valor	Entrada
<input type="radio"/>	0	R134A
<input type="radio"/>	1	R410A
<input type="radio"/>	2	R407C
<input type="radio"/>	3	R32
<input type="radio"/>	4	R290

Figure 47- Text Lists



FINAL PROJECT

Date: 19.06.2014

Page: 147

PROJECT:
"Compressors test live bench under wet compression conditions"

PLANES:
3

ANNEX VI: EXCEL AND VISUAL BASIC CODE

1 INTERFACE WITH WINCC




Figure 48-WINCC Structure

1.1 WORKBOOK

```
VERSION 1.0 CLASS
BEGIN
    MultiUse = -1    'True
END
Attribute VB_Name = "ThisWorkbook"
Attribute VB_GlobalNameSpace = False
Attribute VB_Creatable = False
Attribute VB_PredeclaredId = True
Attribute VB_Exposed = True
Dim Server_Avail As Boolean

Private Sub Workbook_Open()
    Server_Avail = False

    ' update_data
End Sub
```



FINAL PROJECT

Date: 19.06.2014

Page: 148

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

```
Public Sub check_server()
    Dim xml As New XMLHTTP60
    Dim sURL As String
    Dim sEnv As String
    Dim xmlhttp As New MSXML2.XMLHTTP60
    Dim xmlDoc As New DOMDocument
    Dim soap_server As String

    soap_server = Cells(1, 2)

    On Error Resume Next

    sURL = "http://" & soap_server & "/soap/RuntimeAccess?wsdl"
    xmlhttp.Open "GET", sURL, False
    xmlhttp.send

    If (Err.Number > 0 Or xmlhttp.Status <> 200) Then
        Server_Avail = False
        MsgBox "There is a problem contacting the SOAP server at " &
        soap_server
    Else
        Server_Avail = True
    End If
End Sub

Public Function get_response(tag As String) As String
    Dim xml As New XMLHTTP60
    Dim sURL As String
    Dim sEnv As String
    Dim xmlhttp As New MSXML2.XMLHTTP60
    Dim xmlDoc As New DOMDocument
    Dim soap_server As String

    soap_server = Cells(1, 2)

    sURL = "http://" & soap_server & "/soap/RuntimeAccess"

    sEnv = "<?xml version=""1.0"" encoding=""utf-8""?>"
    sEnv = sEnv & "<soap:Envelope
targetNamespace=""http://tempuri.org/wsdl/""
xmlns:wsdl=""http://tempuri.org/wsdl/""
xmlns:soap=""http://schemas.xmlsoap.org/wsdl/soap/""
xmlns:xsd=""http://www.w3.org/2001/XMLSchema""
xmlns=""http://schemas.xmlsoap.org/wsdl/"" >"
    sEnv = sEnv & "    <soap:Body>"
    sEnv = sEnv & "        <GetValue xmlns=""http://tempuri.org/wsdl/"">"
    sEnv = sEnv & "            <A type=""xsd:string"">"" & tag & ""</A>"
    sEnv = sEnv & "        </GetValue>"
```



FINAL PROJECT

Date: 19.06.2014

Page: 149

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

```
sEnv = sEnv & " </soap:Body>"
sEnv = sEnv & "</soap:Envelope>"

With xmlhttp
    .Open "post", sURL, False, "administrator", "100"
    '.Open "post", sURL, False, "HH", "200"
    .setRequestHeader "Host", soap_server
    .setRequestHeader "Content-Type", "text/xml; charset=utf-8"
    .setRequestHeader "soapAction", "http://" & soap_server &
":80/soap/RuntimeAccess"
    .setRequestHeader "Accept-encoding", "zip"
    .send sEnv
    xmlDoc.LoadXML .responseText
    ' MsgBox .responseText
End With

get_response = xmlDoc.Text

End Function

Public Function set_value(tag As String, value As String) As String
    Dim xml As New XMLHTTP60
    Dim sURL As String
    Dim sEnv As String
    Dim xmlhttp As New MSXML2.XMLHTTP60
    Dim xmlDoc As New DOMDocument
    Dim soap_server As String

    soap_server = Cells(1, 2)

    sURL = "http://" & soap_server & "/soap/RuntimeAccess"

    sEnv = "<?xml version=""1.0"" encoding=""utf-8""?>"
    sEnv = sEnv & "<soap:Envelope
targetNamespace=""http://tempuri.org/wsdl/""
xmlns:wsdlns=""http://tempuri.org/wsdl/""
xmlns:soap=""http://schemas.xmlsoap.org/wsdl/soap/""
xmlns:xsd=""http://www.w3.org/2001/XMLSchema""
xmlns=""http://schemas.xmlsoap.org/wsdl/"" >"
    sEnv = sEnv & " <soap:Body>"
    sEnv = sEnv & " <SetValue xmlns=""http://tempuri.org/wsdl/"">"
    sEnv = sEnv & " <A type=""xsd:string"">" & tag & "</A>"
    sEnv = sEnv & " <B type=""xsd:string"">" & value & "</B>"
    sEnv = sEnv & " </SetValue>"
    sEnv = sEnv & " </soap:Body>"
    sEnv = sEnv & "</soap:Envelope>"

    With xmlhttp
        .Open "post", sURL, False, "administrator", "100"
```



FINAL PROJECT

Date: 19.06.2014

Page: 150

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

```
        '.Open "post", sURL, False, "HH", "200"  
        .setRequestHeader "Host", soap_server  
        .setRequestHeader "Content-Type", "text/xml; charset=utf-8"  
        .setRequestHeader "soapAction", "http://" & soap_server &  
":80/soap/RuntimeAccess"  
        .setRequestHeader "Accept-encoding", "zip"  
        .send sEnv  
        xmlDoc.LoadXML .responseText  
        '    MsgBox .responseText  
End With  
  
set_value = xmlDoc.Text
```

End Function

Public Sub update_data()

```
    Dim row As Integer  
    Dim tag As String  
    Dim value As String  
    Dim objWorksheet  
    Set objWorksheet = Excel.Worksheets("Data")  
  
    If (Server_Avail = False) Then  
        check_server  
    End If  
  
    If (Server_Avail = True) Then  
  
        'Startwert, an welcher Zeile die erste HMI Variable steht  
        'Start value at which row the first HMI variable begins  
        row = 3  
  
        Do  
  
            'Vorgabe, in welcher Spalte die HMI Variablen angegeben sind.  
            In diesem Fall "Spalte B"  
            'Setting the column in which the HMI variables are specified.  
            In this case, "Column B"  
            tag = objWorksheet.Cells(row, 2)  
  
            'Auswertung, steht in der Spalte 4 der Buchstabe "W" oder "w"  
            f³r "writing"  
            'Evaluation, in Column 4 are the character "W" or "w" for  
            "writing"  
            If (objWorksheet.Cells(row, 4) = "W") Or  
            (objWorksheet.Cells(row, 4) = "w") Then
```



FINAL PROJECT

Date: 19.06.2014

Page: 151

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

```
Variable      'Schreibe den Variablenwert aus der Excelliste in die HMI
              'Write the excel tag value into the HMI tag
              value = objWorksheet.Cells(row, 3)

              'Schreibe die Statusinfo in die Zeile 5
              'Write status info into row 5
              If set_value(tag, value) <> 0 Then
                  objWorksheet.Cells(row, 5) = "Fault"

                  'Meldung, wenn die Variable nicht vorhanden ist
                  'Message if the variable does not exist
                  'MsgBox "Der angegebene Variablen Name in der
Spalte B Zeile" & " " & row & " " & "ist nicht vorhanden!"
                  MsgBox "The specified variable name in the column B
line" & " " & row & " " & "does not exist!"
              Else
                  objWorksheet.Cells(row, 5) = "done"
              End If
            End If

            'Auswertung, steht in der Spalte 4 der Buchstabe "R" oder "r"
f³r "reading"
            'Evaluation, in Column 4 are the character "R" or "r" for
"reading"
            If (objWorksheet.Cells(row, 4) = "R") Or
(objWorksheet.Cells(row, 4) = "r") Then

                'Schreibe Wert der HMI Variable in die Excelliste
                'Write HMI tag value into the Excel list
                objWorksheet.Cells(row, 3) = get_response(tag)

                'Schreibe die Statusinfo in die Zeile 5
                'Write status info into row 5
                If objWorksheet.Cells(row, 3) = "###" Then
                    objWorksheet.Cells(row, 5) = "Fault"

                    'Meldung, wenn die Variable nicht vorhanden ist
                    'Message if the variable does not exist
                    'MsgBox "Der angegebene Variablen Name in der
Spalte B Zeile" & " " & row & " " & "ist nicht vorhanden!"
                    MsgBox "The specified variable name in the column B
line" & " " & row & " " & "does not exist!"
                Else
                    objWorksheet.Cells(row, 5) = "done"
                End If
            End If

            row = row + 1
```




FINAL PROJECT

Date: 19.06.2014

Page: 152

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

```
'Wiederhole die Schleife solange, bis in der Zeile 2 ein "end"
steht bzw. die Zeile "500" erreicht ist.
```

```
'Repeat the loop until in line 2 comes the word "end" or the line
"500" has been reached.
```

```
Loop Until tag = "end" Or row > 500
```

```
End If
```

```
'Call the function that permorms the calculations with the data
imported from WINCC, and save the results
```

```
'in the parameters to be exported to WINCC again
```

```
Call calc
```

```
'Call the functions that save the values of the magnitudes and
allows itsposterior study
```

```
Call DataLogger
```

```
End Sub
```

1.2 MODULE 1

```
Attribute VB_Name = "M34dulol1"
```

```
Sub mimacro()
```

```
On Error GoTo lin1
```

```
Sheets("Data").Select
```

```
Range("H1").value = "OK"
```

```
ActiveWorkbook.update_data
```

```
lin1:
```

```
Windows("Excel_interface_mod.xls").Activate
```

```
'ChDir "E:\040_Claudio-Javier"
```

```
'Workbooks.Open Filename:="E:\040_Claudio-
Javier\Excel_interface_mod.xls"
```

```
Sheets("Data").Select
```

```
Range("H1").value = "Error"
```

```
End Sub
```

```
Sub programarMacro()
```

```
Worksheets("Data").Range("I7").Formula = "=Now()"
```

```
Application.OnTime Now + TimeValue("00:00:01"), "tiempo2"
```

```
Range("I7").value = Time
```

```
tiempoac = Range("I7").value + Range("I9").value
```

```
' TimeValue("00:15:00")
```

```
Range("I8").value = tiempoac
```

```
Application.OnTime tiempoac, "mimacro", , True
```

```
Worksheets("Data").Select
```



FINAL PROJECT

Date: 19.06.2014

Page: 153

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

End Sub

Public Sub update_data()

```
Dim row As Integer
Dim tag As String
Dim value As String
Dim objWorksheet
Set objWorksheet = Excel.Worksheets("Data")
```

```
If (Server_Avail = False) Then
    check_server
End If
```

```
If (Server_Avail = True) Then
```

```
    'Startwert, an welcher Zeile die erste HMI Variable steht
    'Start value at which row the first HMI variable begins
    row = 3
```

```
Do
```

```
    'Vorgabe, in welcher Spalte die HMI Variablen angegeben sind.
    In diesem Fall "Spalte B"
    'Setting the column in which the HMI variables are specified.
    In this case, "Column B"
    tag = objWorksheet.Cells(row, 2)
```

```
    'Auswertung, steht in der Spalte 4 der Buchstabe "W" oder "w"
    f³r "writing"
```

```
    'Evaluation, in Column 4 are the character "W" or "w" for
    "writing"
```

```
    If (objWorksheet.Cells(row, 4) = "W") Or
    (objWorksheet.Cells(row, 4) = "w") Then
```

```
        'Schreibe den Variablenwert aus der Excelliste in die HMI
    Variable
```

```
        'Write the excel tag value into the HMI tag
        value = objWorksheet.Cells(row, 3)
```

```
        'Schreibe die Statusinfo in die Zeile 5
```

```
        'Write status info into row 5
```

```
        If set_value(tag, value) <> 0 Then
```

```
            objWorksheet.Cells(row, 5) = "Fault"
```

```
            'Meldung, wenn die Variable nicht vorhanden ist
```

```
            'Message if the variable does not exist
```

```
            'MsgBox "Der angegebene Variablen Name in der
    Spalte B Zeile" & " " & row & " " & "ist nicht vorhanden!"
```



FINAL PROJECT

Date: 19.06.2014

Page: 154

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

```
                MsgBox "The specified variable name in the column B
line" & " " & row & " " & "does not exist!"
            Else
                objWorksheet.Cells(row, 5) = "done"
            End If
        End If

        'Auswertung, steht in der Spalte 4 der Buchstabe "R" oder "r"
f³r "reading"
        'Evaluation, in Column 4 are the character "R" or "r" for
"reading"
        If (objWorksheet.Cells(row, 4) = "R") Or
(objWorksheet.Cells(row, 4) = "r") Then

            'Schreibe Wert der HMI Variable in die Excelliste
            'Write HMI tag value into the Excel list
            objWorksheet.Cells(row, 3) = get_response(tag)

            'Schreibe die Statusinfo in die Zeile 5
            'Write status info into row 5
            If objWorksheet.Cells(row, 3) = "###" Then
                objWorksheet.Cells(row, 5) = "Fault"

                'Meldung, wenn die Variable nicht vorhanden ist
                'Message if the variable does not exist
                'MsgBox "Der angegebene Variablen Name in der
Spalte B Zeile" & " " & row & " " & "ist nicht vorhanden!"
                MsgBox "The specified variable name in the column B
line" & " " & row & " " & "does not exist!"
            Else
                objWorksheet.Cells(row, 5) = "done"
            End If
        End If

        row = row + 1

        'Wiederhole die Schleife solange, bis in der Zeile 2 ein "end"
steht bzw. die Zeile "500" erreicht ist.
        'Repeat the loop until in line 2 comes the word "end" or the line
"500" has been reached.
        Loop Until tag = "end" Or row > 500

    End If

    'Call the function that permorms the calculations with the data
imported from WINCC, and save the results
    'in the parameters to be exported to WINCC again

    Call calc
```



FINAL PROJECT

Date: 19.06.2014

Page: 155

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

'Call the functions that save the values of the magnitudes and allows its posterior study

Call DataLogger

End Sub

Temporizador

```
Dim tiempoac As Variant
Dim ejecutando As Boolean
Dim celdam20 As Variant
Public Cont_Err_Resume_Next
```

```
Private Sub tiempo2()
On Error GoTo lin3
'Workbook.Unprotect (abc9999)
Worksheets("Data").Range("I7").Formula = "=Now()"
Application.OnTime Now + TimeValue("00:00:30"), "tiempo2"
'Workbook.Protect (abc9999)
lin3:
Worksheets("Data").Select
End Sub
```

1.3 MODULE 2

```
Attribute VB_Name = "Módulo2"
Sub calc()
Attribute calc.VB_ProcData.VB_Invoke_Func = " \n14"
'
' calc Macro
'
'Open the calculation book
ChDir _

"E:\010_BSH_USB\120_Programation\040_TABLAS_EXCEL_MACROS\020_Density_Enthalpy_Temperature\040_Improvements_DirectCalculations"
Workbooks.Open Filename:= _

"E:\010_BSH_USB\120_Programation\040_TABLAS_EXCEL_MACROS\020_Density_Enthalpy_Temperature\040_Improvements_DirectCalculations\Station1_rho_imp2.xlsx"
```



FINAL PROJECT

Date: 19.06.2014

Page: 156

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

```
'COPY THE INPUTS
'VALUES FROM "EXCEL_INTERFACE" TO "STATION1_RHO_IMP2"

'Copy the value of the Ref.number to the calculation sheet
Windows("Excel_interface.xls").Activate
Range("C3").Select
Selection.Copy
Windows("Station1_rho_imp2.xlsx").Activate
Range("A6").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks _
:=False, Transpose:=False

Windows("Excel_interface.xls").Activate
Range("C4").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Station1_rho_imp2.xlsx").Activate
Range("B6").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks _
:=False, Transpose:=False

Windows("Excel_interface.xls").Activate
Range("C5").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Station1_rho_imp2.xlsx").Activate
Range("C6").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks _
:=False, Transpose:=False

Windows("Excel_interface.xls").Activate
Range("C6").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Station1_rho_imp2.xlsx").Activate
Range("D6").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks _
:=False, Transpose:=False

Windows("Excel_interface.xls").Activate
Range("C7").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Station1_rho_imp2.xlsx").Activate
```



FINAL PROJECT

Date: 19.06.2014

Page: 157

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

```
Range("E6").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks_
:=False, Transpose:=False

Windows("Excel_interface.xls").Activate
Range("C8").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Station1_rho_imp2.xlsx").Activate
Range("F6").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks_
:=False, Transpose:=False

Windows("Excel_interface.xls").Activate
Range("C9").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Station1_rho_imp2.xlsx").Activate
Range("G6").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks_
:=False, Transpose:=False

Windows("Excel_interface.xls").Activate
Range("C10").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Station1_rho_imp2.xlsx").Activate
Range("B9").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks_
:=False, Transpose:=False

Windows("Excel_interface.xls").Activate
Range("C11").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Station1_rho_imp2.xlsx").Activate
Range("C9").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks_
:=False, Transpose:=False

Windows("Excel_interface.xls").Activate
Range("C12").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Station1_rho_imp2.xlsx").Activate
```



FINAL PROJECT

Date: 19.06.2014

Page: 158

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

```
Range("D9").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks_
:=False, Transpose:=False

'COPY THE OUTPUTS
'VALUES FROM "STATION1_RHO_IMP2" TO "EXCEL_INTERFACE"

Windows("Station1_rho_imp2.xlsx").Activate
Range("A23").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Excel_interface.xls").Activate
Range("C20").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks_
:=False, Transpose:=False

Windows("Station1_rho_imp2.xlsx").Activate
Range("B23").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Excel_interface.xls").Activate
Range("C21").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks_
:=False, Transpose:=False

Windows("Station1_rho_imp2.xlsx").Activate
Range("C23").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Excel_interface.xls").Activate
Range("C22").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks_
:=False, Transpose:=False

Windows("Station1_rho_imp2.xlsx").Activate
Range("D23").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Excel_interface.xls").Activate
Range("C23").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks_
:=False, Transpose:=False

Range("D1").Select
Windows("Station1_rho_imp2.xlsx").Activate
```



FINAL PROJECT

Date: 19.06.2014

Page: 159

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

```
Application.CutCopyMode = False
Selection.Copy
Windows("Excel_interface.xls").Activate
Range("C16").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks _
:=False, Transpose:=False

Windows("Station1_rho_imp2.xlsx").Activate
Range("E23").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Excel_interface.xls").Activate
Range("C24").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks _
:=False, Transpose:=False

Windows("Station1_rho_imp2.xlsx").Activate
Range("F23").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Excel_interface.xls").Activate
Range("C25").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks _
:=False, Transpose:=False

Windows("Station1_rho_imp2.xlsx").Activate
Range("G23").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Excel_interface.xls").Activate
Range("C26").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks _
:=False, Transpose:=False

Windows("Station1_rho_imp2.xlsx").Activate
Range("A26").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Excel_interface.xls").Activate
Range("C27").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks _
:=False, Transpose:=False

Windows("Station1_rho_imp2.xlsx").Activate
Range("B26").Select
```




FINAL PROJECT

Date: 19.06.2014

Page: 160

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

```
Application.CutCopyMode = False
Selection.Copy
Windows("Excel_interface.xls").Activate
Range("C28").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks _
:=False, Transpose:=False

Windows("Station1_rho_imp2.xlsx").Activate
Range("C26").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Excel_interface.xls").Activate
Range("C29").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks _
:=False, Transpose:=False

Windows("Station1_rho_imp2.xlsx").Activate
Range("D26").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Excel_interface.xls").Activate
Range("C30").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks _
:=False, Transpose:=False

Windows("Station1_rho_imp2.xlsx").Activate
Range("E26").Select
Application.CutCopyMode = False
Selection.Copy
Windows("Excel_interface.xls").Activate
Range("C31").Select
Selection.PasteSpecial Paste:=xlPasteValues, Operation:=xlNone,
SkipBlanks _
:=False, Transpose:=False

'Save and close "STATION1_RHO_IMP2"

Windows("Station1_rho_imp2.xlsx").Activate
Application.CutCopyMode = False
ActiveWorkbook.Save
ActiveWorkbook.Close

End Sub

Sub DataLogger()
'
```



FINAL PROJECT

Date: 19.06.2014

Page: 161

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

```
' DataLogger Macro
'
' Acceso directo: CTRL+a
'Hour
    Sheets("Data Logger").Select
    Range("A2").value = Now()

'Insert a new empty row

    Rows("5:5").Select
    Selection.Insert Shift:=xlDown, CopyOrigin:=xlFormatFromLeftOrAbove
    With Selection.Interior
        .Pattern = xlNone
        .TintAndShade = 0
        .PatternTintAndShade = 0
    End With

    'Copy the value of the magnitudes

    Rows("2:2").Select
    Selection.Copy
    Rows("5:5").Select
    Rows("2:2").Select
    Application.CutCopyMode = False
    Selection.Copy
    Rows("5:5").Select
    Selection.PasteSpecial Paste:=xlPasteAll, Operation:=xlNone,
SkipBlanks:= _
        False, Transpose:=False
    Application.CutCopyMode = False
    'Select the principal sheet
    Sheets("Data").Select
End Sub
```

1.4 SHEET 1

```
VERSION 1.0 CLASS
BEGIN
    MultiUse = -1    'True
END
Attribute VB_Name = "Sheet1"
Attribute VB_GlobalNameSpace = False
Attribute VB_Creatable = False
Attribute VB_PredeclaredId = True
Attribute VB_Exposed = True
```



FINAL PROJECT

Date: 19.06.2014

Page: 162

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

```
Private Sub CommandButton1_Click()  
    ActiveWorkbook.update_data  
End Sub
```

```
Private Sub CommandButton2_Click()  
    UserForm1.Show vbModeless  
End Sub
```

```
Private Sub CommandButton3_Click()  
    UserForm2.Show vbModeless  
End Sub
```

In order to know how the interface looks, in the figure below is shown a fragment of the "Data" sheet (of the excel interface).

	A	B	C	D	E	F	G	H	I	J
1	HMI Server	192.168.0.8					Status	OK		
2	Description	Tag Name	Value	Read/Write	Status		Update Data			
3	0->R134A, 1->R410A, 2->R407C, 3->R22	Puestos1.UDT1_1Ref_number	0,00	r						
4	Input pressure of the compressor	Puestos1.UDT1_1P1_m	3,40	r			Hour	13:34:21		
5	Pressure desired at point one	Puestos1.UDT1_1P1_set	3,50	r			Next actualization	11:33:14		
6	Quality at the entering of the compressor	Puestos1.UDT1_1x1	0,95	r			Actualization time	0:00:05		
7	Water output temperature	Puestos1.UDT1_1Tout_m	23,00	r			Info Deutsch			
8	input pressure of the condenser	Puestos1.UDT1_1P2_m	20,30	r						
9	Extra temperature degrees above the sat.T* to be obtained by the resistance	Puestos1.UDT2_1delta_T_resistance	3,00	r			Info English			
10	Water flux measured	Puestos1.UDT1_1m_w_m	2,50	r						
11	$m_ref/rho_ref = displ [m^3/rev]*rps[rev/s]*vol_eff$	Puestos1.UDT6_1m_ref_div_rho	0,00	r						
12	Input temperature of the condenser	Puestos1.UDT1_1T2_m	70,90	r						
13	Refrigerant flux measured	Puestos1.UDT1_1m_ref_m	50,50	r						
14	Pressure at the exit of the condenser	Puestos1.UDT1_1P3_m	20,29	r						
15	Temperature at the entering of the compressor	Puestos1.UDT1_1T1_m	5,03	r						
16	Temperature at the exit of the condenser	Puestos1.UDT1_1T3_m	68,23	r						
17	Input water temperature of the condenser	Puestos1.UDT1_1Tin_m	15,40	r						
18	Water flux calculated (l/min)	Puestos1.UDT2_1flow_w_lit_min	2,56	r						
19	1-> Ref flux sensor connected, 0-> Flux sensor not connect	Puestos1.UDT4_1m_ref_conectado	1,00	r						
20	Theoretical temperatura ata point1, saturation temperature	Puestos1.UDT2_1T1sat	5,01	w						
21	Enthalpy at point 1, according to the desired P1	Puestos1.UDT2_1h1_th	243,62	w						
22	Enthalpy computed with the data of the sensor in the operating point 1	Puestos1.UDT2_1h1	243,12	w						
23	Saturation temperature for P2	Puestos1.UDT2_1T2sat	68,11	w						
24	Enthalpy at point 2, with theoretical data	Puestos1.UDT2_1h2_th	284,84	w						
25	Enthalpy desired at point 3 (= h1_th)	Puestos1.UDT2_1h3_th	243,62	w						
26	Desired temperatura at point 2, T2sat+delta_T_resistance	Puestos1.UDT2_1T2deseada	71,11	w						
27	Refrigerant density at the entrance of the compressor	Puestos1.UDT2_1rho_ref	17,54	w						
28	Enthalpy at point 2, with measured data	Puestos1.UDT2_1h2_m	186,71	w						
29	Enthalpy at point 3, with measured data	Puestos1.UDT2_1h3_m	243,12	w						
30	Theoretical refrigerant flux	Puestos1.UDT2_1m_ref_th	0,05	w						
31	$m_ref_th*1000-> [g/s]$	Puestos1.UDT6_1m_ref_grams	50,00	w						

Figure 49-Excel interface



FINAL PROJECT

Date: 19.06.2014

Page: 163

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2 DATA LOGGER

There is a possibility to store the values of the magnitudes exported, with date-time register. It could be useful when the study of the data is been performed, in order to determine whether the test was valid or not.


2.1 DATA LOGGER FUNCTION

It is stored in the "Module 2":

```
Sub DataLogger()  
'  
' DataLogger Macro  
'  
' Acceso directo: CTRL+a  
'Hour  
    Sheets("Data Logger").Select  
    Range("A2").value = Now()  
  
'Insert a new empty row  
  
    Rows("5:5").Select  
    Selection.Insert Shift:=xlDown, CopyOrigin:=xlFormatFromLeftOrAbove  
    With Selection.Interior  
        .Pattern = xlNone  
        .TintAndShade = 0  
        .PatternTintAndShade = 0  
    End With  
  
    'Copy the value of the magnitudes  
  
    Rows("2:2").Select  
    Selection.Copy  
    Rows("5:5").Select  
    Rows("2:2").Select  
    Application.CutCopyMode = False  
    Selection.Copy  
    Rows("5:5").Select  
    Selection.PasteSpecial Paste:=xlPasteAll, Operation:=xlNone,  
SkipBlanks:= _  
    False, Transpose:=False  
    Application.CutCopyMode = False  
    'Select the principal sheet  
    Sheets("Data").Select  
End Sub
```

	FINAL PROJECT	Date: 19.06.2014 Page: 164
PROJECT: “Compressors test live bench under wet compression conditions”		ANNEX: 2

In order to know how the interface looks, in the figure bellow is shown a fragment of the “Data Logger” sheet (of the excel interface).



	A	B	C	D	E	F	G
1	Time&Date	Puestos1.UDT1_1P1_m	Puestos1.UDT1_1P2_m	Puestos1.UDT1_1P3_m	Puestos1.UDT1_1T1_m	Puestos1.UDT1_1T2_m	Puestos1.UDT1_1T3_m
2	17/06/2014 13:19	3,40	20,30	20,29	5,03	70,90	68,23
3							
4	Time&Date	Puestos1.UDT1_1P1_m	Puestos1.UDT1_1P2_m	Puestos1.UDT1_1P3_m	Puestos1.UDT1_1T1_m	Puestos1.UDT1_1T2_m	Puestos1.UDT1_1T3_m
5	17/06/2014 13:19	3,40	20,30	20,29	5,03	70,90	68,23
6	17/06/2014 13:18	3,40	20,30	20,29	5,03	70,90	68,23
7	17/06/2014 13:18	3,40	20,30	20,29	5,03	70,90	68,23
8	17/06/2014 13:18	3,40	20,30	20,29	5,03	70,90	68,23
9	17/06/2014 13:18	3,40	20,30	20,29	5,03	70,90	68,23
10	17/06/2014 13:17	3,40	20,30	20,29	5,03	70,90	68,23
11	17/06/2014 13:17	3,40	20,30	20,29	5,03	70,90	68,23

Figure 50- Data Logger

3 CALCULATION FILE

There would be defined a file for each station in which the thermodynamic tables could be found. The first sheet of the excel file, would be a “summary”: The inputs would be copy from the “excel_interface”, and once that the output have been computed they would be transpose as well to the “excel_interface”, to return to the WINCC and PLC.

As the refrigerant number is provided, even if the calculations would be made in each refrigerant sheet, the summary would only contain the results of the selected refrigerant (“0” for the R134A, “1” for R410A, “2” for R407C, “3” for R32 and “4”for R290).

Mainly, the operations computed is the “search” in the corresponding thermodynamic tables, the pressure, temperature and /or quality import, to return a value of enthalpy, density,....As finding the same value in the tables as the one that was imported is difficult to achieve (the tables have limited values), interpolations have been defined.



FINAL PROJECT

Date: 19.06.2014

Page: 165

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

DATA IMPORT-EXPORT

INPUTS.-Second calculations

Num.Ref	P1_m	P1_set	x1	Tout	P2_m	delta_T_res
0,00	3,40	3,50	0,95	23,00	20,30	3,00

Refrigerant	m_w_m	mrefDivRho	T2_m
R134A	2,50	0,00	70,90

OUTPUTS.-Second calculations

T1sat	h1_th	h1	T2sat	h2_th	h3_th	T2desired
5,01	243,62	243,12	68,11	284,84	243,62	71,11

rho_ref	h2_m	h3_m	m_ref_th	m_ref_gram
17,54	186,71	243,12	0,05	50,00

Figure 51-Summary data import-export

For the "refrigerant sheets", the same structure as the "summary" has been employed. However, as interpolations must be made, another section has had to be added.

DATA IMPORT-EXPORT FOR R134A

R134A.-INPUTS.-Second calculations

Num.Ref	P1_m	P1_set	x1	Tout	P2_m	delta_T_res
0	3,4	3,5	0,95	23	20,3	3

Refrigerant	m_w_m	mrefDivRho	T2_m
R134A	2,5	0,00285	70,9

R134A.-OUTPUTS.-Second calculations

T1sat	h1_th	h1	T2sat	h2_th	h3_th	T2desired
5,008	243,620772	243,120772	68,11	284,84	243,620772	71,11

rho_ref	h2_m	h3_m	m_ref_th	m_ref_gram
17,5434718	186,7082	243,120772	0,04999889	49,9988947



FINAL PROJECT

Date: 19.06.2014

Page: 166

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

R134A.-AUXILIAR-Second calculations

h1 m min	x1 min	h1 m max	x1 max
237,5	0,9213	244,1	0,955

h1 th min	x1 min	h1 th max	x1 max
238	0,9213	244,6	0,955

h2 th min	T2th min	h2 th max	T2th max
287,6	73,11	294,5	78,11

rho ref min	x1 min	rho ref max	x1 max
18,08	0,9213	17,45	0,955

h2 th min	T2th min	h2 th max	T2th max
287,6	73,11	294,5	78,11

Figure 52-R134A import-export data

DATA IMPORT-EXPORT FOR R410A

R410A.-INPUTS.-Second calculations

Num.Ref	P1_m	P1_set	x1	Tout	P2_m	delta_T_res
1	3,4	3,5	0,95	23	20,3	3

Refrigerant	m_w_m	mrefDivRho	T2_m
R410A	2,5	0,00285	70,9

DATA IMPORT-EXPORT FOR R407C

R407C.-INPUTS.-Second calculations

Num.Ref	P1_m	P1_set	x1	Tout	P2_m	delta_T_res
2	3,4	3,5	0,95	23	20,3	3

Refrigerant	m_w_m	mrefDivRho	T2_m
R407C	2,5	0,00285	70,9

R410A.-OUTPUTS.-Second calculations

T1set	h1 th	h1	T2set	h2 th	h3 th	T2desired
-23,45	400,368546	399,968546	32,93	427	400,368546	32,93

rho_ref	h2_m	h3_m	m_ref_th	m_ref_gram
13,8827003	380,898	399,968546	0,0395657	39,5656958

R407C.-OUTPUTS.-Second calculations

T1set	h1 th	h1	T2set	h2 th	h3 th	T2desired
-7,586	394,602077	394,18724	50,87	426,6	394,602077	50,87

rho_ref	h2_m	h3_m	m_ref_th	m_ref_gram
15,2208309	358,4342	394,18724	0,04337957	43,379368

R410A.-AUXILIAR-Second calculations

h1 m min	x1 min	h1 m max	x1 max
392,9	0,9213	401,2	0,955

h1 th min	x1 min	h1 th max	x1 max
393,3	0,9213	401,6	0,955

h2 th min	T2th min	h2 th max	T2th max
434	37,93	441	42,93

rho ref min	x1 min	rho ref max	x1 max
14,3	0,9213	13,81	0,955

h2 th min	T2th min	h2 th max	T2th max
434	37,93	441	42,93

R407C.-AUXILIAR-Second calculations

h1 m min	x1 min	h1 m max	x1 max
387,8	0,9213	395,3	0,955

h1 th min	x1 min	h1 th max	x1 max
388,3	0,9213	395,7	0,955

h2 th min	T2th min	h2 th max	T2th max
433,3	55,87	440	60,87

rho ref min	x1 min	rho ref max	x1 max
15,57	0,9213	15,16	0,955

h2 th min	T2th min	h2 th max	T2th max
433,3	55,87	440	60,87

Figure 53-R410A & R407C import_export data



FINAL PROJECT

Date: 19.06.2014

Page: 167

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2




Figure 54-R32 & R290 import_export data

The same structure would be implemented for all the refrigerant sheets, only the color would vary from one to another.



FINAL PROJECT

Date: 19.06.2014

Page: 168

PROJECT:
"Compressors test live bench under wet compression conditions"

PLANES:
3

ANNEX VII: STEP 7

1 STRUCTURE

SIMATIC TFG_BSH\SIMATIC 300(1)\CPU 315- 16/06/2014 09:25:46
2 PN/DP...\Bloques -- Estructura del programa

Estructura del programa (estructura de llamada)

Bloque (símbolo), DB de instancia (símbolo)	Datos	Lenguaje	Punto de aplicación		
Programa S7					
OBI [máximo: 664]	[22]				
FC1 (START_STOP_HMI_button)	[48]	AWL	Seg	1	Ins 1
DB10 (Puesto1)	[48]	AWL	Seg	1	Ins 1
DB20 (Puesto2)	[48]	AWL	Seg	1	Ins 6
DB30 (Puesto3)	[48]	AWL	Seg	1	Ins 11
DB40 (Puesto4)	[48]	AWL	Seg	1	Ins 16
DB50 (Puesto5)	[48]	AWL	Seg	1	Ins 21
DB60 (Puesto6)	[48]	AWL	Seg	1	Ins 26
DB70 (Puesto7)	[48]	AWL	Seg	1	Ins 31
DB80 (Puesto8)	[48]	AWL	Seg	1	Ins 36
DB90 (Puesto9)	[48]	AWL	Seg	1	Ins 41
DB100 (Puesto10)	[48]	AWL	Seg	1	Ins 46
DB110 (Puesto11)	[48]	AWL	Seg	1	Ins 51
DB120 (Puesto12)	[48]	AWL	Seg	1	Ins 56
FC8 (STOP_manual&automatic)	[70]	AWL	Seg	1	Ins 66
FC2 (Real->Int->Word)	[70]	AWL	Seg	4	Ins 1
FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg	4	Ins 12
FC2 (Real->Int->Word)	[70]	AWL	Seg	4	Ins 13
FC2 (Real->Int->Word)	[70]	AWL	Seg	5	Ins 7
FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg	5	Ins 18
FC10 (Station1_set)	[252]	AWL	Seg	5	Ins 19
DB10 (Puesto1)	[252]	AWL	Seg	1	Ins 1
FC97 (Station_AUT_ON)	[446]	AWL	Seg	2	Ins 8
FC5 (AUT_SensON/OFF->th/calc)	[640]	AWL	Seg	1	Ins 1
FC3 (Sensor conect/desconect)	[640]	AWL	Seg	1	Ins 11
FC105 (SCALE)	[660]	AWL	Seg	1	Ins 13
FC105 (SCALE)	[660]	AWL	Seg	1	Ins 15
FC105 (SCALE)	[660]	AWL	Seg	1	Ins 17
FC105 (SCALE)	[660]	AWL	Seg	1	Ins 19
FC105 (SCALE)	[660]	AWL	Seg	1	Ins 21
FC94 (Excel_DB)	[640]	AWL	Seg	3	Ins 3
FC6 (OperationCalculation)	[664]	AWL	Seg	4	Ins 2
FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 3
FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 6
FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 9
FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 12
FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 15
FC105 (SCALE)	[660]	AWL	Seg	5	Ins 17
FC105 (SCALE)	[660]	AWL	Seg	5	Ins 19
FC105 (SCALE)	[660]	AWL	Seg	5	Ins 21
FC105 (SCALE)	[660]	AWL	Seg	5	Ins 23
FC105 (SCALE)	[660]	AWL	Seg	5	Ins 25
FC94 (Excel_DB)	[640]	AWL	Seg	6	Ins 3
FC6 (OperationCalculation)	[664]	AWL	Seg	7	Ins 3
FC7 (AUT_Control PID)	[468]	AWL	Seg	2	Ins 1
FC2 (Real->Int->Word)	[468]	AWL	Seg	1	Ins 9
FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg	1	Ins 10
FC10 (Station1_set)	[650]	AWL	Seg	1	Ins 11
FC2 (Real->Int->Word)	[468]	AWL	Seg	1	Ins 12



FINAL PROJECT

Date: 19.06.2014

Page: 169

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

SIMATIC TFG_BSH\SIMATIC 300(1)\CPU 315- 16/06/2014 09:25:47
2 PN/DP\...\Bloques -- Estructura del programa

Bloque (símbolo), DB de instancia (símbolo)	Datos	Lenguaje	Punto de aplicación
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 2 Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg 2 Ins 2
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 2 Ins 3
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 3 Ins 1
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[520]	AWL	Seg 3 Ins 2
<input type="checkbox"/> FC4 (Alarm)	[278]	AWL	Seg 2 Ins 9
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg 2 Ins 13
<input type="checkbox"/> FC96 (Station_MAN_ON)	[314]	AWL	Seg 3 Ins 21
<input type="checkbox"/> FC98 (MAN_SensON/SensOFF->th)	[330]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 1 Ins 6
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 1 Ins 8
<input type="checkbox"/> FC3 (Sensor conect/desconnect)	[330]	AWL	Seg 3 Ins 4
<input type="checkbox"/> FC3 (Sensor conect/desconnect)	[330]	AWL	Seg 3 Ins 7
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 11
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 13
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 15
<input type="checkbox"/> FC9 (MAN_ControlPID)	[340]	AWL	Seg 2 Ins 9
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 1 Ins 14
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[392]	AWL	Seg 1 Ins 15
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 11
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 2 Ins 12
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg 2 Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 14
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 24
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 2 Ins 25
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg 2 Ins 26
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 27
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 5
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 3 Ins 6
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 7
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 3 Ins 10
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 11
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg 3 Ins 23
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 5 Ins 20
<input type="checkbox"/> FC8 (STOP_manual&automatic)	[70]	AWL	Seg 1 Ins 83
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 4 Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg 4 Ins 12
<input type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg 4 Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 4 Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 5 Ins 7
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg 5 Ins 18
<input type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg 5 Ins 18
<input type="checkbox"/> FC10 (Station1_set)	[252]	AWL	Seg 5 Ins 19
<input type="checkbox"/> DB10 (Puestos1)	[252]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC97 (Station_AUT_ON)	[446]	AWL	Seg 2 Ins 8
<input type="checkbox"/> FC5 (AUT_SensON/OFF->th/calc)	[640]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC3 (Sensor conect/desconnect)	[640]	AWL	Seg 1 Ins 11
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 13
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 21
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg 3 Ins 3



FINAL PROJECT

Date: 19.06.2014

Page: 170

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

SIMATIC TFG_BSH\SIMATIC 300(1)\CPU 315- 16/06/2014 09:25:48
2 PN/DP\...\Bloques -- Estructura del programa

Bloque (símbolo), DB de instancia (símbolo)	Datos	Lenguaje	Punto de aplicación			
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg	4	Ins	2
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins	3
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins	6
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins	9
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins	12
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins	15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins	17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins	19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins	21
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins	23
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins	25
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg	6	Ins	3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg	7	Ins	3
<input type="checkbox"/> FC7 (AUT_Control PID)	[468]	AWL	Seg	2	Ins	1
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	1	Ins	9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg	1	Ins	10
<input checked="" type="checkbox"/> FC10 (Station1_set)	[650]	AWL	Seg	1	Ins	11
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	1	Ins	12
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	2	Ins	1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg	2	Ins	2
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	2	Ins	3
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	3	Ins	1
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[520]	AWL	Seg	3	Ins	2
<input type="checkbox"/> FC4 (Alarm)	[278]	AWL	Seg	2	Ins	9
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg	2	Ins	13
<input type="checkbox"/> FC96 (Station_MAN_ON)	[314]	AWL	Seg	3	Ins	21
<input type="checkbox"/> FC98 (MAN_SensON/SensOFF->th)	[330]	AWL	Seg	1	Ins	1
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	1	Ins	6
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	1	Ins	8
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[330]	AWL	Seg	3	Ins	4
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[330]	AWL	Seg	3	Ins	7
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	3	Ins	11
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	3	Ins	13
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	3	Ins	15
<input type="checkbox"/> FC9 (MAN_ControlPID)	[340]	AWL	Seg	2	Ins	9
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	1	Ins	14
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[392]	AWL	Seg	1	Ins	15
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins	11
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	2	Ins	12
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg	2	Ins	13
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins	14
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins	24
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	2	Ins	25
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg	2	Ins	26
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins	27
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins	5
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	3	Ins	6
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins	7
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins	9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	3	Ins	10
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins	11
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg	3	Ins	23



FINAL PROJECT

Date: 19.06.2014

Page: 171

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

SIMATIC TFG_BSH\SIMATIC 300(1)\CPU 315- 16/06/2014 09:25:50
2 PN/DP\...\Bloques -- Estructura del programa

Bloque (símbolo), DB de instancia (símbolo)	Datos	Lenguaje	Punto de aplicación		
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg	5	Ins 20
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[70]	AWL	Seg	1	Ins 100
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg	4	Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg	4	Ins 12
<input type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg	4	Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg	4	Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg	5	Ins 7
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg	5	Ins 18
<input type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg	5	Ins 18
<input type="checkbox"/> FC10 (Station1_set)	[252]	AWL	Seg	5	Ins 19
<input type="checkbox"/> DB10 (Puestos1)	[252]	AWL	Seg	1	Ins 1
<input type="checkbox"/> FC97 (Station_AUT_ON)	[446]	AWL	Seg	2	Ins 8
<input type="checkbox"/> FC5 (AUT_SensON/OFF->th/calc)	[640]	AWL	Seg	1	Ins 1
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	1	Ins 11
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	1	Ins 13
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	1	Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	1	Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	1	Ins 19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	1	Ins 21
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg	3	Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg	4	Ins 2
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 3
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 6
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 9
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 12
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins 19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins 21
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins 23
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins 25
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg	6	Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg	7	Ins 3
<input type="checkbox"/> FC7 (AUT_Control PID)	[468]	AWL	Seg	2	Ins 1
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	1	Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg	1	Ins 10
<input checked="" type="checkbox"/> FC10 (Station1_set)	[650]	AWL	Seg	1	Ins 11
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	1	Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	2	Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg	2	Ins 2
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	2	Ins 3
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	3	Ins 1
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[520]	AWL	Seg	3	Ins 2
<input type="checkbox"/> FC4 (Alarm)	[278]	AWL	Seg	2	Ins 9
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg	2	Ins 13
<input type="checkbox"/> FC96 (Station_MAN_ON)	[314]	AWL	Seg	3	Ins 21
<input type="checkbox"/> FC98 (MAN_SensON/SensOFF->th)	[330]	AWL	Seg	1	Ins 1
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	1	Ins 6
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	1	Ins 8
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[330]	AWL	Seg	3	Ins 4
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[330]	AWL	Seg	3	Ins 7



FINAL PROJECT

Date: 19.06.2014

Page: 172

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

SIMATIC TFG_BSH\SIMATIC 300(1)\CPU 315- 16/06/2014 09:25:51
2 PN/DP\...\Bloques -- Estructura del programa

Bloque (símbolo), DB de instancia (símbolo)	Datos	Lenguaje	Punto de aplicación
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 11
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 13
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 15
<input type="checkbox"/> FC9 (MAN_ControlPID)	[340]	AWL	Seg 2 Ins 9
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 1 Ins 14
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[392]	AWL	Seg 1 Ins 15
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 11
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 2 Ins 12
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg 2 Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 14
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 24
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 2 Ins 25
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg 2 Ins 26
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 27
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 5
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 3 Ins 6
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 7
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 3 Ins 10
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 11
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg 3 Ins 23
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 5 Ins 20
<input type="checkbox"/> FC8 (STOP_manual&automatic)	[70]	AWL	Seg 1 Ins 117
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 4 Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg 4 Ins 12
<input checked="" type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg 4 Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 4 Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 5 Ins 7
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg 5 Ins 18
<input checked="" type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg 5 Ins 18
<input type="checkbox"/> FC10 (Station1_set)	[252]	AWL	Seg 5 Ins 19
<input checked="" type="checkbox"/> DB10 (Puestos1)	[252]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC97 (Station AUT_ON)	[446]	AWL	Seg 2 Ins 8
<input type="checkbox"/> FC5 (AUT_SensON/OFF->th/calc)	[640]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 1 Ins 11
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 13
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 21
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg 3 Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg 4 Ins 2
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 3
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 6
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 9
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 12
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 21
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 23
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 25



FINAL PROJECT

Date: 19.06.2014

Page: 173

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

SIMATIC TFG_BSH\SIMATIC 300(1)\CPU 315- 16/06/2014 09:25:52
2 PN/DP\...\Bloques -- Estructura del programa

Bloque (símbolo), DB de instancia (símbolo)	Datos	Lenguaje	Punto de aplicación
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg 6 Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg 7 Ins 3
<input checked="" type="checkbox"/> FC7 (AUT_Control PID)	[468]	AWL	Seg 2 Ins 1
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 1 Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg 1 Ins 10
<input checked="" type="checkbox"/> FC10 (Station1_set)	[650]	AWL	Seg 1 Ins 11
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 1 Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 2 Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg 2 Ins 2
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 2 Ins 3
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 3 Ins 1
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[520]	AWL	Seg 3 Ins 2
<input type="checkbox"/> FC4 (Alarm)	[278]	AWL	Seg 2 Ins 9
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg 2 Ins 13
<input type="checkbox"/> FC96 (Station_MAN_ON)	[314]	AWL	Seg 3 Ins 21
<input type="checkbox"/> FC98 (MAN_SensON/SensOFF->th)	[330]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 1 Ins 6
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 1 Ins 8
<input type="checkbox"/> FC3 (Sensor connect/desconnect)	[330]	AWL	Seg 3 Ins 4
<input type="checkbox"/> FC3 (Sensor connect/desconnect)	[330]	AWL	Seg 3 Ins 7
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 11
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 13
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 15
<input type="checkbox"/> FC9 (MAN_ControlPID)	[340]	AWL	Seg 2 Ins 9
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 1 Ins 14
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[392]	AWL	Seg 1 Ins 15
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 11
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 2 Ins 12
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg 2 Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 14
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 24
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 2 Ins 25
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg 2 Ins 26
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 27
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 5
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 3 Ins 6
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 7
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 3 Ins 10
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 11
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg 3 Ins 23
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 5 Ins 20
<input type="checkbox"/> FC8 (STOP_manual&automatic)	[70]	AWL	Seg 1 Ins 134
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 4 Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg 4 Ins 12
<input type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg 4 Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 4 Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 5 Ins 7
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg 5 Ins 18
<input type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg 5 Ins 18
<input type="checkbox"/> FC10 (Station1_set)	[252]	AWL	Seg 5 Ins 19
<input type="checkbox"/> DB10 (Puestos1)	[252]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC97 (Station_AUT_ON)	[446]	AWL	Seg 2 Ins 8
<input type="checkbox"/> FC5 (AUT_SensON/OFF->th/calc)	[640]	AWL	Seg 1 Ins 1



FINAL PROJECT

Date: 19.06.2014

Page: 174

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

SIMATIC TFG_BSH\SIMATIC 300(1)\CPU 315- 16/06/2014 09:25:54
2 PN/DP\...\Bloques -- Estructura del programa

Bloque (símbolo), DB de instancia (símbolo)	Datos	Lenguaje	Punto de aplicación
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 1 Ins 11
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 13
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 21
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg 3 Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg 4 Ins 2
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 3
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 6
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 9
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 12
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 21
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 23
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 25
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg 6 Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg 7 Ins 3
<input type="checkbox"/> FC7 (AUT_Control PID)	[468]	AWL	Seg 2 Ins 1
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 1 Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg 1 Ins 10
<input checked="" type="checkbox"/> FC10 (Station1_set)	[650]	AWL	Seg 1 Ins 11
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 1 Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 2 Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg 2 Ins 2
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 2 Ins 3
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 3 Ins 1
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[520]	AWL	Seg 3 Ins 2
<input type="checkbox"/> FC4 (Alarm)	[278]	AWL	Seg 2 Ins 9
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg 2 Ins 13
<input type="checkbox"/> FC96 (Station_MAN_ON)	[314]	AWL	Seg 3 Ins 21
<input type="checkbox"/> FC98 (MAN_SensON/SensOFF->th)	[330]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 1 Ins 6
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 1 Ins 8
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[330]	AWL	Seg 3 Ins 4
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[330]	AWL	Seg 3 Ins 7
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 11
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 13
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 15
<input type="checkbox"/> FC9 (MAN_ControlPID)	[340]	AWL	Seg 2 Ins 9
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 1 Ins 14
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[392]	AWL	Seg 1 Ins 15
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 11
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 2 Ins 12
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg 2 Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 14
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 24
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 2 Ins 25
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg 2 Ins 26



FINAL PROJECT

Date: 19.06.2014

Page: 175

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

SIMATIC TFG_BSH\SIMATIC 300(1)\CPU 315- 16/06/2014 09:25:55
2 PN/DP\...\Bloques -- Estructura del programa

Bloque (símbolo), DB de instancia (símbolo)	Datos	Lenguaje	Punto de aplicación
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 27
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 5
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 3 Ins 6
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 7
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 3 Ins 10
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 11
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg 3 Ins 23
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 5 Ins 20
<input type="checkbox"/> FC8 (STOP_manual&automatic)	[70]	AWL	Seg 1 Ins 151
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 4 Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg 4 Ins 12
<input type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg 4 Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 4 Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 5 Ins 7
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg 5 Ins 18
<input type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg 5 Ins 18
<input type="checkbox"/> FC10 (Station1_set)	[252]	AWL	Seg 5 Ins 19
<input type="checkbox"/> DB10 (Puestos1)	[252]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC97 (Station_AUT_ON)	[446]	AWL	Seg 2 Ins 8
<input type="checkbox"/> FC5 (AUT_SensON/OFF->th/calc)	[640]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 1 Ins 11
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 13
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 21
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg 3 Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg 4 Ins 2
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 3
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 6
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 9
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 12
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 21
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 23
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 25
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg 6 Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg 7 Ins 3
<input type="checkbox"/> FC7 (AUT_Control PID)	[468]	AWL	Seg 2 Ins 1
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 1 Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg 1 Ins 10
<input checked="" type="checkbox"/> FC10 (Station1_set)	[650]	AWL	Seg 1 Ins 11
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 1 Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 2 Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg 2 Ins 2
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 2 Ins 3
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 3 Ins 1
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[520]	AWL	Seg 3 Ins 2
<input type="checkbox"/> FC4 (Alarm)	[278]	AWL	Seg 2 Ins 9



FINAL PROJECT

Date: 19.06.2014

Page: 176

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

SIMATIC TFG_BSH\SIMATIC 300(1)\CPU 315- 16/06/2014 09:25:57
2 PN/DP\...\Bloques -- Estructura del programa

Bloque (símbolo), DB de instancia (símbolo)	Datos	Lenguaje	Punto de aplicación		
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg	2	Ins 13
<input type="checkbox"/> FC96 (Station_MAN_ON)	[314]	AWL	Seg	3	Ins 21
<input type="checkbox"/> FC98 (MAN_SensON/SensOFF->th)	[330]	AWL	Seg	1	Ins 1
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	1	Ins 6
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	1	Ins 8
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[330]	AWL	Seg	3	Ins 4
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[330]	AWL	Seg	3	Ins 7
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	3	Ins 11
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	3	Ins 13
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	3	Ins 15
<input type="checkbox"/> FC9 (MAN_ControlPID)	[340]	AWL	Seg	2	Ins 9
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	1	Ins 14
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[392]	AWL	Seg	1	Ins 15
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins 11
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	2	Ins 12
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg	2	Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins 14
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins 24
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	2	Ins 25
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg	2	Ins 26
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins 27
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins 5
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	3	Ins 6
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins 7
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	3	Ins 10
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins 11
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg	3	Ins 23
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg	5	Ins 20
<input type="checkbox"/> FC8 (STOP_manual&automatic)	[70]	AWL	Seg	1	Ins 168
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg	4	Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg	4	Ins 12
<input type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg	4	Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg	4	Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg	5	Ins 7
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg	5	Ins 18
<input type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg	5	Ins 18
<input type="checkbox"/> FC10 (Station1_set)	[252]	AWL	Seg	5	Ins 19
<input type="checkbox"/> DB10 (Puestos1)	[252]	AWL	Seg	1	Ins 1
<input type="checkbox"/> FC97 (Station_AUT_ON)	[446]	AWL	Seg	2	Ins 8
<input type="checkbox"/> FC5 (AUT_SensON/OFF->th/calc)	[640]	AWL	Seg	1	Ins 1
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	1	Ins 11
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	1	Ins 13
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	1	Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	1	Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	1	Ins 19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	1	Ins 21
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg	3	Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg	4	Ins 2
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 3
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 6
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 9



FINAL PROJECT

Date: 19.06.2014

Page: 177

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

SIMATIC TFG_BSH\SIMATIC 300(1)\CPU 315- 16/06/2014 09:25:59
2 PN/DP\...\Bloques -- Estructura del programa

Bloque (símbolo), DB de instancia (símbolo)	Datos	Lenguaje	Punto de aplicación			
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins	12
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins	15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins	17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins	19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins	21
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins	23
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins	25
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg	6	Ins	3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg	7	Ins	3
<input type="checkbox"/> FC7 (AUT_Control PID)	[468]	AWL	Seg	2	Ins	1
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	1	Ins	9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg	1	Ins	10
<input checked="" type="checkbox"/> FC10 (Station1_set)	[650]	AWL	Seg	1	Ins	11
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	1	Ins	12
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	2	Ins	1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg	2	Ins	2
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	2	Ins	3
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	3	Ins	1
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[520]	AWL	Seg	3	Ins	2
<input type="checkbox"/> FC4 (Alarm)	[278]	AWL	Seg	2	Ins	9
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg	2	Ins	13
<input type="checkbox"/> FC96 (Station_MAN_ON)	[314]	AWL	Seg	3	Ins	21
<input type="checkbox"/> FC98 (MAN_SensON/SensOFF->th)	[330]	AWL	Seg	1	Ins	1
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	1	Ins	6
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	1	Ins	8
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[330]	AWL	Seg	3	Ins	4
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[330]	AWL	Seg	3	Ins	7
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	3	Ins	11
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	3	Ins	13
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	3	Ins	15
<input type="checkbox"/> FC9 (MAN_ControlPID)	[340]	AWL	Seg	2	Ins	9
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	1	Ins	14
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[392]	AWL	Seg	1	Ins	15
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins	11
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	2	Ins	12
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg	2	Ins	13
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins	14
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins	24
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	2	Ins	25
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg	2	Ins	26
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins	27
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins	5
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	3	Ins	6
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins	7
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins	9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	3	Ins	10
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins	11
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg	3	Ins	23
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg	5	Ins	20
<input type="checkbox"/> FC8 (STOP_manual&automatic)	[70]	AWL	Seg	1	Ins	185
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg	4	Ins	1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg	4	Ins	12
<input type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg	4	Ins	12



FINAL PROJECT

Date: 19.06.2014

Page: 178

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

SIMATIC TFG_BSH\SIMATIC 300(1)\CPU 315- 16/06/2014 09:26:01
2 PN/DP\...\Bloques -- Estructura del programa

Bloque (símbolo), DB de instancia (símbolo)	Datos	Lenguaje	Punto de aplicación
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 4 Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 5 Ins 7
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg 5 Ins 18
<input checked="" type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg 5 Ins 18
<input type="checkbox"/> FC10 (Station1_set)	[252]	AWL	Seg 5 Ins 19
<input checked="" type="checkbox"/> DB10 (Puestos1)	[252]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC97 (Station_AUT_ON)	[446]	AWL	Seg 2 Ins 8
<input type="checkbox"/> FC5 (AUT_SensON/OFF->th/calc)	[640]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 1 Ins 11
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 13
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 21
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg 3 Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg 4 Ins 2
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 3
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 6
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 9
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 12
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 21
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 23
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 25
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg 6 Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg 7 Ins 3
<input type="checkbox"/> FC7 (AUT_Control PID)	[468]	AWL	Seg 2 Ins 1
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 1 Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg 1 Ins 10
<input checked="" type="checkbox"/> FC10 (Station1_set)	[650]	AWL	Seg 1 Ins 11
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 1 Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 2 Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg 2 Ins 2
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 2 Ins 3
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 3 Ins 1
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[520]	AWL	Seg 3 Ins 2
<input type="checkbox"/> FC4 (Alarm)	[278]	AWL	Seg 2 Ins 9
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg 2 Ins 13
<input type="checkbox"/> FC96 (Station_MAN_ON)	[314]	AWL	Seg 3 Ins 21
<input type="checkbox"/> FC98 (MAN_SensON/SensOFF->th)	[330]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 1 Ins 6
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 1 Ins 8
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[330]	AWL	Seg 3 Ins 4
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[330]	AWL	Seg 3 Ins 7
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 11
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 13
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 15
<input type="checkbox"/> FC9 (MAN_ControlPID)	[340]	AWL	Seg 2 Ins 9
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 1 Ins 14



FINAL PROJECT

Date: 19.06.2014

Page: 179

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

SIMATIC TFG_BSH\SIMATIC 300(1)\CPU 315- 16/06/2014 09:26:03
2 PN/DP\...\Bloques -- Estructura del programa

Bloque (símbolo), DB de instancia (símbolo)	Datos	Lenguaje	Punto de aplicación
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[392]	AWL	Seg 1 Ins 15
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 11
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 2 Ins 12
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg 2 Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 14
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 24
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 2 Ins 25
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg 2 Ins 26
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 27
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 5
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 3 Ins 6
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 7
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 3 Ins 10
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 11
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg 3 Ins 23
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 5 Ins 20
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[70]	AWL	Seg 1 Ins 202
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 4 Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg 4 Ins 12
<input type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg 4 Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 4 Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 5 Ins 7
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg 5 Ins 18
<input type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg 5 Ins 18
<input type="checkbox"/> FC10 (Station1_set)	[252]	AWL	Seg 5 Ins 19
<input type="checkbox"/> DB10 (Puestos1)	[252]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC97 (Station_AUT_ON)	[446]	AWL	Seg 2 Ins 8
<input type="checkbox"/> FC5 (AUT_SensON/OFF->th/calc)	[640]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 1 Ins 11
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 13
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 21
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg 3 Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg 4 Ins 2
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 3
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 6
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 9
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 12
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 21
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 23
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 25
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg 6 Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg 7 Ins 3
<input type="checkbox"/> FC7 (AUT_Control PID)	[468]	AWL	Seg 2 Ins 1
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 1 Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg 1 Ins 10



FINAL PROJECT

Date: 19.06.2014

Page: 180

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

SIMATIC TFG_BSH\SIMATIC 300(1)\CPU 315- 16/06/2014 09:26:05
2 PN/DP\...\Bloques -- Estructura del programa

Bloque (símbolo), DB de instancia (símbolo)	Datos	Lenguaje	Punto de aplicación
<input checked="" type="checkbox"/> FC10 (Station1_set)	[650]	AWL	Seg 1 Ins 11
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 1 Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 2 Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg 2 Ins 2
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 2 Ins 3
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg 3 Ins 1
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[520]	AWL	Seg 3 Ins 2
<input type="checkbox"/> FC4 (Alarm)	[278]	AWL	Seg 2 Ins 9
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg 2 Ins 13
<input type="checkbox"/> FC96 (Station_MAN_ON)	[314]	AWL	Seg 3 Ins 21
<input type="checkbox"/> FC98 (MAN_SensON/SensOFF->th)	[330]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 1 Ins 6
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 1 Ins 8
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[330]	AWL	Seg 3 Ins 4
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[330]	AWL	Seg 3 Ins 7
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 11
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 13
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 15
<input type="checkbox"/> FC9 (MAN_ControlPID)	[340]	AWL	Seg 2 Ins 9
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 1 Ins 14
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[392]	AWL	Seg 1 Ins 15
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 11
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 2 Ins 12
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg 2 Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 14
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 24
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 2 Ins 25
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg 2 Ins 26
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 27
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 5
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 3 Ins 6
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 7
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 3 Ins 10
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 11
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg 3 Ins 23
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 5 Ins 20
<input type="checkbox"/> FC8 (STOP_manual&automatic)	[70]	AWL	Seg 1 Ins 219
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 4 Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg 4 Ins 12
<input type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg 4 Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 4 Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 5 Ins 7
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg 5 Ins 18
<input type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg 5 Ins 18
<input type="checkbox"/> FC10 (Station1_set)	[252]	AWL	Seg 5 Ins 19
<input type="checkbox"/> DB10 (Puestos1)	[252]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC97 (Station_AUT_ON)	[446]	AWL	Seg 2 Ins 8
<input type="checkbox"/> FC5 (AUT_SensON/OFF->th/calc)	[640]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 1 Ins 11
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 13
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 19



FINAL PROJECT

Date: 19.06.2014

Page: 181

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

SIMATIC TFG_BSH\SIMATIC 300(1)\CPU 315- 16/06/2014 09:26:08
2 PN/DP\...\Bloques -- Estructura del programa

Bloque (símbolo), DB de instancia (símbolo)	Datos	Lenguaje	Punto de aplicación		
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	1	Ins 21
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg	3	Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg	4	Ins 2
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 3
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 6
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 9
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 12
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins 19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins 21
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins 23
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins 25
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg	6	Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg	7	Ins 3
<input type="checkbox"/> FC7 (AUT_Control PID)	[468]	AWL	Seg	2	Ins 1
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	1	Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg	1	Ins 10
<input checked="" type="checkbox"/> FC10 (Station1_set)	[650]	AWL	Seg	1	Ins 11
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	1	Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	2	Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg	2	Ins 2
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	2	Ins 3
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	3	Ins 1
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[520]	AWL	Seg	3	Ins 2
<input type="checkbox"/> FC4 (Alarm)	[278]	AWL	Seg	2	Ins 9
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg	2	Ins 13
<input type="checkbox"/> FC96 (Station_MAN_ON)	[314]	AWL	Seg	3	Ins 21
<input type="checkbox"/> FC98 (MAN_SensON/SensOFF->th)	[330]	AWL	Seg	1	Ins 1
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	1	Ins 6
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	1	Ins 8
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[330]	AWL	Seg	3	Ins 4
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[330]	AWL	Seg	3	Ins 7
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	3	Ins 11
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	3	Ins 13
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	3	Ins 15
<input type="checkbox"/> FC9 (MAN_ControlPID)	[340]	AWL	Seg	2	Ins 9
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	1	Ins 14
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[392]	AWL	Seg	1	Ins 15
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins 11
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	2	Ins 12
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg	2	Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins 14
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins 24
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	2	Ins 25
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg	2	Ins 26
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins 27
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins 5
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	3	Ins 6
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins 7
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	3	Ins 10



FINAL PROJECT

Date: 19.06.2014

Page: 182

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

SIMATIC TFG_BSH\SIMATIC 300(1)\CPU 315- 16/06/2014 09:26:11
2 PN/DP...\Bloques -- Estructura del programa

Bloque (símbolo), DB de instancia (símbolo)	Datos	Lenguaje	Punto de aplicación		
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins 11
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg	3	Ins 23
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg	5	Ins 20
<input type="checkbox"/> FC8 (STOP_manual&automatic)	[70]	AWL	Seg	1	Ins 236
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg	4	Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg	4	Ins 12
<input type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg	4	Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg	4	Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg	5	Ins 7
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg	5	Ins 18
<input type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg	5	Ins 18
<input type="checkbox"/> FC10 (Station1_set)	[252]	AWL	Seg	5	Ins 19
<input type="checkbox"/> DB10 (Puestos1)	[252]	AWL	Seg	1	Ins 1
<input type="checkbox"/> FC97 (Station AUT_ON)	[446]	AWL	Seg	2	Ins 8
<input type="checkbox"/> FC5 (AUT_SensON/OFF->th/calc)	[640]	AWL	Seg	1	Ins 1
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	1	Ins 11
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	1	Ins 13
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	1	Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	1	Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	1	Ins 19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	1	Ins 21
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg	3	Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg	4	Ins 2
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 3
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 6
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 9
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 12
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg	5	Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins 19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins 21
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins 23
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins 25
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg	6	Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg	7	Ins 3
<input type="checkbox"/> FC7 (AUT_Control PID)	[468]	AWL	Seg	2	Ins 1
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	1	Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg	1	Ins 10
<input checked="" type="checkbox"/> FC10 (Station1_set)	[650]	AWL	Seg	1	Ins 11
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	1	Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	2	Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg	2	Ins 2
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	2	Ins 3
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	3	Ins 1
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[520]	AWL	Seg	3	Ins 2
<input type="checkbox"/> FC4 (Alarm)	[278]	AWL	Seg	2	Ins 9
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg	2	Ins 13
<input type="checkbox"/> FC96 (Station_MAN_ON)	[314]	AWL	Seg	3	Ins 21
<input type="checkbox"/> FC98 (MAN_SensON/SensOFF->th)	[330]	AWL	Seg	1	Ins 1
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	1	Ins 6
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	1	Ins 8
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[330]	AWL	Seg	3	Ins 4



FINAL PROJECT

Date: 19.06.2014

Page: 183

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

SIMATIC TFG_BSH\SIMATIC 300(1)\CPU 315- 16/06/2014 09:26:13
2 PN/DP\...\Bloques -- Estructura del programa

Bloque (símbolo), DB de instancia (símbolo)	Datos	Lenguaje	Punto de aplicación
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[330]	AWL	Seg 3 Ins 7
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 11
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 13
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg 3 Ins 15
<input checked="" type="checkbox"/> FC9 (MAN_ControlPID)	[340]	AWL	Seg 2 Ins 9
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 1 Ins 14
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[392]	AWL	Seg 1 Ins 15
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 11
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 2 Ins 12
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg 2 Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 14
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 24
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 2 Ins 25
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg 2 Ins 26
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 2 Ins 27
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 5
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 3 Ins 6
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 7
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg 3 Ins 10
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg 3 Ins 11
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg 3 Ins 23
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 5 Ins 20
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[70]	AWL	Seg 1 Ins 253
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 4 Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg 4 Ins 12
<input checked="" type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg 4 Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 4 Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg 5 Ins 7
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[144]	AWL	Seg 5 Ins 18
<input checked="" type="checkbox"/> DB41 (PID_1)	[70]	AWL	Seg 5 Ins 18
<input checked="" type="checkbox"/> FC10 (Station1_set)	[252]	AWL	Seg 5 Ins 19
<input checked="" type="checkbox"/> DB10 (Puestos1)	[252]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC97 (Station_AUT_ON)	[446]	AWL	Seg 2 Ins 8
<input type="checkbox"/> FC5 (AUT_SensON/OFF->th/calc)	[640]	AWL	Seg 1 Ins 1
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 1 Ins 11
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 13
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 1 Ins 21
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg 3 Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg 4 Ins 2
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 3
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 6
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 9
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 12
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[640]	AWL	Seg 5 Ins 15
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 17
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 19
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 21
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg 5 Ins 23



FINAL PROJECT

Date: 19.06.2014

Page: 184

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

SIMATIC TFG_BSH\SIMATIC 300(1)\CPU 315- 16/06/2014 09:26:16
2 PN/DP\...\Bloques -- Estructura del programa

Bloque (símbolo), DB de instancia (símbolo)	Datos	Lenguaje	Punto de aplicación		
<input type="checkbox"/> FC105 (SCALE)	[660]	AWL	Seg	5	Ins 25
<input type="checkbox"/> FC94 (Excel_DB)	[640]	AWL	Seg	6	Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[664]	AWL	Seg	7	Ins 3
<input type="checkbox"/> FC7 (AUT_Control PID)	[468]	AWL	Seg	2	Ins 1
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	1	Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg	1	Ins 10
<input checked="" type="checkbox"/> FC10 (Station1_set)	[650]	AWL	Seg	1	Ins 11
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	1	Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	2	Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[542]	AWL	Seg	2	Ins 2
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	2	Ins 3
<input type="checkbox"/> FC2 (Real->Int->Word)	[468]	AWL	Seg	3	Ins 1
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[520]	AWL	Seg	3	Ins 2
<input type="checkbox"/> FC4 (Alarm)	[278]	AWL	Seg	2	Ins 9
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg	2	Ins 13
<input type="checkbox"/> FC96 (Station_MAN_ON)	[314]	AWL	Seg	3	Ins 21
<input type="checkbox"/> FC98 (MAN_SensON/SensOFF->th)	[330]	AWL	Seg	1	Ins 1
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	1	Ins 6
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	1	Ins 8
<input type="checkbox"/> FC3 (Sensor conect/desconnect)	[330]	AWL	Seg	3	Ins 4
<input type="checkbox"/> FC3 (Sensor conect/desconnect)	[330]	AWL	Seg	3	Ins 7
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	3	Ins 11
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	3	Ins 13
<input type="checkbox"/> FC105 (SCALE)	[350]	AWL	Seg	3	Ins 15
<input type="checkbox"/> FC9 (MAN_ControlPID)	[340]	AWL	Seg	2	Ins 9
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	1	Ins 14
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[392]	AWL	Seg	1	Ins 15
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins 11
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	2	Ins 12
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg	2	Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins 14
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins 24
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	2	Ins 25
<input checked="" type="checkbox"/> FC10 (Station1_set)	[522]	AWL	Seg	2	Ins 26
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	2	Ins 27
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins 5
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	3	Ins 6
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins 7
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[414]	AWL	Seg	3	Ins 10
<input type="checkbox"/> FC2 (Real->Int->Word)	[340]	AWL	Seg	3	Ins 11
<input checked="" type="checkbox"/> FC8 (STOP_manual&automatic)	[274]	AWL	Seg	3	Ins 23
<input type="checkbox"/> FC2 (Real->Int->Word)	[70]	AWL	Seg	5	Ins 20
<input checked="" type="checkbox"/> DB10 (Puestos1)	[22]	AWL	Seg	2	Ins 1
<input type="checkbox"/> FC95 (Reset_StationNOT_SET)	[22]	AWL	Seg	2	Ins 3
<input type="checkbox"/> FC10 (Station1_set)	[204]	AWL	Seg	2	Ins 5
<input checked="" type="checkbox"/> DB10 (Puestos1)	[204]	AWL	Seg	1	Ins 1
<input type="checkbox"/> FC97 (Station_AUT_ON)	[398]	AWL	Seg	2	Ins 8
<input type="checkbox"/> FC5 (AUT_SensON/OFF->th/calc)	[592]	AWL	Seg	1	Ins 1
<input type="checkbox"/> FC3 (Sensor conect/desconnect)	[592]	AWL	Seg	1	Ins 11
<input type="checkbox"/> FC105 (SCALE)	[612]	AWL	Seg	1	Ins 13
<input type="checkbox"/> FC105 (SCALE)	[612]	AWL	Seg	1	Ins 15
<input type="checkbox"/> FC105 (SCALE)	[612]	AWL	Seg	1	Ins 17
<input type="checkbox"/> FC105 (SCALE)	[612]	AWL	Seg	1	Ins 19



FINAL PROJECT

Date: 19.06.2014

Page: 185

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

SIMATIC TFG_BSH\SIMATIC 300(1)\CPU 315- 16/06/2014 09:26:19
2 PN/DP\...\Bloques -- Estructura del programa

Bloque (símbolo), DB de instancia (símbolo)	Datos	Lenguaje	Punto de aplicación		
<input type="checkbox"/> FC105 (SCALE)	[612]	AWL	Seg	1	Ins 21
<input type="checkbox"/> FC94 (Excel_DB)	[592]	AWL	Seg	3	Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[616]	AWL	Seg	4	Ins 2
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[592]	AWL	Seg	5	Ins 3
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[592]	AWL	Seg	5	Ins 6
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[592]	AWL	Seg	5	Ins 9
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[592]	AWL	Seg	5	Ins 12
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[592]	AWL	Seg	5	Ins 15
<input type="checkbox"/> FC105 (SCALE)	[612]	AWL	Seg	5	Ins 17
<input type="checkbox"/> FC105 (SCALE)	[612]	AWL	Seg	5	Ins 19
<input type="checkbox"/> FC105 (SCALE)	[612]	AWL	Seg	5	Ins 21
<input type="checkbox"/> FC105 (SCALE)	[612]	AWL	Seg	5	Ins 23
<input type="checkbox"/> FC105 (SCALE)	[612]	AWL	Seg	5	Ins 25
<input type="checkbox"/> FC94 (Excel_DB)	[592]	AWL	Seg	6	Ins 3
<input type="checkbox"/> FC6 (OperationCalculation)	[616]	AWL	Seg	7	Ins 3
<input type="checkbox"/> FC7 (AUT_Control PID)	[420]	AWL	Seg	2	Ins 1
<input type="checkbox"/> FC2 (Real->Int->Word)	[420]	AWL	Seg	1	Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[494]	AWL	Seg	1	Ins 10
<input checked="" type="checkbox"/> FC10 (Station1_set)	[602]	AWL	Seg	1	Ins 11
<input type="checkbox"/> FC2 (Real->Int->Word)	[420]	AWL	Seg	1	Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[420]	AWL	Seg	2	Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[494]	AWL	Seg	2	Ins 2
<input type="checkbox"/> FC2 (Real->Int->Word)	[420]	AWL	Seg	2	Ins 3
<input type="checkbox"/> FC2 (Real->Int->Word)	[420]	AWL	Seg	3	Ins 1
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[472]	AWL	Seg	3	Ins 2
<input type="checkbox"/> FC4 (Alarm)	[230]	AWL	Seg	2	Ins 9
<input type="checkbox"/> FC8 (STOP_manual&automatic)	[226]	AWL	Seg	2	Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[226]	AWL	Seg	4	Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[300]	AWL	Seg	4	Ins 12
<input type="checkbox"/> DB41 (PID_1)	[226]	AWL	Seg	4	Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[226]	AWL	Seg	4	Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[226]	AWL	Seg	5	Ins 7
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[300]	AWL	Seg	5	Ins 18
<input type="checkbox"/> DB41 (PID_1)	[226]	AWL	Seg	5	Ins 18
<input checked="" type="checkbox"/> FC10 (Station1_set)	[408]	AWL	Seg	5	Ins 19
<input type="checkbox"/> FC2 (Real->Int->Word)	[226]	AWL	Seg	5	Ins 20
<input type="checkbox"/> FC96 (Station_MAN_ON)	[266]	AWL	Seg	3	Ins 21
<input type="checkbox"/> FC98 (MAN_SensON/SensOFF->th)	[282]	AWL	Seg	1	Ins 1
<input type="checkbox"/> FC105 (SCALE)	[302]	AWL	Seg	1	Ins 6
<input type="checkbox"/> FC105 (SCALE)	[302]	AWL	Seg	1	Ins 8
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[282]	AWL	Seg	3	Ins 4
<input type="checkbox"/> FC3 (Sensor conect/desconect)	[282]	AWL	Seg	3	Ins 7
<input type="checkbox"/> FC105 (SCALE)	[302]	AWL	Seg	3	Ins 11
<input type="checkbox"/> FC105 (SCALE)	[302]	AWL	Seg	3	Ins 13
<input type="checkbox"/> FC105 (SCALE)	[302]	AWL	Seg	3	Ins 15
<input type="checkbox"/> FC9 (MAN_ControlPID)	[292]	AWL	Seg	2	Ins 9
<input type="checkbox"/> FC2 (Real->Int->Word)	[292]	AWL	Seg	1	Ins 14
<input type="checkbox"/> FB42 (CONT_S), DB42 (PID_2)	[344]	AWL	Seg	1	Ins 15
<input type="checkbox"/> FC2 (Real->Int->Word)	[292]	AWL	Seg	2	Ins 11
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[366]	AWL	Seg	2	Ins 12
<input checked="" type="checkbox"/> FC10 (Station1_set)	[474]	AWL	Seg	2	Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[292]	AWL	Seg	2	Ins 14
<input type="checkbox"/> FC2 (Real->Int->Word)	[292]	AWL	Seg	2	Ins 24
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[366]	AWL	Seg	2	Ins 25
<input checked="" type="checkbox"/> FC10 (Station1_set)	[474]	AWL	Seg	2	Ins 26



FINAL PROJECT

Date: 19.06.2014

Page: 186

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

SIMATIC TFG_BSH\SIMATIC 300(1)\CPU 315- 16/06/2014 09:26:23
2 PN/DP\...\Bloques -- Estructura del programa

Bloque (símbolo), DB de instancia (símbolo)	Datos	Lenguaje	Punto de aplicación		
<input type="checkbox"/> FC2 (Real->Int->Word)	[292]	AWL	Seg	2	Ins 27
<input type="checkbox"/> FC2 (Real->Int->Word)	[292]	AWL	Seg	3	Ins 5
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[366]	AWL	Seg	3	Ins 6
<input type="checkbox"/> FC2 (Real->Int->Word)	[292]	AWL	Seg	3	Ins 7
<input type="checkbox"/> FC2 (Real->Int->Word)	[292]	AWL	Seg	3	Ins 9
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[366]	AWL	Seg	3	Ins 10
<input type="checkbox"/> FC2 (Real->Int->Word)	[292]	AWL	Seg	3	Ins 11
<input type="checkbox"/> FC8 (STOP_manual&automatic)	[226]	AWL	Seg	3	Ins 23
<input type="checkbox"/> FC2 (Real->Int->Word)	[226]	AWL	Seg	4	Ins 1
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[300]	AWL	Seg	4	Ins 12
<input type="checkbox"/> DB41 (PID_1)	[226]	AWL	Seg	4	Ins 12
<input type="checkbox"/> FC2 (Real->Int->Word)	[226]	AWL	Seg	4	Ins 13
<input type="checkbox"/> FC2 (Real->Int->Word)	[226]	AWL	Seg	5	Ins 7
<input type="checkbox"/> FB41 (CONT_C), DB41 (PID_1)	[300]	AWL	Seg	5	Ins 18
<input type="checkbox"/> DB41 (PID_1)	[226]	AWL	Seg	5	Ins 18
<input type="checkbox"/> FC10 (Station1_set)	[408]	AWL	Seg	5	Ins 19
<input type="checkbox"/> FC2 (Real->Int->Word)	[226]	AWL	Seg	5	Ins 20
<input type="checkbox"/> DB20 (Puesto2)	[22]	AWL	Seg	3	Ins 1
<input checked="" type="checkbox"/> DB11 (Excel_Interface)	[0]				
<input checked="" type="checkbox"/> FC99 (DiagramIntermitences)	[2]				
<input checked="" type="checkbox"/> FC106 (UNSCALE)	[16]				
<input checked="" type="checkbox"/> SFC20 (BLKMOV)	[0]				
<input checked="" type="checkbox"/> SFC24 (TEST_DB)	[0]				
<input checked="" type="checkbox"/> SFC55 (WR_PARM)	[0]				
<input checked="" type="checkbox"/> SFC105 (READ_SI)	[0]				
<input checked="" type="checkbox"/> SFC106 (DEL_SI)	[0]				
<input checked="" type="checkbox"/> FB1 (Excel)	[0]				
<input checked="" type="checkbox"/> SFB41	[0]				

2 INPUTS & OUTPUTS

Operando (símbolo)	Bloque (símbolo)	Acceso	Lenguaje	Punto de aplicación		
	FC10 (Station1_set)	R	AWL	Seg	2	Ins 8
					/CALL	
				Seg	3	Ins 21
					/CALL	
	FC7 (AUT_Control PID)	W	AWL	Seg	1	Ins 10
					/CALL	
				Seg	1	Ins 10
					/CALL	
				Seg	2	Ins 2
					/CALL	
				Seg	2	Ins 2
					/CALL	



FINAL PROJECT

Date: **19.06.2014**

Page: **187**

PROJECT:
“Compressors test live bench under wet compression conditions”

ANNEX:
2

FC8 (STOP_manual&automatic)	W	AWL	Seg 3 Ins 2	/CALL	
			Seg 4 Ins 12		/CALL
			Seg 4 Ins 12		
	FC9 (MAN_ControlPID)	W	AWL	Seg 5 Ins 18	/CALL
				Seg 5 Ins 18	
				Seg 1 Ins 15	
				Seg 2 Ins 12	
				Seg 2 Ins 12	
				Seg 2 Ins 25	
		R W W	AWL AWL AWL	Seg 2 Ins 25	/CALL
				Seg 3 Ins 6	
				Seg 3 Ins 6	
				Seg 3 Ins 10	
				Seg 3 Ins 10	
				Seg 3 Ins 10	
FC99 (DiagramIntermitenc es) FC99 (DiagramIntermitenc es) FC7 (AUT_Control PID)	R W W	AWL AWL AWL	Seg 2 Ins 6 /U	/CALL	
			Seg 2 Ins 5 /T		
			Seg 1 Ins 10		
			Seg 1 Ins 10		
			Seg 1 Ins 10		
			Seg 1 Ins 10		
			Seg 2 Ins 2		
			Seg 2 Ins 2		
			Seg 2 Ins 2		
			Seg 2 Ins 2		



FINAL PROJECT

Date: **19.06.2014**

Page: **188**

PROJECT:
“Compressors test live bench under wet compression conditions”

ANNEX:
2

Operando (símbolo)	Bloque (símbolo)	Acceso	Lenguaje	Punto de aplicación
MW 0	FC8 (STOP_manual&automatic)	W	AWL	Seg 3 Ins 2 /CALL
				Seg 3 Ins 2 /CALL
				Seg 4 Ins 12 /CALL
				Seg 4 Ins 12 /CALL
				Seg 4 Ins 12 /CALL
				Seg 4 Ins 12 /CALL
				Seg 4 Ins 12 /CALL
				Seg 5 Ins 18 /CALL
				Seg 5 Ins 18 /CALL
				Seg 5 Ins 18 /CALL
	FC9 (MAN_ControlPID)	W	AWL	Seg 5 Ins 18 /CALL
				Seg 1 Ins 15 /CALL
				Seg 1 Ins 15 /CALL
				Seg 2 Ins 12 /CALL
				Seg 2 Ins 12 /CALL
				Seg 2 Ins 12 /CALL
				Seg 2 Ins 12 /CALL
				Seg 2 Ins 12 /CALL
				Seg 2 Ins 12 /CALL
				Seg 2 Ins 12 /CALL
				Seg 2 Ins 25 /CALL
				Seg 2 Ins 25 /CALL
				Seg 2 Ins 25 /CALL
				Seg 2 Ins 25 /CALL
				Seg 2 Ins 25 /CALL
				Seg 3 Ins 6 /CALL
				Seg 3 Ins 6 /CALL



FINAL PROJECT

Date: **19.06.2014**

Page: **189**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

				Seg 3 Ins 6 /CALL
				Seg 3 Ins 6 /CALL
				Seg 3 Ins 6 /CALL
				Seg 3 Ins 10 /CALL
				Seg 3 Ins 10 /CALL
				Seg 3 Ins 10 /CALL
				Seg 3 Ins 10 /CALL
				Seg 3 Ins 10 /CALL
				Seg 1 Ins 13 /CALL
				Seg 1 Ins 15 /CALL
	FC5 (AUT_SensON/OFF- >th /calc)	W	AWL	
Operando (símbolo)	Bloque (símbolo)	Acceso	Lenguaje	Punto de aplicación
T 99	FC99 (DiagramIntermitenc es)	W	AWL	Seg 8 Ins 12 /FR
		R	AWL	Seg 8 Ins 15 /SE Seg 1 Ins 6 /U
				Seg 2 Ins 1 /UN
				Seg 2 Ins 4 /L
		W	AWL	Seg 1 Ins 2 /FR
				Seg 1 Ins 5 /SE
Z 0	FC4 (Alarm)	R	AWL	Seg 2 Ins 3 /SE Seg 7 Ins 32 /L
		W	AWL	Seg 7 Ins 31 /ZV

OB1 - <offline>

""

Nombre: **Familia:**
Autor: **Versión:** 0.1
Versión del bloque: 2
Hora y fecha Código: 16/06/2014 09:14:59
Interface: 15/02/1996 16:51:12
Longitud (bloque / código / datos): 00360 00236 00022

Propiedades del objeto:

S7_language 9(1) Inglés (Estados Unidos) 23/05/2014 13:19:47

Nombre	Tipo de datos	Dirección	Comentario
TEMP		0.0	
OB1_EV_CLASS	Byte	0.0	Bits 0-3 = 1 (Coming event), Bits 4-7 = 1 (Event class 1)
OB1_SCAN_1	Byte	1.0	1 (Cold restart scan 1 of OB 1), 3 (Scan 2-n of OB 1)
OB1_PRIORITY	Byte	2.0	Priority of OB Execution
OB1_OB_NUMBR	Byte	3.0	1 (Organization block 1, OB1)
OB1_RESERVED_1	Byte	4.0	Reserved for system
OB1_RESERVED_2	Byte	5.0	Reserved for system
OB1_PREV_CYCLE	Int	6.0	Cycle time of previous OB1 scan (milliseconds)
OB1_MIN_CYCLE	Int	8.0	Minimum cycle time of OB1 (milliseconds)
OB1_MAX_CYCLE	Int	10.0	Maximum cycle time of OB1 (milliseconds)
OB1_DATE_TIME	Date_And_Time	12.0	Date and time OB1 started

Bloque: OB1 "Main Program Sweep (Cycle)"

From here, the rest of subroutines (for the different stations) are summoned (if they are set).
The STAR/ STOP functions are also control.

Segm.: 1 Start-Stop

Define the state of each individual station, or for all at once.
It determine the status of the buttons depending on the status selected of the stations.
It also performs the switch off, of the stations, in case they are no habilitated or their status have been changed to "OFF".

```
CALL "START_STOP_HMI_button" FC1
```

Segm.: 2 Station 1

If the station has been set, the function that controls the individual station would be summoned.

```

U      "Puestos1".UDT4_1.Puesto_habilitado          DB10.DBX234.0    -- Indicates if the station is
                                                    "built", if it can be
                                                    turned ON

SPB    C_1                                           //Go to CALL station 1

CALL  "Reset_StationNOT_SET"                        FC95
T1_conectado := "Puestos1".UDT4_1.T1_conec         DB10.DBX234.1    -- Indicates the connection
tado                                           state of the sensor T1

T2_conectado := "Puestos1".UDT4_1.T2_conec         DB10.DBX234.3    -- Indicates the connection
tado                                           state of the sensor T2

T3_conectado := "Puestos1".UDT4_1.T3_conec         DB10.DBX234.5    -- Indicates the connection
tado                                           state of the sensor T3

Tin_conectado := "Puestos1".UDT4_1.Tin_cone       DB10.DBX234.7    -- Indicates the connection
ctado                                           state of the sensor Tin
  
```

```

    Tout_conectado      := "Puestos1".UDT4_1.Tout_con
estado                 DB10.DBX235.0      -- Indicates the connection s
                        tate of the sensor Tout
    P1_conectado        := "Puestos1".UDT4_1.P1_conec
tado                   DB10.DBX234.2      -- Indicates the connection s
                        tate of the sensor P1
    P2_conectado        := "Puestos1".UDT4_1.P2_conec
tado                   DB10.DBX234.4      -- Indicates the connection s
                        tate of the sensor P2
    P3_conectado        := "Puestos1".UDT4_1.P3_conec
tado                   DB10.DBX234.6      -- Indicates the connection s
                        tate of the sensor P3
    m_ref_conectado     := "Puestos1".UDT4_1.m_ref_co
nnectado               DB10.DBX235.3      -- Indicates the connection s
                        tate of the sensor m_ref
    Qw_conectado        := "Puestos1".UDT4_1.Qw_conec
tado                   DB10.DBX235.1      -- Indicates the connection s
                        tate of the sensor Qw
    Resistance_conecta := "Puestos1".UDT4_1.Resistan
ce_conectado           DB10.DBX235.2      -- Indicates if a heating resi
                        stance can be uses
    dir_compressor      := A1.0
    dir_resistance      := A1.1
    dir_EEV             := AW328
    dir_pump            := AW324

    SPA    ST2

C_1: CALL "Station1_set"                                FC10

```

Segm.: 3	Station 2
----------	-----------

If the station has been set, the function that controls the individual station would be summoned.

```

ST2: U    "Puesto2".UDT4_2.Puesto_habilitado DB20.DBX234.0      -- Indicates if the station is "built", if
                                                it can be turned ON
//Go to call station 2
// SPA ST3

```

Segm.: 4	END
----------	-----

END segment

```

NOP    0

```


FC1 - <offline>

"START_STOP_HMI_button"

Nombre:**Familia:****Autor:****Versión:** 0.1**Hora y fecha Código:****Versión del bloque:** 2

09/06/2014 09:46:32

Interface: 13/05/2014 12:47:36**Longitud (bloque / código / datos):** 05340 05110 00026**Propiedades del objeto:**

S7_language 9(1) Inglés (Estados Unidos) 23/05/2014 13:19:47

Nombre	Tipo de datos	Dirección	Comentario
IN		0.0	
OUT		0.0	
IN_OUT		0.0	
TEMP		0.0	
RETURN		0.0	
RET_VAL		0.0	

Bloque: FC1 START ALL/ STOP ALL

When all the station are in the STOP mode, all the corresponding buttons/indicators of each station must be activated, besides de button/indicator of "STOP ALL" must be activate (only if all the stations implemented are in the STOP mode).

For the "START", and "START ALL" buttons/indicatos the exact opposite operations must be realized.

If the sations are not implemented, the function FC 8 ("Stop") is summoned to guarantee their OFF state.

Segm.: 1 Station state

If the station is disabled, its ON_OFF state would not be taken into the comparison to calculate the state of the "STAR ALL/STOP ALL" button/indicator.

If the station is disabled, habilitado=0, then the station would be configured as OFF and the variable AUXI_COMP=1.

If on the contrary, habilitado=1, then AUXI_COMP=ON_OFF since the station is set, its state must be taken into the comparation.

If the stations are set, the value of the AUXI_COMP would be equal to the station state, if not, the AUXI_COMP would be set as 1.

U "Puestos1".UDT4_1.Puesto_habilitado

DB10.DBX234.0 -- Indicates if the station is "built", if it can be turned ON

SPBN P1A

//if it is activated, the the auxiliar variable
//AUXI_COMP would copy the value ON_OFF of the station

U "Puestos1".UDT4_1.ON_OFF

DB10.DBX235.4 -- Indicates if the station is ON (ON=1, OFF=0)

= "Puestos1".UDT4_1.AUXI_COMP

DB10.DBX235.6 -- Its an auxiliar variable, in order to make the comparat ions

SPBN P1O

IR2: U "Puesto2".UDT4_2.Puesto_habilitado

DB20.DBX234.0 -- Indicates if the station is "built", if it can be turned ON

SPBN P2A

//if it is activated, the the auxiliar variable
//AUXI_COMP would copy the value ON_OFF of the station

U "Puesto2".UDT4_2.ON_OFF

DB20.DBX235.4 -- Indicates if the station is ON (ON=1, OFF=0)

```

=      "Puesto2".UDT4_2.AUXI_COMP                DB20.DBX235.6      -- Its an auxiliar
                                                variable,in order to make the comparat
                                                ions

SPBN  P20

IR3:  U      "Puesto3".UDT4_3.Puesto_habilitado  DB30.DBX234.0      -- Indicates if the
                                                station is "built", if it can be turn
                                                ed ON

SPBN  P3A

//if it is activated, the the auxiliar variable
//AUXI_COMP would copy the value ON_OFF of the station

U      "Puesto3".UDT4_3.ON_OFF                DB30.DBX235.4      -- Indicates if the
                                                station is ON (ON=1, OFF=0)
=      "Puesto3".UDT4_3.AUXI_COMP                DB30.DBX235.6      -- Its an auxiliar
                                                variable,in order to make the comparat
                                                ions

SPBN  P30

IR4:  U      "Puesto4".UDT4_4.Puesto_habilitado  DB40.DBX234.0      -- Indicates if the
                                                station is "built", if it can be turn
                                                ed ON

SPBN  P4A

//if it is activated, the the auxiliar variable
//AUXI_COMP would copy the value ON_OFF of the station

U      "Puesto4".UDT4_4.ON_OFF                DB40.DBX235.4      -- Indicates if the
                                                station is ON (ON=1, OFF=0)
=      "Puesto4".UDT4_4.AUXI_COMP                DB40.DBX235.6      -- Its an auxiliar
                                                variable,in order to make the comparat
                                                ions

SPBN  P40

IR5:  U      "Puesto5".UDT4_5.Puesto_habilitado  DB50.DBX234.0      -- Indicates if the
                                                station is "built", if it can be turn
                                                ed ON

SPBN  P5A

//if it is activated, the the auxiliar variable
//AUXI_COMP would copy the value ON_OFF of the station

U      "Puesto5".UDT4_5.ON_OFF                DB50.DBX235.4      -- Indicates if the
                                                station is ON (ON=1, OFF=0)
=      "Puesto5".UDT4_5.AUXI_COMP                DB50.DBX235.6      -- Its an auxiliar
                                                variable,in order to make the comparat
                                                ions

SPBN  P50

IR6:  U      "Puesto6".UDT4_6.Puesto_habilitado  DB60.DBX234.0      -- Indicates if the
                                                station is "built", if it can be turn
                                                ed ON

SPBN  P6A

//if it is activated, the the auxiliar variable
//AUXI_COMP would copy the value ON_OFF of the station

U      "Puesto6".UDT4_6.ON_OFF                DB60.DBX235.4      -- Indicates if the
                                                station is ON (ON=1, OFF=0)
=      "Puesto6".UDT4_6.AUXI_COMP                DB60.DBX235.6      -- Its an auxiliar
                                                variable,in order to make the comparat
                                                ions

SPBN  P60

IR7:  U      "Puesto7".UDT4_7.Puesto_habilitado  DB70.DBX234.0      -- Indicates if the
                                                station is "built", if it can be turn
                                                ed ON

SPBN  P7A

//if it is activated, the the auxiliar variable
//AUXI_COMP would copy the value ON_OFF of the station

U      "Puesto7".UDT4_7.ON_OFF                DB70.DBX235.4      -- Indicates if the
                                                station is ON (ON=1, OFF=0)
=      "Puesto7".UDT4_7.AUXI_COMP                DB70.DBX235.6      -- Its an auxiliar
                                                variable,in order to make the comparat
                                                ions

SPBN  P70

IR8:  U      "Puesto8".UDT4_8.Puesto_habilitado  DB80.DBX234.0      -- Indicates if the
                                                station is "built", if it can be turn
                                                ed ON

SPBN  P8A

```

```

//if it is activated, the the auxiliar variable
//AUXI_COMP would copy the value ON_OFF of the station

U      "Puesto8".UDT4_8.ON_OFF          DB80.DBX235.4      -- Indicates if the
=      "Puesto8".UDT4_8.AUXI_COMP      DB80.DBX235.6      -- Its an auxiliar
                                           variable,in order to make the comparat
                                           ions

SPBN   P80

IR9:   U      "Puesto9".UDT4_9.Puesto_habilitado  DB90.DBX234.0      -- Indicates if the
                                           station is "built", if it can be turn
                                           ed ON

SPBN   P9A

//if it is activated, the the auxiliar variable
//AUXI_COMP would copy the value ON_OFF of the station

U      "Puesto9".UDT4_9.ON_OFF          DB90.DBX235.4      -- Indicates if the
=      "Puesto9".UDT4_9.AUXI_COMP      DB90.DBX235.6      -- Its an auxiliar
                                           variable,in order to make the comparat
                                           ions

SPBN   P9O

IR10:  U      "Puesto10".UDT4_10.Puesto_habilitado  DB100.DBX234.0     -- Indicates if the
                                           station is "built", if it can be turn
                                           ed ON

SPBN   P10A

//if it is activated, the the auxiliar variable
//AUXI_COMP would copy the value ON_OFF of the station

U      "Puesto10".UDT4_10.ON_OFF        DB100.DBX235.4     -- Indicates if the
=      "Puesto10".UDT4_10.AUXI_COMP    DB100.DBX235.6     -- Its an auxiliar
                                           variable,in order to make the comparat
                                           ions

SPBN   P10O

IR11:  U      "Puesto11".UDT4_11.Puesto_habilitado  DB110.DBX234.0     -- Indicates if the
                                           station is "built", if it can be turn
                                           ed ON

SPBN   P11A

//if it is activated, the the auxiliar variable
//AUXI_COMP would copy the value ON_OFF of the station

U      "Puesto11".UDT4_11.ON_OFF        DB110.DBX235.4     -- Indicates if the
=      "Puesto11".UDT4_11.AUXI_COMP    DB110.DBX235.6     -- Its an auxiliar
                                           variable,in order to make the comparat
                                           ions

SPBN   P11O

IR12:  U      "Puesto12".UDT4_12.Puesto_habilitado  DB120.DBX234.0     -- Indicates if the
                                           station is "built", if it can be turn
                                           ed ON

SPBN   P12A

//if it is activated, the the auxiliar variable
//AUXI_COMP would copy the value ON_OFF of the station

U      "Puesto12".UDT4_12.ON_OFF        DB120.DBX235.4     -- Indicates if the
=      "Puesto12".UDT4_12.AUXI_COMP    DB120.DBX235.6     -- Its an auxiliar
                                           variable,in order to make the comparat
                                           ions

SPBN   P12O
SPA    SEG2

//*****//
//NOT IMPLEMENTED STATIONS//
//*****//

//Part of the following code would be execute when the stations are habilitated but OFF

//__ST1__//

//If the station is not implemented, then the station would be set as OFF
//and the auxiliar variable AUXI_COMP=1

```

```

P1A: S      "Puestos1".UDT4_1.AUXI_COMP      DB10.DBX235.6      -- Its an auxiliar
                                         variable,in order to make the comparat
                                         ions
      R      "Puestos1".UDT4_1.ON_OFF      DB10.DBX235.4      -- Indicates if the
                                         station is ON (ON=1, OFF=0)

P10: UN     "Puestos1".UDT4_1.ON_OFF      DB10.DBX235.4      -- Indicates if the
                                         station is ON (ON=1, OFF=0)
      =      "Puestos1".UDT4_1.OFF      DB10.DBX235.5      -- Indicates if the
                                         station is OFF(OFF=1, ON=0)

```

```

//The programs leads to P10when the station is habilitated but it is off
//It calculates the OFF variable and execute the OFF functions

```

```

CALL "STOP_manual&automatic"      FC8
Dir_compressor      :=A1.0
Dir_resistance      :=A1.1
P3      :="Puestos1".UDT1_1.P3_m      DB10.DBD32      -- Output pressure
                                         of the condenser
P1      :="Puestos1".UDT1_1.P1_m      DB10.DBD24      -- Input pressure o
                                         f the compressor
OFF      :="Puestos1".UDT4_1.OFF      DB10.DBX235.5      -- Indicates if the
                                         station is OFF(OFF=1, ON=0)
Mode_manual_automat:= "Puestos1".UDT8_1.Mode_manual_automat DB10.DBX358.5      -- It determine weh
                                         ter the cycle works automatically (0)
                                         or in a manual way (1)
Manual_Resistance   := "Puestos1".UDT8_1.Manual_resistance DB10.DBX358.2      -- Test the correct
                                         functioning of the resistance
Manual_EEV          := "Puestos1".UDT8_1.Manual_EEV      DB10.DBX358.3      -- test the correct
                                         funtioning of the EEV
Manual_compressor   := "Puestos1".UDT8_1.Manual_compressor DB10.DBX358.1      -- Test the correct
                                         functioning of the compressor in the
                                         manual mode
Manual_pump         := "Puestos1".UDT8_1.Manual_Pump      DB10.DBX358.4      -- Test the correct
                                         functioning of the pump
m_w                := "Puestos1".UDT1_1.m_w_m      DB10.DBD40      -- Water flux
orden_pump_int      := "Puestos1".UDT3_1.Orden_pump_int DB10.DBW200      -- Control signal o
                                         f the water pump
orden_EEVreal       := "Puestos1".UDT5_1.orden_EEVreal DB10.DBD244      -- EEV control orde
                                         r
Dir_pump            :=AW324
Dir_EEV             :=AW328
orden_EEV           := "Puestos1".UDT3_1.Orden_EEV_int DB10.DBW198      -- Control signal o
                                         f the EEV
orden_pump_real     := "Puestos1".UDT5_1.orden_pump_real DB10.DBD248      -- Pump control ord
                                         er, REAL

```

```

//RESET of the connected sensors signals//

```

```

R      "Puestos1".UDT4_1.T1_conectado      DB10.DBX234.1      -- Indicates the co
                                         nnection state of the sensor T1
R      "Puestos1".UDT4_1.T2_conectado      DB10.DBX234.3      -- Indicates the co
                                         nnection state of the sensor T2
R      "Puestos1".UDT4_1.T3_conectado      DB10.DBX234.5      -- Indicates the co
                                         nnection state of the sensor T3
R      "Puestos1".UDT4_1.Tin_conectado      DB10.DBX234.7      -- Indicates the co
                                         nnection state of the sensor Tin
R      "Puestos1".UDT4_1.Tout_conectado      DB10.DBX235.0      -- Indicates the co
                                         nnection state of the sensor Tout
R      "Puestos1".UDT4_1.P1_conectado      DB10.DBX234.2      -- Indicates the co
                                         nnection state of the sensor P1
R      "Puestos1".UDT4_1.P2_conectado      DB10.DBX234.4      -- Indicates the co
                                         nnection state of the sensor P2
R      "Puestos1".UDT4_1.P3_conectado      DB10.DBX234.6      -- Indicates the co
                                         nnection state of the sensor P3
R      "Puestos1".UDT4_1.m_ref_conectado      DB10.DBX235.3      -- Indicates the co
                                         nnection state of the sensor m_ref
R      "Puestos1".UDT4_1.Qw_conectado      DB10.DBX235.1      -- Indicates the co
                                         nnection state of the sensor Qw
R      "Puestos1".UDT4_1.Resistance_conectado DB10.DBX235.2      -- Indicates ifa he
                                         ating resistance can be uses

```

```

SPA      IR2

```

```

//__ST2__//

```

```

P2A: S      "Puesto2".UDT4_2.AUXI_COMP      DB20.DBX235.6      -- Its an auxiliar
                                         variable,in order to make the comparat
                                         ions
      R      "Puesto2".UDT4_2.ON_OFF      DB20.DBX235.4      -- Indicates if the
                                         station is ON (ON=1, OFF=0)

P20: UN     "Puesto2".UDT4_2.ON_OFF      DB20.DBX235.4      -- Indicates if the
                                         station is ON (ON=1, OFF=0)
      =      "Puesto2".UDT4_2.OFF      DB20.DBX235.5      -- Indicates if the
                                         station is OFF(OFF=1, ON=0)

```

```
//The programs leads to PX0 when the station is habilitated but it is off
//It calculates the OFF variable and execute the OFF functions
```

```
CALL "STOP_manual&automatic" FC8
Dir_compressor :=A2.0
Dir_resistance :=A2.1
P3 :="Puesto2".UDT1_2.P3_m DB20.DBD32 -- Output pressure
of the condenser
P1 :="Puesto2".UDT1_2.P1_m DB20.DBD24 -- Input pressure o
f the compressor
OFF :="Puesto2".UDT4_2.OFF DB20.DBX235.5 -- Indicates if the
station is OFF(OFF=1, ON=0)
Mode_manual_automatic:= "Puesto2".UDT8_2.Mode_manual_automatic DB20.DBX358.5 -- It determine weh
ter the cycle works automatically (0)
or in a manual way (1)
Manual_Resistance :="Puesto2".UDT8_2.Manual_resistance DB20.DBX358.2 -- Test the correct
functioning of the resistance
Manual_EEV :="Puesto2".UDT8_2.Manual_EEV DB20.DBX358.3 -- test the correct
funtioning of the EEV
Manual_compressor :="Puesto2".UDT8_2.Manual_compressor DB20.DBX358.1 -- Test the correct
functioning of the compressor in the
manual mode
Manual_pump :="Puesto2".UDT8_2.Manual_Pump DB20.DBX358.4 -- Test the correct
functioning of the pump
m_w :="Puesto2".UDT1_2.m_w_m DB20.DBD40 -- Water flux
orden_pump_int :="Puesto2".UDT3_2.Orden_pump_int DB20.DBW200 -- Control signal o
f the water pump
orden_EEVreal :="Puesto2".UDT5_2.orden_EEVreal DB20.DBD244 -- EEV control orde
r
Dir_pump :=AW424
Dir_EEV :=AW428
orden_EEV :="Puesto2".UDT3_2.Orden_EEV_int DB20.DBW198 -- Control signal o
f the EEV
orden_pump_real :="Puesto2".UDT5_2.orden_pump_real DB20.DBD248 -- Pump control ord
er, REAL
```

```
//RESET of the connected sensors signals//
```

```
R "Puesto2".UDT4_2.T1_conectado DB20.DBX234.1 -- Indicates the co
nnection state of the sensor T1
R "Puesto2".UDT4_2.T2_conectado DB20.DBX234.3 -- Indicates the co
nnection state of the sensor T2
R "Puesto2".UDT4_2.T3_conectado DB20.DBX234.5 -- Indicates the co
nnection state of the sensor T3
R "Puesto2".UDT4_2.Tin_conectado DB20.DBX234.7 -- Indicates the co
nnection state of the sensor Tin
R "Puesto2".UDT4_2.Tout_conectado DB20.DBX235.0 -- Indicates the co
nnection state of the sensor Tout
R "Puesto2".UDT4_2.P1_conectado DB20.DBX234.2 -- Indicates the co
nnection state of the sensor P1
R "Puesto2".UDT4_2.P2_conectado DB20.DBX234.4 -- Indicates the co
nnection state of the sensor P2
R "Puesto2".UDT4_2.P3_conectado DB20.DBX234.6 -- Indicates the co
nnection state of the sensor P3
R "Puesto2".UDT4_2.m_ref_conectado DB20.DBX235.3 -- Indicates the co
nnection state of the sensor m_ref
R "Puesto2".UDT4_2.Qw_conectado DB20.DBX235.1 -- Indicates the co
nnection state of the sensor Qw
R "Puesto2".UDT4_2.Resistance_conectado DB20.DBX235.2 -- Indicates ifa he
ating resistance can be uses
```

```
SPA IR3
```

```
//__ST3__//
```

```
P3A: R "Puesto3".UDT4_3.ON_OFF DB30.DBX235.4 -- Indicates if the
station is ON (ON=1, OFF=0)
S "Puesto3".UDT4_3.AUXI_COMP DB30.DBX235.6 -- Its an auxiliar
variable,in order to make the comparat
ions
P30: UN "Puesto3".UDT4_3.ON_OFF DB30.DBX235.4 -- Indicates if the
station is ON (ON=1, OFF=0)
= "Puesto3".UDT4_3.OFF DB30.DBX235.5 -- Indicates if the
station is OFF(OFF=1, ON=0)
```

```
//The programs leads to PX0 when the station is habilitated but it is off
//It calculates the OFF variable and execute the OFF functions
```

```
CALL "STOP_manual&automatic" FC8
Dir_compressor :=A3.0
Dir_resistance :=A3.1
P3 :="Puesto3".UDT1_3.P3_m DB30.DBD32 -- Output pressure
of the condenser
```

```

P1           := "Puesto3".UDT1_3.P1_m           DB30.DBD24           -- Input pressure o
f the compressor
OFF          := "Puesto3".UDT4_3.OFF           DB30.DBX235.5       -- Indicates if the
station is OFF (OFF=1, ON=0)
Mode_manual_automat:= "Puesto3".UDT8_3.Mode_manual_automat DB30.DBX358.5       -- It determine weh
ter the cycle works automatically (0)
or in a manual way (1)
Manual_Resistance := "Puesto3".UDT8_3.Manual_resistance DB30.DBX358.2       -- Test the correct
functioning of the resistance
Manual_EEV      := "Puesto3".UDT8_3.Manual_EEV   DB30.DBX358.3       -- test the correct
funtioning of the EEV
Manual_compressor := "Puesto3".UDT8_3.Manual_compressor DB30.DBX358.1       -- Test the correct
functioning of the compressor in the
manual mode
Manual_pump     := "Puesto3".UDT8_3.Manual_Pump  DB30.DBX358.4       -- Test the correct
functioning of the pump
m_w            := "Puesto3".UDT1_3.m_w_m        DB30.DBD40          -- Water flux
orden_pump_int := "Puesto3".UDT3_3.Orden_pump_int DB30.DBW200         -- Control signal o
f the water pump
orden_EEVreal  := "Puesto3".UDT5_3.orden_EEVreal DB30.DBD244        -- EEV control orde
r
Dir_pump       := AW524
Dir_EEV        := AW528
orden_EEV      := "Puesto3".UDT3_3.Orden_EEV_int DB30.DBW198        -- Control signal o
f the EEV
orden_pump_real := "Puesto3".UDT5_3.orden_pump_real DB30.DBD248        -- Pump control ord
er, REAL

//RESET of the connected sensors signals//

R   "Puesto3".UDT4_3.T1_conectado DB30.DBX234.1       -- Indicates the co
nnection state of the sensor T1
R   "Puesto3".UDT4_3.T2_conectado DB30.DBX234.3       -- Indicates the co
nnection state of the sensor T2
R   "Puesto3".UDT4_3.T3_conectado DB30.DBX234.5       -- Indicates the co
nnection state of the sensor T3
R   "Puesto3".UDT4_3.Tin_conectado DB30.DBX234.7       -- Indicates the co
nnection state of the sensor Tin
R   "Puesto3".UDT4_3.Tout_conectado DB30.DBX235.0       -- Indicates the co
nnection state of the sensor Tout
R   "Puesto3".UDT4_3.P1_conectado DB30.DBX234.2       -- Indicates the co
nnection state of the sensor P1
R   "Puesto3".UDT4_3.P2_conectado DB30.DBX234.4       -- Indicates the co
nnection state of the sensor P2
R   "Puesto3".UDT4_3.P3_conectado DB30.DBX234.6       -- Indicates the co
nnection state of the sensor P3
R   "Puesto3".UDT4_3.m_ref_conectado DB30.DBX235.3       -- Indicates the co
nnection state of the sensor m_ref
R   "Puesto3".UDT4_3.Qw_conectado DB30.DBX235.1       -- Indicates the co
nnection state of the sensor Qw
R   "Puesto3".UDT4_3.Resistance_conectado DB30.DBX235.2       -- Indicates ifa he
ating resistance can be uses

SPA   IR4

//__ST4__//

P4A: R   "Puesto4".UDT4_4.ON_OFF DB40.DBX235.4       -- Indicates if the
station is ON (ON=1, OFF=0)
S   "Puesto4".UDT4_4.AUXI_COMP DB40.DBX235.6       -- Its an auxiliari
variable,in order to make the comparati
ons

P4O: UN  "Puesto4".UDT4_4.ON_OFF DB40.DBX235.4       -- Indicates if the
station is ON (ON=1, OFF=0)
=   "Puesto4".UDT4_4.OFF DB40.DBX235.5       -- Indicates if the
station is OFF (OFF=1, ON=0)

//The programs leads to PX0 when the station is habilitated but it is off
//It calculates the OFF variable and execute the OFF functions

CALL "STOP_manual&automatic" FC8
Dir_compressor := A4.0
Dir_resistance := A4.1
P3            := "Puesto4".UDT1_4.P3_m           DB40.DBD32           -- Output pressure
of the condenser
P1           := "Puesto4".UDT1_4.P1_m           DB40.DBD24           -- Input pressure o
f the compressor
OFF          := "Puesto4".UDT4_4.OFF           DB40.DBX235.5       -- Indicates if the
station is OFF (OFF=1, ON=0)
Mode_manual_automat:= "Puesto4".UDT8_4.Mode_manual_automat DB40.DBX358.5       -- It determine weh
ter the cycle works automatically (0)
or in a manual way (1)
Manual_Resistance := "Puesto4".UDT8_4.Manual_resistance DB40.DBX358.2       -- Test the correct
functioning of the resistance

```

```

Manual_EEV          := "Puesto4".UDT8_4.Manual_EEV          DB40.DBX358.3    -- test the correct
                    :                                     funtioning of the EEV
Manual_compressor   := "Puesto4".UDT8_4.Manual_compressor   DB40.DBX358.1    -- Test the correct
                    :                                     functioning of the compressor in the
                    :                                     manual mode
Manual_pump         := "Puesto4".UDT8_4.Manual_Pump         DB40.DBX358.4    -- Test the correct
                    :                                     functioning of the pump
m_w                := "Puesto4".UDT1_4.m_w_m               DB40.DBD40       -- Water flux
orden_pump_int     := "Puesto4".UDT3_4.Orden_pump_int       DB40.DBW200      -- Control signal o
                    :                                     f the water pump
orden_EEVreal      := "Puesto4".UDT5_4.orden_EEVreal       DB40.DBD244      -- EEV control orde
                    :                                     r
Dir_pump           := AW624
Dir_EEV            := AW628
orden_EEV          := "Puesto4".UDT3_4.Orden_EEV_int       DB40.DBW198      -- Control signal o
                    :                                     f the EEV
orden_pump_real    := "Puesto4".UDT5_4.orden_pump_real     DB40.DBD248      -- Pump control ord
                    :                                     er, REAL

//RESET of the connected sensors signals//

R    "Puesto4".UDT4_4.T1_conectado    DB40.DBX234.1    -- Indicates the co
                    :                                     nnection state of the sensor T1
R    "Puesto4".UDT4_4.T2_conectado    DB40.DBX234.3    -- Indicates the co
                    :                                     nnection state of the sensor T2
R    "Puesto4".UDT4_4.T3_conectado    DB40.DBX234.5    -- Indicates the co
                    :                                     nnection state of the sensor T3
R    "Puesto4".UDT4_4.Tin_conectado   DB40.DBX234.7    -- Indicates the co
                    :                                     nnection state of the sensor Tin
R    "Puesto4".UDT4_4.Tout_conectado  DB40.DBX235.0    -- Indicates the co
                    :                                     nnection state of the sensor Tout
R    "Puesto4".UDT4_4.P1_conectado    DB40.DBX234.2    -- Indicates the co
                    :                                     nnection state of the sensor P1
R    "Puesto4".UDT4_4.P2_conectado    DB40.DBX234.4    -- Indicates the co
                    :                                     nnection state of the sensor P2
R    "Puesto4".UDT4_4.P3_conectado    DB40.DBX234.6    -- Indicates the co
                    :                                     nnection state of the sensor P3
R    "Puesto4".UDT4_4.m_ref_conectado DB40.DBX235.3    -- Indicates the co
                    :                                     nnection state of the sensor m_ref
R    "Puesto4".UDT4_4.Qw_conectado    DB40.DBX235.1    -- Indicates the co
                    :                                     nnection state of the sensor Qw
R    "Puesto4".UDT4_4.Resistance_con DB40.DBX235.2    -- Indicates ifa he
                    :                                     ating resistance can be uses

SPA    IR5

//__ST5__//

P5A: R    "Puesto5".UDT4_5.ON_OFF      DB50.DBX235.4    -- Indicates if the
                    :                                     station is ON (ON=1, OFF=0)
S    "Puesto5".UDT4_5.AUXI_COMP       DB50.DBX235.6    -- Its an auxiliari
                    :                                     variable,in order to make the comparat
                    :                                     ions

P50: UN   "Puesto5".UDT4_5.ON_OFF      DB50.DBX235.4    -- Indicates if the
                    :                                     station is ON (ON=1, OFF=0)
=    "Puesto5".UDT4_5.OFF             DB50.DBX235.5    -- Indicates if the
                    :                                     station is OFF(OFF=1, ON=0)

//The programs leads to PX0 when the station is habilitated but it is off
//It calculates the OFF variable and execute the OFF functions

CALL "STOP_manual&automatic"          FC8
Dir_compressor   := A5.0
Dir_resistance   := A5.1
P3               := "Puesto5".UDT1_5.P3_m    DB50.DBD32       -- Output pressure
                    :                                     of the condenser
P1               := "Puesto5".UDT1_5.P1_m    DB50.DBD24       -- Input pressure o
                    :                                     f the compressor
OFF              := "Puesto5".UDT4_5.OFF     DB50.DBX235.5    -- Indicates if the
                    :                                     station is OFF(OFF=1, ON=0)
Mode_manual_autom := "Puesto5".UDT8_5.Mode_manual_automat DB50.DBX358.5    -- It determine weh
                    :                                     ter the cycle works automatically (0)
                    :                                     or in a manual way (1)
Manual_Resistance := "Puesto5".UDT8_5.Manual_resistance DB50.DBX358.2    -- Test the correct
                    :                                     functioning of the resistance
Manual_EEV       := "Puesto5".UDT8_5.Manual_EEV DB50.DBX358.3    -- test the correct
                    :                                     funtioning of the EEV
Manual_compressor := "Puesto5".UDT8_5.Manual_compressor DB50.DBX358.1    -- Test the correct
                    :                                     functioning of the compressor in the
                    :                                     manual mode
Manual_pump      := "Puesto5".UDT8_5.Manual_Pump DB50.DBX358.4    -- Test the correct
                    :                                     functioning of the pump
m_w              := "Puesto5".UDT1_5.m_w_m    DB50.DBD40       -- Water flux
orden_pump_int   := "Puesto5".UDT3_5.Orden_pump_int DB50.DBW200      -- Control signal o
                    :                                     f the water pump
orden_EEVreal    := "Puesto5".UDT5_5.orden_EEVreal DB50.DBD244      -- EEV control orde
                    :                                     r

```

```

Dir_pump           :=AW724
Dir_EEV           :=AW728
orden_EEV         :="Puesto5".UDT3_5.Orden_EEV_int      DB50.DBW198      -- Control signal o
f the EEV
orden_pump_real   :="Puesto5".UDT5_5.orden_pump_real    DB50.DBD248      -- Pump control ord
er, REAL

//RESET of the connected sensors signals//

R   "Puesto5".UDT4_5.T1_conectado      DB50.DBX234.1    -- Indicates the co
nnection state of the sensor T1
R   "Puesto5".UDT4_5.T2_conectado      DB50.DBX234.3    -- Indicates the co
nnection state of the sensor T2
R   "Puesto5".UDT4_5.T3_conectado      DB50.DBX234.5    -- Indicates the co
nnection state of the sensor T3
R   "Puesto5".UDT4_5.Tin_conectado     DB50.DBX234.7    -- Indicates the co
nnection state of the sensor Tin
R   "Puesto5".UDT4_5.Tout_conectado    DB50.DBX235.0    -- Indicates the co
nnection state of the sensor Tout
R   "Puesto5".UDT4_5.P1_conectado     DB50.DBX234.2    -- Indicates the co
nnection state of the sensor P1
R   "Puesto5".UDT4_5.P2_conectado     DB50.DBX234.4    -- Indicates the co
nnection state of the sensor P2
R   "Puesto5".UDT4_5.P3_conectado     DB50.DBX234.6    -- Indicates the co
nnection state of the sensor P3
R   "Puesto5".UDT4_5.m_ref_conectado   DB50.DBX235.3    -- Indicates the co
nnection state of the sensor m_ref
R   "Puesto5".UDT4_5.Qw_conectado     DB50.DBX235.1    -- Indicates the co
nnection state of the sensor Qw
R   "Puesto5".UDT4_5.Resistance_conec
tado DB50.DBX235.2    -- Indicates if a he
ating resistance can be uses

SPA   IR6

//__ST6__//

P6A: R   "Puesto6".UDT4_6.ON_OFF      DB60.DBX235.4    -- Indicates if the
station is ON (ON=1, OFF=0)
S   "Puesto6".UDT4_6.AUXI_COMP      DB60.DBX235.6    -- Its an auxiliar
variable,in order to make the comparat
ions

P60: UN  "Puesto6".UDT4_6.ON_OFF      DB60.DBX235.4    -- Indicates if the
station is ON (ON=1, OFF=0)
=   "Puesto6".UDT4_6.OFF            DB60.DBX235.5    -- Indicates if the
station is OFF(OFF=1, ON=0)

//The programs leads to PX0 when the station is habilitated but it is off
//It calculates the OFF variable and execute the OFF functions

CALL "STOP_manual&automatic"      FC8
Dir_compressor   :=A6.0
Dir_resistance   :=A6.1
P3               :="Puesto6".UDT1_6.P3_m      DB60.DBD32      -- Output pressure
of the condenser
P1               :="Puesto6".UDT1_6.P1_m      DB60.DBD24      -- Input pressure o
f the compressor
OFF              :="Puesto6".UDT4_6.OFF      DB60.DBX235.5    -- Indicates if the
station is OFF(OFF=1, ON=0)
Mode_manual_au
tomatic:= "Puesto6".UDT8_6.Mode_manual_au
tomatic DB60.DBX358.5    -- It determine weh
ter the cycle works automatically (0)
or in a manual way (1)
Manual_Resistan
ce := "Puesto6".UDT8_6.Manual_resistance    DB60.DBX358.2    -- Test the correct
functioning of the resistance
Manual_EEV       := "Puesto6".UDT8_6.Manual_EEV    DB60.DBX358.3    -- test the correct
funtioning of the EEV
Manual_compress
or := "Puesto6".UDT8_6.Manual_compressor    DB60.DBX358.1    -- Test the correct
functioning of the compressor in the
manual mode
Manual_pump      := "Puesto6".UDT8_6.Manual_Pump    DB60.DBX358.4    -- Test the correct
functioning of the pump
m_w              := "Puesto6".UDT1_6.m_w_m      DB60.DBD40      -- Water flux
orden_pump_int   := "Puesto6".UDT3_6.Orden_pump_int    DB60.DBW200      -- Control signal o
f the water pump
orden_EEVreal    := "Puesto6".UDT5_6.orden_EEVreal    DB60.DBD244      -- EEV control orde
r
Dir_pump         :=AW824
Dir_EEV         :=AW828
orden_EEV       := "Puesto6".UDT3_6.Orden_EEV_int    DB60.DBW198      -- Control signal o
f the EEV
orden_pump_real  := "Puesto6".UDT5_6.orden_pump_real    DB60.DBD248      -- Pump control ord
er, REAL

```

```
//RESET of the connected sensors signals//
```



```

R      "Puesto6".UDT4_6.T1_conectado      DB60.DBX234.1      -- Indicates the co
nnection state of the sensor T1
R      "Puesto6".UDT4_6.T2_conectado      DB60.DBX234.3      -- Indicates the co
nnection state of the sensor T2
R      "Puesto6".UDT4_6.T3_conectado      DB60.DBX234.5      -- Indicates the co
nnection state of the sensor T3
R      "Puesto6".UDT4_6.Tin_conectado     DB60.DBX234.7      -- Indicates the co
nnection state of the sensor Tin
R      "Puesto6".UDT4_6.Tout_conectado    DB60.DBX235.0      -- Indicates the co
nnection state of the sensor Tout
R      "Puesto6".UDT4_6.P1_conectado     DB60.DBX234.2      -- Indicates the co
nnection state of the sensor P1
R      "Puesto6".UDT4_6.P2_conectado     DB60.DBX234.4      -- Indicates the co
nnection state of the sensor P2
R      "Puesto6".UDT4_6.P3_conectado     DB60.DBX234.6      -- Indicates the co
nnection state of the sensor P3
R      "Puesto6".UDT4_6.m_ref_conectado   DB60.DBX235.3      -- Indicates the co
nnection state of the sensor m_ref
R      "Puesto6".UDT4_6.Qw_conectado     DB60.DBX235.1      -- Indicates the co
nnection state of the sensor Qw
R      "Puesto6".UDT4_6.Resistance_conec
tado                                       DB60.DBX235.2      -- Indicates ifa he
ating resistance can be uses

```

SPA IR7

//__ST7__//

```

P7A: R      "Puesto7".UDT4_7.ON_OFF      DB70.DBX235.4      -- Indicates if the
station is ON (ON=1, OFF=0)
S      "Puesto7".UDT4_7.AUXI_COMP      DB70.DBX235.6      -- Its an auxiliar
variable,in order to make the comparat
ions

P7O: UN     "Puesto7".UDT4_7.ON_OFF      DB70.DBX235.4      -- Indicates if the
station is ON (ON=1, OFF=0)
=      "Puesto7".UDT4_7.OFF            DB70.DBX235.5      -- Indicates if the
station is OFF(OFF=1, ON=0)

```

//The programs leads to PX0 when the station is habilitated but it is off
//It calculates the OFF variable and execute the OFF functions

```

CALL "STOP_manual&automatic"          FC8
Dir_compressor      :=A7.0
Dir_resistance      :=A7.1
P3                  :="Puesto7".UDT1_7.P3_m      DB70.DBD32      -- Output pressure
of the condenser
P1                  :="Puesto7".UDT1_7.P1_m      DB70.DBD24      -- Input pressure o
f the compressor
OFF                 :="Puesto7".UDT4_7.OFF      DB70.DBX235.5  -- Indicates if the
station is OFF(OFF=1, ON=0)
Mode_manual_automat
ic:= "Puesto7".UDT8_7.Mode_manual_automat
ic      DB70.DBX358.5  -- It determine weh
ter the cycle works automatically (0)
or in a manual way (1)
Manual_Resistance   :="Puesto7".UDT8_7.Manual_resistance
        DB70.DBX358.2  -- Test the correct
functioning of the resistance
Manual_EEV          :="Puesto7".UDT8_7.Manual_EEV
        DB70.DBX358.3  -- test the correct
funtioning of the EEV
Manual_compressor   :="Puesto7".UDT8_7.Manual_compressor
        DB70.DBX358.1  -- Test the correct
functioning of the compressor in the
manual mode
Manual_pump         :="Puesto7".UDT8_7.Manual_Pump
        DB70.DBX358.4  -- Test the correct
functioning of the pump
m_w                 :="Puesto7".UDT1_7.m_w_m      DB70.DBD40      -- Water flux
orden_pump_int      :="Puesto7".UDT3_7.Orden_pump_int
        DB70.DBW200   -- Control signal o
f the water pump
orden_EEVreal       :="Puesto7".UDT5_7.orden_EEVreal
        DB70.DBD244   -- EEV control orde
r
Dir_pump            :=AW924
Dir_EEV             :=AW928
orden_EEV           :="Puesto7".UDT3_7.Orden_EEV_int
        DB70.DBW198   -- Control signal o
f the EEV
orden_pump_real     :="Puesto7".UDT5_7.orden_pump_real
        DB70.DBD248   -- Pump control ord
er, REAL

```

//RESET of the connected sensors signals//

```

R      "Puesto7".UDT4_7.T1_conectado      DB70.DBX234.1      -- Indicates the co
nnection state of the sensor T1
R      "Puesto7".UDT4_7.T2_conectado      DB70.DBX234.3      -- Indicates the co
nnection state of the sensor T2
R      "Puesto7".UDT4_7.T3_conectado      DB70.DBX234.5      -- Indicates the co
nnection state of the sensor T3
R      "Puesto7".UDT4_7.Tin_conectado     DB70.DBX234.7      -- Indicates the co
nnection state of the sensor Tin
R      "Puesto7".UDT4_7.Tout_conectado    DB70.DBX235.0      -- Indicates the co
nnection state of the sensor Tout

```

```

R      "Puesto7".UDT4_7.P1_conectado      DB70.DBX234.2      -- Indicates the co
R      "Puesto7".UDT4_7.P2_conectado      DB70.DBX234.4      -- Indicates the co
R      "Puesto7".UDT4_7.P3_conectado      DB70.DBX234.6      -- Indicates the co
R      "Puesto7".UDT4_7.m_ref_conectado    DB70.DBX235.3      -- Indicates the co
R      "Puesto7".UDT4_7.Qw_conectado      DB70.DBX235.1      -- Indicates the co
R      "Puesto7".UDT4_7.Resistance_conectado DB70.DBX235.2      -- Indicates ifa he
ating resistance can be uses

```

SPA IR8

//__ST8__//

```

P8A: R      "Puesto8".UDT4_8.ON_OFF      DB80.DBX235.4      -- Indicates if the
S      "Puesto8".UDT4_8.AUXI_COMP      DB80.DBX235.6      -- Its an auxiliar
variable,in order to make the comparat
ions

P8O: UN     "Puesto8".UDT4_8.ON_OFF      DB80.DBX235.4      -- Indicates if the
=      "Puesto8".UDT4_8.OFF            DB80.DBX235.5      -- Indicates if the
station is OFF(OFF=1, ON=0)

```

//The programs leads to PX0 when the station is habilitated but it is off
//It calculates the OFF variable and execute the OFF functions

```

CALL "STOP_manual&automatic"          FC8
Dir_compressor      :=A8.0
Dir_resistance      :=A8.1
P3                  :="Puesto8".UDT1_8.P3_m      DB80.DBD32      -- Output pressure
of the condenser
P1                  :="Puesto8".UDT1_8.P1_m      DB80.DBD24      -- Input pressure o
f the compressor
OFF                 :="Puesto8".UDT4_8.OFF      DB80.DBX235.5   -- Indicates if the
station is OFF(OFF=1, ON=0)
Mode_manual_automat:= "Puesto8".UDT8_8.Mode_manual_automat DB80.DBX358.5   -- It determine weh
ter the cycle works automatically (0)
or in a manual way (1)
Manual_Resistance   := "Puesto8".UDT8_8.Manual_resistance DB80.DBX358.2   -- Test the correct
functioning of the resistance
Manual_EEV          := "Puesto8".UDT8_8.Manual_EEV      DB80.DBX358.3   -- test the correct
funtioning of the EEV
Manual_compressor   := "Puesto8".UDT8_8.Manual_compressor DB80.DBX358.1   -- Test the correct
functioning of the compressor in the
manual mode
Manual_pump         := "Puesto8".UDT8_8.Manual_Pump      DB80.DBX358.4   -- Test the correct
functioning of the pump
m_w                 := "Puesto8".UDT1_8.m_w_m          DB80.DBD40      -- Water flux
orden_pump_int      := "Puesto8".UDT3_8.Orden_pump_int   DB80.DBW200     -- Control signal o
f the water pump
orden_EEVreal       := "Puesto8".UDT5_8.orden_EEVreal   DB80.DBD244     -- EEV control orde
r
Dir_pump            :=AW1024
Dir_EEV             :=AW1028
orden_EEV           := "Puesto8".UDT3_8.Orden_EEV_int   DB80.DBW198     -- Control signal o
f the EEV
orden_pump_real     := "Puesto8".UDT5_8.orden_pump_real   DB80.DBD248     -- Pump control ord
er, REAL

```

//RESET of the connected sensors signals//

```

R      "Puesto8".UDT4_8.T1_conectado      DB80.DBX234.1      -- Indicates the co
R      "Puesto8".UDT4_8.T2_conectado      DB80.DBX234.3      -- Indicates the co
R      "Puesto8".UDT4_8.T3_conectado      DB80.DBX234.5      -- Indicates the co
R      "Puesto8".UDT4_8.Tin_conectado     DB80.DBX234.7      -- Indicates the co
R      "Puesto8".UDT4_8.Tout_conectado    DB80.DBX235.0      -- Indicates the co
R      "Puesto8".UDT4_8.P1_conectado      DB80.DBX234.2      -- Indicates the co
R      "Puesto8".UDT4_8.P2_conectado      DB80.DBX234.4      -- Indicates the co
R      "Puesto8".UDT4_8.P3_conectado      DB80.DBX234.6      -- Indicates the co
R      "Puesto8".UDT4_8.m_ref_conectado    DB80.DBX235.3      -- Indicates the co
R      "Puesto8".UDT4_8.Qw_conectado      DB80.DBX235.1      -- Indicates the co
nnection state of the sensor Qw

```

```
R      "Puesto8".UDT4_8.Resistance_conectado      DB80.DBX235.2      -- Indicates ifa he
ating resistance can be uses
```

```
SPA   IR9
```

```
//__ST9__//
```

```
P9A: R      "Puesto9".UDT4_9.ON_OFF                DB90.DBX235.4      -- Indicates if the
station is ON (ON=1, OFF=0)
S      "Puesto9".UDT4_9.AUXI_COMP                DB90.DBX235.6      -- Its an auxiliar
variable,in order to make the comparat
ions
P90: UN     "Puesto9".UDT4_9.ON_OFF                DB90.DBX235.4      -- Indicates if the
station is ON (ON=1, OFF=0)
=      "Puesto9".UDT4_9.OFF                      DB90.DBX235.5      -- Indicates if the
station is OFF(OFF=1, ON=0)
```

```
//The programs leads to PX0 when the station is habilitated but it is off
//It calculates the OFF variable and execute the OFF functions
```

```
CALL  "STOP_manual&automatic"                    FC8
Dir_compressor      :=A9.0
Dir_resistance      :=A9.1
P3                  :="Puesto9".UDT1_9.P3_m      DB90.DBD32        -- Output pressure
of the condenser
P1                  :="Puesto9".UDT1_9.P1_m      DB90.DBD24        -- Input pressure o
f the compressor
OFF                 :="Puesto9".UDT4_9.OFF        DB90.DBX235.5     -- Indicates if the
station is OFF(OFF=1, ON=0)
Mode_manual_automat:= "Puesto9".UDT8_9.Mode_manual_automat DB90.DBX358.5     -- It determine weh
ter the cycle works automatically (0)
or in a manual way (1)
Manual_Resistance   := "Puesto9".UDT8_9.Manual_resistance DB90.DBX358.2     -- Test the correct
functioning of the resistance
Manual_EEV          := "Puesto9".UDT8_9.Manual_EEV   DB90.DBX358.3     -- test the correct
functioning of the EEV
Manual_compressor   := "Puesto9".UDT8_9.Manual_compressor DB90.DBX358.1     -- Test the correct
functioning of the compressor in the
manual mode
Manual_pump         := "Puesto9".UDT8_9.Manual_Pump  DB90.DBX358.4     -- Test the correct
functioning of the pump
m_w                 := "Puesto9".UDT1_9.m_w_m      DB90.DBD40        -- Water flux
orden_pump_int      := "Puesto9".UDT3_9.Orden_pump_int DB90.DBW200       -- Control signal o
f the water pump
orden_EEVreal       := "Puesto9".UDT5_9.orden_EEVreal DB90.DBD244       -- EEV control orde
r
Dir_pump            :=AW1124
Dir_EEV             :=AW1128
orden_EEV           := "Puesto9".UDT3_9.Orden_EEV_int DB90.DBW198       -- Control signal o
f the EEV
orden_pump_real     := "Puesto9".UDT5_9.orden_pump_real DB90.DBD248       -- Pump control ord
er, REAL
```

```
//RESET of the connected sensors signals//
```

```
R      "Puesto9".UDT4_9.T1_conectado              DB90.DBX234.1     -- Indicates the co
nnection state of the sensor T1
R      "Puesto9".UDT4_9.T2_conectado              DB90.DBX234.3     -- Indicates the co
nnection state of the sensor T2
R      "Puesto9".UDT4_9.T3_conectado              DB90.DBX234.5     -- Indicates the co
nnection state of the sensor T3
R      "Puesto9".UDT4_9.Tin_conectado             DB90.DBX234.7     -- Indicates the co
nnection state of the sensor Tin
R      "Puesto9".UDT4_9.Tout_conectado            DB90.DBX235.0     -- Indicates the co
nnection state of the sensor Tout
R      "Puesto9".UDT4_9.P1_conectado              DB90.DBX234.2     -- Indicates the co
nnection state of the sensor P1
R      "Puesto9".UDT4_9.P2_conectado              DB90.DBX234.4     -- Indicates the co
nnection state of the sensor P2
R      "Puesto9".UDT4_9.P3_conectado              DB90.DBX234.6     -- Indicates the co
nnection state of the sensor P3
R      "Puesto9".UDT4_9.m_ref_conectado           DB90.DBX235.3     -- Indicates the co
nnection state of the sensor m_ref
R      "Puesto9".UDT4_9.Qw_conectado              DB90.DBX235.1     -- Indicates the co
nnection state of the sensor Qw
R      "Puesto9".UDT4_9.Resistance_conectado      DB90.DBX235.2     -- Indicates ifa he
ating resistance can be uses
```

```
SPA   IR10
```

```
//__ST10__//
```

```

P10A: R    "Puesto10".UDT4_10.ON_OFF          DB100.DBX235.4    -- Indicates if the
          S    "Puesto10".UDT4_10.AUXI_COMP   DB100.DBX235.6    -- Its an auxiliar
                                                    variable,in order to make the comparat
                                                    ions

P100: UN   "Puesto10".UDT4_10.ON_OFF          DB100.DBX235.4    -- Indicates if the
          =    "Puesto10".UDT4_10.OFF         DB100.DBX235.5    -- Indicates if the
                                                    station is OFF(OFF=1, ON=0)

```

```

//The programs leads to PX0 when the station is habilitated but it is off
//It calculates the OFF variable and execute the OFF functions

```

```

CALL "STOP_manual&automatic"                FC8
Dir_compressor      :=A10.0
Dir_resistance      :=A10.1
P3                  :="Puesto10".UDT1_10.P3_m   DB100.DBD32      -- Output pressure
                                                    of the condenser
P1                  :="Puesto10".UDT1_10.P1_m   DB100.DBD24      -- Input pressure o
                                                    f the compressor
OFF                 :="Puesto10".UDT4_10.OFF    DB100.DBX235.5   -- Indicates if the
                                                    station is OFF(OFF=1, ON=0)
Mode_manual_automatic:= "Puesto10".UDT8_10.Mode_manual_automatic DB100.DBX358.5   -- It determine weh
                                                    ter the cycle works automatically (0)
                                                    or in a manual way (1)
Manual_Resistance   := "Puesto10".UDT8_10.Manual_resistance DB100.DBX358.2   -- Test the correct
                                                    functioning of the resistance
Manual_EEV          := "Puesto10".UDT8_10.Manual_EEV   DB100.DBX358.3   -- test the correct
                                                    funtioning of the EEV
Manual_compressor   := "Puesto10".UDT8_10.Manual_compressor DB100.DBX358.1   -- Test the correct
                                                    functioning of the compressor in the
                                                    manual mode
Manual_pump         := "Puesto10".UDT8_10.Manual_Pump   DB100.DBX358.4   -- Test the correct
                                                    functioning of the pump
m_w                 := "Puesto10".UDT1_10.m_w_m       DB100.DBD40      -- Water flux
orden_pump_int      := "Puesto10".UDT3_10.Orden_pump_int DB100.DBW200     -- Control signal o
                                                    f the water pump
orden_EEVreal       := "Puesto10".UDT5_10.orden_EEVreal DB100.DBD244     -- EEV control orde
                                                    r
Dir_pump            :=AW1224
Dir_EEV             :=AW1228
orden_EEV           := "Puesto10".UDT3_10.Orden_EEV_int DB100.DBW198     -- Control signal o
                                                    f the EEV
orden_pump_real     := "Puesto10".UDT5_10.orden_pump_real DB100.DBD248     -- Pump control ord
                                                    er, REAL

```

```

//RESET of the connected sensors signals//

```

```

R    "Puesto10".UDT4_10.T1_conectado          DB100.DBX234.1    -- Indicates the co
nnection state of the sensor T1
R    "Puesto10".UDT4_10.T2_conectado          DB100.DBX234.3    -- Indicates the co
nnection state of the sensor T2
R    "Puesto10".UDT4_10.T3_conectado          DB100.DBX234.5    -- Indicates the co
nnection state of the sensor T3
R    "Puesto10".UDT4_10.Tin_conectado         DB100.DBX234.7    -- Indicates the co
nnection state of the sensor Tin
R    "Puesto10".UDT4_10.Tout_conectado        DB100.DBX235.0    -- Indicates the co
nnection state of the sensor Tout
R    "Puesto10".UDT4_10.P1_conectado          DB100.DBX234.2    -- Indicates the co
nnection state of the sensor P1
R    "Puesto10".UDT4_10.P2_conectado          DB100.DBX234.4    -- Indicates the co
nnection state of the sensor P2
R    "Puesto10".UDT4_10.P3_conectado          DB100.DBX234.6    -- Indicates the co
nnection state of the sensor P3
R    "Puesto10".UDT4_10.m_ref_conectado       DB100.DBX235.3    -- Indicates the co
nnection state of the sensor m_ref
R    "Puesto10".UDT4_10.Qw_conectado          DB100.DBX235.1    -- Indicates the co
nnection state of the sensor Qw
R    "Puesto10".UDT4_10.Resistance_conectado DB100.DBX235.2    -- Indicates ifa he
ating resistance can be uses

```

```

SPA  IR11

```

```

//__ST11__//

```

```

P11A: R    "Puesto11".UDT4_11.ON_OFF          DB110.DBX235.4    -- Indicates if the
          S    "Puesto11".UDT4_11.AUXI_COMP   DB110.DBX235.6    -- Its an auxiliar
                                                    variable,in order to make the comparat
                                                    ions

P110: UN   "Puesto11".UDT4_11.ON_OFF          DB110.DBX235.4    -- Indicates if the
                                                    station is ON (ON=1, OFF=0)

```

```

=      "Puesto11".UDT4_11.OFF                                DB110.DBX235.5    -- Indicates if the
                                                           station is OFF(OFF=1, ON=0)

//The programs leads to PX0 when the station is habilitated but it is off
//It calculates the OFF variable and execute the OFF functions

CALL  "STOP_manual&automatic"                               FC8
Dir_compressor      :=A11.0
Dir_resistance      :=A11.1
P3                  :="Puesto11".UDT1_11.P3_m              DB110.DBD32      -- Output pressure
                                                           of the condenser
P1                  :="Puesto11".UDT1_11.P1_m              DB110.DBD24      -- Input pressure o
                                                           f the compressor
OFF                 :="Puesto11".UDT4_11.OFF              DB110.DBX235.5  -- Indicates if the
                                                           station is OFF(OFF=1, ON=0)
Mode_manual_automat:= "Puesto11".UDT8_11.Mode_manual_automat DB110.DBX358.5  -- It determine weh
                                                           ter the cycle works automatically (0)
                                                           or in a manual way (1)
Manual_Resistance   :="Puesto11".UDT8_11.Manual_resistance DB110.DBX358.2  -- Test the correct
                                                           functioning of the resistance
Manual_EEV          :="Puesto11".UDT8_11.Manual_EEV       DB110.DBX358.3  -- test the correct
                                                           funtioning of the EEV
Manual_compressor   :="Puesto11".UDT8_11.Manual_compressor DB110.DBX358.1  -- Test the correct
                                                           functioning of the compressor in the
                                                           manual mode
Manual_pump         :="Puesto11".UDT8_11.Manual_Pump      DB110.DBX358.4  -- Test the correct
                                                           functioning of the pump
m_w                :="Puesto11".UDT1_11.m_w_m             DB110.DBD40      -- Water flux
orden_pump_int     :="Puesto11".UDT3_11.Orden_pump_int    DB110.DBW200     -- Control signal o
                                                           f the water pump
orden_EEVreal      :="Puesto11".UDT5_11.orden_EEVreal    DB110.DBD244     -- EEV control orde
                                                           r
Dir_pump           :=AW1324
Dir_EEV            :=AW1328
orden_EEV          :="Puesto11".UDT3_11.Orden_EEV_int    DB110.DBW198     -- Control signal o
                                                           f the EEV
orden_pump_real    :="Puesto11".UDT5_11.orden_pump_real  DB110.DBD248     -- Pump control ord
                                                           er, REAL

//RESET of the connected sensors signals//

R      "Puesto11".UDT4_11.T1_conectado                    DB110.DBX234.1  -- Indicates the co
                                                           nnection state of the sensor T1
R      "Puesto11".UDT4_11.T2_conectado                    DB110.DBX234.3  -- Indicates the co
                                                           nnection state of the sensor T2
R      "Puesto11".UDT4_11.T3_conectado                    DB110.DBX234.5  -- Indicates the co
                                                           nnection state of the sensor T3
R      "Puesto11".UDT4_11.Tin_conectado                   DB110.DBX234.7  -- Indicates the co
                                                           nnection state of the sensor Tin
R      "Puesto11".UDT4_11.Tout_conectado                  DB110.DBX235.0  -- Indicates the co
                                                           nnection state of the sensor Tout
R      "Puesto11".UDT4_11.P1_conectado                    DB110.DBX234.2  -- Indicates the co
                                                           nnection state of the sensor P1
R      "Puesto11".UDT4_11.P2_conectado                    DB110.DBX234.4  -- Indicates the co
                                                           nnection state of the sensor P2
R      "Puesto11".UDT4_11.P3_conectado                    DB110.DBX234.6  -- Indicates the co
                                                           nnection state of the sensor P3
R      "Puesto11".UDT4_11.m_ref_conectado                 DB110.DBX235.3  -- Indicates the co
                                                           nnection state of the sensor m_ref
R      "Puesto11".UDT4_11.Qw_conectado                    DB110.DBX235.1  -- Indicates the co
                                                           nnection state of the sensor Qw
R      "Puesto11".UDT4_11.Resistance_conectado            DB110.DBX235.2  -- Indicates ifa he
                                                           ating resistance can be uses

SPA   IR12

//__ST12__//

P12A: R      "Puesto12".UDT4_12.ON_OFF                    DB120.DBX235.4  -- Indicates if the
                                                           station is ON (ON=1, OFF=0)
S      "Puesto12".UDT4_12.AUXI_COMP                      DB120.DBX235.6  -- Its an auxiliariar
                                                           variable,in order to make the comparat
                                                           ions

P120: UN     "Puesto12".UDT4_12.ON_OFF                    DB120.DBX235.4  -- Indicates if the
                                                           station is ON (ON=1, OFF=0)
=      "Puesto12".UDT4_12.OFF                            DB120.DBX235.5  -- Indicates if the
                                                           station is OFF(OFF=1, ON=0)

//The programs leads to PX0 when the station is habilitated but it is off
//It calculates the OFF variable and execute the OFF functions

CALL  "STOP_manual&automatic"                               FC8
Dir_compressor      :=A12.0
Dir_resistance      :=A12.1

```

```

P3          := "Puesto12".UDT1_12.P3_m          DB120.DBD32      -- Output pressure
of the condenser
P1          := "Puesto12".UDT1_12.P1_m          DB120.DBD24      -- Input pressure o
f the compressor
OFF         := "Puesto12".UDT4_12.OFF          DB120.DBX235.5   -- Indicates if the
station is OFF (OFF=1, ON=0)
Mode_manual_automat:= "Puesto12".UDT8_12.Mode_manual_automat DB120.DBX358.5   -- It determine weh
ter the cycle works automatically (0)
or in a manual way (1)
Manual_Resistance := "Puesto12".UDT8_12.Manual_resistance DB120.DBX358.2   -- Test the correct
functioning of the resistance
Manual_EEV     := "Puesto12".UDT8_12.Manual_EEV   DB120.DBX358.3   -- test the correct
funtioning of the EEV
Manual_compressor := "Puesto12".UDT8_12.Manual_compressor DB120.DBX358.1   -- Test the correct
functioning of the compressor in the
manual mode
Manual_pump    := "Puesto12".UDT8_12.Manual_Pump  DB120.DBX358.4   -- Test the correct
functioning of the pump
m_w           := "Puesto12".UDT1_12.m_w_m        DB120.DBD40      -- Water flux
orden_pump_int := "Puesto12".UDT3_12.Orden_pump_int DB120.DBW200     -- Control signal o
f the water pump
orden_EEVreal  := "Puesto12".UDT5_12.orden_EEVreal DB120.DBD244     -- EEV control orde
r
Dir_pump      := AW1424
Dir_EEV       := AW1428
orden_EEV     := "Puesto12".UDT3_12.Orden_EEV_int DB120.DBW198     -- Control signal o
f the EEV
orden_pump_real := "Puesto12".UDT5_12.orden_pump_real DB120.DBD248     -- Pump control ord
er, REAL

```

```
//RESET of the connected sensors signals//
```

```

R   "Puesto12".UDT4_12.T1_conectado  DB120.DBX234.1   -- Indicates the co
nnection state of the sensor T1
R   "Puesto12".UDT4_12.T2_conectado  DB120.DBX234.3   -- Indicates the co
nnection state of the sensor T2
R   "Puesto12".UDT4_12.T3_conectado  DB120.DBX234.5   -- Indicates the co
nnection state of the sensor T3
R   "Puesto12".UDT4_12.Tin_conectado DB120.DBX234.7   -- Indicates the co
nnection state of the sensor Tin
R   "Puesto12".UDT4_12.Tout_conectado DB120.DBX235.0   -- Indicates the co
nnection state of the sensor Tout
R   "Puesto12".UDT4_12.P1_conectado  DB120.DBX234.2   -- Indicates the co
nnection state of the sensor P1
R   "Puesto12".UDT4_12.P2_conectado  DB120.DBX234.4   -- Indicates the co
nnection state of the sensor P2
R   "Puesto12".UDT4_12.P3_conectado  DB120.DBX234.6   -- Indicates the co
nnection state of the sensor P3
R   "Puesto12".UDT4_12.m_ref_conectado DB120.DBX235.3   -- Indicates the co
nnection state of the sensor m_ref
R   "Puesto12".UDT4_12.Qw_conectado  DB120.DBX235.1   -- Indicates the co
nnection state of the sensor Qw
R   "Puesto12".UDT4_12.Resistance_conectado DB120.DBX235.2   -- Indicates ifa he
ating resistance can be uses

NOP 0

```

Segm.: 2	Simultaneous start of the stations
----------	------------------------------------

The stations can be activated all at once. If one of them is stopped, then the start button/indicator should stop being active.

```

SEG2: U   "Puestos1".UDT4_1.AUXI_COMP  DB10.DBX235.6   -- Its an auxiliar variable,in order to mak
e the comparations
U   "Puesto2".UDT4_2.AUXI_COMP        DB20.DBX235.6   -- Its an auxiliar variable,in order to mak
e the comparations
U   "Puesto3".UDT4_3.AUXI_COMP        DB30.DBX235.6   -- Its an auxiliar variable,in order to mak
e the comparations
U   "Puesto4".UDT4_4.AUXI_COMP        DB40.DBX235.6   -- Its an auxiliar variable,in order to mak
e the comparations
U   "Puesto5".UDT4_5.AUXI_COMP        DB50.DBX235.6   -- Its an auxiliar variable,in order to mak
e the comparations
U   "Puesto6".UDT4_6.AUXI_COMP        DB60.DBX235.6   -- Its an auxiliar variable,in order to mak
e the comparations
U   "Puesto7".UDT4_7.AUXI_COMP        DB70.DBX235.6   -- Its an auxiliar variable,in order to mak
e the comparations
U   "Puesto8".UDT4_8.AUXI_COMP        DB80.DBX235.6   -- Its an auxiliar variable,in order to mak
e the comparations
U   "Puesto9".UDT4_9.AUXI_COMP        DB90.DBX235.6   -- Its an auxiliar variable,in order to mak
e the comparations
U   "Puesto10".UDT4_10.AUXI_COMP      DB100.DBX235.6  -- Its an auxiliar variable,in order to mak
e the comparations
U   "Puesto11".UDT4_11.AUXI_COMP     DB110.DBX235.6  -- Its an auxiliar variable,in order to mak
e the comparations

```

```

U   "Puesto12".UDT4_12.AUXI_COMP      DB120.DBX235.6    -- Its an auxiliar variable,in order to mak
e the comparations

=   "Puestos1".UDT9_1.Button_start_all  DB10.DBX370.2     -- Just for the HMI

```

Segm.: 3	Simultaneous stop for all the stations
----------	--

If all the implemented stations are OFF (ON_OFF=0 ot OFF=1), then STOP ALL=1

The programation that stablish that OFF=1 (for all the stations) when the button STOP ALL is pulsed, has been developed in the WINCC program.

```

UN  "Puestos1".UDT4_1.ON_OFF          DB10.DBX235.4     -- Indicates if the station is ON (ON=1, OFF
=0)
UN  "Puesto2".UDT4_2.ON_OFF          DB20.DBX235.4     -- Indicates if the station is ON (ON=1, OFF
=0)
UN  "Puesto3".UDT4_3.ON_OFF          DB30.DBX235.4     -- Indicates if the station is ON (ON=1, OFF
=0)
UN  "Puesto4".UDT4_4.ON_OFF          DB40.DBX235.4     -- Indicates if the station is ON (ON=1, OFF
=0)
UN  "Puesto5".UDT4_5.ON_OFF          DB50.DBX235.4     -- Indicates if the station is ON (ON=1, OFF
=0)
UN  "Puesto6".UDT4_6.ON_OFF          DB60.DBX235.4     -- Indicates if the station is ON (ON=1, OFF
=0)
UN  "Puesto7".UDT4_7.ON_OFF          DB70.DBX235.4     -- Indicates if the station is ON (ON=1, OFF
=0)
UN  "Puesto8".UDT4_8.ON_OFF          DB80.DBX235.4     -- Indicates if the station is ON (ON=1, OFF
=0)
UN  "Puesto9".UDT4_9.ON_OFF          DB90.DBX235.4     -- Indicates if the station is ON (ON=1, OFF
=0)
UN  "Puesto10".UDT4_10.ON_OFF         DB100.DBX235.4    -- Indicates if the station is ON (ON=1, OFF
=0)
UN  "Puesto11".UDT4_11.ON_OFF        DB110.DBX235.4    -- Indicates if the station is ON (ON=1, OFF
=0)
UN  "Puesto12".UDT4_12.ON_OFF        DB120.DBX235.4    -- Indicates if the station is ON (ON=1, OFF
=0)

=   "Puestos1".UDT9_1.Button_stop_all  DB10.DBX370.3     -- Just for the HMI

```

Segm.: 4	START ALL
----------	-----------

When the "START ALL" button is pressed (once, twice...) all the stations IMPLEMENTED are set as "ON".

```

U   "Puestos1".START_ALL              DB10.DBX400.1     -- All th
e stations must be turned on
simustaneuosly

SPB  S_AL
SPA  SEG5                             //If it is not active, continue the execution of the program
in the next segment

```

//The variable is active, so the stations implemented must be set as "ON"

```

S_AL: U   "Puestos1".UDT4_1.Puesto_habilitado  DB10.DBX234.0     -- Indica
tes if the station is "built
", if it can be turned ON

SPB  S_1                                 //If the station is implemented, then set the ON variable
and reset the OFF
SPA  P2                                 //If the station is not implemented, check the next station
S_1: S   "Puestos1".UDT4_1.ON_OFF          DB10.DBX235.4     -- Indica
tes if the station is ON (ON
=1, OFF=0)
R     "Puestos1".UDT4_1.OFF              DB10.DBX235.5     -- Indica
tes if the station is OFF(OFF
=1, ON=0)

```

//__ST2__//

```

P2:  U   "Puesto2".UDT4_2.Puesto_habilitado  DB20.DBX234.0     -- Indica
tes if the station is "built
", if it can be turned ON

SPB  S_2
SPA  P3
S_2: S   "Puesto2".UDT4_2.ON_OFF          DB20.DBX235.4     -- Indica
tes if the station is ON (ON
=1, OFF=0)
R     "Puesto2".UDT4_2.OFF              DB20.DBX235.5     -- Indica
tes if the station is OFF(OFF
=1, ON=0)

```

//__ST3__//

```

P3:  U      "Puesto3".UDT4_3.Puesto_habilitado          DB30.DBX234.0      -- Indica
                                     tes if the station is "built
                                     ", if it can be turned ON

      SPB   S_3
      SPA   P4
S_3:  S      "Puesto3".UDT4_3.ON_OFF                    DB30.DBX235.4      -- Indica
                                     tes if the station is ON (ON
                                     =1, OFF=0)
      R      "Puesto3".UDT4_3.OFF                      DB30.DBX235.5      -- Indica
                                     tes if the station is OFF(OFF
                                     F=1, ON=0)

//__ST4__//

P4:  U      "Puesto4".UDT4_4.Puesto_habilitado          DB40.DBX234.0      -- Indica
                                     tes if the station is "built
                                     ", if it can be turned ON

      SPB   S_4
      SPA   P5
S_4:  S      "Puesto4".UDT4_4.ON_OFF                    DB40.DBX235.4      -- Indica
                                     tes if the station is ON (ON
                                     =1, OFF=0)
      R      "Puesto4".UDT4_4.OFF                      DB40.DBX235.5      -- Indica
                                     tes if the station is OFF(OFF
                                     F=1, ON=0)

//__ST5__//

P5:  U      "Puesto5".UDT4_5.Puesto_habilitado          DB50.DBX234.0      -- Indica
                                     tes if the station is "built
                                     ", if it can be turned ON

      SPB   S_5
      SPA   P6
S_5:  S      "Puesto5".UDT4_5.ON_OFF                    DB50.DBX235.4      -- Indica
                                     tes if the station is ON (ON
                                     =1, OFF=0)
      R      "Puesto5".UDT4_5.OFF                      DB50.DBX235.5      -- Indica
                                     tes if the station is OFF(OFF
                                     F=1, ON=0)

//__ST6__//

P6:  U      "Puesto6".UDT4_6.Puesto_habilitado          DB60.DBX234.0      -- Indica
                                     tes if the station is "built
                                     ", if it can be turned ON

      SPB   S_6
      SPA   P7
S_6:  S      "Puesto6".UDT4_6.ON_OFF                    DB60.DBX235.4      -- Indica
                                     tes if the station is ON (ON
                                     =1, OFF=0)
      R      "Puesto6".UDT4_6.OFF                      DB60.DBX235.5      -- Indica
                                     tes if the station is OFF(OFF
                                     F=1, ON=0)

//__ST7__//

P7:  U      "Puesto7".UDT4_7.Puesto_habilitado          DB70.DBX234.0      -- Indica
                                     tes if the station is "built
                                     ", if it can be turned ON

      SPB   S_7
      SPA   P8
S_7:  S      "Puesto7".UDT4_7.ON_OFF                    DB70.DBX235.4      -- Indica
                                     tes if the station is ON (ON
                                     =1, OFF=0)
      R      "Puesto7".UDT4_7.OFF                      DB70.DBX235.5      -- Indica
                                     tes if the station is OFF(OFF
                                     F=1, ON=0)

//__ST8__//

P8:  U      "Puesto8".UDT4_8.Puesto_habilitado          DB80.DBX234.0      -- Indica
                                     tes if the station is "built
                                     ", if it can be turned ON

      SPB   S_8
      SPA   P9
S_8:  S      "Puesto8".UDT4_8.ON_OFF                    DB80.DBX235.4      -- Indica
                                     tes if the station is ON (ON
                                     =1, OFF=0)
      R      "Puesto8".UDT4_8.OFF                      DB80.DBX235.5      -- Indica
                                     tes if the station is OFF(OFF
                                     F=1, ON=0)

//__ST9__//

P9:  U      "Puesto9".UDT4_9.Puesto_habilitado          DB90.DBX234.0      -- Indica
                                     tes if the station is "built
                                     ", if it can be turned ON

      SPB   S_9
      SPA   P10

```



```

S_9: S      "Puesto9".UDT4_9.ON_OFF          DB90.DBX235.4      -- Indica
                                         tes if the station is ON (ON
                                         =1, OFF=0)
      R      "Puesto9".UDT4_9.OFF           DB90.DBX235.5      -- Indica
                                         tes if the station is OFF(OFF
                                         =1, ON=0)

//__ST10__//

P10: U      "Puesto10".UDT4_10.Puesto_habilitado DB100.DBX234.0     -- Indica
                                         tes if the station is "built
                                         ", if it can be turned ON

      SPB    S_10
      SPA    P11
S_10: S      "Puesto10".UDT4_10.ON_OFF       DB100.DBX235.4     -- Indica
                                         tes if the station is ON (ON
                                         =1, OFF=0)
      R      "Puesto10".UDT4_10.OFF         DB100.DBX235.5     -- Indica
                                         tes if the station is OFF(OFF
                                         =1, ON=0)

//__ST11__//

P11: U      "Puesto11".UDT4_11.Puesto_habilitado DB110.DBX234.0     -- Indica
                                         tes if the station is "built
                                         ", if it can be turned ON

      SPB    S_11
      SPA    P12
S_11: S      "Puesto11".UDT4_11.ON_OFF       DB110.DBX235.4     -- Indica
                                         tes if the station is ON (ON
                                         =1, OFF=0)
      R      "Puesto11".UDT4_11.OFF         DB110.DBX235.5     -- Indica
                                         tes if the station is OFF(OFF
                                         =1, ON=0)

//__ST12__//

P12: U      "Puesto12".UDT4_12.Puesto_habilitado DB120.DBX234.0     -- Indica
                                         tes if the station is "built
                                         ", if it can be turned ON

      SPB    S_12
      SPA    SEG5
S_12: S      "Puesto12".UDT4_12.ON_OFF       DB120.DBX235.4     -- Indica
                                         tes if the station is ON (ON
                                         =1, OFF=0)
      R      "Puesto12".UDT4_12.OFF         DB120.DBX235.5     -- Indica
                                         tes if the station is OFF(OFF
                                         =1, ON=0)

```

```
Segm.: 5      STOP ALL
```

When the STOP all button is pressed (once, twice...) all the stations are set as "OFF".

We could repeat the code for the "START ALL" button, and invert it. However, since when a station has not been implemented we configure it as "OFF" then there would be no need The code would be much easier .

```

SEG5: U      "Puestos1".STOP_ALL             DB10.DBX400.0      -- All the stations must be turned off simustaneousl
                                         y
      SPB    R_AL
      SPA    END

R_AL: R      "Puestos1".UDT4_1.ON_OFF        DB10.DBX235.4      -- Indicates if the station is ON (ON=1, OFF=0)
      R      "Puesto2".UDT4_2.ON_OFF        DB20.DBX235.4      -- Indicates if the station is ON (ON=1, OFF=0)
      R      "Puesto3".UDT4_3.ON_OFF        DB30.DBX235.4      -- Indicates if the station is ON (ON=1, OFF=0)
      R      "Puesto4".UDT4_4.ON_OFF        DB40.DBX235.4      -- Indicates if the station is ON (ON=1, OFF=0)
      R      "Puesto5".UDT4_5.ON_OFF        DB50.DBX235.4      -- Indicates if the station is ON (ON=1, OFF=0)
      R      "Puesto6".UDT4_6.ON_OFF        DB60.DBX235.4      -- Indicates if the station is ON (ON=1, OFF=0)
      R      "Puesto7".UDT4_7.ON_OFF        DB70.DBX235.4      -- Indicates if the station is ON (ON=1, OFF=0)
      R      "Puesto8".UDT4_8.ON_OFF        DB80.DBX235.4      -- Indicates if the station is ON (ON=1, OFF=0)
      R      "Puesto9".UDT4_9.ON_OFF        DB90.DBX235.4      -- Indicates if the station is ON (ON=1, OFF=0)
      R      "Puesto10".UDT4_10.ON_OFF       DB100.DBX235.4     -- Indicates if the station is ON (ON=1, OFF=0)
      R      "Puesto11".UDT4_11.ON_OFF      DB110.DBX235.4     -- Indicates if the station is ON (ON=1, OFF=0)
      R      "Puesto12".UDT4_12.ON_OFF      DB120.DBX235.4     -- Indicates if the station is ON (ON=1, OFF=0)

      S      "Puestos1".UDT4_1.OFF          DB10.DBX235.5      -- Indicates if the station is OFF(OFF=1, ON=0)
      S      "Puesto2".UDT4_2.OFF          DB20.DBX235.5      -- Indicates if the station is OFF(OFF=1, ON=0)
      S      "Puesto3".UDT4_3.OFF          DB30.DBX235.5      -- Indicates if the station is OFF(OFF=1, ON=0)
      S      "Puesto4".UDT4_4.OFF          DB40.DBX235.5      -- Indicates if the station is OFF(OFF=1, ON=0)
      S      "Puesto5".UDT4_5.OFF          DB50.DBX235.5      -- Indicates if the station is OFF(OFF=1, ON=0)
      S      "Puesto6".UDT4_6.OFF          DB60.DBX235.5      -- Indicates if the station is OFF(OFF=1, ON=0)
      S      "Puesto7".UDT4_7.OFF          DB70.DBX235.5      -- Indicates if the station is OFF(OFF=1, ON=0)

```

```
S  "Puesto8".UDT4_8.OFF      DB80.DBX235.5      -- Indicates if the station is OFF(OFF=1, ON=0)
S  "Puesto9".UDT4_9.OFF      DB90.DBX235.5      -- Indicates if the station is OFF(OFF=1, ON=0)
S  "Puesto10".UDT4_10.OFF    DB100.DBX235.5     -- Indicates if the station is OFF(OFF=1, ON=0)
S  "Puesto11".UDT4_11.OFF    DB110.DBX235.5     -- Indicates if the station is OFF(OFF=1, ON=0)
S  "Puesto12".UDT4_12.OFF    DB120.DBX235.5     -- Indicates if the station is OFF(OFF=1, ON=0)
```

Segm.: 6	END
----------	-----

END segment

END: NOP 0

FC2 - <offline>

"Real->Int->Word"

Nombre: **Familia:**
Autor: **Versión:** 0.1
Versión del bloque: 2
Hora y fecha Código: 27/05/2014 09:21:49
Interface: 14/05/2014 15:25:04
Longitud (bloque / código / datos): 00122 00024 00000

Propiedades del objeto:

S7_language 9(1) Inglés (Estados Unidos) 23/05/2014 13:19:47

Nombre	Tipo de datos	Dirección	Comentario
IN		0.0	
valor_REAL	Real	0.0	
OUT		0.0	
valor_INT	Int	4.0	
valor_WORD	Word	6.0	
IN_OUT		0.0	
TEMP		0.0	
RETURN		0.0	
RET_VAL		0.0	

Bloque: FC2 REAL->INT->WORD

```

Conversion:
REAL--> DINT
DINT--> BCD
BCD--> INT
INT--> WORD
  
```

Segm.: 1 Conversion

```

RND-> From REAL to DINT
DTB-> From DINT to BCD
BTD-> From BCD to INT
  
```

//REAL--> WORD

```

L   #valor_REAL //Value REAL (32 bits)           #valor_REAL
RND //Conversion to DINT
DTB //Conversion to BCD
BTD //From BCD to INT
T   #valor_INT  //The INT value is stored         #valor_INT

L   #valor_INT  #valor_INT
T   #valor_WORD //We save the INT value as a WORD #valor_WORD
  
```

FC3 - <offline>

"Sensor conect/desconect"

Nombre:**Familia:****Autor:****Versión:** 0.1**Hora y fecha Código:****Versión del bloque:** 2

30/05/2014 18:21:32

Interface: 21/05/2014 13:15:41**Longitud (bloque / código / datos):** 00120 00020 00000**Propiedades del objeto:**

S7_language

9(1) Inglés (Estados Unidos) 23/05/2014 13:19:47

Nombre	Tipo de datos	Dirección	Comentario
IN		0.0	
Sensor_conectado	Bool	0.0	It indicates if the sensor has been connected
Valor_teorico	Real	2.0	The theoretical value that should have
OUT		0.0	
Valor_a_GUARDAR	Real	6.0	If it is not connected, the theoretical value would be stored to use it
IN_OUT		0.0	
TEMP		0.0	
RETURN		0.0	
RET_VAL		0.0	

Bloque: FC3 Connected sensor

If the sensor has been connected, then it would measure the real value and store it.
Otherwise, the theoretical value calculated would have to be store as if it was the real value.

Segm.: 1 Not connected sensor

The program is written for when the sensor IS connected.
The code below is a correction of this fact, in other words, what have to me done if the sensor hasn't been implemented.

```

      U      #Sensor_conectado  #Sensor_conectado  -- It indicates if the sensor has been connected
      SPBN  NO_C

NO_C: L      #Valor_teorico    #Valor_teorico    -- The theoretical value that should have
      T      #Valor_a_GUARDAR  #Valor_a_GUARDAR -- If it is not connected, the theoretical value would be st
                                ored to use it

      NOP    0

```

FC4 - <offline>

"Alarm"

Nombre:**Familia:****Autor:****Versión:** 0.1**Versión del bloque:** 2**Hora y fecha Código:**

11/06/2014 16:27:54

Interface:

11/06/2014 16:27:54

Longitud (bloque / código / datos): 00772 00522 00026

Nombre	Tipo de datos	Dirección	Comentario
IN		0.0	
DeviationT1	Real	0.0	Deviation of T1 allowed (%)
DeviationP1	Real	4.0	Deviation of P1 allowed (%)
MaxP2	Real	8.0	Maximum pressure allowed at point 2 (bar)
MaxT2	Real	12.0	Maximum temperature allowed at point 2 (°C)
T1_m	Real	16.0	Temperature at point 1, measured
P1_m	Real	20.0	Pressure at point 1, measured
T2_m	Real	24.0	Temperature at point 2, measured
P2_m	Real	28.0	Pressure at point 2 , measured
OUT		0.0	
IN_OUT		0.0	
T1sat	Real	32.0	Saturation temperature at P1_set
P1_set	Real	36.0	Set pressure at point 1
ON_OFF	Bool	40.0	0->OFF When an error occurs
OFF	Bool	40.1	1->OFF when an error occurs
T1_Low	Bool	40.2	Indicator of T1< T1min->1
T1_High	Bool	40.3	Indicator of T1> T1max->1
T1_Error	Bool	40.4	Temperature 1 is not between the limits->1
P1_Low	Bool	40.5	Indicator of P1< P1min->1
P1_High	Bool	40.6	Indicator of P1> P1max->1
P1_Error	Bool	40.7	Pressure 1 is not between the limits->1
T2_Error	Bool	41.0	Temperature 2> T2 maximum
P2_Error	Bool	41.1	Pressure 2 > P2 maximum
Stable	Bool	41.2	Indicates when the bench has been stabilized for the first time
Alarm	Bool	41.3	The bench needs to be stopped, and a signal must be emitted
TEMP		0.0	
T1_max	Real	0.0	Max temperature at point 1 allowed
T1_min	Real	4.0	Min temperature at point 1 allowed
P1_max	Real	8.0	Max pressure at point 1 allowed
P1_min	Real	12.0	Min pressure at point 1 allowed
ToleranceT1	Real	16.0	Tolerance of T1
ToleranceP1	Real	20.0	Tolerance of P1
Point1_failure	Bool	24.0	Indicates when an error has occurred in point 1
Point2_failure	Bool	24.1	Indicates when an error has occurred in point 2
ST	Bool	24.2	Auxiliar variable to increment the counter
Wait_settling_time_max	Bool	24.3	Active while it is in the settling time (15min,..)
Wait_sample_time	Bool	24.4	
Sample	Bool	24.5	
Failure_time_P1_done	Bool	24.6	The failure in Point 1 has persist the time allowed
Failure_time_P2_done	Bool	24.7	The failure in Point 2 has persist the time allowed
RETURN		0.0	
RET_VAL		0.0	

Bloque: FC4 ALARM

When the station is working (ON) in the AUTOMATIC mode, some parameters must be checked in order to guarantee the correct functioning of the station.

Segm.: 1 Maximum settling time

During the settling time, the alarm actions would not be performed. The station needs time to stabilize.
There would be different samples of the error status. (EVERY 3 MIN)

//Set the maximum settling time (no alarm actions would be performed)

```

U   #ON_OFF          #ON_OFF          -- O->OFF When an error occurs
L   S5T#5M
SE  T      0
UN  T      0
=   #Wait_settling_time_max #Wait_settling_time_max -- Active while it is in the settling time (15min
    ,..)
UN  #Wait_settling_time_max #Wait_settling_time_max -- Active while it is in the settling time (15min
    ,..)
SPB SEG1

```

//SI no relanzar el timer

SPA END

Segm.: 2 Temperature at point 1

Alarm settings have been defined. A deviation (expressed in %) would be permitted for the temperature T1 and the pressure P1

```

SEG1: L   #DeviationT1          #DeviationT1          -- Deviation of T1 allowed (%)
      L   1.000000e+002
      /R

```

//It is expressed in %, we must divided it

```

L   #T1sat          #T1sat          -- Saturation temperature at P1_set
      *R
T   #ToleranceT1    #ToleranceT1    -- Tolerance of T1

```

//By multiplying the deviation by the value desired we obtain the tolerance

//Tol+Desired value=Max value allowed

```

L   #T1sat          #T1sat          -- Saturation temperature at P1_set
      +R
T   #T1_max         #T1_max         -- Max temperature at point 1 allowed

```

//Desired value- Tol=Min value allowed

```

L   #T1sat          #T1sat          -- Saturation temperature at P1_set
      L   #ToleranceT1    #ToleranceT1    -- Tolerance of T1
      -R
T   #T1_min         #T1_min         -- MIN temperature at point 1 allowed

```

//COMPARATION T1_m>T1_min?

```

L   #T1_m          #T1_m          -- Temperature at point 1, measured
      L   #T1_min         #T1_min         -- MIN temperature at point 1 allowed
      >R
SPB OT1L          //If it is OK RESET its error indicator and check if it is greater than the maximum
SPA ET1L          //If it is lower than the minimum, go to Error T1 Lower (ET1L)

```

//COMPARATION T1_m<T1_max?

```

CT1H: L   #T1_m          //Check if it is greater than the maximum #T1_m          -- Temperature at point 1, measured
      L   #T1_max         #T1_max         -- Max temperature at point 1 allowed
      <R

```

```

SPB  OT1H      //If it is OK (less than maximum)RESET its error indicator AND go to the SEGment2 a
           nd check the pressure 1
SPA  ET1H      //If it is higher than the maximum, go to Error T1 Higher (ET1H)

```

Segm.: 3	Pressure at point 1
----------	---------------------

Alarm settings have been defined. A deviation (expressed in %) would be permitted for P1 .

```

SEG2: L      #DeviationP1          #DeviationP1      -- Deviation of P1 a
           L      1.000000e+002    llowed (%)
           /R

//It is expressed in %, we must divided

           L      #P1_set          #P1_set          -- Set pressure at p
           *R      oint 1
           T      #ToleranceP1     #ToleranceP1     -- Tolerance of P1

//By multiplying the deviation by the value desired we obtain the tolerance

//Tol+Desired value=Max value allowed

           L      #P1_set          #P1_set          -- Set pressure at p
           +R      oint 1
           T      #P1_max          #P1_max          -- Max pressure at p
           oint 1 allowed

////Desired value- Tol=Min value allowed

           L      #P1_set          #P1_set          -- Set pressure at p
           L      #ToleranceT1     #ToleranceT1     -- Tolerance of T1
           -R      oint 1
           T      #P1_min          #P1_min          -- Min pressure at p
           oint 1 allowed

//COMPARATION P1_m>P1_min?

           L      #P1_m            #P1_m            -- Pressure at point
           L      #P1_min          #P1_min            1, measured
           >R      oint 1 allowed
           SPB  OP1L              //If it is OK RESET its error indicator, check if it is greater than the maximum
           SPA  EP1L              //If it is lower than the minimum, go to Error P1 Lower (EP1L)

//COMPARATION T1_m<T1_max?

CP1H: L      #P1_m            #P1_m            -- Pressure at point
           L      #P1_max          #P1_max            1, measured
           <R      oint 1 allowed
           SPB  OP1H              //If it is OK (less than maximum)RESET its error indicator go to the SEGment3 and c
           SPA  EP1H              //If it is higher than the maximum, go to Error P1 Higher (EP1H)
           heck the temperature 2

```

Segm.: 4	Temperature at point 2
----------	------------------------

The temperature T2 has been defined so it has a maximum value allowed

```

//COMPARATION MaxT2>T2_m?
SEG3: L      #MaxT2          #MaxT2          -- Maximum temperature a
           L      #T2_m            #T2_m            llowed at point 2 (^C)
           >R      2, measured      #T2_m            -- Temperature at point
           SPB  OKT2              //If the value measured is lower than the maximum RESET its error indicator, AND then chec
           SPA  ET2              //If the value measured is greater than the maximum, then go to Error T2 (ET2)
           k the pressure 2

```

Segm.: 5	Pressure at point 2
The pressure P2 has been defined so it has a maximum value allowed	

//COMPARATION MaxP2>P2_m?

```

SEG4: L      #MaxP2                #MaxP2                -- Maximum pressure allo
      L      #P2_m                wed at point 2 (bar)
      #P2_m                #P2_m                -- Pressure at point 2 ,
      measured
>R
SPB  OKP2    //If the value measured is lower than the maximum, then check the pressure 2
SPA  EP2     //If the value measured is greater than the maximum, then go to Error T2 (ET2)

```

Segm.: 6	ERRORS
When a variable does not fullfield the conditions then, in this segments, the actions related to its failure are performed.	

```

ET1L: S      #T1_Low  #T1_Low          -- Indicator of T1< T1min->1
      SPA  SEG2
ET1H: S      #T1_High  #T1_High          -- Indicator of T1> T1max->1
      SPA  SEG2
EP1L: S      #P1_Low  #P1_Low          -- Indicator of P1< P1min->1
      SPA  SEG3
EP1H: S      #P1_High  #P1_High          -- Indicator of P1> P1max->1
      SPA  SEG3
ET2:  S      #T2_Error #T2_Error        -- Temperature 2> T2 maximum
      SPA  SEG4
EP2:  S      #P2_Error #P2_Error        -- Pressure 2 > P2 maximum
      SPA  TEST

```

Segm.: 7	OK and TEST
When the measurements are between the limits established, then the indicators must be turn OFF (Green).	

```

OT1L: R      #T1_Low                #T1_Low                -- Indicator of T1<
      SPA  CT1H                    T1min->1
OT1H: R      #T1_High                #T1_High                -- Indicator of T1>
      SPA  SEG2                    T1max->1
OP1L: R      #P1_Low                #P1_Low                -- Indicator of P1<
      SPA  CP1H                    P1min->1
OP1H: R      #P1_High                #P1_High                -- Indicator of P1>
      SPA  SEG3                    P1max->1
OKT2: R      #T2_Error                #T2_Error                -- Temperature 2> T
      SPA  SEG4                    2 maximum
OKP2: R      #P2_Error                #P2_Error                -- Pressure 2 > P2
      SPA  TEST                    maximum

//In the case of the indicators of P1 and T1, wether the error is because of they
//are bellow the minimum or above the maximum the indicator must turn ON (red)
TEST: U      #T1_Low                #T1_Low                -- Indicator of T1<
      O      #T1_High                #T1_High                -- Indicator of T1>
      T1min->1                    T1max->1

```



```

=      #T1_Error                                #T1_Error      -- Temperature 1 is
                                                not between the limits->1

U      #P1_Low                                  #P1_Low        -- Indicator of P1<
                                                Plmin->1
O      #P1_High                                  #P1_High       -- Indicator of P1>
                                                Plmax->1
=      #P1_Error                                  #P1_Error      -- Pressure 1 is n
                                                ot between the limits->1

//ERROR IN POINT 1

U      #P1_Error                                  #P1_Error      -- Pressure 1 is n
                                                ot between the limits->1
O      #T1_Error                                  #T1_Error      -- Temperature 1 is
                                                not between the limits->1
=      #Point1_failure                          #Point1_failure -- Indicates when a
                                                n error has occurred in point 1

//ERROR IN POINT 2

U      #P2_Error                                  #P2_Error      -- Pressure 2 > P2
                                                maximum
O      #T2_Error                                  #T2_Error      -- Temperature 2> T
                                                2 maximum
=      #Point2_failure                          #Point2_failure -- Indicates when a
                                                n error has occurred in point 2

//STABLE?

U      #Stable                                    #Stable        -- Indicates when t
                                                he bench has been stabilized for the f
                                                irst time

SPB   STBL
//If the station has already been stabilized, don' t execute this part of the code

R      #ST                                        #ST            -- Auxiliar variabl
                                                e to increment the counter

UN     #Point1_failure                          #Point1_failure -- Indicates when a
                                                n error has occurred in point 1
UN     #Point2_failure                          #Point2_failure -- Indicates when a
                                                n error has occurred in point 2
=      #ST                                        #ST            -- Auxiliar variabl
                                                e to increment the counter

//As ST has been reset, when it changes its value to 1, (meaning that there is no errors in either of the oper
ating points) the counter increases its value.

U      #ST                                        #ST            -- Auxiliar variabl
                                                e to increment the counter

ZV    Z      0

//If it has reach its maximum load 2 (one is only to indicate when it has been stabilized)
//  L      Z      0
//  L      999
//  ==I
//  SPB   CONT
//  SPA   Z0_1

//CONT: L      C#2
//       S      Z      0

//When it is 1, it means that the station has stabilized, for the first time

L      Z      0
L      1
==I
SPB   STBL          //It is STABLE
R      #Stable      //It is not stable                                #Stable        -- Indicates when t
                                                he bench has been stabilized for the f
                                                irst time

SPA   END

```

Segm.: 8	STABLE station
----------	----------------

```

STBL: S      #Stable                                //In WINCC a message would have to be
                                                shown                                #Stable        -- Indicates whe
                                                n the bench has been stabilized for
                                                the first time

U      #Point2_failure                          #Point2_failure -- Indicates whe
                                                n an error has occurred in point 2

```

```

SPB T_P2
CP1F: U #Point1_failure #Point1_failure -- Indicates whe
n an error has occurred in point 1
SPB T_P1
CALP: U #Failure_time_P1_done #Failure_time_P1_done -- The failur
e in Point 1 has persist the time a
llowed
U #Failure_time_P2_done #Failure_time_P2_done -- The failur
e in Point 2 has persist the time a
llowed
= #Alarm #Alarm -- The bench nee
ds to be stopped, and a signal must
be emitted
SPB ALAR
SPA END

```

```

//When it is stable X_failure=0. So when it changes to 1 (there is an error) the timer starts
//If there is an error, but during a short time then the next time that the error occurs the timer must be r
eset.

```

```

T_P2: U #Point2_failure #Point2_failure -- Indicates whe
n an error has occurred in point 2
FR T 3
U #Point2_failure #Point2_failure -- Indicates whe
n an error has occurred in point 2
L S5T#5S
SE T 3
U T 3
= #Failure_time_P2_done #Failure_time_P2_done -- The failur
e in Point 2 has persist the time a
llowed

SPA CP1F

T_P1: U #Point1_failure #Point1_failure -- Indicates whe
n an error has occurred in point 1
FR T 2
U #Point1_failure #Point1_failure -- Indicates whe
n an error has occurred in point 1
L S5T#10S
SE T 2
U T 2
= #Failure_time_P1_done #Failure_time_P1_done -- The failur
e in Point 1 has persist the time a
llowed

SPA CALP //Check if the alarm (because of the points failure) must be turned ON

```

Segm.: 9	ALARM ACTIONS
----------	---------------

If the "Error" in one of the poins, has remained more than the time fixed, then the bench would have to be turned OFF
--

```

ALAR: S #OFF #OFF -- 1->OFF when an error occurs
R #ON_OFF #ON_OFF -- 0->OFF When an error occurs

```

Segm.: 10	END
-----------	-----

```

END: NOP 0

```

FC5 - <offline>

"AUT_SensON/OFF->th/calc"

Nombre:**Familia:****Autor:****Versión:** 0.1**Versión del bloque:** 2**Hora y fecha Código:**

16/06/2014 09:50:32

Interface:

16/06/2014 09:50:32

Longitud (bloque / código / datos): 04058 03702 00194**Propiedades del objeto:**

S7_language

9(1) Inglés (Estados Unidos) 23/05/2014 13:19:47

Nombre	Tipo de datos	Dirección	Comentario
IN		0.0	
IN_T1	Int	0.0	Analog INPUT of T1
IN_T2	Int	2.0	Analog INPUT of T2
IN_T3	Int	4.0	Analog INPUT of T3
IN_Tin	Int	6.0	Analog INPUT of Tin
IN_Tout	Int	8.0	Analog INPUT of Tout
IN_P1	Int	10.0	Analog INPUT of P1
IN_P2	Int	12.0	Analog INPUT of P2
IN_P3	Int	14.0	Analog INPUT of P3
IN_m_ref	Int	16.0	Analog INPUT of m_ref
IN_m_w	Int	18.0	Analog INPUT of m_w
T1_connected	Bool	20.0	0-> sensor not connected, 1--> sensor connected
T2_connected	Bool	20.1	0-> sensor not connected, 1--> sensor connected
T3_connected	Bool	20.2	0-> sensor not connected, 1--> sensor connected
Tin_connected	Bool	20.3	0-> sensor not connected, 1--> sensor connected
Tout_connected	Bool	20.4	0-> sensor not connected, 1--> sensor connected
P1_connected	Bool	20.5	0-> sensor not connected, 1--> sensor connected
P2_connected	Bool	20.6	0-> sensor not connected, 1--> sensor connected
P3_connected	Bool	20.7	0-> sensor not connected, 1--> sensor connected
m_ref_connected	Bool	21.0	0-> sensor not connected, 1--> sensor connected
m_w_connected	Bool	21.1	0-> sensor not connected, 1--> sensor connected
T1_calc	Real	22.0	Theoretical/set/calculated value of the magnitude
T2_calc	Real	26.0	Theoretical/set/calculated value of the magnitude
T3_calc	Real	30.0	Theoretical/set/calculated value of the magnitude
P3_calc	Real	34.0	Theoretical/set/calculated value of the magnitude->P2
m_ref_calc	Real	38.0	Theoretical/set/calculated value of the magnitude
m_w_calc	Real	42.0	Theoretical/set/calculated value of the magnitude
displ	Real	46.0	Displacement of the compressor
rpm	Real	50.0	rpm of the compressor
Cp_w	Real	54.0	
delta_T_resistance	Real	58.0	Extra temperature degrees to be obtained above the sat. T by the resistance
P1_set	Real	62.0	Set pressured at the operating point 1
c_vol	Real	66.0	Coefficient of the second degree equation to calculate the volumetric eff.
b_iso	Real	70.0	Coefficient of the second degree equation to calculate the isentropic eff.
c_iso	Real	74.0	Coefficient of the second degree equation to calculate the isentropic eff.
a_iso	Real	78.0	Coefficient of the second degree equation to calculate the isentropic eff.
a_vol	Real	82.0	Coefficient of the second degree equation to calculate the volumetric eff.
b_vol	Real	86.0	Coefficient of the second degree equation to calculate the volumetric eff.
Mode_manual_automatic	Bool	90.0	When mode is manual->1, UDT8

Nombre	Tipo de datos	Dirección	Comentario
UDT11_12	Bool	90.1	When it is 1->inputs to the UDT 11, when it is 0->outputs to UDT12
x1	Real	92.0	Quality of the refrigerant, UDT 1
ref_number	Int	96.0	Refrigerant number (0->r134a, 1->r410a, 2->r407c, 3->r22, 4->r290)
rho_water	Real	98.0	
OUT		0.0	
DB_T1	Real	102.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_T3	Real	106.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_P3	Real	110.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_m_ref	Real	114.0	Indicate the direction in which the value (measured/theoretical) must be stored
IN_OUT		0.0	
Tin_chiller	Real	118.0	Tin set by the chiller, theoretically it should be equal to the Tin measured
DB_Tout	Real	122.0	Indicate the direction in which the value (measured/theoretical) must be stored
m_ref_grams	Real	126.0	Refrigerant flux calculated in g/s
flow_w_lit_min	Real	130.0	Water flux calculated in l/min
T2_deseada	Real	134.0	Temperature desired at point 2
m_ref_th	Real	138.0	Refrigerant flux in kg/s
Qcond_necesitado	Real	142.0	Heat exchanged needed in the condenser
m_w_th	Real	146.0	Water flux in kg/s
rend_iso_th	Real	150.0	Isentropic efficiency computed with the second degree equation
PR	Real	154.0	Pressure ratio P2measured/P1 set
rend_vol_th	Real	158.0	Volumetric efficiency computed with the second degree equation
DB_P2	Real	162.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_Tin	Real	166.0	Indicate the direction in which the value (measured/theoretical) must be stored
h1	Real	170.0	Enthalpy at x1 and P1_m
h1_th	Real	174.0	Enthalpy at the desired pressure and quality
h3_th	Real	178.0	Equal to the enthalpy h1_th
h2_th	Real	182.0	Enthalpy at point 2, with the theoretical values
h3_m	Real	186.0	Enthalpy measured (equal to h1)
h2_m	Real	190.0	Enthalpy computed with the data of the sensors
T2sat	Real	194.0	Saturation temperature at pressure P2
m_ref_div_rho	Real	198.0	$m_ref/\rho \rightarrow displ [m^3/rev]*rps [rev/s]*vol_eff$
DB_P1	Real	202.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_m_w	Real	206.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_T2	Real	210.0	Indicate the direction in which the value (measured/theoretical) must be stored
Ref_number_11	Int	214.0	Refrigerant number, UDT 11
P1_m_11	Real	216.0	P1_m, UDT 11
P1_set_11	Real	220.0	P1_set, UDT 11
x1_11	Real	224.0	x1, UDT 11
Tout_m_11	Real	228.0	Tout_m, UDT 11
P2_m_11	Real	232.0	P2_m, UDT 11
delta_T_resistance_11	Real	236.0	delta_T_resistance, UDT 11
m_w_m_11	Real	240.0	m_w_m, UDT 11
m_ref_div_rho_11	Real	244.0	m-ref_div_rho, UDT 11
T2_m_11	Real	248.0	T2_m, UDT 11

Nombre	Tipo de datos	Dirección	Comentario
T1sat_12	Real	252.0	T1_sat,UDT 12
h1_th_12	Real	256.0	h1_th, UDT 12
h1_12	Real	260.0	h1, UDT 12
T2sat_12	Real	264.0	T2sat, UDT 12
h2_th_12	Real	268.0	h2_th,UDT 12
h3_th_12	Real	272.0	h3_th, UDT 12
T2desired_12	Real	276.0	T2desired, UDT 12
rho_ref_12	Real	280.0	rho_ref, UDT 12
h2_m_12	Real	284.0	h2_m, UDT 12
h3_m_12	Real	288.0	h3_m, UDT 12
m_ref_th_12	Real	292.0	m_ref_th, UDT 12
m_ref_grams_12	Real	296.0	m_ref_grams, UDT 12
T1sat	Real	300.0	T1sat, UDT2
T2desired	Real	304.0	Desired temperature after the heating resistance
rho_ref	Real	308.0	Refrigerant density (entering of the compressor)
TEMP		0.0	
delta_T	Real	0.0	Tout-Tin
rps	Real	4.0	rpm/60
rend_div_1000000	Real	8.0	rend_vol/100000
a_vol_X_PR	Real	12.0	
a_iso_X_PR	Real	16.0	
RETURN		0.0	
RET_VAL		0.0	

Bloque: FC5 Measurement of the sensors/calculate the theoretical values

The measurements of the sensors will be conditionate and stored. First the sensors that MUST BE CONECTED would be measured.
 With this measured values, the theoretial ones can be computed.
 Then the progam check wether T1, T2, P3 andm_ref are connected. If they are, it measures their values, otherwise, the thoeretical values calculated are stored.

Segm.: 1 Measurement of the sensors IMPLEMENTED FOR SURE

The data will be measured, conditionate and stored.

The FC 105 "SCALE" takes an input between the Hi and Lo limits, and transforms it in a biolar way (-27.648, +27.648) or unipolar(0,+ 27.648), obtaining an output between K1 and K2 (0,27.648)--> unipolar

//TEMPERATURE T_OUT

```

U      #Tout_connected          #Tout_connected  -- 0-> sensor
                                not connected, 1--> sensor connec
                                ted
SPB   To_M

```

//PRESSURE 1

```

C_P1: U      #P1_connected          #P1_connected    -- 0-> sensor
                                not connected, 1--> sensor connec
                                ted
SPB   M_P1

```

//PRESSURE 2

```

C_P2: U      #P2_connected          #P2_connected    -- 0-> sensor
                                not connected, 1--> sensor connec
                                ted
SPB   M_P2

```

//WATER

```

C_WF: U      #m_w_connected          #m_w_connected   -- 0-> sensor
                                not connected, 1--> sensor connec
                                ted
SPB   W_M

```

//TEMPERATURE 2

```

C_T2: U      #T2_connected          #T2_connected      -- 0-> sensor
                                         not connected, 1--> sensor connec
                                         ted

      SPB   T2_M

      CALL  "Sensor conect/desconect"    FC3
      Sensor_conectado:=#T2_connected    #T2_connected      -- 0-> sensor
                                         not connected, 1--> sensor connec
                                         ted

      Valor_teorico :=#T2_calc           //T2 sat + delta_T    #T2_calc           -- Theoretical
                                         /set/calculated value of the magn
                                         itude

      Valor_a_GUARDAR :=#DB_T2          #DB_T2             -- Indicate th
                                         e direction in which the value (m
                                         easured/theoretical) must be stored

      SPA   SEG2

```

```

//If the sensor T2 is connected, then the value measured (after the aconditionating processs)
//then, it will be stored in the UDT1_1.T2
//If not, the corresponding value of T2sat ( saturation temperature at the pressure P2)
//will be considered as valid, and stored in the UDT

```

//MEASUREMENTS AND SCALING

```

To_M: CALL  "SCALE"                  // Termopar Tout          FC105              -- Scaling Val
                                         ues
      IN      :=#IN_Tout              #IN_Tout           -- Analog INPU
                                         T of Tout

      HI_LIM :=3.000000e+001
      LO_LIM :=5.000000e+000
      BIPOLAR:=FALSE
      RET_VAL:=MW0
      OUT     :=#DB_Tout              #DB Tout          -- Indicate th
                                         e direction in which the value (m
                                         easured/theoretical) must be stored

```

```

//Check the sensor P2
SPA   C_P1

```

```

M_P1: CALL  "SCALE"                  //Presión 1, puesto 1    FC105              -- Scaling Val
                                         ues
      IN      :=#IN_P1                #IN_P1            -- Analog INPU
                                         T of P1

      HI_LIM :=6.000000e+001
      LO_LIM :=1.000000e+000
      BIPOLAR:=FALSE
      RET_VAL:=MW0
      OUT     :=#DB_P1                #DB P1            -- Indicate th
                                         e direction in which the value (m
                                         easured/theoretical) must be stored

```

```

// Check the sensor P2
SPA   C_P2

```

```

M_P2: CALL  "SCALE"                  //Presión 2, puesto 1    FC105              -- Scaling Val
                                         ues
      IN      :=#IN_P2                #IN_P2            -- Analog INPU
                                         T of P2

      HI_LIM :=6.000000e+001
      LO_LIM :=1.000000e+000
      BIPOLAR:=FALSE
      RET_VAL:=MW0
      OUT     :=#DB_P2                #DB_P2            -- Indicate th
                                         e direction in which the value (m
                                         easured/theoretical) must be stored

      SPA   C_WF

```

```

W_M: CALL  "SCALE"                  //m_w_P1,caudal del agua del puesto FC105              -- Scaling Val
                                         1
      IN      :=#IN_m_w                #IN_m_w           -- Analog INPU
                                         T of m_w

      HI_LIM :=5.500000e+001           //lo máximo son 5 l/min, pongo 5,5 l/min
      LO_LIM :=1.000000e-001           //lo mínimo es 0.25 l/min, pongo 0.1 l/min
      BIPOLAR:=FALSE
      RET_VAL:=MW0
      OUT     :=#DB_m_w                #DB_m_w           -- Indicate th
                                         e direction in which the value (m
                                         easured/theoretical) must be stored

      SPA   C_T2

```

```
T2_M: CALL "SCALE" // Measured T2 FC105 -- Scaling Values
      IN :=#IN_T2 #IN_T2 -- Analog INPUT of T2
      HI_LIM :=8.000000e+001
      LO_LIM :=5.000000e+000
      BIPOLAR:=FALSE
      RET_VAL:=MW0
      OUT :=#DB_T2 #DB_T2 -- Indicate the direction in which the value (measured/theoretical) must be stored

SPA SEG2
```

```
Segm.: 2 Volumetric efficiency and m_ref_div_rho
```

```
We calculate the volumetric efficiency and the variable m_ref_div_rho. This last variable only needs to be multiplied by the rho_ref to become the m_ref (kg/s).
```

```
//CALCULATIONS
```

```
// First, we calculate the pressure ratio
```

```
L #DB_P2 #DB_P2 -- Indicate the direction in which the value (measured/theoretical) must be stored
L #P1_set #P1_set -- Set pressure at the operating point 1
/R
T #PR #PR -- Pressure ratio P2measured/P1 set
```

```
//The equations for the efficiencies are second degree equations
//Eff=a·PR^2+ b·PR + c
```

```
//*****//
// VOLUMETRIC EFFICIENCY//
//*****//
```

```
L #PR #PR -- Pressure ratio P2measured/P1 set
L #PR #PR -- Pressure ratio P2measured/P1 set
*R
// PR^2
L #a_vol #a_vol -- Coefficient of the second degree equation to calculate the volumetric eff.
*R
T #a_vol_X_PR #a_vol_X_PR
//a_vol x PR^2
L #b_vol #b_vol -- Coefficient of the second degree equation to calculate the volumetric eff.
L #PR #PR -- Pressure ratio P2measured/P1 set
*R
// b_vol ·PR
L #a_vol_X_PR #a_vol_X_PR
+R
//a_vol x PR^2 + b_vol ·PR
L #c_vol #c_vol -- Coefficient of the second degree equation to calculate the volumetric eff.
+R
T #rend_vol_th #rend_vol_th -- Volumetric efficiency computed with the second degree equation

//Is the result of: a_vol x PR^2 + b_vol ·PR +c_vol
```

```
//*****//
// M_REF_DIV_RHO //
//*****//
```

```
//The operations are performed by "blocks"
// rps //
```

```

L      #rpm                                #rpm                -- rpm of the comp
L      6.000000e+001                       ressor
/R
T      #rps                                #rps                -- rpm/60

//The las "block":  rend_vol_th/1000000

L      #rend_vol_th                        #rend_vol_th       -- Volumetric effi
L      1.000000e+006 //factor de corrección cm^3/m^3        ciency computed with the second degr
/R                                          ee equation
T      #rend_div_1000000                   #rend_div_1000000 -- rend_vol/100000

//We multiply the three "blocks" defined

L      #rps                                #rps                -- rpm/60
*R
L      #displ                              #displ              -- Displacement of
L                                          the compressor
*R
T      #m_ref_div_rho                      #m_ref_div_rho     -- m_ref/rho--> di
L                                          spl [m^3/rev]*rps [rev/s]*vol_eff

```

Segm.: 3	EXCEL INTERFACE
----------	-----------------

To execute the excel interface we first need the isentropic efficiency
--

SEG2: NOP 0

```

//Set the variable, so the inputsthat must be export to the excel file, are copy to the UDT 11
S      #UDT11_12                          #UDT11_12          -- When it is 1->inputs to the UDT 11
L                                          , when it is 0->outputs to UDT12

CALL "Excel_DB"                          FC94
Ref_number                               :=#ref_number      #ref_number        -- Refrigerant number (0->r134a, 1->r
L                                          410a, 2->r407c, 3->r22, 4->r290)
P1_m                                       :=#DB_P1           #DB_P1             -- Indicate the direction in which th
L                                          e value (measured/theoretical) must be stored
P1_set                                     :=#P1_set         #P1_set           -- Set pressured at the operating poi
L                                          nt 1
x1                                          :=#x1             #x1               -- Quality of the refrigerant, UDT 1
L                                          Tout_m           :=#DB_Tout        #DB_Tout          -- Indicate the direction in which th
L                                          e value (measured/theoretical) must be stored
P2_m                                       :=#DB_P2           #DB_P2             -- Indicate the direction in which th
L                                          e value (measured/theoretical) must be stored
delta_T_resistance                       :=#delta_T_resistance #delta_T_resistance -- Extra temperature degrees to be o
L                                          btained above the sat. T by the resistance
m_w_m                                     :=#DB_m_w         #DB_m_w           -- Indicate the direction in which th
L                                          e value (measured/theoretical) must be stored
m_ref_div_rho                            :=#m_ref_div_rho  #m_ref_div_rho    -- m_ref/rho--> displ [m^3/rev]*rps [
L                                          rev/s]*vol_eff
T2_m                                       :=#DB_T2           #DB_T2             -- Indicate the direction in which th
L                                          e value (measured/theoretical) must be stored
T1sat_12                                  :=#T1sat_12      #T1sat_12         -- T1 sat,UDT 12
h1_th_12                                  :=#h1_th_12      #h1_th_12         -- h1_th, UDT 12
h1_12                                     :=#h1_12         #h1_12            -- h1, UDT 12
T2sat_12                                  :=#T2sat_12      #T2sat_12         -- T2sat, UDT 12
h2_th_12                                  :=#h2_th_12      #h2_th_12         -- h2_th,UDT 12
h3_th_12                                  :=#h3_th_12      #h3_th_12         -- h3 th, UDT 12
T2desired_12                              :=#T2desired_12  #T2desired_12    -- T2desired, UDT 12
rho_ref_12                                 :=#rho_ref_12    #rho_ref_12       -- rho_ref, UDT 12
h2_m_12                                    :=#h2_m_12       #h2_m_12          -- h2_m, UDT 12
h3_m_12                                    :=#h3_m_12       #h3_m_12          -- h3_m, UDT 12
m_ref_th_12                                :=#m_ref_th_12   #m_ref_th_12      -- m_ref_th, UDT 12
m_ref_grams_12                             :=#m_ref_grams_12 #m_ref_grams_12  -- m_ref_grams, UDT 12
UDT11_12                                   :=#UDT11_12     #UDT11_12        -- When it is 1->inputs to the UDT 11
L                                          , when it is 0->outputs to UDT12
Ref_number_11                             :=#Ref_number_11 #Ref_number_11    -- Refrigerant number, UDT 11
P1_m_11                                    :=#P1_m_11       #P1_m_11          -- P1_m, UDT 11
P1_set_11                                  :=#P1_set_11     #P1_set_11        -- P1_set, UDT 11
x1_11                                      :=#x1_11         #x1_11            -- x1, UDT 11
Tout_m_11                                  :=#Tout_m_11     #Tout_m_11        -- Tout_m, UDT 11
P2_m_11                                    :=#P2_m_11       #P2_m_11          -- P2_m, UDT 11
delta_T_resistance_11                     :=#delta_T_resistance_11 #delta_T_resistance_11 -- delta_T_resistance, UDT 11
m_w_m_11                                   :=#m_w_m_11      #m_w_m_11         -- m_w_m, UDT 11
m_ref_div_rho_11                           :=#m_ref_div_rho_11 #m_ref_div_rho_11 -- m-ref_div_rho, UDT 11
T2_m_11                                    :=#T2_m_11       #T2_m_11          -- T2_m, UDT 11
T1sat                                       :=#T1sat         #T1sat            -- T1sat, UDT2
h1_th                                       :=#h1_th         #h1_th            -- Enthalpy at the desired pressure a
L                                          nd quality
h1                                          :=#h1            #h1               -- Enthalpy at x1 and P1_m

```



```

T2sat          :=#T2sat          #T2sat          -- Saturation temperature at pressure
h2_th          :=#h2_th          #h2_th          -- Enthalpy at point 2, with the theo
retical values
h3_th          :=#h3_th          #h3_th          -- Equal to the enthalpy h1_th
T2desired     :=#T2desired      #T2desired      -- Desired temperature after the heat
ing resistance
rho_ref        :=#rho_ref        #rho_ref        -- Refrigerant density (entering of t
he compressor)
h2_m           :=#h2_m           #h2_m           -- Enthalpy computed with the data of
the sensors
h3_m           :=#h3_m           #h3_m           -- Enthalpy measured (equal to h1)
m_ref_th       :=#m_ref_th       #m_ref_th       -- Refrigerant flux in kg/s
m_ref_grams    :=#m_ref_grams    #m_ref_grams    -- Refirgerant flux calculated in g/s

/**WITH THE DATA MEASURED WE HAVE TO OBTAIN rho_ref...
//SENT
//-->P1measured,P1_set,x1, P2mesaured,delta_T_resistance,T2desired
//-->Tout measured,T2measured, Refrigerant--> Num_ref(0->134a,1->410a,2->407c, 3->22 , 4->290)
//-->Water flux measured,m_ref_div_rho

//RECEIVE
//--> T1sat, T2 sat
//-->h1_th(P1set,x1),h1(P1,x1), h2_th (P2,T2desired), h3_th (=h1_th),h2_m, h3_m(=h1_m)
//--> rho_ref,m_ref_th (kg/s), m_ref_grams (g/s), T2desired

SPA   SEG3

```

Segm.: 4	Theoretical values
This function to calculate the theoretical values is been summoned with the measured data of P2, Tout. When P1 must be used, the P1 set by the user is the value considered.	

```
SEG3: NOP 0
```

```
//There is no need to calculate it because the desired values in the manual mode are set by the HMI
//and the measured values needed to permormed the PID control have already been measured.
```

```

CALL "OperationCalculation"          FC6
Tout          :=#DB_Tout             #DB_Tout          -- Indicate the direction in which th
e value (measured/theoretical) must be stored
Tin           :=#Tin_chiller          #Tin_chiller      -- Tin set by the chiller, theoretica
lly it should be equal to the Tin measured
rho_ref       :=#rho_ref              #rho_ref          -- Refrigerant density (entering of t
he compressor)
displ         :=#displ                #displ           -- Displacement of the compressor
rpm           :=#rpm                  #rpm             -- rpm of the compressor
h1_th         :=#h1_th                 #h1_th           -- Enthalpy at the desired pressure a
nd quality
h2_th         :=#h2_th                 #h2_th           -- Enthalpy at point 2, with the theo
retical values
Cp_w          :=4.180000e+000
rho_water     :=9.970000e-001
T2sat         :=#T2sat                #T2sat           -- Saturation temperature at pressure
P2            :=#DB_P2                #DB_P2           -- Indicate the direction in which th
e value (measured/theoretical) must be stored
P1_set        :=#P1_set                #P1_set          -- Set pressured at the operating poi
nt 1
c_vol         :=#c_vol                 #c_vol           -- Coefficient of the second degree
equation to calculate the volumetric eff.
b_iso         :=#b_iso                 #b_iso           -- Coefficient of the second degree
equation to calculate the isentropic eff.
c_iso         :=#c_iso                 #c_iso           -- Coefficient of the second degree
equation to calculate the isentropic eff.
a_iso         :=#a_iso                 #a_iso           -- Coefficient of the second degree
equation to calculate the isentropic eff.
a_vol         :=#a_vol                 #a_vol           -- Coefficient of the second degree
equation to calculate the volumetric eff.
b_vol         :=#b_vol                 #b_vol           -- Coefficient of the second degree
equation to calculate the volumetric eff.
Tin_conectado :=#Tin_connected        #Tin_connected    -- 0-> sensor not connected, 1--> sen
sor connected
Tin_chiller   :=#Tin_chiller          #Tin_chiller      -- Tin set by the chiller, theoretica
lly it should be equal to the Tin measured
Mode_manual_automatic:=#Mode_manual_automatic #Mode_manual_automatic -- When mode is manual->1, UDT8
m_ref_grams   :=#m_ref_grams          #m_ref_grams      -- Refirgerant flux calculated in g/s
flow_w_lit_min :=#flow_w_lit_min      #flow_w_lit_min   -- Water flux calculated in l/min
T2_deseada    :=#T2_deseada           #T2_deseada       -- Temperature desired at point 2
m_ref_th      :=#m_ref_th              #m_ref_th         -- Refrigerant flux in kg/s
Qcond_necesitado :=#Qcond_necesitado  #Qcond_necesitado -- Heat exchanged needed in the conde
nser

```

```

m_w_th      :=#m_w_th      #m_w_th      -- Water flux in kg/s
PR          :=#PR          #PR          -- Pressure ratio P2measured/P1 set
rend_vol_th :=#rend_vol_th #rend_vol_th -- Volumetric efficiency computed with
the second degree equation
rend_iso_th :=#rend_iso_th #rend_iso_th -- Isentropic efficiency computed with
the second degree equation

```

```

Segm.: 5      Check and measured the rest of the sensors

```

```

If the rest of the sensors are not connected, the theoretical values
calculated above must be stored.

```

```

//TEMPERATURE 1

```

```

U      #T1_connected      #T1_connected      -- 0-> sensor
not connected, 1--> sensor connected

```

```

SPB    T1_M

```

```

//If the sensor is not connected, we employ de theoretical value
//NO se si esto debería hacerse.Cuando no haya sensor, nos lo incica el X_conectado
//Si no está conecttado en las parametrizado habrá que poner el valor teórico y el "medido"
//Yque el código emplee para los cálculos uno o otro dependiendo del resultado.

```

```

//La gráfica dibuja lo del DB_T1 (medido) si queremos evitar que dibuje el valor teórico cuando no esta conect
ado

```

```

//habria que guardar el teórico en otro lado

```

```

CALL "Sensor conect/desconect"      FC3
Sensor_conectado:=#T1_connected      #T1_connected      -- 0-> senso
r not connected, 1--> sensor co
nected
Valor_teorico    :=#T1_calc          #T1_calc          -- Theoretic
al/set/calculated value of the
magnitude
Valor_a_GUARDAR :=#DB_T1            #DB_T1            -- Indicate
the direction in which the valu
e (measured/theoretical) must be
stored

```

```

//TEMPERATURE 3

```

```

C_T3: U      #T3_connected      #T3_connected      -- 0-> senso
r not connected, 1--> sensor co
nected

```

```

SPB    T3_M

```

```

CALL "Sensor conect/desconect"      FC3
Sensor_conectado:=#T3_connected      #T3_connected      -- 0-> senso
r not connected, 1--> sensor co
nected
Valor_teorico    :=#T3_calc          #T3_calc          -- Theoretic
al/set/calculated value of the
magnitude
Valor_a_GUARDAR :=#DB_T3            #DB_T3            -- Indicate
the direction in which the valu
e (measured/theoretical) must be
stored

```

```

//If the sensor T3 is connected, then the value measured (after the aconditionating processs)
//then, it will be stored in the UDT1_1.T3
//If not, the corresponding value of T2sat ( saturation temperature at the pressure P2=P3)
// will be considered as valid, and stored in the UDT1_T3

```

```

//TEMPERATURE T_IN

```

```

C_Ti: U      #Tin_connected      #Tin_connected      -- 0-> senso
r not connected, 1--> sensor co
nected

```

```

SPB    Ti_M

```

```

//If the sensor is not connected, we employ de theoretical value

```

```

CALL "Sensor conect/desconect"      FC3
Sensor_conectado:=#Tin_connected      #Tin_connected      -- 0-> senso
r not connected, 1--> sensor co
nected
Valor_teorico    :=#Tin_chiller      #Tin_chiller      -- Tin set b
y the chiller, theoretically it
should be equal to the Tin mea
sured
Valor_a_GUARDAR :=#DB_Tin            #DB_Tin            -- Indicate
the direction in which the valu
e (measured/theoretical) must be
stored

```

//PRESSURE 3

C_P3: U #P3_connected

#P3_connected -- 0-> sensor not connected, 1--> sensor connected

SPB M_P3

//If the sensor is not connected, we employ the value of P2 MEASURED

CALL "Sensor conect/desconect"
Sensor_conectado:=#P3_connectedFC3
#P3_connected -- 0-> sensor not connected, 1--> sensor connected

Valor_teorico :=#P3_calc

#P3_calc -- Theoretical/set/calculated value of the magnitude->P2

Valor_a_GUARDAR :=#DB_P3

#DB_P3 -- Indicate the direction in which the value (measured/theoretical) must be stored

// Aunque el sensor nos lo de en kg/s , se está haciendo que esté en un rango de g/s

//REFRIGERANT

C_RF: U #m_ref_connected

#m_ref_connected -- 0-> sensor not connected, 1--> sensor connected

SPB R_M

//If it is not connected

CALL "Sensor conect/desconect"
Sensor_conectado:=#m_ref_connectedFC3
#m_ref_connected -- 0-> sensor not connected, 1--> sensor connected

Valor_teorico :=#m_ref_calc

#m_ref_calc -- Theoretical/set/calculated value of the magnitude

Valor_a_GUARDAR :=#DB_m_ref

#DB_m_ref -- Indicate the direction in which the value (measured/theoretical) must be stored

//We use the theoretical value of m_ref (in grams) as if it was
//the real value measured

SPA SEG5

//IF THE SENSORS ARE CONNECTED//

T1_M: CALL "SCALE" // Measure T1, T1

FC105 -- Scaling Values
#IN_T1 -- Analog IN PUT of T1

IN :=#IN_T1

HI_LIM :=8.000000e+001

LO_LIM :=5.000000e+000

BIPOLAR:=FALSE

RET_VAL:=MW0

OUT :=#DB_T1

#DB_T1 -- Indicate the direction in which the value (measured/theoretical) must be stored

//Go to the comprobation of the sensor T2

SPA C_T3

T3_M: CALL "SCALE" // Termopar 1, T3_P1

FC105 -- Scaling Values
#IN_T3 -- Analog IN PUT of T3

IN :=#IN_T3

HI_LIM :=8.000000e+001

LO_LIM :=5.000000e+000

BIPOLAR:=FALSE

RET_VAL:=MW0

OUT :=#DB_T3

#DB_T3 -- Indicate the direction in which the value (measured/theoretical) must be stored

// Check the sensor Tin

SPA C_Ti

```
Ti_M: CALL "SCALE" // Termopar 1, Tin_P1 FC105 -- Scaling V
      alues
      IN :=#IN_Tin #IN_Tin -- Analog IN
      PUT of Tin
      HI_LIM :=3.000000e+001
      LO_LIM :=5.000000e+000
      BIPOLAR:=FALSE
      RET_VAL:=MW0
      OUT :=#DB_Tin #DB_Tin -- Indicate
      the direction in which the valu
      e (measured/theoretical) must be
      stored
```

```
// Check the sensor P3
SPA C_P3
```

```
M_P3: CALL "SCALE" //Presión 3, puesto 1 FC105 -- Scaling V
      alues
      IN :=#IN_P3 #IN_P3 -- Analog IN
      PUT of P3
      HI_LIM :=6.000000e+001
      LO_LIM :=1.000000e+000
      BIPOLAR:=FALSE
      RET_VAL:=MW0
      OUT :=#DB_P3 #DB_P3 -- Indicate
      the direction in which the valu
      e (measured/theoretical) must be
      stored
```

```
// Check the sensor m_ref
SPA C_RF
```

```
R_M: CALL "SCALE" //m_ref_P1,flujo másico del refri FC105 -- Scaling V
      alues
      IN :=#IN_m_ref #IN_m_ref -- Analog IN
      PUT of m_ref
      HI_LIM :=1.100000e+002 //lo máximo son 100g, pongo 110g
      LO_LIM :=3.500000e+000 // lo mínimo son 5.8g, pongo 3.5g
      BIPOLAR:=FALSE
      RET_VAL:=MW0
      OUT :=#DB_m_ref #DB_m_ref -- Indicate
      the direction in which the valu
      e (measured/theoretical) must be
      stored
```

```
//Check the water flux sensor
```

SPA SEG5

Segm.: 6	EXCEL INTERFACE 2.0
----------	---------------------

h2, h3, rho_w...with the new measurements of the sensors (in case that they have been connected)their values might change

```
SEG5: NOP 0
R #UDT11_12 #UDT11_12 -- When it is 1->inputs to the UDT 11
, when it is 0->outputs to UDT12
CALL "Excel_DB"
Ref_number :=#ref_number #ref_number -- Refrigerant number (0->r134a, 1->r
410a, 2->r407c, 3->r22, 4->r290)
P1_m :=#DB_P1 #DB_P1 -- Indicate the direction in which th
e value (measured/theoretical) must be stored
P1_set :=#P1_set #P1_set -- Set pressured at the operating poi
nt 1
x1 :=#x1 #x1 -- Quality of the refrigerant, UDT 1
Tout_m :=#DB_Tout #DB_Tout -- Indicate the direction in which th
e value (measured/theoretical) must be stored
P2_m :=#DB_P2 #DB_P2 -- Indicate the direction in which th
e value (measured/theoretical) must be stored
delta_T_resistance :=#delta_T_resistance #delta_T_resistance -- Extra temperature degrees to be o
btained above the sat. T by the resistance
m_w_m :=#DB_m_w #DB_m_w -- Indicate the direction in which th
e value (measured/theoretical) must be stored
m_ref_div_rho :=#m_ref_div_rho #m_ref_div_rho -- m_ref/rho--> displ [m^3/rev]*rps [
rev/s]*vol_eff
T2_m :=#DB_T2 #DB_T2 -- Indicate the direction in which th
e value (measured/theoretical) must be stored
T1sat_12 :=#T1sat_12 #T1sat_12 -- T1_sat,UDT 12
h1_th_12 :=#h1_th_12 #h1_th_12 -- h1_th, UDT 12
h1_12 :=#h1_12 #h1_12 -- h1, UDT 12
T2sat_12 :=#T2sat_12 #T2sat_12 -- T2sat, UDT 12
h2_th_12 :=#h2_th_12 #h2_th_12 -- h2_th,UDT 12
h3_th_12 :=#h3_th_12 #h3_th_12 -- h3_th, UDT 12
T2desired_12 :=#T2desired_12 #T2desired_12 -- T2desired, UDT 12
rho_ref_12 :=#rho_ref_12 #rho_ref_12 -- rho_ref, UDT 12
```

```

h2_m_12      :=#h2_m_12      #h2_m_12      -- h2_m, UDT 12
h3_m_12      :=#h3_m_12      #h3_m_12      -- h3_m, UDT 12
m_ref_th_12   :=#m_ref_th_12   #m_ref_th_12   -- m_ref_th, UDT 12
m_ref_grams_12 :=#m_ref_grams_12 #m_ref_grams_12 -- m_ref_grams, UDT 12
UDT11_12     :=#UDT11_12     #UDT11_12     -- When it is 1->inputs to the UDT 11
, when it is 0->outputs to UDT12
Ref_number_11 :=#Ref_number_11 #Ref_number_11 -- Refrigerant number, UDT 11
P1_m_11      :=#P1_m_11      #P1_m_11      -- P1_m, UDT 11
P1_set_11    :=#P1_set_11    #P1_set_11    -- P1_set, UDT 11
x1_11       :=#x1_11       #x1_11       -- x1, UDT 11
Tout_m_11   :=#Tout_m_11   #Tout_m_11   -- Tout_m, UDT 11
P2_m_11     :=#P2_m_11     #P2_m_11     -- P2_m, UDT 11
delta_T_resistance_11 :=#delta_T_resistance_11 #delta_T_resistance_11 -- delta_T_resistance, UDT 11
m_w_m_11    :=#m_w_m_11    #m_w_m_11    -- m_w_m, UDT 11
m_ref_div_rho_11 :=#m_ref_div_rho_11 #m_ref_div_rho_11 -- m-ref_div_rho, UDT 11
T2_m_11     :=#T2_m_11     #T2_m_11     -- T2_m, UDT 11
T1sat       :=#T1sat       #T1sat       -- T1sat, UDT2
h1_th       :=#h1_th       #h1_th       -- Enthalpy at the desired pressure and quality
h1          :=#h1          #h1          -- Enthalpy at x1 and P1_m
T2sat       :=#T2sat       #T2sat       -- Saturation temperature at pressure P2
h2_th       :=#h2_th       #h2_th       -- Enthalpy at point 2, with the theoretical values
h3_th       :=#h3_th       #h3_th       -- Equal to the enthalpy h1_th
T2desired   :=#T2desired   #T2desired   -- Desired temperature after the heating resistance
rho_ref     :=#rho_ref     #rho_ref     -- Refrigerant density (entering of the compressor)
h2_m        :=#h2_m        #h2_m        -- Enthalpy computed with the data of the sensors
h3_m        :=#h3_m        #h3_m        -- Enthalpy measured (equal to h1)
m_ref_th    :=#m_ref_th    #m_ref_th    -- Refrigerant flux in kg/s
m_ref_grams :=#m_ref_grams #m_ref_grams -- Refirgerant flux calculated in g/s

```

```

/**WITH THE DATA MEASURED WE HAVE TO OBTAIN rho_ref...

```

```

//SENT

```

```

//-->T1 measured, P1measured,P1_set,x1, P2mesasured, T2 measured, P3 measured, T3 measured

```

```

//--> Tin_chiller, Tout measured,

```

```

//RECEIVE

```

```

//-->h1_th,h1, h2,h3,rho_ref, rho_water, Cp_w

```

```

SPA SEG6

```

```

Segm.: 7 Theoretical values 2.0

```

```

This function to calculate the theoretical values is been summoned with the measured data of P2, Tout and the possible values measured with the sensors T1, T2, T3, Tin, m_ref, m.w. Those sensors could not be implemented, nevertheless, the calculations of the desired values are done again in case theyaport some neww data.

```

```

//If it is MANUAL don't CALL FC6

```

```

//There is no need to calculate it because the desired values in the manual mode are set by the HMI

```

```

//and the measured values needed to permormed the PID control have already been measured.

```

```

SEG6: U      #Mode_manual_automatic      //"WINCC".UDT8 Manual?      #Mode_manual_automatic --
When mode is manual->1, UDT
T8

SPB END

CALL "OperationCalculation"      FC6
Tout      :=#DB_Tout      #DB_Tout      -- Indi
cate the direction in whic
h the value (measured/theo
rical) must be stored
Tin        :=#DB_Tin      #DB_Tin      -- Indi
cate the direction in whic
h the value (measured/theo
rical) must be stored
rho_ref    :=#rho_ref      #rho_ref      -- Refr
igerant density (entering
of the compressor)
displ      :=#displ      #displ      -- Disp
lacement of the compressor
rpm        :=#rpm        #rpm        -- rpm
of the compressor
h1_th      :=#h1_th      #h1_th      -- Enth
alpy at the desired pressu
re and quality
h2_th      :=#h2_th      #h2_th      -- Enth
alpy at point 2, with the
theoretical values

```

```

Cp_w           :=#Cp_w           #Cp_w
rho_water      :=#rho_water      #rho_water
T2sat          :=#T2sat          #T2sat          -- Satu
                                     ration temperature at pres
                                     sure P2
delta_T_resistance :=#delta_T_resistance #delta_T_resistance -- Ext
                                     ra temperature degrees to
                                     be obtained above the sat.
                                     T by the resistance
P2             :=#DB_P2          #DB_P2          -- Indi
                                     cate the direction in whic
                                     h the value (measured/theo
                                     rical) must be stored
P1_set        :=#P1_set          #P1_set          -- Set
                                     pressured at the operating
                                     point 1
c_vol         :=#c_vol          #c_vol          -- Coef
                                     ficient of the second de
                                     gree equation to calculate
                                     the volumetric eff.
b_iso         :=#b_iso          #b_iso          -- Coef
                                     ficient of the second de
                                     gree equation to calculate
                                     the isentropic eff.
c_iso         :=#c_iso          #c_iso          -- Coef
                                     ficient of the second de
                                     gree equation to calculate
                                     the isentropic eff.
a_iso         :=#a_iso          #a_iso          -- Coef
                                     ficient of the second de
                                     gree equation to calculate
                                     the isentropic eff.
a_vol         :=#a_vol          #a_vol          -- Coef
                                     ficient of the second de
                                     gree equation to calculate
                                     the volumetric eff.
b_vol         :=#b_vol          #b_vol          -- Coef
                                     ficient of the second de
                                     gree equation to calculate
                                     the volumetric eff.
Tin_conectado :=#Tin_connected  #Tin_connected -- 0->
                                     sensor not connected, 1-->
                                     sensor connected
Tin_chiller    :=#Tin_chiller    #Tin_chiller  -- Tin
                                     set by the chiller, theore
                                     tically it should be equal
                                     to the Tin measured
Mode_manual_automatic:=#Mode_manual_automatic #Mode_manual_automatic --
                                     When mode is manual->1, UD
                                     T8
m_ref_grams    :=#m_ref_grams    #m_ref_grams  -- Refi
                                     rgerant flux calculated in
                                     g/s
flow_w_lit_min :=#flow_w_lit_min #flow_w_lit_min -- Wate
                                     r flux calculated in l/min
T2_deseada     :=#T2_deseada     #T2_deseada    -- Temp
                                     erature desired at point 2
m_ref_th       :=#m_ref_th       #m_ref_th     -- Refr
                                     igerant flux in kg/s
Qcond_necesitado :=#Qcond_necesitado #Qcond_necesitado -- Heat
                                     exchanged needed in the c
                                     ondenser
m_w_th         :=#m_w_th         #m_w_th         -- Wate
                                     r flux in kg/s
PR             :=#PR             #PR             -- Pres
                                     sure ratio P2measured/P1 s
                                     et
rend_vol_th    :=#rend_vol_th    #rend_vol_th  -- Volu
                                     metric efficiency computed
                                     with the second degree e
                                     quation
rend_iso_th    :=#rend_iso_th    #rend_iso_th  -- Isen
                                     tropc efficiency computed
                                     with the second degree equ
                                     ation

```

Segm.: 8	END
----------	-----

END segment

END: NOP 0

FC6 - <offline>

"OperationCalculation"

Nombre:**Familia:****Autor:****Versión:** 0.1**Versión del bloque:** 2**Hora y fecha Código:**

13/06/2014 10:06:09

Interface:

03/06/2014 13:00:16

Longitud (bloque / código / datos): 00506 00316 00024**Propiedades del objeto:**

S7_language

9(1) Inglés (Estados Unidos) 23/05/2014 13:19:47

Nombre	Tipo de datos	Dirección	Comentario
IN		0.0	
Tout	Real	0.0	Water output temperaure of the condenser
Tin	Real	4.0	Water input temperature (condenser)
rho_ref	Real	8.0	Refrigerant density (entering of the compressor)
displ	Real	12.0	Displacement of the compressor
rpm	Real	16.0	rpm of the compressor
h1_th	Real	20.0	Enthalpy at the desired pressure and quality
h2_th	Real	24.0	Enthalpy computed with the data of P2 and T2 desired
Cp_w	Real	28.0	
rho_water	Real	32.0	
T2sat	Real	36.0	Saturation temperature at pressure P2
delta_T_resistance	Real	40.0	Extra temperature degrees to be obtained above the sat. T by the resistance
P2	Real	44.0	Pressure at operating point 2 (measured)
P1_set	Real	48.0	Set pressured at the operating point 1
c_vol	Real	52.0	Coefficient of the second degree equation to calculate the volumetric eff.
b_iso	Real	56.0	Coefficient of the second degree equation to calculate the isentropic eff.
c_iso	Real	60.0	Coefficient of the second degree equation to calculate the isentropic eff.
a_iso	Real	64.0	Coefficient of the second degree equation to calculate the isentropic eff.
a_vol	Real	68.0	Coefficient of the second degree equation to calculate the volumetric eff.
b_vol	Real	72.0	Coefficient of the second degree equation to calculate the volumetric eff.
Tin_conectado	Bool	76.0	Indicates if the sensor is connected
Tin_chiller	Real	78.0	The Tin fixed in the chiller
Mode_manual_automatic	Bool	82.0	When the mode is manual=1, automatic=0(UDT8)
OUT		0.0	
m_ref_grams	Real	84.0	Refirgerant flux in g/s
flow_w_lit_min	Real	88.0	Water flux in l/min
T2_deseada	Real	92.0	Temperature desired at point 2
IN_OUT		0.0	
m_ref_th	Real	96.0	Refrigerant flux in kg/s
Qcond_necesitado	Real	100.0	Heat exchanged needed in the condenser
m_w_th	Real	104.0	Water flux in kg/s
PR	Real	108.0	Pressure ratio P2measured/P1 set
rend_vol_th	Real	112.0	Volumetric efficiency computed with the second degree equation
rend_iso_th	Real	116.0	Isentropic efficiency computed with the second degree equation
TEMP		0.0	
a_vol_X_PR	Real	0.0	Intermediate calculation $a_vol \cdot PR^2$
a_iso_X_PR	Real	4.0	Intermediate calculation $a_iso \cdot PR^2$
rho_x_displ	Real	8.0	The result of the multiplication of the ref density and the displacement

Nombre	Tipo de datos	Dirección	Comentario
rps	Real	12.0	rps=rpm/60
rend_div_1000000	Real	16.0	volumetric efficiency/1000000-->Is part of the formula
delta_T	Real	20.0	Tout-Tin
RETURN		0.0	
RET_VAL		0.0	

Bloque: FC6 Operations_Calculations

The math to calculate the flow,etc...are going to be done

These functions are implemented in the EES. However, due to the "difficult" for sequentially calculating program variables and functions in this software will be defined below.

To define them, you will need to have a set of outputs, as enthalpies, densities, ... etc.
If, as suspected, the use of EES is not feasible, we must perform interpolations with data from a database or otherwise with thermodynamic tables.

Segm.: 1 Temperature delta of the condenser

We calculate Tout-Tin and storage it in the auxiliar data bench.

```
//CALCULATIONS
U      #Tin_conectado  #Tin_conectado    -- Indicates if the sensor is connected
SPB    Ti_S

L      #Tout           #Tout             -- Water output temperaure of the condenser
L      #Tin_chiller    #Tin_chiller      -- The Tin fixed in the chiller
-R
T      #delta_T        #delta_T          -- Tout-Tin
NOP    0

Ti_S:  L      #Tout           #Tout             -- Water output temperaure of the condenser
L      #Tin            #Tin              -- Water input temperature (condenser)
-R
T      #delta_T        #delta_T          -- Tout-Tin
NOP    0
```

Segm.: 2 Temperature to be achieve at operating point 2r

With the delta_T_resistance and the saturation temperature at pressure 2, the desired temperature to be obtained can be calculatd.

```
//CALCULATIONS -->done in the excel

L      #T2sat          #T2sat            -- Saturation temperature at pressure P2
L      #delta_T_resistance  #delta_T_resistance -- Extra temperature degrees to be obtained above the sat
.      T by the resistance
+R
T      #T2_deseada     #T2_deseada       -- Temperature desired at point 2
NOP    0
```

Segm.: 3 Pressure ratio and efficiencies

Calculating the pressure ratio, and with the second degree coefficients the efficiencies are defined.

```
//CALCULATIONS

// First, we calculate the pressure ratio

L      #P2             #P2                -- Pressure at operating point 2 (measured)
L      #P1_set         #P1_set             -- Set pressured at the operating point 1
/R
T      #PR             #PR                -- Pressure ratio P2measured/P1 set

//The equations for the efficiencies are second degree equations
//Eff=a·PR^2+ b·PR + c
```

```
//*****//
```

```
// VOLUMETRIC EFFICIENCY//
//*****//

L   #PR          #PR          -- Pressure ratio P2measured/P1 set
L   #PR          #PR          -- Pressure ratio P2measured/P1 set
*R
// PR^2

L   #a_vol       #a_vol       -- Coefficient of the second degree equation to calculate the v
                        olumetric eff.
*R
T   #a_vol_X_PR  #a_vol_X_PR  -- Intermediate calculation a_vol·PR^2

//a_vol x PR^2
L   #b_vol       #b_vol       -- Coefficient of the second degree equation to calculate the v
                        olumetric eff.
L   #PR          #PR          -- Pressure ratio P2measured/P1 set
*R
// b_vol ·PR

L   #a_vol_X_PR  #a_vol_X_PR  -- Intermediate calculation a_vol·PR^2
+R

//a_vol x PR^2 + b_vol ·PR
L   #c_vol       #c_vol       -- Coefficient of the second degree equation to calculate the v
                        olumetric eff.
+R
T   #rend_vol_th #rend_vol_th -- Volumetric efficiency computed with the second degree equatio
                        n
//Is the result of: a_vol x PR^2 + b_vol ·PR +c_vol

//*****//
// ISENTROPIC EFFICIENCY //
//*****//

L   #PR          #PR          -- Pressure ratio P2measured/P1 set
L   #PR          #PR          -- Pressure ratio P2measured/P1 set
*R
// PR^2

L   #a_iso       #a_iso       -- Coefficient of the second degree equation to calculate the i
                        sentropic eff.
*R
T   #a_iso_X_PR  #a_iso_X_PR  -- Intermediate calculation a_iso·PR^2

//a_iso x PR^2
L   #b_iso       #b_iso       -- Coefficient of the second degree equation to calculate the i
                        sentropic eff.
L   #PR          #PR          -- Pressure ratio P2measured/P1 set
*R
// b_iso ·PR

L   #a_iso_X_PR  #a_iso_X_PR  -- Intermediate calculation a_iso·PR^2
+R

//a_iso x PR^2 + b_iso ·PR
L   #c_iso       #c_iso       -- Coefficient of the second degree equation to calculate the i
                        sentropic eff.
+R
T   #rend_iso_th #rend_iso_th -- Isentropic efficiency computed with the second degree equation
//Is the result of: a_iso x PR^2 + b_iso ·PR +c_iso

NOP 0
```

Segm.: 4	Theoretical refrigerant flux
----------	------------------------------

We will employ this value when the coriolis sensor is not connected	
---	--

```
//CALCULATIONS
```

```
//The operations are performed by "blocks"
// rho_ref*displ
```

```
L   #rho_ref          #rho_ref          -- Refrigerant den
                        sity (entering of the compressor)
L   #displ            #displ            -- Displacement of
                        the compressor
*R
T   #rho_x_displ     #rho_x_displ     -- The result of t
                        he multiplication of the ref density
                        and the displacement
```

```
// rps
```

```

L      #rpm                                #rpm                -- rpm of the comp
L      6.000000e+001                       ressor
/R
T      #rps                                #rps                -- rps=rpm/60

//The las "block":  rend_vol_th/1000000

L      #rend_vol_th                        #rend_vol_th       -- Volumetric effi
                                                ciency computed with the second degr
                                                ee equation

L      1.000000e+006      //factor de corrección lit/m^3
/R
T      #rend_div_1000000                   #rend_div_1000000 -- volumetric effi
                                                ciency/1000000-->Is part of the formu
                                                la

//We multiply the three "blocks" defined

L      #rho_x_displ                        #rho_x_displ       -- The result of t
                                                he multiplication of the ref density
                                                and the displacement

L      #rps                                #rps                -- rps=rpm/60
*R
L      #rend_div_1000000                   #rend_div_1000000 -- volumetric effi
                                                ciency/1000000-->Is part of the formu
                                                la

*R
T      #m_ref_th                            #m_ref_th          -- Refrigerant flu
                                                x in kg/s

//The final formula calculated:
//m_ref_th=(rho_ref*displ*rend_vol*rpm)/(60*1000000) --> [kg/s]

//To obtain its value in [g/s]

L      #m_ref_th                            #m_ref_th          -- Refrigerant flu
                                                x in kg/s

L      1.000000e+003      //factor de conversión de kg->g
*R
T      #m_ref_grams                        #m_ref_grams       -- Refirgerant flu
                                                x in g/s

NOP    0

```

Segm.: 5	Heat exchanged in the condenser
----------	---------------------------------

Calculations for obtaining the heat exchanged needed are to be made.	
--	--

```

//THE HEAT EXCHANGE IS CALCULATED WITH H2 TH
//H2 TH HAS BEEN COMPUTED WITH THE T2 DESIRED,THEREFORE THE VALUES CALCULATED WOULD BE
//THE VALUES TO BE ACHIEVE

```

```

L      #h2_th          #h2_th          -- Enthalpy computed with the data of P2 and T2 desired
L      #h1_th          #h1_th          -- Enthalpy at the desired pressure and quality
-R

```

```

//We have calculated h2-h1-> enthalpy difference that
// must be obtained in the condenser

```

```

L      #m_ref_th          #m_ref_th          -- Refrigerant flux in kg/s
*R
T      #Qcond_necesitado #Qcond_necesitado -- Heat exchanged needed in the condenser

```

```

//The result is the corresponding to the formula:
//Qcond_necesitado=m_ref_th*(h2-h1)

```

```

NOP    0

```

Segm.: 6	Water flux needed
----------	-------------------

Knowing the formula, we calculate the kg/s and the lit/min needed.	
--	--

```

//CALCULATIONS

```

```

L      #Qcond_necesitado                   #Qcond_necesitado -- Heat exchanged
                                                needed in the condenser

L      #Cp_w                               #Cp_w
/R

```

```

//Qcond/Cp_w

```

```
L      #delta_T                #delta_T                -- Tout-Tin
/R
T      #m_w_th                  #m_w_th                  -- Water flux in k
                                g/s
```

```
//According to the formula, we have calculated the kg/s
//m_w_th=Qcond_necesitado/(Cp_w*delta_T)->[kg/s]
```

```
//For expresing it in [l/mi]
```

```
L      #m_w_th                #m_w_th                -- Water flux in k
                                g/s
L      #rho_water              #rho_water
/R
```

```
//And we multiplied it for 60*1000 lit->m^3 and seg->min)
```

```
L      6.000000e+004          //cambio de seg-min y de m^3-lit
*R
T      #flow_w_lit_min        #flow_w_lit_min        -- Water flux in l
                                /min
```

```
//We storaged it in flow_w_lit_min
//flow_w_lit_min= m_w_th*60000/rho_water
```

```
NOP 0
```

FC7 - <offline>

"AUT_Control PID"

Nombre:**Familia:****Autor:****Versión:** 0.1**Versión del bloque:** 2**Hora y fecha Código:**

07/06/2014 10:43:59

Interface:

03/06/2014 10:04:35

Longitud (bloque / código / datos): 01222 01086 00022**Propiedades del objeto:**

S7_language

9(1) Inglés (Estados Unidos) 23/05/2014 13:19:47

Nombre	Tipo de datos	Dirección	Comentario
IN		0.0	
P3	Real	0.0	Pressure at operating point 3, REAL
P1_set	Real	4.0	Set pressure at operating point 1,REAL
OFF	Bool	8.0	Indicates if the saturation is OFF (OFF=1)
m_w_th	Real	10.0	Desired water flux , REAL
m_w	Real	14.0	Measured water flux, REAL
T2deseada	Real	18.0	Desired temperature 2, REAL
T2	Real	22.0	Measured temperature 2, REAL
P1	Real	26.0	Measured pressure at the operating point 1, REAL
OUT		0.0	
resistance_relay_dir	Bool	30.0	Direction of the digital output that controls the resistance
Dir_pump	Word	32.0	Direction of the analog output of the pump
Dir_EEV	Word	34.0	Direction of the EEV analog output
IN_OUT		0.0	
orden_EEV	Int	36.0	EEV control signal,INT
orden_pump	Real	38.0	Pump control order, REAL
orden_pump_int	Int	42.0	Pump control order,INT
orden_EEVreal	Real	44.0	EEV control signal, REAL
TEMP		0.0	
delta_Pressure_EEV	Real	0.0	Ratio of pressures
delta_Pword	Word	4.0	Pressure ratio, WORD
delta_P_set_EEV	Real	6.0	Ratio of pressures ,P3 measured/ P1 set, REAL
mw_word	Word	10.0	Measured water flux, WORD
T2word	Word	12.0	Measures temperature 2,WORD
RETURN		0.0	
RET_VAL		0.0	

Bloque: FC7 CONTROL ACTIONS

The output signals would be calculated

Segm.: 1 EEV action

To determine the control action for the EEV, as we know the values of P1 and P3, a proportional order must be employed.
P3/P1 is defines as the signal that would determine the control
The block funstion FB41 is chosen because of iis continuos input and output signals.

//Desired value//

L #P3

#P3 -- Pressure at
operating point 3, REAL

L #P1_set

#P1_set -- Set pressur
e at operating point 1,REAL

/R

```

T      #delta_P_set_EEV                                #delta_P_set_EEV  -- Ratio of p
                                                    pressures ,P3 measured/ P1 set, RE
                                                    AL

//Measured value//

L      #P3                                              #P3                -- Pressure at
                                                    operating point 3, REAL
L      #P1                                              #P1                -- Measured pr
                                                    essure at the operating point 1,
                                                    REAL

/R
T      #delta_Pressure_EEV                             #delta_Pressure_EEV -- Ratio of p
                                                    ressures

//REAL->INT-> WORD actual value of the sensors

CALL  "Real->Int->Word"                                FC2
      valor_REAL:=#delta_Pressure_EEV                 #delta_Pressure_EEV -- Ratio of p
                                                    ressures

      valor_INT :=MW4                                //Not needed
      valor_WORD:=#delta_Pword                       #delta_Pword      -- Pressure ra
                                                    tio, WORD

// PID control

CALL  "CONT_C" , "PID_1"                              FB41 / DB41      -- Continuous
                                                    Control
      COM_RST :=#OFF                                  //When the station is OFF
                                                    #OFF            -- Indicates i
                                                    f the satation is OFF (OFF=1)

      MAN_ON :=FALSE                                  //DESACTIVATE, the manual set value
      PVPER_ON:=TRUE                                  //valor de periferia activada
      P_SEL :=TRUE                                    //acción proporcional
      I_SEL :=TRUE                                    //acción integral activa
      INT_HOLD:=FALSE                                 //congelar la integración
      I_ITL_ON:=#OFF                                  //Indica cuando se reinicia la acci
                                                    ón integral
                                                    #OFF            -- Indicates i
                                                    f the satation is OFF (OFF=1)

      D_SEL :=TRUE                                    //acción derivatiba
      CYCLE :=T#100MS
      SP_INT :=#delta_P_set_EEV                       //consigna interna-->aquí el valor
                                                    deseado
                                                    #delta_P_set_EEV -- Ratio of p
                                                    ressures ,P3 measured/ P1 set, RE
                                                    AL

      PV_IN :=0.000000e+000                          //Una especie de offset entorno al valor real (precision...)
      PV_PER :=#delta_Pword                            // entrada en WORD
                                                    #delta_Pword    -- Pressure ra
                                                    tio, WORD

      MAN :=0.000000e+000                             //Establece un valor de visualización para el HMI, fijas el valor
      GAIN :=2.000000e+000                             //ganancia
      TI :=T#2S
      TD :=T#1S
      TM_LAG :=T#100MS
      DEADB_W :=2.500000e+001                          //está en porcentaje
      LMN_HLM :=1.000000e+002                          //lo máximo que t puedes exceder
      LMN_LLM :=0.000000e+000                          //lo maximo que te puedes quedar por debajo
      PV_FAC :=1.000000e+000                          //medir lo que tenemos
      PV_OFF :=0.000000e+000                          //offset
      LMN_FAC :=1.000000e+000                          //se multiplica por el valor manipulado y sirve para establecer los lí
                                                    mites

      LMN_OFF :=0.000000e+000
      I_ITLVAL:=8.500000e+001                          //porcentaje
      DISV :=0.000000e+000
      LMN :=#orden_EEVreal                             //valor manipulado que actua (REAL)
                                                    #orden_EEVreal -- EEV control
                                                    signal, REAL
      LMN_PER :=#Dir_EEV                               //valor manipulado en la periferia,
                                                    word
                                                    #Dir_EEV       -- Direction o
                                                    f the EEV analog output

      QLMN_HLM:=M4.0
      QLMN_LLM:=M4.0
      LMN_P :=MD4
      LMN_I :=MD4
      LMN_D :=MD4
      PV :=MD4                                          //No interesa
      ER :=MD4

// Storage of the order in the data block DBX0
// REAL-->INT

CALL  "Station1 set"                                  FC10
CALL  "Real->Int->Word"                                FC2
      valor_REAL:=#orden_EEVreal                       #orden_EEVreal  -- EEV control
                                                    signal, REAL
      valor_INT :=#orden_EEV                           #orden_EEV      -- EEV control
                                                    signal,INT
      valor_WORD:=MW4                                  // No interesa su valor

```

Segm.: 2	PUMP action
----------	-------------

A theoretical water flux must be obtained to get the heat exchange needed. The real water flux value must achieve the water flux desired.
--

```
// REAL desired value  m_w_th
```

```
// REAL->INT-> WORD actual sensor value
```

```
CALL "Real->Int->Word"          FC2
  valor_REAL:=#m_w              //valor real medido del sensor    #m_w          -- Measured water
                               r flux, REAL
  valor_INT :=MW4                //guardamos el valor en INT    #mw word      -- Measured water
  valor_WORD:=#mw_word          // Lo pasamos a word              r flux, WORD
```

```
//PID control
```

```
CALL "CONT_C" , "PID_1"        FB41 / DB41      -- Continuous Co
                               ntrol
  COM_RST :=#OFF                #OFF             -- Indicates if
                               the saturation is OFF (OFF=1)
  MAN_ON  :=FALSE                //Introducción manual por HMI desactivada
  PVPER_ON:=TRUE                //Introducción por periféricos ON
  P_SEL   :=TRUE
  I_SEL   :=TRUE
  INT_HOLD:=FALSE
  I_ITL_ON:=#OFF                #OFF             -- Indicates if
                               the saturation is OFF (OFF=1)
  D_SEL   :=TRUE
  CYCLE   :=T#100MS
  SP_INT  :=#m_w_th              //Desired value, REAL    #m_w_th       -- Desired water
                               flux , REAL
  PV_IN   :=0.000000e+000        //offse
  PV_PER  :=#mw_word            //Measured value, WORD   #mw word      -- Measured water
                               r flux, WORD
  MAN     :=0.000000e+000
  GAIN    :=2.000000e+000
  TI      :=T#2S
  TD      :=T#1S
  TM_LAG  :=T#100MS
  DEADB_W :=2.500000e+001        //esta en porcentaje
  LMN_HLM :=1.000000e+002        //100%
  LMN_LLM :=0.000000e+000        //0% (desde el 0% hasta el 100% de lo q he fijado)
  PV_FAC  :=1.000000e+000        // la entrada mutiplicada por "1"
  PV_OFF  :=0.000000e+000        //sin offset
  LMN_FAC :=1.000000e+000        //Ampliamos el valor superior? No, lo multiplicamos por 1m así que se qued
  a en el 100%
  LMN_OFF :=0.000000e+000        //0%
  I_ITLVAL:=8.500000e+001        //Empieza a integrar al 85 % del valor consigna
  DISV    :=0.000000e+000        // acción perturbadora
  LMN     :=#orden_pump          // valor de orden real    #orden_pump   -- Pump control
                               order, REAL
  LMN_PER :=#Dir_pump            #Dir_pump      -- Direction of
                               the analog output of the pump
  QLMN_HLM:=M4.0
  QLMN_LLM:=M4.0
  LMN_P   :=MD4
  LMN_I   :=MD4
  LMN_D   :=MD4
  PV      :=MD4                //no interesa
  ER      :=MD4
```

```
// Storage of the order in the data block DBX0
```

```
// REAL->INT
```

```
CALL "Real->Int->Word"          FC2
  valor_REAL:=#orden_pump        #orden_pump     -- Pump control
                               order, REAL
  valor_INT :=#orden_pump_int    #orden_pump_int -- Pump control
  valor_WORD:=MW4                order,INT
```

Segm.: 3	Heating Resistance control
----------	----------------------------

The PID employed must have a pulse output signal, since the resistance would be controlled by a relay.
--

```
// REAL desired T2deseada

// REAL--> WORD actual sensor value

CALL "Real->Int->Word"
valor_REAL:=#T2 //valor real FC2
//T2 -- Measured te
mperature 2, REAL

valor_INT :=MW4 // guardamos el valor en INT
valor_WORD:=#T2word // Lo pasamos a word #T2word
// Measures te
mperature 2,WORD

// PID control

CALL "CONT_S" , "PID_2" FB42 / DB42 -- Step Contro
l
COM_RST :=#OFF //Indica cuando el puesto está a OF #OFF -- Indicates i
f the satation is OFF (OFF=1)
LMNR_HS :=FALSE // Señal de límite superior
LMNR_LS :=TRUE // el control se enncuentra en su tope inferior
LMNS_ON :=FALSE // Conectar consigna de modo manual nNO,se obtiene del periferico
LMNUP :=TRUE // señal de salida QLMNUP
LMNDN :=FALSE //no se tiene como salida QLMNDN
PVPER_ON:=TRUE // valor de periferia, sensor T2
CYCLE :=T#100MS //Tiempo de muestreo
SP_INT :=#T2deseada //Consigna interna!!T2 deseada #T2deseada
// Desired tem
perature 2, REAL

PV_IN :=0.000000e+000
PV_PER :=#T2word // valor real de entrada en WORD #T2word
// Measures te
mperature 2,WORD

GAIN :=1.000000e+000
TI :=T#2S
DEADB_W :=2.500000e-001 //ancho de zona muerta
PV_FAC :=1.000000e+000 //factor por el que se multiplica la entrada
PV_OFF :=0.000000e+000 //offset de la entrada
PULSE_TM:=T#1S // duración minima de impulso
BREAK_TM:=T#200MS //duración minima depausa
MTR_TM :=T#20S //Tiempo de desplazamiento de tope a tope ¿lo que le cuesta llegar?
DISV :=0.000000e+000 //magnitud perturbadora
QLMNUP :=#resistance_relay_dir //debe activarse el relé de la resi #resistance_relay_dir -- Directio
n of the digital output that cont
rols the resistance
stencia

QLMNDN :=M4.0 //debe desactivarse el relé ??
PV :=MD4 //valor real que actua
ER :=MD4 // diferencia o error de regulación que actúa realmente

//The digital output than controls the realy would be activate
//(and control the resistance) with the parameter
//QLMNU
```


FC8 - <offline>

"STOP_manual&automatic"

Nombre:**Familia:****Autor:****Versión:** 0.1**Versión del bloque:** 2**Hora y fecha Código:**

07/06/2014 10:44:05

Interface:

03/06/2014 17:04:05

Longitud (bloque / código / datos): 01228 01036 00022

Nombre	Tipo de datos	Dirección	Comentario
IN		0.0	
Dir_compressor	Bool	0.0	Digital output of the compressor (Ax.0)
Dir_resistance	Bool	0.1	Digital output of the resistance(Ax.1)
P3	Real	2.0	Measured pressure at the point 3
P1	Real	6.0	Measured pressure at point 1
OFF	Bool	10.0	Station off signal (OFF=1)
Mode_manual_automatic	Bool	10.1	MANUAL=1, AUTOMATIC=0 (UDT8)
Manual_Resistance	Bool	10.2	In manual mode, if the resistance is being tested->1
Manual_EEV	Bool	10.3	In manual mode, if the EEV is being tested->1
Manual_compressor	Bool	10.4	In manual mode,if the compressor is beeing tested->1
Manual_pump	Bool	10.5	In manual mode, if the pump is being tested->1
m_w	Real	12.0	Water flux measured, UDT1, REAL
OUT		0.0	
IN_OUT		0.0	
orden_pump_int	Int	16.0	Pump order, INT (UDT3)
orden_EEVreal	Real	18.0	EEV order, REAL
Dir_pump	Word	22.0	Analog output of the pump ((3+x)28)
Dir_EEV	Word	24.0	Analog output of the EEV ((3+x)24)
orden_EEV	Int	26.0	EEV order, INT
orden_pump_real	Real	28.0	Pump order, REAL
TEMP		0.0	
delta_Pressure_eev	Real	0.0	P3measured/P1 measured, REAL
delta_Pword	Word	4.0	P3 measured/P1 measured, WORD
delta_P_set_EEV	Real	6.0	Desired value of P3/P1=1-->real
Mode_automatic_manual	Bool	10.0	
mw_word	Word	12.0	
Man_compressor_OFF	Bool	14.0	
Man_EEV_OFF	Bool	14.1	
Man_Pump_OFF	Bool	14.2	
Man_Resistance_OFF	Bool	14.3	
OFF_1	Bool	14.4	To make the"OFF" distinctions between the manual mode and the automatic
RETURN		0.0	
RET_VAL		0.0	

Bloque: FC8 STOP_manual&automatic

Stop the station regardless the funtioning mode (Manual or automatic)

Segm.: 1	MANUAL OR AUTOMATIC
----------	---------------------

Depending on the mode selected, there would have different procedures. MANUAL: Each component can be turned off separately AUTOMATIC: All the components should be turned off.
--

```
//If it is set -->manual mode
U      #Mode_manual_automatic          #Mode_manual_automatic -- MANUAL=1,
                                           AUTOMATIC=0 (UDT8)

SPB   MAN

U      #Mode_manual_automatic          #Mode_manual_automatic -- MANUAL=1,
                                           AUTOMATIC=0 (UDT8)

SPBN  AUT

//If it is set in automatic, go to the compressor off segment
//it would keep executing all the segments

AUT:   SPA   C_OF
      SPA   SEG2                      //end, it would continue from C_OF
```

```
//*****//
//MANUAL//
//*****//
```

```
//If it is set in manual then a comprobation should be done to turn off every component individually
```

```
MAN:   UN      #Mode_manual_automatic          #Mode_manual_automatic -- MANUAL=1,
                                           AUTOMATIC=0 (UDT8)
      =      #Mode_automatic_manual          #Mode_automatic_manual

UN      #Manual_compressor                  #Manual_compressor -- In manual mod
                                           e,if the compressor is beeing teste
                                           d->1
      =      #Man_compressor_OFF            #Man_compressor_OFF

UN      #Manual_Resistance                  #Manual_Resistance -- In manual mod
                                           e, if the resistance is being teste
                                           d->1
      =      #Man_Resistance_OFF            #Man_Resistance_OFF

UN      #Manual_pump                        #Manual_pump          -- In manual mod
                                           e, if the pump is being tested->1
      =      #Man_Pump_OFF                  #Man_Pump_OFF

UN      #Manual_EEV                          #Manual_EEV          -- In manual mod
                                           e, if the EEV is being tested->1
      =      #Man_EEV_OFF                  #Man_EEV_OFF

UN      #Manual_compressor                  #Manual_compressor -- In manual mod
                                           e,if the compressor is beeing teste
                                           d->1

SPB   C_OF

COM2:  UN      #Manual_Resistance            #Manual_Resistance -- In manual mod
                                           e, if the resistance is being teste
                                           d->1

      SPB   R_OF

COM3:  UN      #Manual_pump                  #Manual_pump          -- In manual mod
                                           e, if the pump is being tested->1

      SPB   P_OF

COM4:  UN      #Manual_EEV                  #Manual_EEV          -- In manual mod
                                           e, if the EEV is being tested->1

      SPB   E_OF

      NOP   0
```

Segm.: 2	Compresor
----------	-----------

Disconect the compressor abruptly.

```
//Compresor
SEG2:  NOP   0
C_OF:  R      #Dir_compressor              //Compressor OFF
                                           #Dir_compressor  -- Digital output
                                           t of the compressor (Ax.0)

//If it has been set as Manual, we need to check if the rest of components must be turned off
U      #Mode_manual_automatic          #Mode_manual_automatic -- MANUAL=1,
                                           AUTOMATIC=0 (UDT8)

SPB   COM2
```

```
//If it is automatic, it would continue in the next segment
```

Segm.: 3	Resistance
Disconnect the heating resistance	

```
// Resistance
```

```
R_OF: R      #Dir_resistance      //Resistance OFF                #Dir_resistance  -- Digital output
                                         t of the resistance(Ax.1)
```

```
//If it has been set as Manual, we need to check if the rest of components must be turned off
U      #Mode_manual_automatic      #Mode_manual_automatic -- MANUAL=1,
                                         AUTOMATIC=0 (UDT8)
```

```
SPB    COM3
```

```
//If it is automatic, it would continue in the next segment
```

Segm.: 4	PUMP
For the pump, a PID control to turned it off would be performed. The desired value would be water flux=0	

```
//PUMP
```

```
// REAL desired value m_w=0
```

```
// REAL->INT-> WORD actual sensor value
```

```
P_OF: CALL  "Real->Int->Word"          FC2
        valor_REAL:=#m_w              //valor real medido del sensor    #m_w
                                         -- Water flux m
                                         easured, UDT1, REAL
        valor_INT :=MW4                //guardamos el valor en INT
        valor_WORD:=#mw_word          // Lo pasamos a word                #mw_word
```

```
//-----//
// PUMP PID OFF control //
//-----//
```

```
//Change of the "RESET" variable
```

```
U      #Mode_manual_automatic      #Mode_manual_automatic -- MANUAL=1
                                         , AUTOMATIC=0 (UDT8)
```

```
SPB    POFM
```

```
UN     #Mode_manual_automatic      #Mode_manual_automatic -- MANUAL=1
                                         , AUTOMATIC=0 (UDT8)
```

```
SPB    POFA
```

```
//In Manual mode
```

```
POFM: U     #Man_Pump_OFF            #Man_Pump_OFF
        =     #OFF_1                  #OFF_1
                                         -- To make the
                                         OFF" distinctions between the manua
                                         l mode and the automatic
```

```
SPA    PPID
```

```
//Automatic Mode
```

```
POFA: U     #OFF                    #OFF
                                         -- Station off
                                         signal (OFF=1)
        =     #OFF_1                  #OFF_1
                                         -- To make the
                                         OFF" distinctions between the manua
                                         l mode and the automatic
```

```
SPA    PPID
```

```
//Either way, the both paths go to PPID (Pump PID control)
```

```
//-----//
// PUMP PID OFF control //
//-----//
```

```
PPID: CALL  "CONT_C" , "PID_1"          FB41 / DB41
                                         -- Continuous C
                                         ontrol
        COM_RST :=#OFF_1              #OFF_1
                                         -- To make the
                                         OFF" distinctions between the manua
                                         l mode and the automatic
```

```
MAN_ON :=FALSE                        //Introducción manual por HMI desactivada
P_VPER_ON:=TRUE                       //Introducción por periféricos ON
```

```
P_SEL :=TRUE
```

```
I_SEL :=TRUE
```

```
INT_HOLD:=FALSE
```

```
I_ITL_ON:=#OFF
```

```
#OFF
signal (OFF=1)
-- Station off
```

```
D_SEL :=TRUE
```

```
CYCLE :=T#100MS
```

```

SP_INT :=0.000000e+000 //Desired value, REAL -->OFF
PV_IN :=0.000000e+000 //offset
PV_PER :=#mw_word //Measured value, WORD #mw_word
MAN :=0.000000e+000
GAIN :=2.000000e+000
TI :=T#2S
TD :=T#1S
TM_LAG :=T#100MS
DEADB_W :=2.500000e+001 //esta en porcentaje
LMN_HLM :=1.000000e+002 //100%
LMN_LLM :=0.000000e+000 //0% (desde el 0% hasta el 100% de lo q he fijado)
PV_FAC :=1.000000e+000 // la entrada multiplicada por "1"
PV_OFF :=0.000000e+000 //sin offset
LMN_FAC :=1.000000e+000 //Ampliamos el valor superior? No, lo multiplicamos por 1m así que se queda en el 100%

LMN_OFF :=0.000000e+000 //0%
I_ITLVAL:=8.500000e+001 //Empieza a integrar al 85 % del valor consigna
DISV :=0.000000e+000 // acción perturbadora
LMN :=#orden_pump_real // valor de orden real #orden_pump_real -- Pump order, REAL
LMN_PER :=#Dir_pump #Dir_pump -- Analog output of the pump ((3*x)28)

QLMN_HLM:=M4.0
QLMN_LLM:=M4.0
LMN_P :=MD4
LMN_I :=MD4
LMN_D :=MD4
PV :=MD4 //no interesa
ER :=MD4

```

```

// Storage of the order in the data block DBX0
// REAL->INT

```

```

CALL "Real->Int->Word" FC2
valor_REAL:=#orden_pump_real #orden_pump_real -- Pump order, REAL
valor_INT :=#orden_pump_int #orden_pump_int -- Pump order, INT (UDT3)
valor_WORD:=MW4

```

```

//If it has been set as Manual, we need to check if the rest of components must be turned off
U #Mode_manual_automatic #Mode_manual_automatic -- MANUAL=1, AUTOMATIC=0 (UDT8)
SPB COM4

```

```

//If it is automatic, it would continue in the next segment

```

Segm.: 5	EEV
----------	-----

Must be turned off after the pressure has been released. That means that the delta_Pressure-set=P3/P1-->1	
---	--

```

//Desired value delta_P_set_EEV=1
E_OF: L 1.000000e+000
T #delta_P_set_EEV

```

```

#delta_P_set_EEV -- Desired value of P3/P1=1-->real

```

```

//Measured value//

```

```

L #P3 #P3 -- Measured pressure at the point 3
L #P1 #P1 -- Measured pressure at point 1
/R
T #delta_Pressure_eev #delta_Pressure_eev -- P3measured /P1 measured, REAL

```

```

//REAL->INT-> WORD actual value of the sensors

```

```

CALL "Real->Int->Word" FC2
valor_REAL:=#delta_Pressure_eev #delta_Pressure_eev -- P3measured /P1 measured, REAL
valor_INT :=MW4 //Not needed
valor_WORD:=#delta_Pword #delta_Pword -- P3 measured /P1 measured, WORD

```

```

//Change of the "RESET" variable

```

```

U #Mode_manual_automatic #Mode_manual_automatic -- MANUAL=1, AUTOMATIC=0 (UDT8)
SPB EOFM

```

```

UN      #Mode_manual_automatic                                #Mode_manual_automatic -- MANUAL=
SPB     EOFA                                                    1, AUTOMATIC=0 (UDT8)

//Manual Mode
EOFM: U      #Man_Pump_OFF                                     #Man_Pump_OFF
=          #OFF_1                                             #OFF_1           -- To make the
                                                    "OFF" distinctions between the man
                                                    ual mode and the automatic

SPA     EPID

//Automatic mode
EOFA: U      #OFF                                             #OFF             -- Station off
=          #OFF_1                                             #OFF_1          -- To make the
                                                    "OFF" distinctions between the man
                                                    ual mode and the automatic

SPA     EPID

//Either way, both paths leads to the EPID (EEV PID control)

//-----//
// EEV PID OFF control //
//-----//

EPID: CALL "CONT_C" , "PID_1"                                FB41 / DB41      -- Continuous
                                                    Control
COM_RST :=#OFF_1                                           //When the station is OFF
                                                    #OFF_1          -- To make the
                                                    "OFF" distinctions between the man
                                                    ual mode and the automatic

MAN_ON :=FALSE                                             //DEACTIVATE, the manual set value
P_VPER_ON:=TRUE                                           //valor de periferia activada
P_SEL :=TRUE                                               //acción proporcional
I_SEL :=TRUE                                               //acción integral activa
INT_HOLD:=FALSE                                           //congelar la integración
I_ITL_ON:=#OFF                                             //Indica cuando se reinicia la acci
ón integral
                                                    #OFF           -- Station off
                                                    signal (OFF=1)

D_SEL :=TRUE                                               //acción derivatiba
CYCLE :=T#100MS
SP_INT :=#delta_P_set_EEV                                 //consigna interna-->aquí el valor
deseado                                                    #delta_P_set_EEV -- Desired val
ue of P3/P1=1-->real
PV_IN :=0.000000e+000                                     //Una especie de offset entorno al valor real (precision...)
PV_PER :=#delta_Pword                                     // entrada en WORD
                                                    #delta_Pword   -- P3 measured
                                                    /P1 measured, WORD

MAN :=0.000000e+000                                       //Establece un valor de visualización para el HMI, fijas el valor
GAIN :=2.000000e+000                                     //ganancia
TI :=T#2S
TD :=T#1S
TM_LAG :=T#100MS
DEADB_W :=2.500000e+001                                   //está en porcentaje
LMN_HLM :=1.000000e+002                                   //lo máximo que t puedes exceder
LMN_LLM :=0.000000e+000                                   //lo maximo que te puedes quedar por debajo
PV_FAC :=1.000000e+000                                   //medir lo que tenemos
PV_OFF :=0.000000e+000                                   //offset
LMN_FAC :=1.000000e+000                                   //se multiplica por el valor manipulado y sirve para establecer los lí
mites

LMN_OFF :=0.000000e+000
I_ITLVAL:=8.500000e+001                                   //porcentaje
DISV :=0.000000e+000
LMN :=#orden_EEVreal                                     //valor manipulado que actua (REAL)
                                                    #orden_EEVreal -- EEV order,
REAL

LMN_PER :=#Dir_EEV                                       //valor manipulado en la periferia,
word                                                       #Dir_EEV       -- Analog outp
ut of the EEV ((3+x)24)

QLMN_HLM:=M4.0
QLMN_LLM:=M4.0
LMN_P :=MD4
LMN_I :=MD4
LMN_D :=MD4
PV :=MD4
ER :=MD4
                                                    //No interesa

// Storage of the order in the data block DBX0
// REAL-->INT

CALL "Station1_set"                                       FC10
CALL "Real->Int->Word"                                    FC2
valor_REAL:=#orden_EEVreal                               #orden_EEVreal -- EEV order,
REAL
valor_INT :=#orden_EEV                                   #orden_EEV     -- EEV order,
INT
valor_WORD:=MW4                                         // No interesa su valor

NOP 0

```

FC9 - <offline>

"MAN_ControlPID"

Nombre:**Familia:****Autor:****Versión:** 0.1**Versión del bloque:** 2**Hora y fecha Código:**

07/06/2014 10:44:10

Interface:

04/06/2014 20:48:37

Longitud (bloque / código / datos): 02194 02016 00026

Nombre	Tipo de datos	Dirección	Comentario
IN		0.0	
Man_delta_T_res_int	Int	0.0	When manual mode is set, the delta temperature is fixed, INT
Man_delta_P_EEV_int	Int	2.0	Delta P of the EEV in manual mode, INT
Man_WF_pump_int	Int	4.0	Water flux of the pump in manual mode, INT
Man_resistance	Bool	6.0	-->1 Resistance ON
Man_Pump	Bool	6.1	-->1 Pump ON
Man_EEV	Bool	6.2	-->1 EEV ON
Man_Compressor	Bool	6.3	-->1 Compressor ON
T2sat	Real	8.0	Saturation temperature at 2
P1	Real	12.0	Pressure 1 measured
P3	Real	16.0	Pressure 3 measured
m_w_m	Real	20.0	Value measured of the water flux
T2_m	Real	24.0	Temperature at 2 measured
OUT		0.0	
IN_OUT		0.0	
Man_delta_T_res_real	Real	28.0	Delta T of the resistance in manual mode, REAL
Man_delta_P_EEV_real	Real	32.0	Delta P of the EEV in manual mode, REAL
Man_WF_pump_real	Real	36.0	Water flux of the pump in manual mode, REAL
T2deseada	Real	40.0	
Dir_res	Bool	44.0	Direction of the resistance output (A X.1)
Dir_comp	Bool	44.1	Direction of the compressor output (A X.0)
Dir_pump	Word	46.0	Direction of the pump output (PAW (2+x)24)
Dir_EEV	Word	48.0	Direction of the EEV output (PAW (2+x)28)
orden_EEVreal	Real	50.0	EEV order, REAL(UDT5)
Orden_EEV	Int	54.0	EEV order, INT (UDT3)
orden_pump_int	Int	56.0	PUMP order, INT (UDT3)
orden_pump_real	Real	58.0	PUMP order, REAL (UDT5)
TEMP		0.0	
Man_res_OFF	Bool	0.0	
T2word	Word	2.0	
Man_EEV_OFF	Bool	4.0	
delta_P_set_EEV	Real	6.0	
Delta_Pressure_eev	Real	10.0	
delta_Pword	Word	14.0	
mw_word	Word	16.0	
Man_pump_OFF	Bool	18.0	
RETURN		0.0	
RET_VAL		0.0	

Bloque: FC9 PID control in Manual Mode

Each component can be turned ON/OFF individually. Before the PID control is made, it would have to check the state (ON/OFF) of each component.

Segm.: 1	Resistance
If the "Resistance Test Button" has been activated, then according to the delta_T_signal rode (from de HMI interface), a different order would be given.	

```
//Check if the resistance is ON
```

```
UN  #Man_resistance          #Man_resistance  -- -->1 Resistan
=   #Man_res_OFF             ce ON
                                   #Man_res_OFF
U   #Man_resistance          #Man_resistance  -- -->1 Resistan
                                   ce ON
SPB  R_ON
```

```
//*****//
//HEATING RESISTANCE TURN OFF//
//*****//
```

```
R   #Dir_res                 #Dir_res         -- Direction of
SPA  SEG2                    the resistance output (A X.1)
```

```
//*****//
//HEATING RESISTANCE TURN ON CONTROL//
//*****//
```

```
//Delta_T-->INT->DINT->REAL
```

```
R_ON: L   #Man_delta_T_res_int  #Man_delta_T_res_int -- When manual
                                   mode is set, the delta temperature
                                   is fixed, INT
```

```
ITD                                     //INT-->DINT
DTR                                     //DINT-->REAL
T   #Man_delta_T_res_real
```

```
#Man_delta_T_res_real -- Delta T of
the resistance in manual mode, REA
L
```

```
L   #T2sat                    #T2sat            -- Saturation te
                                   mperature at 2
```

```
+R
T   #T2deseada                #T2deseada
```

```
//The temperature to be achievedis the saturatios temperature, plus the delta_res fixed in theHMI
```

```
// REAL--> WORD actual sensor value
```

```
CALL "Real->Int->Word"          FC2
  valor_REAL:=#T2_m             #T2_m            -- Temperature a
                                   t 2 measured
  valor_INT :=MW4
  valor_WORD:=#T2word           #T2word
```

```
//-----//
// PID ON control //
//-----//
```

```
CALL "CONT_S" , "PID 2"        FB42 / DB42      -- Step Control
  COM_RST :=#Man_res_OFF       #Man_res_OFF
                                   //Indica cuando el puesto está a OFF,
                                   cuando se reinicia
  LMNR_HS :=FALSE              //Señal de límite superior
  LMNR_LS :=TRUE               //el control se enncuentra en su tope inferior
  LMNS_ON :=FALSE              //Conectar consigna de modo manual NO,se obtiene del periferico
  LMNUF :=TRUE                 //señal de salida QLMNUP
  LMNDN :=FALSE                //no se tiene como salida QLMNDN
  PVPER_ON:=TRUE               //valor de periferia, sensor T2
  CYCLE :=T#100MS              //Tiempo de muestreo
  SP_INT :=#T2deseada          #T2deseada
  PV_IN :=0.000000e+000
  PV_PER :=#T2word             //valor real de entrada en WORD      #T2word
  GAIN :=1.000000e+000
  TI :=T#2S
  DEADB_W :=2.500000e-001      //ancho de zona muerta
  PV_FAC :=1.000000e+000      //factor por el que se multiplica la entrada
  PV_OFF :=0.000000e+000      //offset de la entrada
  PULSE_TM:=T#1S              //duración minima de impulso
  BREAK_TM:=T#200MS           //duración minima depausa
  MTR_TM :=T#20S               //Tiempo de desplazamiento de tope a tope ¿lo que le cuesta llegar?
  DISV :=0.000000e+000        //magnitud perturbadora
  QLMNUP :=#Dir_res            //debe activarse el relé de la resist #Dir_res -- Direction of
                                   encia the resistance output (A X.1)
  QLMNDN :=M4.0                //debe desactivarse el relé ??
  PV :=MD4                      //valor real que actua
  ER :=MD4                      //diferencia o error de regulación que actúa realmente
```

```
//The digital output than controls the really would be activate
//(and control the resistance) with the parameter
//QLMNUP= A X.1
```

```
NOP 0
```

```
Segm.: 2 EEV
```

```
If the "EEV Test Button" has been activated, then according to the
delta_P_signal rode (from de HMI interface), a different order would be given.
```

```
//4-20 mA
```

```
//Check if the EEV is ON (being tested) then the signal rode from de HMI must be converted in 4-20 mA
```

```
SEG2: U      #Man_EEV                      #Man_EEV          -- -->1 EEV ON
      SPB    E_ON
```

```
//If it is OFF, no signal shoud be emited --> GRADUALLY
```

```
//*****//
//EEV TURN OFF CONTROL//
//*****//
```

```
UN      #Man_EEV                      //Manual mode, EEV ON_OFF (ON=1, O #Man_EEV          -- -->1 EEV ON
      =      #Man_EEV_OFF              //Manual mode,EEV OFF (OFF=1, ON=0) #Man_EEV_OFF
```

```
//Desired value: delta_P_set_EEV=1
```

```
//That means that P3=P1, it is open, so there is no pressure difference
```

```
L      1.000000e+000
T      #delta_P_set_EEV                      #delta_P_set_EEV
```

```
//Measured value//
```

```
L      #P3                                #P3                -- Pressure 3
                                          measured
L      #P1                                #P1                -- Pressure 1
                                          measured
/R
T      #Delta_Pressure_eev                #Delta_Pressure_eev
```

```
//REAL->INT-> WORD actual value of the sensors
```

```
CALL "Real->Int->Word"                    FC2
      valor_REAL:=#Delta_Pressure_eev      #Delta_Pressure_eev
      valor_INT :=MW4                      //Not needed
      valor_WORD:=#delta_Pword            #delta_Pword
```

```
//-----//
// EEV PID OFF control //
//-----//
```

```
CALL "CONT_C" , "PID_1"                  FB41 / DB41        -- Continuous
                                          Control
COM_RST :=#Man_EEV_OFF                    //When the station is OFF      #Man_EEV_OFF
MAN_ON  :=FALSE                            //DEACTIVATE, the manual set value
PVPER_ON:=TRUE                             //valor de periferia activada
P_SEL   :=TRUE                             //acción proporcional
I_SEL   :=TRUE                             //acción integral activa
INT_HOLD:=FALSE                            //congelar la integración
I_ITL_ON:=#Man_EEV_OFF                    //Indica cuando se reinicia la acci #Man_EEV_OFF
ón integral
D_SEL   :=TRUE                             //acción derivatiba
CYCLE   :=T#100MS
SP_INT  :=#delta_P_set_EEV                 //consigna interna-->aqui el valor #delta_P_set_EEV
deseado
PV_IN   :=0.000000e+000                    //Una especie de offset entorno al valor real (precision...)
PV_PER  :=#delta_Pword                      // entrada en WORD              #delta_Pword
MAN     :=0.000000e+000                    //Establece un valor de visualización para el HMI, fijas el valor
GAIN    :=2.000000e+000                    //ganancia
TI      :=T#2S
TD      :=T#1S
TM_LAG  :=T#100MS
DEADB_W :=2.500000e+001                    //está en porcentaje
LMN_HLM :=1.000000e+002                    //lo máximo que t puedes exceder
LMN_LLM :=0.000000e+000                    //lo maximo que te puedes quedar por debajo
PV_FAC  :=1.000000e+000                    //medir lo que tenemos
PV_OFF  :=0.000000e+000                    //offset
```



```

LMN_FAC :=1.000000e+000 //se multiplica por el valor manipulado y sirve para establecer los límites
LMN_OFF :=0.000000e+000
I_ITLVAL:=8.500000e+001 //porcentaje
DISV :=0.000000e+000
LMN :=#orden_EEVreal //valor manipulado que actua (REAL) #orden_EEVreal -- EEV order, REAL(UDT5)
LMN_PER :=#Dir_EEV //valor manipulado en la periferia, #Dir_EEV -- Direction of the EEV output (PAW (2+x)28) word
QLMN_HLM:=M4.0
QLMN_LLM:=M4.0
LMN_P :=MD4
LMN_I :=MD4
LMN_D :=MD4
PV :=MD4 //No interesa
ER :=MD4

// Storage of the order in the data block DBX0
// REAL-->INT

CALL "Station1_set" FC10
CALL "Real->Int->Word" FC2
valor_REAL:=#orden_EEVreal //UDT5 #orden_EEVreal -- EEV order, REAL(UDT5)
valor_INT :=#Orden_EEV //UDT3 #Orden_EEV -- EEV order, INT (UDT3)
valor_WORD:=MW4

SPA SEG3

//*****//
//EEV TURN ON CONTROL//
//*****//

//If it is ON, the value of the variable set in the HMI should be read and scaled, to be transfered to its analog output direction

//ESTO ES LO QUE HABÍA HECHO ANTES, PONER UNA SALIDA PROPORCIONAL A UNA VARIABLE FIJADA EN EL HMI
// CALL "SCALE"
// IN :=#Man_delta_P_EEV_int
// HI_LIM :=2.000000e-002
// LO_LIM :=4.000000e-003
// BIPOLAR:=FALSE
// RET_VAL:=MW0
// OUT :=#Man_delta_P_EEV_real

// L #Man_delta_P_EEV_real
// RND
// T #Dir_EEV

//-----//
// EEV PID ON control //
//-----//

//Desired value--> Man_delta_p_eev_int=P2/P1
//#Man_delta_P_EEV_int--> Fixed in WINCC

E_ON: L #Man_delta_P_EEV_int #Man_delta_P_EEV_int -- Delta P of the EEV in manual mode, INT
ITD //INT-->DINT
DTR //DINT-->REAL
T #delta_P_set_EEV #delta_P_set_EEV

//Measured value//

L #P3 #P3 -- Pressure 3 measured
L #P1 #P1 -- Pressure 1 measured
/R
T #Delta_Pressure_eev #Delta_Pressure_eev

//REAL->INT-> WORD actual value of the sensors

CALL "Real->Int->Word" FC2
valor_REAL:=#Delta_Pressure_eev #Delta_Pressure_eev
valor_INT :=MW4 //Not needed
valor_WORD:=#delta_Pword #delta_Pword

//-----//

```

```
// EEV PID ON control//
//-----//

CALL "CONT_C" , "PID_1"                                FB41 / DB41      -- Continuous
                                                         Control
COM_RST :=#Man_EEV                                    //When the EEV has to be tested   #Man_EEV        -- -->1 EEV ON
MAN_ON :=FALSE                                        //DESACTIVATE, the manual set value
PVPER_ON:=TRUE                                       //valor de periferia activada
P_SEL :=TRUE                                         //acción proporcional
I_SEL :=TRUE                                         //acción integral activa
INT_HOLD:=FALSE                                      //congelar la integración
I_ITL_ON:=#Man_EEV                                  //Indica cuando se reinicia la acci #Man_EEV        -- -->1 EEV ON
                                                         ón integral
D_SEL :=TRUE                                         //acción derivatiba
CYCLE :=T#100MS
SP_INT :=#delta_P_set_EEV                            //consigna interna-->aquí el valor #delta_P_set_EEV
                                                         deseado
PV_IN :=0.000000e+000                                //Una especie de offset entorno al valor real (precision...)
PV_PER :=#delta_Pword                                 // entrada en WORD #delta_Pword
MAN :=0.000000e+000                                  //Establece un valor de visualización para el HMI, fijas el valor
GAIN :=2.000000e+000                                 //ganancia
TI :=T#2S
TD :=T#1S
TM_LAG :=T#100MS
DEADB_W :=2.500000e+001                              //está en porcentaje
LMN_HLM :=1.000000e+002                              //lo máximo que t puedes exceder
LMN_LLM :=0.000000e+000                              //lo maximo que te puedes quedar por debajo
PV_FAC :=1.000000e+000                              //medir lo que tenemos
PV_OFF :=0.000000e+000                              //offset
LMN_FAC :=1.000000e+000                              //se multiplica por el valor manipulado y sirve para establecer los lí
                                                         mites
LMN_OFF :=0.000000e+000
I_ITLVAL:=8.500000e+001                              //porcentaje
DISV :=0.000000e+000
LMN :=#orden_EEVreal                                //valor manipulado que actua (REAL) #orden_EEVreal -- EEV order,
                                                         REAL(UDT5)
LMN_PER :=#Dir_EEV                                  //valor manipulado en la periferia, #Dir_EEV        -- Direction o
                                                         f the EEV output (PAW (2+x)28)
QLMN_HLM:=M4.0
QLMN_LLM:=M4.0
LMN_P :=MD4
LMN_I :=MD4
LMN_D :=MD4
PV :=MD4                                             //No interesa
ER :=MD4

// Storage of the order in the data block DBX0
// REAL-->INT

CALL "Station1_set"                                  FC10
CALL "Real->Int->Word"                               FC2
valor_REAL:=#orden_EEVreal                          #orden_EEVreal -- EEV order,
                                                         REAL(UDT5)
valor_INT :=#Orden_EEV                              #Orden_EEV     -- EEV order,
                                                         INT (UDT3)
valor_WORD:=MW4                                     // No interesa su valor

NOP 0
```

Segm.: 3	Pump
If the "Pump Test Button" has been activated, then according to the WF_signal rode (from de HMI interface), a different order would be given.	

```
//0-10 V

SEG3: U #Man_Pump #Man_Pump -- -->1 Pump ON
      SPB P_ON

//*****//
// PUMP TURNED OFF //
//*****//

UN #Man_Pump #Man_Pump -- -->1 Pump ON
 = #Man_pump_OFF #Man_pump_OFF

// REAL desired value m_w=0

// REAL->INT-> WORD actual sensor value

CALL "Real->Int->Word"                               FC2
valor_REAL:=#m_w_m                                  //valor real medido del sensor #m_w_m        -- Value measur
                                                         ed of the water flux
valor_INT :=MW4                                     //guardamos el valor en INT
valor_WORD:=#mw_word                                // Lo pasamos a word #mw_word
```

```

//-----//
// PUMP PID OFF control //
//-----//

CALL "CONT_C" , "PID_1"                                FB41 / DB41      -- Continuous C
                                                         ontrol
                                                         #Man_pump_OFF

COM_RST :=#Man_pump_OFF
MAN_ON  :=FALSE                                       //Introducción manual por HMI desactivada
PVPER_ON:=TRUE                                        //Introducción por periféricos ON
P_SEL   :=TRUE
I_SEL   :=TRUE
INT_HOLD:=FALSE
I_ITL_ON:=#Man_pump_OFF                              #Man_pump_OFF
D_SEL   :=TRUE
CYCLE   :=T#100MS
SP_INT  :=0.000000e+000                              //Desired value, REAL -->OFF
PV_IN   :=0.000000e+000                              //offset
PV_PER  :=#mw word                                    //Measured value, WORD          #mw_word
MAN     :=0.000000e+000
GAIN    :=2.000000e+000
TI      :=T#2S
TD      :=T#1S
TM_LAG  :=T#100MS
DEADB_W :=2.500000e+001                              //esta en porcentaje
LMN_HLM :=1.000000e+002                              //100%
LMN_LLM :=0.000000e+000                              //0% (desde el 0% hasta el 100% de lo q he fijado)
PV_FAC  :=1.000000e+000                              // la entrada mutiplicada por "1"
PV_OFF  :=0.000000e+000                              //sin offset
LMN_FAC :=1.000000e+000                              //Ampliamos el valor superior? No, lo multiplicamos por 1m asi que se que
                                                         da en el 100%
LMN_OFF :=0.000000e+000                              //0%
I_ITLVAL:=8.500000e+001                              //Empieza a integrar al 85 % del valor consigna
DISV    :=0.000000e+000                              // acción perturbadora
LMN     :=#orden_pump_real                            // valor de orden real          #orden_pump_real  -- PUMP order,
                                                         REAL (UDT5)
LMN_PER :=#Dir_pump                                   #Dir_pump        -- Direction of
                                                         the pump output (PAW (2+x)24)

QLMN_HLM:=M4.0
QLMN_LLM:=M4.0
LMN_P   :=MD4
LMN_I   :=MD4
LMN_D   :=MD4
PV      :=MD4                                       //no interesa
ER      :=MD4

// Storage of the order in the data block DBX0
// REAL->INT

CALL "Real->Int->Word"                                FC2
valor_REAL:=#orden_pump_real                          #orden_pump_real  -- PUMP order,
                                                         REAL (UDT5)
valor_INT :=#orden_pump_int                            #orden_pump_int   -- PUMP order,
                                                         INT (UDT3)
valor_WORD:=MW4

SPA    SEG4

//*****//
// PUMP TURNED ON //
//*****//

//If it is ON, the value of the variable set in the HMI should be read and scaled, to be transfered to its ana
log output direction

//SE HABIA HECHO ANTES
//CALL "SCALE"
//   IN      :=#Man_WF_pump_int
//   HI_LIM :=1.000000e+001
//   LO_LIM :=0.000000e+000
//   BIPOLAR:=FALSE
//   RET_VAL:=MW0
//   OUT     :=#Man_WF_pump_real

//   L      #Man_WF_pump_real
//   RND
//   T      #Dir_pump

// REAL desired value : Man_WF_pump_real (UDT3)
// REAL->INT-> WORD actual sensor value

P_ON: CALL "Real->Int->Word"                          FC2
valor_REAL:=#m_w_m                                    //valor real medido del sensor  #m_w_m          -- Value measur
                                                         ed of the water flux
valor_INT :=MW4                                       //guardamos el valor en INT

```

```

valor_WORD:=#mw_word          // Lo pasamos a word          #mw_word

//-----//
// Pump PID ON control //
//-----//

CALL "CONT_C" , "PID_1"          FB41 / DB41          -- Continuous C
                                ontrol
                                #Man_Pump          -- -->1 Pump ON

COM_RST :=#Man_Pump
MAN_ON :=FALSE                  //Introducción manual por HMI desactivada
P_VPER_ON:=TRUE                 //Introducción por periféricos ON
P_SEL :=TRUE
I_SEL :=TRUE
INT_HOLD:=FALSE
I_ITL_ON:=#Man_Pump            #Man_Pump          -- -->1 Pump ON
D_SEL :=TRUE
CYCLE :=T#100MS
SP_INT :=#Man_WF_pump_real     //Desired value, REAL          #Man_WF_pump_real -- Water flux o
                                f the pump in manual mode, REAL

PV_IN :=0.000000e+000          //offse
PV_PER :=#mw_word              //Measured value, WORD          #mw_word
MAN :=0.000000e+000
GAIN :=2.000000e+000
TI :=T#2S
TD :=T#1S
TM_LAG :=T#100MS
DEADB_W :=2.500000e+001         //esta en porcentaje
LMN_HLM :=1.000000e+002         //100%
LMN_LLM :=0.000000e+000         //0% (desde el 0% hasta el 100% de lo q he fijado)
PV_FAC :=1.000000e+000         // la entrada mutiplicada por "1"
PV_OFF :=0.000000e+000         //sin offset
LMN_FAC :=1.000000e+000         //Ampliamos el valor superior? No, lo multiplicamos por lm así que se que
                                da en el 100%
LMN_OFF :=0.000000e+000         //0%
I_ITLVAL:=8.500000e+001         //Empieza a integrar al 85 % del valor consigna
DISV :=0.000000e+000          // acción perturbadora
LMN :=#orden_pump_real         // valor de orden real          #orden_pump_real -- PUMP order,
                                REAL (UDT5)
LMN_PER :=#Dir_pump            #Dir_pump          -- Direction of
                                the pump output (PAW (2+x)24)

QLMN_HLM:=M4.0
QLMN_LLM:=M4.0
LMN_P :=MD4
LMN_I :=MD4
LMN_D :=MD4
PV :=MD4                       //no interesa
ER :=MD4

// Storage of the order in the data block DBX0
// REAL->INT

CALL "Real->Int->Word"          FC2
valor_REAL:=#orden_pump_real   #orden_pump_real -- PUMP order,
                                REAL (UDT5)
valor_INT :=#orden_pump_int    #orden_pump_int -- PUMP order,
                                INT (UDT3)
valor_WORD:=MW4

```

Segm.: 4	Compressor
----------	------------

If the "Compressor Test Button" has been activated, then according to the compressor_signal rode (from de HMI interface), a different order would be given.

```

SEG4: U      #Man_Compressor  #Man_Compressor  -- -->1 Compressor ON
        SPB      C_ON

//*****//
//Compressor OFF, its digital output has been deactivated
//*****//

        R      #Dir_comp      #Dir_comp      -- Direction of the compressor output (A X.0)
        SPA      END

//*****//
//Compressor ON, its digital output has been activated
//*****//

C_ON: S      #Dir_comp      #Dir_comp      -- Direction of the compressor output (A X.0)

END: NOP 0

```

FC10 - <offline>

"Station1_set"

Nombre: **Familia:**
Autor: **Versión:** 0.1
Versión del bloque: 2
Hora y fecha Código: 16/06/2014 10:12:51
Interface: 23/05/2014 12:54:00
Longitud (bloque / código / datos): 03706 03584 00290

Propiedades del objeto:

S7_language 9(1) Inglés (Estados Unidos) 23/05/2014 13:19:47

Nombre	Tipo de datos	Dirección	Comentario
IN		0.0	
OUT		0.0	
IN_OUT		0.0	
TEMP		0.0	
RETURN		0.0	
RET_VAL		0.0	

Bloque: FC10 STATION 1

Within the followings "segments", the subroutines needed to performed the measurement of the sensors, the conditionate of the signals, the control,...of the station 1, will be summoned.

Segm.: 1 MODE: ¿AUTOMATIC OR MANUAL??

The test bench has two different working modes. It would be defined by the variable Mode_manual_automatic (by the HMI).

// Wincc changes the value of Mode_manual_automatic (1-> manual, 0->automatic)
 // the variable mode_automatic_manual is the oppostite

```

UN   "Puestos1".UDT8_1.Mode_manual_automatic  DB10.DBX358.5    -- It determine wehter the cycle works
                                         automatically (0) or in a manual way (1)

=    "Puestos1".UDT8_1.Mode_Automatic_Manual  DB10.DBX358.0    -- It determine wehter the cycle works
                                         automatically (1) or in a manual way (0)
  
```

//If the automatic mode has benn choosen, then we go to the "AUT" (it stands for //automatic) part of the program.

```

U    "Puestos1".UDT8_1.Mode_Automatic_Manual  DB10.DBX358.0    -- It determine wehter the cycle works
                                         automatically (1) or in a manual way (0)
SPB  AUT

U    "Puestos1".UDT8_1.Mode_manual_automatic  DB10.DBX358.5    -- It determine wehter the cycle works
                                         automatically (0) or in a manual way (1)
SPB  MAN
  
```

Segm.: 2 STATION AUTOMATIC. ¿ON/OFF?

If the station is set, and the AUTOMATIC mode has been chosen, then the program must check if the "ON" button is activated (values of the sensors and the automatic settings must be read, calculations should be made and the components must be controled and activated).

//First RESET the variables that indicate the "ON" state of the components , when the station is beeing checke d (MANUAL MODE)

```

AUT:  R    "Puestos1".UDT8_1.Manual_resistance  DB10.DBX358.2    -- Test the cor
                                         rect functioning of the resistance
      R    "Puestos1".UDT8_1.Manual_EEV        DB10.DBX358.3    -- test the cor
                                         rect funtioning of the EEV
      R    "Puestos1".UDT8_1.Manual_Pump       DB10.DBX358.4    -- Test the cor
                                         rect functioning of the pump
      R    "Puestos1".UDT8_1.Manual_compressor DB10.DBX358.1    -- Test the cor
                                         rect functioning of the compressor
                                         in the manual mode
  
```

```
//Check if the STATION is AUTOMATIC and ON, or AUTOMATIC and OFF
```

```
U "Puestos1".UDT4_1.ON_OFF
```

```
DB10.DBX235.4 -- Indicates if  
the station is ON (ON=1, OFF=0)
```

```
SPB A_ON  
SPA A_OF
```

```
// _____ //  
// AUTOMATIC ON //  
// _____ //
```

```
A_ON: CALL "Station_AUT_ON"
```

```
UDT11_12 := "Puestos1".UDT10_1.UDT11_12
```

```
FC97
```

```
DB10.DBX389.2 -- 1-->import t  
he data to UDT11, 0--> save the ex  
port data in UDT 12
```

```
x1 := "Puestos1".UDT1_1.x1  
ref_number := "Puestos1".UDT1_1.Ref_number
```

```
DB10.DBD0 -- Quality  
DB10.DBW52 -- 0->R134A , 1  
->R410A, 2->R407C, 3->R22
```

```
IN_T1 := EW300
```

```
IN_T2 := EW302
```

```
IN_T3 := EW304
```

```
IN_Tin := EW306
```

```
IN_Tout := EW308
```

```
IN_P1 := EW312
```

```
IN_P2 := EW314
```

```
IN_P3 := EW316
```

```
IN_m_ref := EW320
```

```
IN_m_w := EW322
```

```
T1_connected := "Puestos1".UDT4_1.T1_conectado
```

```
DB10.DBX234.1 -- Indicates th  
e connection state of the sensor T  
1
```

```
T2_connected := "Puestos1".UDT4_1.T2_conectado
```

```
DB10.DBX234.3 -- Indicates th  
e connection state of the sensor T  
2
```

```
T3_connected := "Puestos1".UDT4_1.T3_conectado
```

```
DB10.DBX234.5 -- Indicates th  
e connection state of the sensor T  
3
```

```
Tin_connected := "Puestos1".UDT4_1.Tin_conectado
```

```
DB10.DBX234.7 -- Indicates th  
e connection state of the sensor T  
in
```

```
Tout_connected := "Puestos1".UDT4_1.Tout_conectado
```

```
DB10.DBX235.0 -- Indicates th  
e connection state of the sensor T  
out
```

```
P1_connected := "Puestos1".UDT4_1.P1_conectado
```

```
DB10.DBX234.2 -- Indicates th  
e connection state of the sensor P  
1
```

```
P2_connected := "Puestos1".UDT4_1.P2_conectado
```

```
DB10.DBX234.4 -- Indicates th  
e connection state of the sensor P  
2
```

```
P3_connected := "Puestos1".UDT4_1.P3_conectado
```

```
DB10.DBX234.6 -- Indicates th  
e connection state of the sensor P  
3
```

```
m_ref_connected := "Puestos1".UDT4_1.m_ref_conectado
```

```
DB10.DBX235.3 -- Indicates th  
e connection state of the sensor m  
_ref
```

```
m_w_connected := "Puestos1".UDT4_1.Qw_conectado
```

```
DB10.DBX235.1 -- Indicates th  
e connection state of the sensor Q  
w
```

```
T1_calc := "Puestos1".UDT2_1.T1sat
```

```
DB10.DBD98 -- Theoretical  
temperatura ata point1, saturation  
temperature for P1
```

```
T2_calc := "Puestos1".UDT2_1.T2deseada
```

```
DB10.DBD106 -- Desired temp  
eratura at point 2, T2sat+delta_T_  
resistance
```

```
T3_calc := "Puestos1".UDT2_1.T2sat
```

```
DB10.DBD94 -- Saturation t  
emperature for P2
```

```
P3_calc := "Puestos1".UDT1_1.P2_m
```

```
DB10.DBD28 -- input pressu  
re of the condenser
```

```
displ := "Puestos1".UDT2_1.displ
```

```
DB10.DBD178 -- Displacement  
-->CC/rev
```

```
rpm := "Puestos1".UDT2_1.rpm
```

```
DB10.DBD174 -- Revolutions  
per minute
```

```
Cp_w := 4.180000e+000
```

```
delta_T_resistance := "Puestos1".UDT2_1.delta_T_resistance
```

```
DB10.DBD186 -- Extra temper  
ature degrees above the sat.T° to  
be obtained by the resistance
```

```
P1_set := "Puestos1".UDT1_1.P1_set
```

```
DB10.DBD44 -- Pressure des  
ired at point one
```

```
c_vol := "Puestos1".UDT7_1.c_vol
```

```
DB10.DBD326 -- Coefficient  
"c" of the second degree equation  
to calculate the volumetric eff.
```

```
b_iso := "Puestos1".UDT7_1.b_iso
```

```
DB10.DBD310 -- Coefficient  
"b" of the second degree equation  
to calculate the isentropic eff.
```

```
c_iso := "Puestos1".UDT7_1.c_iso
```

```
DB10.DBD314 -- Coefficient  
"c" of the second degree equation  
to calculate the isentropic eff.
```

```

a_iso                := "Puestos1".UDT7_1.a_iso                DB10.DBD306        -- Coefficient
                    "a" of the second degree equation
                    to calculate the isentropic eff.
a_vol                := "Puestos1".UDT7_1.a_vol                DB10.DBD318        -- Coefficient
                    "a" of the second degree equation
                    to calculate the volumetric eff.
b_vol                := "Puestos1".UDT7_1.b_vol                DB10.DBD322        -- Coefficient
                    "b" of the second degree equation
                    to calculate the volumetric eff.
Mode_manual_automat := "Puestos1".UDT8_1.Mode_Automatic_Manual DB10.DBX358.0      -- It determine
                    whether the cycle works automatica
                    lly (1) or in a manual way (0)
ON_OFF               := "Puestos1".UDT4_1.ON_OFF               DB10.DBX235.4      -- Indicates if
                    the station is ON (ON=1, OFF=0)
Dir_comp             := A1.0
Dir_pump             := AW324
Dir_EEV              := AW328
Dir_res              := A1.1
DB_Tout              := "Puestos1".UDT1_1.Tout_m              DB10.DBD20         -- Water output
                    temperature
m_ref_grams          := "Puestos1".UDT6_1.m_ref_grams          DB10.DBD268        -- m_ref_th*100
                    0--> [g/s]
flow_w_lit_min       := "Puestos1".UDT2_1.flow_w_lit_min       DB10.DBD162        -- Desired wate
                    r flux (l/min)
m_ref_th             := "Puestos1".UDT2_1.m_ref_th             DB10.DBD146        -- Theoretical
                    refrigerant flux (kg/s)
Qcond_necesitado    := "Puestos1".UDT2_1.Qcond_necesitado    DB10.DBD154        -- Heat exchang
                    ed in the condenser
m_w_th              := "Puestos1".UDT2_1.m_w_th              DB10.DBD150        -- Theoretical
                    water flux (kg/s)
rend_iso_th         := "Puestos1".UDT2_1.rend_iso_th         DB10.DBD170        -- Theoretical is
                    entropic efficiency
PR                  := "Puestos1".UDT7_1.PR                  DB10.DBD342        -- Pressure rat
                    io P2measured/P1set--> To calculat
                    e the efficiencies
rend_vol_th         := "Puestos1".UDT2_1.rend_vol_th         DB10.DBD166        -- Theoretical vo
                    lumetric efficiency
DB_P2               := "Puestos1".UDT1_1.P2_m                DB10.DBD28         -- input pressu
                    re of the condenser
DB_Tin              := "Puestos1".UDT1_1.Tin_m                DB10.DBD16         -- Water input
                    temperature
h1_th               := "Puestos1".UDT2_1.h1_th               DB10.DBD74         -- Enthalpy at
                    point 1, according to the desired
                    P1
h2_th               := "Puestos1".UDT2_1.h2_th               DB10.DBD190        -- Enthalpy at
                    point 2, with theoretical data
h2_m                := "Puestos1".UDT2_1.h2_m                DB10.DBD86         -- Enthalpy at
                    point 2, with measured data
rho_water           := "Puestos1".UDT2_1.rho_water           DB10.DBD122        -- Water densit
                    y
T2sat               := "Puestos1".UDT2_1.T2sat               DB10.DBD94         -- Saturation t
                    emperature for P2
T1sat               := "Puestos1".UDT2_1.T1sat               DB10.DBD98         -- Theoretical
                    temperatura ata point1, saturation
                    temperature for P1
Tin_chiller         := "Puestos1".UDT1_1.Tin_chiller         DB10.DBD48         -- Tin temperat
                    ure fixed with the chiller
T2deseada           := "Puestos1".UDT2_1.T2deseada           DB10.DBD106        -- Desired temp
                    eratura at point 2, T2sat+delta_T_
                    resistance
DB_T1               := "Puestos1".UDT1_1.T1_m                DB10.DBD4         -- Input temper
                    ature of the compressors refrigera
                    nt
DB_T2               := "Puestos1".UDT1_1.T2_m                DB10.DBD8         -- Input temper
                    ature of the condenser
DB_T3               := "Puestos1".UDT1_1.T3_m                DB10.DBD12        -- Output tempe
                    rature of the condenser
DB_P1               := "Puestos1".UDT1_1.P1_m                DB10.DBD24        -- Input pressu
                    re of the compressor
DB_P3               := "Puestos1".UDT1_1.P3_m                DB10.DBD32        -- Output press
                    ure of the condenser
DB_m_ref            := "Puestos1".UDT1_1.m_ref_m             DB10.DBD36        -- Refrigerant
                    flux
DB_m_w              := "Puestos1".UDT1_1.m_w_m              DB10.DBD40        -- Water flux
orden_EEV_int       := "Puestos1".UDT3_1.Orden_EEV_int       DB10.DBW198        -- Control sign
                    al of the EEV
orden_EEVreal       := "Puestos1".UDT5_1.orden_EEVreal       DB10.DBD244        -- EEV control
                    order
orden_pump_int      := "Puestos1".UDT3_1.Orden_pump_int      DB10.DBW200        -- Control sign
                    al of the water pump
orden_pump_real     := "Puestos1".UDT5_1.orden_pump_real     DB10.DBD248        -- Pump control
                    order, REAL
OFF                 := "Puestos1".UDT4_1.OFF                 DB10.DBX235.5      -- Indicates if
                    the station is OFF(OFF=1, ON=0)
Ref_number_11       := "Excel_Interface".UDT11_1.Ref_number   DB11.DBW0         -- Is in UDT 1,
                    for the excel interface
P1_m_11             := "Excel_Interface".UDT11_1.P1_m         DB11.DBD2         -- P1_measured,
                    UDT1
P1_set_11           := "Excel_Interface".UDT11_1.P1_set     DB11.DBD6         -- P1 set, UDT
                    1

```

```

x1_11          := "Excel_Interface".UDT11_1.x1          DB11.DBD10      -- Quality of the
Tout_m_11      := "Excel_Interface".UDT11_1.Tout_m      DB11.DBD14      -- Output water
P2_m_11        := "Excel_Interface".UDT11_1.P2_m        DB11.DBD18      -- Pressure after
delta_T_resistance_11 := "Excel_Interface".UDT11_1.delta_T_resistance DB11.DBD22      -- Delta T over
m_w_m_11       := "Excel_Interface".UDT11_1.m_w_m       DB11.DBD26      -- Water flux measured,
m_ref_div_rho_11 := "Excel_Interface".UDT11_1.m_ref_div_rho DB11.DBD30      -- Auxiliary variable
T2_m_11        := "Excel_Interface".UDT11_1.T2_m        DB11.DBD34      -- Temperature after
T1sat_12       := "Excel_Interface".UDT12_1.h1_th       DB11.DBD42      -- Enthalpy computed
h1_th_12       := "Excel_Interface".UDT12_1.h1_th       DB11.DBD42      -- Enthalpy computed
h1_12          := "Excel_Interface".UDT12_1.h1          DB11.DBD46      -- Enthalpy computed
T2sat_12       := "Excel_Interface".UDT12_1.T2sat       DB11.DBD50      -- Saturation temperature
h2_th_12       := "Excel_Interface".UDT12_1.h2_th       DB11.DBD54      -- Enthalpy computed
h3_th_12       := "Excel_Interface".UDT12_1.h3_th       DB11.DBD58      -- Enthalpy computed
T2desired_12   := "Excel_Interface".UDT12_1.T2desired   DB11.DBD62      -- Desired temperature
rho_ref_12     := "Excel_Interface".UDT12_1.rho_ref     DB11.DBD66      -- Refrigerant density
h2_m_12        := "Excel_Interface".UDT12_1.h2_m        DB11.DBD70      -- Enthalpy computed
h3_m_12        := "Excel_Interface".UDT12_1.h3_m        DB11.DBD74      -- Enthalpy equal
m_ref_th_12    := "Excel_Interface".UDT12_1.m_ref_th    DB11.DBD78      -- Theoretical
m_ref_grams_12 := "Excel_Interface".UDT12_1.m_ref_grams DB11.DBD82      -- Theoretical
T2desired      := "Puestos1".UDT2_1.T2deseada          DB10.DBD106     -- Desired temperature
m_ref_div_rho  := "Puestos1".UDT6_1.m_ref_div_rho      DB10.DBD272     -- Is m_ref/rho
h3_th          := "Puestos1".UDT2_1.h3_th             DB10.DBD194     -- Enthalpy at
h3_m           := "Puestos1".UDT2_1.h3_m              DB10.DBD90      -- Enthalpy at
rho_ref        := "Puestos1".UDT2_1.rho_ref           DB10.DBD114     -- Refrigerant density

CALL "Alarm"
DeviationT1 := "Puestos1".UDT10_1.DeviationT1          DB10.DBD376     -- Maximum deviation
DeviationP1 := "Puestos1".UDT10_1.DeviationP1          DB10.DBD372     -- Maximum deviation
MaxP2       := "Puestos1".UDT10_1.MaxP2                DB10.DBD380     -- Maximum value
MaxT2       := "Puestos1".UDT10_1.MaxT2                DB10.DBD384     -- Maximum value
T1_m        := "Puestos1".UDT1_1.T1_m                  DB10.DBD4       -- Input temperature
P1_m        := "Puestos1".UDT1_1.P1_m                  DB10.DBD24      -- Input pressure
T2_m        := "Puestos1".UDT1_1.T2_m                  DB10.DBD8       -- Input temperature
P2_m        := "Puestos1".UDT1_1.P2_m                  DB10.DBD28      -- input pressure
T1sat       := "Puestos1".UDT2_1.T1sat                 DB10.DBD98      -- Theoretical
P1_set      := "Puestos1".UDT1_1.P1_set                 DB10.DBD44      -- Pressure desired
ON_OFF      := "Puestos1".UDT4_1.ON_OFF                 DB10.DBX235.4   -- Indicates if
OFF         := "Puestos1".UDT4_1.OFF                   DB10.DBX235.5   -- Indicates if
T1_Low      := "Puestos1".UDT10_1.T1_Low               DB10.DBX388.0   -- Indicates when

```



```

T1_High      := "Puestos1".UDT10_1.T1_High      DB10.DBX388.1    -- Indicates wh
en the temperature 1 is above the
maximum value
T1_Error     := "Puestos1".UDT10_1.T1_Error     DB10.DBX388.2    -- Inticates wh
en an error because of the tempera
ture 1 (lower o greater)
P1_Low       := "Puestos1".UDT10_1.P1_Low       DB10.DBX388.3    -- Indicates wh
en the pressure 1 is beyond the mi
nimum value
P1_High      := "Puestos1".UDT10_1.P1_High      DB10.DBX388.4    -- Indicates wh
en the pressure 1 is above the max
imum value
P1_Error     := "Puestos1".UDT10_1.P1_Error     DB10.DBX388.5    -- Indicates wh
en an error because of the pressur
e 1 (lower o greater)
T2_Error     := "Puestos1".UDT10_1.T2_Error     DB10.DBX388.6    -- Indicates wh
en the temperature 2 is greater th
an the limit, ERROR
P2_Error     := "Puestos1".UDT10_1.P2_Error     DB10.DBX388.7    -- Indicates wh
en the pressure 2 is greater than
the limit, ERROR
Stable       := "Puestos1".UDT10_1.Stable       DB10.DBX389.0    -- Indicates wh
en the station has been stabilized
-->1
Alarm        := "Puestos1".UDT10_1.Alarm        DB10.DBX389.1    -- The alarm se
tttings haven't been fulfilled (af
ter been stabilized) for a X time

U           "Puestos1".UDT4_1.OFF              DB10.DBX235.5    -- Indicates if
the station is OFF(OFF=1, ON=0)

SPB   A_OF

SPA   END

```

```

// _____ //
// AUTOMATIC OFF //
// _____ //

```

```

A_OF: CALL "STOP_manual&automatic"              FC8
Dir_compressor      := A1.0
Dir_resistance      := A1.1
P3                  := "Puestos1".UDT1_1.P3_m    DB10.DBD32      -- Output press
ure of the condenser
P1                  := "Puestos1".UDT1_1.P1_m    DB10.DBD24      -- Input pressu
re of the compressor
OFF                 := "Puestos1".UDT4_1.OFF     DB10.DBX235.5   -- Indicates if
the station is OFF(OFF=1, ON=0)
Mode_manual_automat := "Puestos1".UDT8_1.Mode_manual_automat DB10.DBX358.5   -- It determine
wether the cycle works automatica
lly (0) or in a manual way (1)
Manual_Resistance   := "Puestos1".UDT8_1.Manual_resistance DB10.DBX358.2   -- Test the cor
rect functioning of the resistance
Manual_EEV          := "Puestos1".UDT8_1.Manual_EEV   DB10.DBX358.3   -- test the cor
rect funtioning of the EEV
Manual_compressor   := "Puestos1".UDT8_1.Manual_compressor DB10.DBX358.1   -- Test the cor
rect functioning of the compressor
in the manual mode
Manual_pump         := "Puestos1".UDT8_1.Manual_Pump   DB10.DBX358.4   -- Test the cor
rect functioning of the pump
m_w                 := "Puestos1".UDT1_1.m_w_m    DB10.DBD40      -- Water flux
orden_pump_int      := "Puestos1".UDT3_1.Orden_pump_int DB10.DBW200     -- Control sign
al of the water pump
orden_EEVreal       := "Puestos1".UDT5_1.orden_EEVreal DB10.DBD244     -- EEV control
order
Dir_pump            := AW324
Dir_EEV             := AW328
orden_EEV           := "Puestos1".UDT3_1.Orden_EEV_int DB10.DBW198     -- Control sign
al of the EEV
orden_pump_real     := "Puestos1".UDT5_1.orden_pump_real DB10.DBD248     -- Pump control
order, REAL

SPA   END

```

Segm.: 3	STATION MANUAL. ¿ON/OFF?
----------	--------------------------

If any of the components is beeing tested, then the manual mode is beeing used-->ON.	
--	--

```

MAN: U           "Puestos1".UDT8_1.Manual_compressor   DB10.DBX358.1    -- Test the correct
functioning of the compressor in the ma
nual mode

```

```

O   "Puestos1".UDT8_1.Manual_EEV          DB10.DBX358.3    -- test the correct
                                         funtioning of the EEV
O   "Puestos1".UDT8_1.Manual_resistance    DB10.DBX358.2    -- Test the correct
                                         functioning of the resistance
O   "Puestos1".UDT8_1.Manual_Pump         DB10.DBX358.4    -- Test the correct
                                         functioning of the pump
=   "Puestos1".UDT4_1.ON_OFF              DB10.DBX235.4    -- Indicates if the
                                         station is ON (ON=1, OFF=0)

```

```

//If one of them is being tested, the START button would have to show it
//ON_OFF would depend to the state of the components, if one of them is set, then it would be "ON"

```

```

//Erase the AUTOMATIC SETTINGS

```

```

L   0.000000e+000
T   "Puestos1".UDT7_1.a_vol              DB10.DBD318      -- Coefficient "a" o
                                         f the second degree equation to calcula
                                         te the volumetric eff.
T   "Puestos1".UDT7_1.b_vol              DB10.DBD322      -- Coefficient "b" o
                                         f the second degree equation to calcula
                                         te the volumetric eff.
T   "Puestos1".UDT7_1.c_vol              DB10.DBD326      -- Coefficient "c" o
                                         f the second degree equation to calcula
                                         te the volumetric eff.
T   "Puestos1".UDT7_1.a_iso              DB10.DBD306      -- Coefficient "a" o
                                         f the second degree equation to calcula
                                         te the isentropic eff.
T   "Puestos1".UDT7_1.b_iso              DB10.DBD310      -- Coefficient "b" o
                                         f the second degree equation to calcula
                                         te the isentropic eff.
T   "Puestos1".UDT7_1.c_iso              DB10.DBD314      -- Coefficient "c" o
                                         f the second degree equation to calcula
                                         te the isentropic eff.
T   "Puestos1".UDT1_1.P1_set             DB10.DBD44       -- Pressure desired
                                         at point one
T   "Puestos1".UDT2_1.delta_T_resistance DB10.DBD186      -- Extra temperature
                                         degrees above the sat.T° to be obtaine
                                         d by the resistance
T   "Puestos1".UDT1_1.x1                 DB10.DBD0        -- Quality
T   "Puestos1".UDT2_1.rpm                DB10.DBD174      -- Revolutions per m
                                         inute
T   "Puestos1".UDT2_1.displ              DB10.DBD178      -- Displacement -->C
                                         C/rev

U   "Puestos1".UDT4_1.ON_OFF            DB10.DBX235.4    -- Indicates if the
                                         station is ON (ON=1, OFF=0)

SPB  M_ON
SPA  M_OF

```

```

//If one component has been activate, we call the STATION_ON_MAN"

```

```

M_ON: CALL "Station_MAN_ON"
      Man_delta_T_res_int :="Puestos1".UDT3_1.Man_delta_T_res_int DB10.DBW204      -- When manual mode
                                         is activated it gives the "order" for t
                                         he resistance
      Man_delta_P_EEV_int :="Puestos1".UDT3_1.Man_delta_P_EEV_int DB10.DBW206      -- When manual mode
                                         is activated it gives the "order" for t
                                         he EEV
      Man_WF_pump_int     :="Puestos1".UDT3_1.Man_WF_pump_int     DB10.DBW208      -- When manual mode
                                         is activated it gives the "order" for t
                                         he pump
      Man_resistance      :="Puestos1".UDT8_1.Manual_resistance    DB10.DBX358.2    -- Test the correct
                                         functioning of the resistance
      Man_Pump            :="Puestos1".UDT8_1.Manual_Pump         DB10.DBX358.4    -- Test the correct
                                         functioning of the pump
      Man_EEV             :="Puestos1".UDT8_1.Manual_EEV         DB10.DBX358.3    -- test the correct
                                         funtioning of the EEV
      Man_Compressor      :="Puestos1".UDT8_1.Manual_compressor    DB10.DBX358.1    -- Test the correct
                                         functioning of the compressor in the ma
                                         nual mode

      IN_T2               :=EW302
      IN_P1               :=EW312
      IN_P2               :=EW314
      IN_P3               :=EW316
      IN_m_w              :=EW322
      T2_connected        :="Puestos1".UDT4_1.T2_conectado        DB10.DBX234.3    -- Indicates the con
                                         nection state of the sensor T2
      P1_connected        :="Puestos1".UDT4_1.P1_conectado        DB10.DBX234.2    -- Indicates the con
                                         nection state of the sensor P1
      P2_connected        :="Puestos1".UDT4_1.P2_conectado        DB10.DBX234.4    -- Indicates the con
                                         nection state of the sensor P2
      P3_connected        :="Puestos1".UDT4_1.P3_conectado        DB10.DBX234.6    -- Indicates the con
                                         nection state of the sensor P3
      m_w_connected       :="Puestos1".UDT4_1.Qw_conectado        DB10.DBX235.1    -- Indicates the con
                                         nection state of the sensor Qw
      Mode_manual_automatic:= "Puestos1".UDT8_1.Mode_manual_automatic DB10.DBX358.5    -- It determine weht
                                         er the cycle works automatically (0) or
                                         in a manual way (1)

```

```

T2deseada          := "Puestos1".UDT2_1.T2deseada          DB10.DBD106          -- Desired temperature at point 2, T2sat+delta_T_resistance

Dir_res            := A1.1
Dir_comp           := A1.0
Dir_pump           := AW324
Dir_EEV            := AW328
orden_EEVreal      := "Puestos1".UDT5_1.orden_EEVreal      DB10.DBD244          -- EEV control order
Orden_EEV_int      := "Puestos1".UDT3_1.Orden_EEV_int        DB10.DBW198          -- Control signal of the EEV

DB_T2              := "Puestos1".UDT1_1.T2_m                DB10.DBD8            -- Input temperature of the condenser
DB_P1              := "Puestos1".UDT1_1.P1_m                DB10.DBD24           -- Input pressure of the compressor
DB_P2              := "Puestos1".UDT1_1.P2_m                DB10.DBD28           -- input pressure of the condenser
DB_P3              := "Puestos1".UDT1_1.P3_m                DB10.DBD32           -- Output pressure of the condenser
DB_m_w             := "Puestos1".UDT1_1.m_w_m               DB10.DBD40           -- Water flux
T1sat              := "Puestos1".UDT2_1.T1sat               DB10.DBD98           -- Theoretical temperature at point1, saturation temperature for P1
T2sat              := "Puestos1".UDT2_1.T2sat               DB10.DBD94           -- Saturation temperature for P2
orden_pump_real    := "Puestos1".UDT5_1.orden_pump_real     DB10.DBD248          -- Pump control order, REAL
Orden_pump_int     := "Puestos1".UDT3_1.Orden_pump_int      DB10.DBW200          -- Control signal of the water pump

SPA   END

M_OF: CALL "STOP_manual&automatic"          FC8
Dir_compressor     := A1.0
Dir_resistance     := A1.1
P3                 := "Puestos1".UDT1_1.P3_m          DB10.DBD32           -- Output pressure of the condenser
P1                 := "Puestos1".UDT1_1.P1_m          DB10.DBD24           -- Input pressure of the compressor
OFF                := "Puestos1".UDT4_1.OFF           DB10.DBX235.5        -- Indicates if the station is OFF (OFF=1, ON=0)
Mode_manual_autom := "Puestos1".UDT8_1.Mode_manual_autom DB10.DBX358.5        -- It determines whether the cycle works automatically (0) or in a manual way (1)
Manual_Resistance  := "Puestos1".UDT8_1.Manual_resistance DB10.DBX358.2        -- Test the correct functioning of the resistance
Manual_EEV         := "Puestos1".UDT8_1.Manual_EEV     DB10.DBX358.3        -- test the correct functioning of the EEV
Manual_compressor  := "Puestos1".UDT8_1.Manual_compressor DB10.DBX358.1        -- Test the correct functioning of the compressor in the manual mode
Manual_pump        := "Puestos1".UDT8_1.Manual_Pump    DB10.DBX358.4        -- Test the correct functioning of the pump
m_w                := "Puestos1".UDT1_1.m_w_m         DB10.DBD40           -- Water flux
orden_pump_int     := "Puestos1".UDT3_1.Orden_pump_int  DB10.DBW200          -- Control signal of the water pump
orden_EEVreal      := "Puestos1".UDT5_1.orden_EEVreal  DB10.DBD244          -- EEV control order
Dir_pump           := AW324
Dir_EEV            := AW328
orden_EEV          := "Puestos1".UDT3_1.Orden_EEV_int  DB10.DBW198          -- Control signal of the EEV
orden_pump_real    := "Puestos1".UDT5_1.orden_pump_real DB10.DBD248          -- Pump control order, REAL

SPA   END

Segm.: 4          END

```

END: NOP 0

FC94 - <offline>

"Excel_DB"

Nombre:**Familia:****Autor:****Versión:** 0.1**Versión del bloque:** 2**Hora y fecha Código:**

13/06/2014 17:02:36

Interface:

13/06/2014 17:02:36

Longitud (bloque / código / datos): 00378 00190 00000

Nombre	Tipo de datos	Dirección	Comentario
IN		0.0	
Ref_number	Int	0.0	Refrigerant number, UDT 1
P1_m	Real	2.0	P1_m, UDT 1
P1_set	Real	6.0	P1_set, UDT 1
x1	Real	10.0	x1, UDT 1
Tout_m	Real	14.0	Tout_m, UDT 1
P2_m	Real	18.0	P2_m, UDT 1
delta_T_resistance	Real	22.0	delta_T_resistance, UDT 2
m_w_m	Real	26.0	m_w_m, UDT 1
m_ref_div_rho	Real	30.0	m-ref_div_rho, UDT 6
T2_m	Real	34.0	T2_m, UDT 1
T1sat_12	Real	38.0	T1_sat,UDT 12
h1_th_12	Real	42.0	h1_th, UDT 12
h1_12	Real	46.0	h1, UDT 12
T2sat_12	Real	50.0	T2sat, UDT 12
h2_th_12	Real	54.0	h2_th,UDT 12
h3_th_12	Real	58.0	h3_th, UDT 12
T2desired_12	Real	62.0	T2desired, UDT 12
rho_ref_12	Real	66.0	rho_ref, UDT 12
h2_m_12	Real	70.0	h2_m, UDT 12
h3_m_12	Real	74.0	h3_m, UDT 12
m_ref_th_12	Real	78.0	m_ref_th, UDT 12
m_ref_grams_12	Real	82.0	m_ref_grams, UDT 12
UDT11_12	Bool	86.0	Indicates wheter the INPUT part or the OUTPUT segment must be executed
OUT		0.0	
IN_OUT		0.0	
Ref_number_11	Int	88.0	Refrigerant number, UDT 11
P1_m_11	Real	90.0	P1_m, UDT 11
P1_set_11	Real	94.0	P1_set, UDT 11
x1_11	Real	98.0	x1, UDT 11
Tout_m_11	Real	102.0	Tout_m, UDT 11
P2_m_11	Real	106.0	P2_m, UDT 11
delta_T_resistance_11	Real	110.0	delta_T_resistance, UDT 11
m_w_m_11	Real	114.0	m_w_m, UDT 11
m_ref_div_rho_11	Real	118.0	m-ref_div_rho, UDT 11
T2_m_11	Real	122.0	T2_m, UDT 11
T1sat	Real	126.0	T1_sat,UDT 2
h1_th	Real	130.0	h1_th, UDT 2
h1	Real	134.0	h1, UDT 2
T2sat	Real	138.0	T2sat, UDT 2
h2_th	Real	142.0	h2_th,UDT 2
h3_th	Real	146.0	h3_th, UDT 2
T2desired	Real	150.0	T2desired, UDT 2
rho_ref	Real	154.0	rho_ref, UDT 2
h2_m	Real	158.0	h2_m, UDT 2
h3_m	Real	162.0	h3_m, UDT 2

Nombre	Tipo de datos	Dirección	Comentario
m_ref_th	Real	166.0	m_ref_th, UDT 2
m_ref_grams	Real	170.0	m_ref_grams, UDT 6
TEMP		0.0	
RETURN		0.0	
RET_VAL		0.0	

Bloque: FC94 EXCEL

The objective is to create a DB with all the data needed by the excel. The inputs are stored mainly in UDT 1, (also in UDT 2 and UDT 6).The outputs are mainly stored in UDT 2 (also in UDT 6)

Segm.: 1 INPUTS

Redirectionate the inputs stored in differents UDT, to the UDT 11

```

U      #UDT11_12          #UDT11_12          -- Indicates wheter the INPUT part or the OUTPUT segmen
      SPB      IN          t must be executed
      SPA      OUT

IN:   L      #Ref_number   #Ref_number        -- Refrigerant number, UDT 1
      T      #Ref_number_11 #Ref_number_11    -- Refrigerant number, UDT 11

      L      #P1_m         #P1_m             -- P1_m, UDT 1
      T      #P1_m_11      #P1_m_11         -- P1_m, UDT 11

      L      #P1_set       #P1_set           -- P1_set, UDT 1
      T      #P1_set_11    #P1_set_11       -- P1_set, UDT 11

      L      #x1           #x1               -- x1, UDT 1
      T      #x1_11        #x1_11           -- x1, UDT 11

      L      #Tout_m       #Tout_m           -- Tout_m, UDT 1
      T      #Tout_m_11    #Tout_m_11       -- Tout_m, UDT 11

      L      #P2_m         #P2_m             -- P2_m, UDT 1
      T      #P2_m_11      #P2_m_11         -- P2_m, UDT 11

      L      #delta_T_resistance #delta_T_resistance -- delta_T_resistance, UDT 2
      T      #delta_T_resistance_11 #delta_T_resistance_11 -- delta_T_resistance, UDT 11

      L      #m_w_m        #m_w_m           -- m_w_m, UDT 1
      T      #m_w_m_11     #m_w_m_11       -- m_w_m, UDT 11

      L      #m_ref_div_rho #m_ref_div_rho    -- m-ref_div_rho, UDT 6
      T      #m_ref_div_rho_11 #m_ref_div_rho_11 -- m-ref_div_rho, UDT 11

      L      #T2_m         #T2_m            -- T2_m, UDT 1
      T      #T2_m_11      #T2_m_11        -- T2_m, UDT 11

```

Segm.: 2 OUTPUTS

Redirectionate the ouputs stored in the UDT 12,to the UDT 2,UDT 6,...

```

OUT:  L      #T1sat_12     #T1sat_12         -- T1_sat,UDT 12
      T      #T1sat        #T1sat            -- T1_sat,UDT 2

      L      #h1_th_12     #h1_th_12        -- h1_th, UDT 12
      T      #h1_th        #h1_th            -- h1_th, UDT 2

      L      #h1_12        #h1_12           -- h1, UDT 12
      T      #h1           #h1               -- h1, UDT 2

      L      #T2sat_12     #T2sat_12        -- T2sat, UDT 12
      T      #T2sat        #T2sat            -- T2sat, UDT 2

      L      #h2_th_12     #h2_th_12        -- h2_th,UDT 12
      T      #h2_th        #h2_th            -- h2_th,UDT 2

      L      #h3_th_12     #h3_th_12        -- h3_th, UDT 12
      T      #h3_th        #h3_th            -- h3_th, UDT 2

      L      #T2desired_12 #T2desired_12    -- T2desired, UDT 12
      T      #T2desired    #T2desired        -- T2desired, UDT 2

      L      #rho_ref_12   #rho_ref_12      -- rho_ref, UDT 12
      T      #rho_ref      #rho_ref          -- rho_ref, UDT 2

```

FC95 - <offline>

"Reset_StationNOT_SET"

Nombre:**Familia:****Autor:****Versión:** 0.1**Hora y fecha Código:****Versión del bloque:** 2

16/06/2014 09:10:07

Interface: 16/06/2014 09:10:07**Longitud (bloque / código / datos):** 00192 00066 00000

Nombre	Tipo de datos	Dirección	Comentario
IN		0.0	
T1_conectado	Bool	0.0	Sensor conected-->1 (UDT 4)
T2_conectado	Bool	0.1	Sensor conected-->1 (UDT 4)
T3_conectado	Bool	0.2	Sensor conected-->1 (UDT 4)
Tin_conectado	Bool	0.3	Sensor conected-->1 (UDT 4)
Tout_conectado	Bool	0.4	Sensor conected-->1 (UDT 4)
P1_conectado	Bool	0.5	Sensor conected-->1 (UDT 4)
P2_conectado	Bool	0.6	Sensor conected-->1 (UDT 4)
P3_conectado	Bool	0.7	Sensor conected-->1 (UDT 4)
m_ref_conectado	Bool	1.0	Sensor conected-->1 (UDT 4)
Qw_conectado	Bool	1.1	Sensor conected-->1 (UDT 4)
Resistance_conectado	Bool	1.2	Equipment connected-->1 (UDT 4)
OUT		0.0	
IN_OUT		0.0	
dir_compressor	Bool	2.0	Direction of the compressor
dir_resistance	Bool	2.1	Direction of the resistance
dir_EEV	Word	4.0	Direction of the EEV
dir_pump	Word	6.0	Direction of the pump
TEMP		0.0	
RETURN		0.0	
RET_VAL		0.0	

Bloque: FC95 RESET

If an station has not been set, then the T1_conected,...,Manual_resistance,..., and the rest of variables related to the automatic/manual, when the station is working, must be reseted.

Segm.: 1 Connected sensors

Set all the sensors as "disconected"

//RESET of the connected sensors signals//

```

R   #T1_conectado      #T1_conectado      -- Sensor conected-->1 (UDT 4)
R   #T2_conectado      #T2_conectado      -- Sensor conected-->1 (UDT 4)
R   #T3_conectado      #T3_conectado      -- Sensor conected-->1 (UDT 4)
R   #Tin_conectado     #Tin_conectado     -- Sensor conected-->1 (UDT 4)
R   #Tout_conectado    #Tout_conectado    -- Sensor conected-->1 (UDT 4)
R   #P1_conectado      #P1_conectado      -- Sensor conected-->1 (UDT 4)
R   #P2_conectado      #P2_conectado      -- Sensor conected-->1 (UDT 4)
R   #P3_conectado      #P3_conectado      -- Sensor conected-->1 (UDT 4)
R   #m_ref_conectado   #m_ref_conectado   -- Sensor conected-->1 (UDT 4)
R   #Qw_conectado      #Qw_conectado      -- Sensor conected-->1 (UDT 4)
R   #Resistance_conectado #Resistance_conectado -- Equipment connected-->1 (UDT 4)

```

Segm.: 2 Manual/Automatic Mode

The outputs must be set as zero, even if the station hasn't been set, we must assure that there won't be current or voltage at the outputs

```
R    #dir_compressor   #dir_compressor   -- Direction of the compressor
R    #dir_resistance   #dir_resistance   -- Direction of the resistance

L    0
T    #dir_EEV           #dir_EEV           -- Direction of the EEV
T    #dir_pump          #dir_pump          -- Direction of the pump
```

FC96 - <offline>

"Station_MAN_ON"

Nombre:**Familia:****Autor:****Versión:** 0.1**Versión del bloque:** 2**Hora y fecha Código:**

05/06/2014 12:33:20

Interface:

05/06/2014 12:33:20

Longitud (bloque / código / datos): 00854 00666 00062

Nombre	Tipo de datos	Dirección	Comentario
IN		0.0	
Man_delta_T_res_int	Int	0.0	When manual mode is set, the delta temperature is fixed, INT
Man_delta_P_EEV_int	Int	2.0	Delta P of the EEV in manual mode, INT
Man_WF_pump_int	Int	4.0	Water flux of the pump in manual mode, INT
Man_resistance	Bool	6.0	-->1 Resistance ON
Man_Pump	Bool	6.1	-->1 Pump ON
Man_EEV	Bool	6.2	-->1 EEV ON
Man_Compressor	Bool	6.3	-->1 Compressor ON
IN_T2	Int	8.0	Analog INPUT of T2 (02)
IN_P1	Int	10.0	Analog INPUT of P1 (12)
IN_P2	Int	12.0	Analog INPUT of P2 (14)
IN_P3	Int	14.0	Analog INPUT of P3 (16)
IN_m_w	Int	16.0	Analog INPUT of m_w (22)
T2_connected	Bool	18.0	0-> sensor not connected, 1--> sensor connected
P1_connected	Bool	18.1	0-> sensor not connected, 1--> sensor connected
P2_connected	Bool	18.2	0-> sensor not connected, 1--> sensor connected
P3_connected	Bool	18.3	0-> sensor not connected, 1--> sensor connected
m_w_connected	Bool	18.4	0-> sensor not connected, 1--> sensor connected
Mode_manual_automatic	Bool	18.5	1->Manual, 0->Automatic
OUT		0.0	
IN_OUT		0.0	
T2deseada	Real	20.0	Desired temperature at point 2r (after the heating resistance)
Dir_res	Bool	24.0	Direction of the resistance output (AX.1)
Dir_comp	Bool	24.1	Direction of the compressor output (AX.0)
Dir_pump	Word	26.0	Direction of the pump output (PAW (2+x)24)
Dir_EEV	Word	28.0	Direction of the EEV output (PAW (2+x)28)
orden_EEVreal	Real	30.0	EEV order, REAL(UDT5)
Orden_EEV_int	Int	34.0	EEV order, INT (UDT3)
DB_T2	Real	36.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_P1	Real	40.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_P2	Real	44.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_P3	Real	48.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_m_w	Real	52.0	Indicate the direction in which the value (measured/theoretical) must be stored
T1sat	Real	56.0	Saturatio temperature at 1. It would be its theoretical/calculated value
T2sat	Real	60.0	Saturation temperature at 2.It is the theoretical value of T3
orden_pump_real	Real	64.0	Pump order, REAL(UDT5)
Orden_pump_int	Int	68.0	Pump order, INT (UDT3)
TEMP		0.0	
Man_res_OFF	Bool	0.0	When the resistance in manual mode is NOT being tested-->1
Man_EEV_OFF	Bool	0.1	When the pump in manual mode is NOT being tested-->1

Nombre	Tipo de datos	Dirección	Comentario
Man_delta_T_res_real	Real	2.0	Delta T of the resistance in manual mode, REAL
Man_delta_P_EEV_real	Real	6.0	Delta P of the EEV in manual mode, REAL
Man_WF_pump_real	Real	10.0	Water fluxof the pump in manual mode, REAL
RETURN		0.0	
RET_VAL		0.0	

Bloque: FC96 START in Manual Mode

The manual mode was defined so the components could be tested separately

Segm.: 1 Measurement of sensors or employment of theoretical values

The FC 5 is summoned to storage the measures of the sensors (after have beeing conditioned),or the theoretical values (in case of not beeing connected)-->call the FC 6

The parameters IN_X correspond to the analog input direccctions of the sensors. Directions of STATION 1 start with a "3".

To developpe the code for the rest of stations,the direcctions would have to be changed.(STATION 2->starts with a "4" STATION 3-> "5"...))

The paremeters DB_X shows the direccction in wich the data must be stored

```

CALL "MAN_SensON/SensOFF->th"          FC98
IN_T2      :=#IN_T2                    #IN_T2      -- Analog INPUT of T2 (02)
IN_P1      :=#IN_P1                    #IN_P1      -- Analog INPUT of P1 (12)
IN_P2      :=#IN_P2                    #IN_P2      -- Analog INPUT of P2 (14)
IN_P3      :=#IN_P3                    #IN_P3      -- Analog INPUT of P3 (16)
IN_m_w     :=#IN_m_w                   #IN_m_w     -- Analog INPUT of m_w (22)
T2_connected :=#T2_connected           #T2_connected -- 0-> sensor not connected, 1--> sensor connected
P1_connected :=#P1_connected           #P1_connected -- 0-> sensor not connected, 1--> sensor connected
P2_connected :=#P2_connected           #P2_connected -- 0-> sensor not connected, 1--> sensor connected
P3_connected :=#P3_connected           #P3_connected -- 0-> sensor not connected, 1--> sensor connected
m_w_connected :=#m_w_connected         #m_w_connected -- 0-> sensor not connected, 1--> sensor connected
T2_calc     :=#T2deseada                #T2deseada  -- Desired temperature at point 2r (after the heating resistance)
P3_calc     :=#DB_P2                    #DB_P2      -- Indicate the direction in which the value (measured/theoretical) must be stored
Mode_manual_automat:=#Mode_manual_automat #Mode_manual_automat -- 1->Manual, 0->Automatic
DB_P1      :=#DB_P1                    #DB_P1      -- Indicate the direction in which the value (measured/theoretical) must be stored
DB_P2      :=#DB_P2                    #DB_P2      -- Indicate the direction in which the value (measured/theoretical) must be stored
DB_P3      :=#DB_P3                    #DB_P3      -- Indicate the direction in which the value (measured/theoretical) must be stored
DB_T2      :=#DB_T2                    #DB_T2      -- Indicate the direction in which the value (measured/theoretical) must be stored
DB_m_w     :=#DB_m_w                   #DB_m_w     -- Indicate the direction in which the value (measured/theoretical) must be stored
T2sat      :=#T2sat                    #T2sat      -- Saturation temperature at 2.It is the theoretical value of T3

```

Segm.: 2 Manual PID control

This segment "calls" the function in which, not only the "ON" control is set, there is also an "OFF" control procedure defined.

```

//INT-->REAL the value of delta P to be achieved, fixed in the screen
L      #Man_delta_P_EEV_int            #Man_delta_P_EEV_int -- Delta P of the EEV in manual mode,
INT
ITD
DTR
T      #Man_delta_P_EEV_real            #Man_delta_P_EEV_real -- Delta P of the EEV in manual mode
, REAL

//INT-->REAL the value of delta t to be achieved, fixed in the screen
L      #Man_delta_T_res_int            #Man_delta_T_res_int -- When manual mode is set, the delta
temperature is fixed, INT
ITD

```

```

DTR
T      #Man_delta_T_res_real      #Man_delta_T_res_real -- Delta T of the resistance in manu
al mode, REAL

CALL  "MAN_ControlPID"           FC9
Man_delta_T_res_int :=#Man_delta_T_res_int #Man_delta_T_res_int -- When manual mode is set, the delta
temperature is fixed, INT
Man_delta_P_EEV_int :=#Man_delta_P_EEV_int #Man_delta_P_EEV_int -- Delta P of the EEV in manual mode,
INT
Man_WF_pump_int      :=#Man_WF_pump_int    #Man_WF_pump_int    -- Water flux of the pump in manual mod
e, INT
Man_resistance       :=#Man_resistance     #Man_resistance     -- -->1 Resistance ON
Man_Pump              :=#Man_Pump          #Man_Pump           -- -->1 Pump ON
Man_EEV               :=#Man_EEV          #Man_EEV            -- -->1 EEV ON
Man_Compressor       :=#Man_Compressor     #Man_Compressor     -- -->1 Compressor ON
T2sat                 :=#T2sat             #T2sat              -- Saturation temperature at 2.It is th
e theoretical value of T3
P1                    :=#DB_P1             #DB_P1              -- Indicate the direction in which the
value (measured/theoretical) must be stored
P3                    :=#DB_P3             #DB_P3              -- Indicate the direction in which the
value (measured/theoretical) must be stored
m_w_m                 :=#DB_m_w           #DB_m_w             -- Indicate the direction in which the
value (measured/theoretical) must be stored
T2_m                  :=#DB_T2            #DB_T2              -- Indicate the direction in which the
value (measured/theoretical) must be stored
Man_delta_T_res_real:=#Man_delta_T_res_real #Man_delta_T_res_real -- Delta T of the resistance in manu
al mode, REAL
Man_delta_P_EEV_real:=#Man_delta_P_EEV_real #Man_delta_P_EEV_real -- Delta P of the EEV in manual mode
, REAL
Man_WF_pump_real      :=#Man_WF_pump_real  #Man_WF_pump_real  -- Water fluxof the pump in manual mode
, REAL
T2deseada             :=#T2deseada        #T2deseada         -- Desired temperature at point 2r (aft
er the heating resistance)
Dir_res               :=#Dir_res           #Dir_res            -- Direction of the resistance output (
AX.1)
Dir_comp              :=#Dir_comp          #Dir_comp           -- Direction of the compressor output (
AX.0)
Dir_pump              :=#Dir_pump          #Dir_pump           -- Direction of the pump output (PAW (2
+x)24)
Dir_EEV               :=#Dir_EEV          #Dir_EEV            -- Direction of the EEV output (PAW (2+
x)28)
orden_EEVreal         :=#orden_EEVreal    #orden_EEVreal     -- EEV order, REAL(UDT5)
Orden_EEV             :=#Orden_EEV_int    #Orden_EEV_int     -- EEV order, INT (UDT3)
orden_pump_int        :=#Orden_pump_int    #Orden_pump_int    -- Pump order, INT (UDT3)
orden_pump_real       :=#orden_pump_real  #orden_pump_real   -- Pump order, REAL(UDT5)

```

FC97 - <offline>

"Station_AUT_ON"

Nombre: **Familia:**
Autor: **Versión:** 0.1
Versión del bloque: 2
Hora y fecha Código: 16/06/2014 09:51:45
Interface: 16/06/2014 09:51:33
Longitud (bloque / código / datos): 02096 01790 00310

Propiedades del objeto:

S7_language 9(1) Inglés (Estados Unidos) 23/05/2014 13:19:47

Nombre	Tipo de datos	Dirección	Comentario
IN		0.0	
UDT11_12	Bool	0.0	When it is 1->inputs to the UDT 11, when it is 0->outputs to UDT12
x1	Real	2.0	Quality of the refrigerant, UDT 1
ref_number	Int	6.0	Refrigerant number (0->r134a, 1->r410a, 2->r407c, 3->r22, 4->r290)
IN_T1	Int	8.0	Analog INPUT of T1
IN_T2	Int	10.0	Analog INPUT of T2
IN_T3	Int	12.0	Analog INPUT of T3
IN_Tin	Int	14.0	Analog INPUT of Tin
IN_Tout	Int	16.0	Analog INPUT of Tout
IN_P1	Int	18.0	Analog INPUT of P1
IN_P2	Int	20.0	Analog INPUT of P2
IN_P3	Int	22.0	Analog INPUT of P3
IN_m_ref	Int	24.0	Analog INPUT of m_ref
IN_m_w	Int	26.0	Analog INPUT of m_w
T1_connected	Bool	28.0	0-> sensor not connected, 1--> sensor connected
T2_connected	Bool	28.1	0-> sensor not connected, 1--> sensor connected
T3_connected	Bool	28.2	0-> sensor not connected, 1--> sensor connected
Tin_connected	Bool	28.3	0-> sensor not connected, 1--> sensor connected
Tout_connected	Bool	28.4	0-> sensor not connected, 1--> sensor connected
P1_connected	Bool	28.5	0-> sensor not connected, 1--> sensor connected
P2_connected	Bool	28.6	0-> sensor not connected, 1--> sensor connected
P3_connected	Bool	28.7	0-> sensor not connected, 1--> sensor connected
m_ref_connected	Bool	29.0	0-> sensor not connected, 1--> sensor connected
m_w_connected	Bool	29.1	0-> sensor not connected, 1--> sensor connected
T1_calc	Real	30.0	Theoretical/set/calculated value of the magnitude
T2_calc	Real	34.0	Theoretical/set/calculated value of the magnitude
T3_calc	Real	38.0	Theoretical/set/calculated value of the magnitude
P3_calc	Real	42.0	Theoretical/set/calculated value of the magnitude->P2
displ	Real	46.0	Displacement of the compressor
rpm	Real	50.0	rpm of the compressor
Cp_w	Real	54.0	
delta_T_resistance	Real	58.0	Extra temperature degrees to be obtained above the sat. T by the resistance
P1_set	Real	62.0	Set pressured at the operating point 1
c_vol	Real	66.0	Coefficient of the second degree equation to calculate the volumetric eff.
b_iso	Real	70.0	Coefficient of the second degree equation to calculate the isentropic eff.
c_iso	Real	74.0	Coefficient of the second degree equation to calculate the isentropic eff.
a_iso	Real	78.0	Coefficient of the second degree equation to calculate the isentropic eff.
a_vol	Real	82.0	Coefficient of the second degree equation to calculate the volumetric eff.
b_vol	Real	86.0	Coefficient of the second degree equation to calculate the volumetric eff.

Nombre	Tipo de datos	Dirección	Comentario
Mode_manual_automatic	Bool	90.0	When mode is manual->1, UDT8
ON_OFF	Bool	90.1	Indicates when the station is ON (-->1), or OFF (-->0)
OUT		0.0	
IN_OUT		0.0	
Dir_comp	Bool	92.0	Digital output that controls the compressor (x.0)
Dir_pump	Word	94.0	Analog output-> PUMP ("2+x"24)
Dir_EEV	Word	96.0	Analog output--> EEV ("2+x"28)
Dir_res	Bool	98.0	Digital output--> Resistance (x.1)
DB_Tout	Real	100.0	Indicate the direction in which the value (measured/theoretical) must be stored
m_ref_grams	Real	104.0	Refrigerant flux calculated in g/s
flow_w_lit_min	Real	108.0	Water flux calculated in l/min
m_ref_th	Real	112.0	Refrigerant flux in kg/s
Qcond_necesitado	Real	116.0	Heat exchanged needed in the condenser
m_w_th	Real	120.0	Water flux in kg/s
rend_iso_th	Real	124.0	Isentropic efficiency computed with the second degree equation
PR	Real	128.0	Pressure ratio P2measured/P1 set
rend_vol_th	Real	132.0	Volumetric efficiency computed with the second degree equation
DB_P2	Real	136.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_Tin	Real	140.0	Indicate the direction in which the value (measured/theoretical) must be stored
h1_th	Real	144.0	Enthalpy at the desired pressure and quality
h2_th	Real	148.0	Enthalpy at point 2, with the theoretical values
h2_m	Real	152.0	Enthalpy at 2, with the "measured" value of T2 (if its implemented)
rho_water	Real	156.0	To determine the l/min of the water flux
T2sat	Real	160.0	Saturation temperature at pressure P2
T1sat	Real	164.0	Saturation temperature at 1, theoretical value of T1
Tin_chiller	Real	168.0	Temperature fixed with the chiller
T2deseada	Real	172.0	Desired temperature at point 2r, after the heating resistance
DB_T1	Real	176.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_T2	Real	180.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_T3	Real	184.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_P1	Real	188.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_P3	Real	192.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_m_ref	Real	196.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_m_w	Real	200.0	Indicate the direction in which the value (measured/theoretical) must be stored
orden_EEV_int	Int	204.0	EEV order, INT
orden_EEVreal	Real	206.0	EEV order, REAL
orden_pump_int	Int	210.0	Pump order, INT
orden_pump_real	Real	212.0	Pump order, REAL
OFF	Bool	216.0	Indicator of the OFF state of the station
Ref_number_11	Int	218.0	Refrigerant number, UDT 11
P1_m_11	Real	220.0	P1_m, UDT 11
P1_set_11	Real	224.0	P1_set, UDT 11
x1_11	Real	228.0	x1, UDT 11
Tout_m_11	Real	232.0	Tout_m, UDT 11

Nombre	Tipo de datos	Dirección	Comentario
P2_m_11	Real	236.0	P2_m, UDT 11
delta_T_resistance_11	Real	240.0	delta_T_resistance, UDT 11
m_w_m_11	Real	244.0	m_w_m, UDT 11
m_ref_div_rho_11	Real	248.0	m-ref_div_rho, UDT 11
T2_m_11	Real	252.0	T2_m, UDT 11
T1sat_12	Real	256.0	T1_sat,UDT 12
h1_th_12	Real	260.0	h1_th, UDT 12
h1_12	Real	264.0	h1, UDT 12
T2sat_12	Real	268.0	T2sat, UDT 12
h2_th_12	Real	272.0	h2_th,UDT 12
h3_th_12	Real	276.0	h3_th, UDT 12
T2desired_12	Real	280.0	T2desired, UDT 12
rho_ref_12	Real	284.0	rho_ref, UDT 12
h2_m_12	Real	288.0	h2_m, UDT 12
h3_m_12	Real	292.0	h3_m, UDT 12
m_ref_th_12	Real	296.0	m_ref_th, UDT 12
m_ref_grams_12	Real	300.0	m_ref_grams, UDT 12
T2desired	Real	304.0	Desired temperature after the heating resistance
m_ref_div_rho	real	308.0	m_ref/rho, displ [m^3/rev]*eff_vol*rps [rev/s]
h3_th	real	312.0	Enthalpy at P1_m, x1
h3_m	real	316.0	Enthalpy at point 3
rho_ref	Real	320.0	Refrigerant density (entering of the compressor)
TEMP		0.0	
RETURN		0.0	
RET_VAL		0.0	

Bloque: FC97 STATION 1_on_aut

Within the followings "segments", the subroutines needed to performed the measurement of the sensors, the conditionate of the signals, the control,...of the station 1, will be summoned.

Segm.: 1 Measurement of sensors or employment of theoretical values

The FC 5 is summoned to storage the meassures of the sensors (after have beeing conditioned),or the theoretical values (in case of not beeing connected)-->call the FC 6

The parameters IN_X correspond to the analog input direcctions of the sensors. Directions of STATION 1 start with a "3".

To developpe the code for the rest of stations,the direcctions would have to be changed.(STATION 2->starts with a "4" STATION 3-> "5"...))

The paremeters DB_X shows the direcction in wich the data must be stored

CALL "AUT_SensON/OFF->th/calc"		FC5	
IN_T1	:=#IN_T1	#IN_T1	-- Anal
		og INPUT of T1	
IN_T2	:=#IN_T2	#IN_T2	-- Anal
		og INPUT of T2	
IN_T3	:=#IN_T3	#IN_T3	-- Anal
		og INPUT of T3	
IN_Tin	:=#IN_Tin	#IN_Tin	-- Anal
		og INPUT of Tin	
IN_Tout	:=#IN_Tout	#IN_Tout	-- Anal
		og INPUT of Tout	
IN_P1	:=#IN_P1	#IN_P1	-- Anal
		og INPUT of P1	
IN_P2	:=#IN_P2	#IN_P2	-- Anal
		og INPUT of P2	
IN_P3	:=#IN_P3	#IN_P3	-- Anal
		og INPUT of P3	
IN_m_ref	:=#IN_m_ref	#IN_m_ref	-- Anal
		og INPUT of m_ref	
IN_m_w	:=#IN_m_w	#IN_m_w	-- Anal
		og INPUT of m_w	

```

T1_connected      :=#T1_connected      #T1_connected      -- 0->
sensor not connected, 1-->
sensor connected

T2_connected      :=#T2_connected      #T2_connected      -- 0->
sensor not connected, 1-->
sensor connected

T3_connected      :=#T3_connected      #T3_connected      -- 0->
sensor not connected, 1-->
sensor connected

Tin_connected     :=#Tin_connected     #Tin_connected     -- 0->
sensor not connected, 1-->
sensor connected

Tout_connected    :=#Tout_connected    #Tout_connected    -- 0->
sensor not connected, 1-->
sensor connected

P1_connected      :=#P1_connected      #P1_connected      -- 0->
sensor not connected, 1-->
sensor connected

P2_connected      :=#P2_connected      #P2_connected      -- 0->
sensor not connected, 1-->
sensor connected

P3_connected      :=#P3_connected      #P3_connected      -- 0->
sensor not connected, 1-->
sensor connected

m_ref_connected   :=#m_ref_connected   #m_ref_connected   -- 0->
sensor not connected, 1-->
sensor connected

m_w_connected     :=#m_w_connected     #m_w_connected     -- 0->
sensor not connected, 1-->
sensor connected

T1_calc           :=#T1sat           #T1sat           -- Satu
ration temperature at 1, t
heoretical value of T1

T2_calc           :=#T2deseada       #T2deseada       -- Desi
red temperature at point 2
r, after the heating resis
tance

T3_calc           :=#T2sat           #T2sat           -- Satu
ration temperature at pres
sure P2

P3_calc           :=#DB_P2           #DB_P2           -- Indi
cate the direction in whic
h the value (measured/theo
rical) must be stored

m_ref_calc        :=#m_ref_grams      //M_ref that would be stored
if the sensor hasn't been c
onnected --> in g/s

m_w_calc          :=#flow_w_lit_min   #flow_w_lit_min   -- Wate
r flux calculated in l/min

displ             :=#displ           #displ           -- Disp
lacement of the compressor

rpm              :=#rpm              #rpm             -- rpm
of the compressor

Cp_w              :=4.180000e+000
delta_T_resistance :=#delta_T_resistance #delta_T_resistance -- Ext
ra temperature degrees to
be obtained above the sat.
T by the resistance

P1_set            :=#P1_set           #P1_set           -- Set
pressured at the operating
point 1

c_vol             :=#c_vol            #c_vol            -- Coef
ficient of the second de
gree equation to calculate
the volumetric eff.

b_iso             :=#b_iso            #b_iso            -- Coef
ficient of the second de
gree equation to calculate
the isentropic eff.

c_iso             :=#c_iso            #c_iso            -- Coef
ficient of the second de
gree equation to calculate
the isentropic eff.

a_iso             :=#a_iso            #a_iso            -- Coef
ficient of the second de
gree equation to calculate
the isentropic eff.

a_vol             :=#a_vol            #a_vol            -- Coef
ficient of the second de
gree equation to calculate
the volumetric eff.

b_vol             :=#b_vol            #b_vol            -- Coef
ficient of the second de
gree equation to calculate
the volumetric eff.

Mode_manual_automatic:=#Mode_manual_automatic #Mode_manual_automatic --
When mode is manual->1, UD
T8

```

```

UDT11_12      :=#UDT11_12      #UDT11_12      -- When
                                     it is 1->inputs to the UD
                                     T 11, when it is 0->output
                                     s to UDT12
x1             :=#x1            #x1            -- Qual
                                     ity of the refrigerant, UD
                                     T 1
ref_number    :=#ref_number    #ref_number    -- Refr
                                     igerant number (0->r134a,
                                     1->r410a, 2->r407c, 3->r22
                                     , 4->r290)
rho_water     :=9.989000e+002
DB_T1         :=#DB_T1        #DB_T1        -- Indi
                                     cate the direction in whic
                                     h the value (measured/theo
                                     rical) must be stored
DB_T3         :=#DB_T3        #DB_T3        -- Indi
                                     cate the direction in whic
                                     h the value (measured/theo
                                     rical) must be stored
DB_P3         :=#DB_P3        #DB_P3        -- Indi
                                     cate the direction in whic
                                     h the value (measured/theo
                                     rical) must be stored
DB_m_ref      :=#DB_m_ref     #DB_m_ref     -- Indi
                                     cate the direction in whic
                                     h the value (measured/theo
                                     rical) must be stored
Tin_chiller   :=#Tin_chiller  #Tin_chiller  -- Temp
                                     erature fixed with the chi
                                     ller
DB_Tout       :=#DB_Tout     #DB_Tout       -- Indi
                                     cate the direction in whic
                                     h the value (measured/theo
                                     rical) must be stored
m_ref_grams   :=#m_ref_grams  #m_ref_grams  -- Refi
                                     rgerant flux calculated in
                                     g/s
flow_w_lit_min :=#flow_w_lit_min #flow_w_lit_min -- Wate
                                     r flux calculated in l/min
T2_deseada    :=#T2deseada    #T2deseada    -- Desi
                                     red temperature at point 2
                                     r, after the heating resis
                                     tance
m_ref_th      :=#m_ref_th     #m_ref_th     -- Refr
                                     igerant flux in kg/s
Qcond_necesitado :=#Qcond_necesitado #Qcond_necesitado -- Heat
                                     exchanged needed in the c
                                     ondenser
m_w_th        :=#m_w_th       #m_w_th        -- Wate
                                     r flux in kg/s
rend_iso_th   :=#rend_iso_th  #rend_iso_th  -- Isen
                                     trope efficiency computed
                                     with the second degree equ
                                     ation
PR            :=#PR          #PR            -- Pres
                                     sure ratio P2measured/P1 s
                                     et
rend_vol_th   :=#rend_vol_th  #rend_vol_th  -- Volu
                                     metric efficiency computed
                                     with the second degree e
                                     quation
DB_P2         :=#DB_P2        #DB_P2        -- Indi
                                     cate the direction in whic
                                     h the value (measured/theo
                                     rical) must be stored
DB_Tin        :=#DB_Tin      #DB_Tin        -- Indi
                                     cate the direction in whic
                                     h the value (measured/theo
                                     rical) must be stored
h1            :=#h3_th       #h3_th        -- Enth
                                     alpy at P1_m, x1
h1_th         :=#h1_th       #h1_th        -- Enth
                                     alpy at the desired pressu
                                     re and quality
h3_th         :=#h3_th       #h3_th        -- Enth
                                     alpy at P1_m, x1
h2_th         :=#h2_th       #h2_th        -- Enth
                                     alpy at point 2, with the
                                     theoretical values
h3_m          :=#h3_m        #h3_m         -- Enth
                                     alpy at point 3
h2_m          :=#h2_m        #h2_m         -- Enth
                                     alpy at 2, with the "meas
                                     ured"value of T2 (if its i
                                     mplemented)
T2sat         :=#T2sat       #T2sat        -- Satu
                                     ration temperature at pres
                                     sure P2

```

```

m_ref_div_rho      :=#m_ref_div_rho      #m_ref_div_rho      -- m_ref
f/rho, displ [m^3/rev]*eff
_vol*rps [rev/s]
DB_P1              :=#DB_P1              #DB_P1              -- Indi
cate the direction in whic
h the value (measured/theo
rical) must be stored
DB_m_w             :=#DB_m_w             #DB_m_w             -- Indi
cate the direction in whic
h the value (measured/theo
rical) must be stored
DB_T2              :=#DB_T2              #DB_T2              -- Indi
cate the direction in whic
h the value (measured/theo
rical) must be stored
Ref_number_11     :=#Ref_number_11     #Ref_number_11     -- Refr
igerant number, UDT 11
P1_m_11           :=#P1_m_11           #P1_m_11           -- P1_m
, UDT 11
P1_set_11         :=#P1_set_11         #P1_set_11         -- P1_s
et, UDT 11
x1_11             :=#x1_11             #x1_11             -- x1,
UDT 11
Tout_m_11        :=#Tout_m_11        #Tout_m_11        -- Tout
_m, UDT 11
P2_m_11           :=#P2_m_11           #P2_m_11           -- P2_m
, UDT 11
delta_T_resistance_11:=#delta_T_resistance_11 -- delta_T_resistance, UDT 11
#m_w_m_11         :=#m_w_m_11         #m_w_m_11         -- m_w_
m, UDT 11
m_ref_div_rho_11  :=#m_ref_div_rho_11  #m_ref_div_rho_11  -- m-re
f_div_rho, UDT 11
T2_m_11           :=#T2_m_11           #T2_m_11           -- T2_m
, UDT 11
T1sat_12          :=#T1sat_12          #T1sat_12          -- T1_s
at, UDT 12
h1_th_12         :=#h1_th_12         #h1_th_12         -- h1_t
h, UDT 12
h1_12            :=#h1_12            #h1_12            -- h1,
UDT 12
T2sat_12          :=#T2sat_12          #T2sat_12          -- T2sa
t, UDT 12
h2_th_12         :=#h2_th_12         #h2_th_12         -- h2_
th, UDT 12
h3_th_12         :=#h3_th_12         #h3_th_12         -- h3_t
h, UDT 12
T2desired_12     :=#T2desired_12     #T2desired_12     -- T2de
sired, UDT 12
rho_ref_12        :=#rho_ref_12        #rho_ref_12        -- rho_
ref, UDT 12
h2_m_12          :=#h2_m_12          #h2_m_12          -- h2_m
, UDT 12
h3_m_12          :=#h3_m_12          #h3_m_12          -- h3_m
, UDT 12
m_ref_th_12      :=#m_ref_th_12      #m_ref_th_12      -- m_re
f_th, UDT 12
m_ref_grams_12   :=#m_ref_grams_12   #m_ref_grams_12   -- m_re
f_grams, UDT 12
T1sat            :=#T1sat            #T1sat            -- Satu
ration temperature at 1, t
heoretical value of T1
T2desired        :=#T2desired        #T2desired        -- Desi
red temperature after the
heating resistance
rho_ref          :=#rho_ref          #rho_ref          -- Refr
igerant density (entering
of the compressor)

```

//The variables X_calc-->might not be necesaiies if we dont want to store the calculated values in the DB were the measured values are being kept.

Segm.: 2 PID Control: Pump, EEV & Resistance

Once that the real and desired values are known (they have been import/export from a database), the control orders must be defined.

```

CALL "AUT_Control PID"          FC7
P3                             :=#DB_P3          #DB_P3          -- Indicate the direction in which the value
(m_easured/theoretical) must be stored
P1_set                          :=#P1_set        #P1_set        -- Set pressured at the operating point 1
OFF                             :=#OFF          #OFF          -- Indicator of the OFF state of the station

```



```

m_w_th      :=#m_w_th      #m_w_th      -- Water flux in kg/s
m_w         :=#DB_m_w      #DB_m_w      -- Indicate the direction in which the value
              (measured/theoretical) must be stored
T2deseada   :=#T2deseada   #T2deseada   -- Desired temperature at point 2r, after th
              e heating resistance
T2          :=#DB_T2       #DB_T2       -- Indicate the direction in which the value
              (measured/theoretical) must be stored
P1          :=#DB_P1       #DB_P1       -- Indicate the direction in which the value
              (measured/theoretical) must be stored
resistance_relay_dir:=#Dir_res #Dir_res     -- Digital output--> Resistance (x.1)
Dir_pump    :=#Dir_pump    #Dir_pump    -- Analog output-> PUMP ("2+x"24)
Dir_EEV     :=#Dir_EEV     #Dir_EEV     -- Analog output--> EEV  ("2+x"28)
orden_EEV   :=#orden_EEV_int #orden_EEV_int -- EEV order, INT
orden_pump  :=#orden_pump_real #orden_pump_real -- Pump order, REAL
orden_pump_int :=#orden_pump_int #orden_pump_int -- Pump order, INT
orden_EEVreal :=#orden_EEVreal #orden_EEVreal -- EEV order, REAL

```

```
//Compressor ON
```

```

UN  #ON_OFF      #ON_OFF      -- Indicates when the station is ON (-->1),
=   #OFF         or OFF (-->0)  -- Indicator of the OFF state of the station
S   #Dir_comp    #Dir_comp    -- Digital output that controls the compress
              or (x.0)

```

FC98 - <offline>

"MAN_SensON/SensOFF->th"

Nombre:**Familia:****Autor:****Versión:** 0.1**Hora y fecha Código:****Versión del bloque:** 2

07/06/2014 10:44:17

Interface: 05/06/2014 12:20:55**Longitud (bloque / código / datos):** 00780 00586 00016**Propiedades del objeto:**

S7_language 9(1) Inglés (Estados Unidos) 23/05/2014 13:19:47

Nombre	Tipo de datos	Dirección	Comentario
IN		0.0	
IN_T2	Int	0.0	Analog INPUT of T2
IN_P1	Int	2.0	Analog INPUT of P1
IN_P2	Int	4.0	Analog INPUT of P2
IN_P3	Int	6.0	Analog INPUT of P3
IN_m_w	Int	8.0	Analog INPUT of m_w
T2_connected	Bool	10.0	0-> sensor not connected, 1--> sensor connected
P1_connected	Bool	10.1	0-> sensor not connected, 1--> sensor connected
P2_connected	Bool	10.2	0-> sensor not connected, 1--> sensor connected
P3_connected	Bool	10.3	0-> sensor not connected, 1--> sensor connected
m_w_connected	Bool	10.4	0-> sensor not connected, 1--> sensor connected
T2_calc	Real	12.0	Theoretical/set/calculated value of the magnitude
P3_calc	Real	16.0	Theoretical/set/calculated value of the magnitude->P2
Mode_manual_automatic	Bool	20.0	When mode is manual->1, UDT8
OUT		0.0	
IN_OUT		0.0	
DB_P1	Real	22.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_P2	Real	26.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_P3	Real	30.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_T2	Real	34.0	Indicate the direction in which the value (measured/theoretical) must be stored
DB_m_w	Real	38.0	Indicate the direction in which the value (measured/theoretical) must be stored
T2sat	Real	42.0	Saturation temperature at pressure P2
TEMP		0.0	
RETURN		0.0	
RET_VAL		0.0	

Bloque: FC98 Measurement of the sensors/calculate the theoretical values

The measurements of the sensors will be conditionate and stored. First the sensors that MUST BE CONECTED would be measured.
 With this measured values, the theoretical ones can be computed.
 Then the program check wether T1, T2, P3 and m_ref are connected. If they are, it measures their values, otherwise, the theoretical values calculated are stored.

```
Segm.: 1      Measurement of the sensors IMPLEMENTED FOR SURE
```

```
The data will be measured, conditionate and stored.
```

```
The FC 105 "SCALE" takes an input between the Hi and Lo limits, and transforms
it in a bipolar way (-27.648, +27.648) or unipolar(0,+ 27.648), obtaining an
output between K1 and K2 (0,27.648)--> unipolar
```

```
//TEMPERATURE T_OUT
```

```
//      U      #Tout_connected
//      SPB    To_M
```

```
//PRESSURE 1
```

```
      U      #P1_connected          #P1_connected      -- 0-> sensor not
      SPB    M_P1                   connected, 1--> sensor connected
```

```
//PRESSURE 2
```

```
C_P2: U      #P2_connected          #P2_connected      -- 0-> sensor not
      SPB    M_P2                   connected, 1--> sensor connected
      SPA    SEG2
```

```
//*****//
// MEASUREMENTS //
//*****//
```

```
//To_M: CALL "SCALE"                // Termopar Tout
```

```
//      IN      :=#IN_Tout
//      HI_LIM :=3.000000e+001
//      LO_LIM :=5.000000e+000
//      BIPOLAR:=FALSE
//      RET_VAL:=MW0
//      OUT      :=#DB_Tout
//Check the sensor P2
//      SPA    C_P1
```

```
M_P1: CALL "SCALE"                  //Presión 1, puesto 1
```

```
      IN      :=#IN_P1
```

```
FC105                                -- Scaling Values
#IN_P1                                -- Analog INPUT of
P1
```

```
      HI_LIM :=6.000000e+001
      LO_LIM :=1.000000e+000
      BIPOLAR:=FALSE
      RET_VAL:=MW0
      OUT      :=#DB_P1
```

```
#DB_P1                                -- Indicate the di
rection in which the value (measured/
theoretical) must be stored
```

```
// Check the sensor P2
```

```
      SPA    C_P2
```

```
M_P2: CALL "SCALE"                  //Presión 2, puesto 1
```

```
      IN      :=#IN_P2
```

```
FC105                                -- Scaling Values
#IN_P2                                -- Analog INPUT of
P2
```

```
      HI_LIM :=6.000000e+001
      LO_LIM :=1.000000e+000
      BIPOLAR:=FALSE
      RET_VAL:=MW0
      OUT      :=#DB_P2
```

```
#DB_P2                                -- Indicate the di
rection in which the value (measured/
theoretical) must be stored
```

```
      SPA    SEG2
```

```
Segm.: 2      EXCEL INTERFACE
```

```
/**WITH THE DATA MEASURED WE HAVE TO OBTAIN rho_ref...
```

```
//SENT
```

```
//-->P1measured,P1_set,x1, P2mesasured,delta_T_resistence,T2desired
```

```
//--> Tin_chiller, Tout measured, Refrigerant--> Num_ref(0->134a,1->410a,2->407c, 3->22)
```

```
//RECEIVE
```

```
//--> T1sat, T2 sat
```

```
//-->h1_th(P1set,x1),h1(P1,x1), h2_th (P2,T2desired), h3_th (P2, T2sat),
```

```
//--> rho_ref, rho_water
```

```
//T1_SAT TIENE QUE SER CALCULADA, SI NO HAY SENSOR EN T1 ENTONCES SE TOMA ESE VALOR COMO REAL
```

```
SEG2: NOP 0
```

```
SPA SEG4
```

```
Segm.: 3 Check and measured the rest of the sensors
```

```
If the rest of the sensors are not connected, the theoretical values calculated above must be stored.
```

```
//TEMPERATURE 1
```

```
//SEG4:// U #T1_connected
// SPB T1_M
```

```
//If the sensor is not connected, we employ de theoretical value
//NO se si esto debería hacerse.Cuando no haya sensor, nos lo indica el X_conectado
//Si no está conecttado en las parametrizado habrá que poner el valor teórico y el "medido"
//Yque el código emplee para los cálculos uno o otro dependiendo del resultado.
```

```
//La gráfica dibuja lo del DB_T1 (medido) si queremos evitar que dibuje el valor teórico cuando no esta conect
ado
//habria que guardar el teórico en otro lado
```

```
// CALL "Sensor conect/desconect"
// Sensor_conectado:=#T1_connected
// Valor_teorico :=
// Valor_a_GUARDAR :=
```

```
//TEMPERATURE 2
```

```
SEG4: NOP 0
U #T2_connected #T2_connected -- 0-> sensor
not connected, 1--> sensor connec
ted

SPB T2_M

CALL "Sensor conect/desconect" FC3
Sensor_conectado:=#T2_connected #T2_connected -- 0-> sensor
not connected, 1--> sensor connec
ted

Valor_teorico :=#T2_calc //T2 sat + delta_T #T2_calc -- Theoretical
/set/calculated value of the magn
itude

Valor_a_GUARDAR :=#DB_T2 #DB_T2 -- Indicate th
e direction in which the value (m
easured/theoretical) must be stored
```

```
//If the sensor T2 is connected, then the value measured (after the aconditionating processs)
//then, it will be stored in the UDT1_1.T2
//If not, the corresponding value of T2sat ( saturation temperature at the pressure P2)
//will be considered as valid, and stored in the UDT
```

```
//TEMPERATURE 3
```

```
//C_T3: U #T3_connected
// SPB T3_M

// CALL "Sensor conect/desconect"
// Sensor_conectado:=#T3_connected
// Valor_teorico :=#T3_calc //T2sat
// Valor_a_GUARDAR :=#DB_T3
```

```
//If the sensor T3 is connected, then the value measured (after the aconditionating processs)
//then, it will be stored in the UDT1_1.T3
//If not, the corresponding value of T2sat ( saturation temperature at the pressure P2=P3)
// will be considered as valid, and stored in the UDT1_T3
```

```
//TEMPERATURE T_IN
```

```
//C_Ti: U #Tin_connected
// SPB Ti_M
```

```
//If the sensor is not connected, we employ de theoretical value
```

```
// CALL "Sensor conect/desconect"
// Sensor_conectado:=#Tin_connected
// Valor_teorico :=#Tin_chiller
// Valor_a_GUARDAR :=#DB_Tin
```

```
//PRESSURE 3
```

```

C_P3: U      #P3_connected                                #P3_connected      -- 0-> sensor
                                                         not connected, 1--> sensor connec
                                                         ted

      SPB      M_P3

//If the sensor is not connected, we employ the value of P2 MEASURED

      CALL "Sensor conect/desconect"                    FC3
      Sensor_conectado:=#P3_connected                  #P3_connected      -- 0-> sensor
                                                         not connected, 1--> sensor connec
                                                         ted
      Valor_teorico   :=#P3_calc                       #P3_calc           -- Theoretical
                                                         /set/calculated value of the magni
                                                         tude->P2
      Valor_a_GUARDAR :=#DB_P3                        #DB_P3             -- Indicate th
                                                         e direction in which the value (m
                                                         easured/theoretical) must be stored

//WATER

C_WF: U      #m_w_connected                              #m_w_connected     -- 0-> sensor
                                                         not connected, 1--> sensor connec
                                                         ted

      SPB      W_M

      SPA      SEG5

//IF THE SENSORS ARE CONNECTED//

//T1_M: CALL "SCALE"                                     // Measure T1, T1
//      IN      :=#IN_T1
//      HI_LIM :=8.000000e+001
//      LO_LIM :=5.000000e+000
//      BIPOLAR:=FALSE
//      RET_VAL:=MW0
//      OUT     :=#DB_T1
//Go to the comprobation of the sensor T2
//      SPA      C_T2

T2_M: CALL "SCALE"                                     // Measured T2
      IN      :=#IN_T2
      HI_LIM :=8.000000e+001
      LO_LIM :=5.000000e+000
      BIPOLAR:=FALSE
      RET_VAL:=MW0
      OUT     :=#DB_T2
      FC105                                     -- Scaling Val
      ues
      #IN_T2                                     -- Analog INPU
      T of T2
      #DB_T2                                     -- Indicate th
      e direction in which the value (m
      easured/theoretical) must be stored

//Check the sensor T2
//      SPA      C_T3

//T3_M: CALL "SCALE"                                     // Termopar 1, T3_P1
//      IN      :=#IN_T3
//      HI_LIM :=8.000000e+001
//      LO_LIM :=5.000000e+000
//      BIPOLAR:=FALSE
//      RET_VAL:=MW0
//      OUT     :=#DB_T3

// Check the sensor Tin
//      SPA      C_Ti

//Ti_M: CALL "SCALE"                                     // Termopar 1, Tin_P1
//      IN      :=#IN_Tin
//      HI_LIM :=3.000000e+001
//      LO_LIM :=5.000000e+000
//      BIPOLAR:=FALSE
//      RET_VAL:=MW0
//      OUT     :=#DB_Tin

// Check the sensor P3

      SPA      C_P3

M_P3: CALL "SCALE"                                     //Presión 3, puesto 1
      FC105                                     -- Scaling Val
      ues

```

```

IN      :=#IN_P3                                #IN_P3          -- Analog INPU
                                                T of P3

HI_LIM :=6.000000e+001
LO_LIM :=1.000000e+000
BIPOLAR:=FALSE
RET_VAL:=MW0
OUT     :=#DB_P3                                #DB_P3          -- Indicate th
                                                e direction in which the value (m
easured/theoretical) must be stored

// Check the sensor m_ref
SPA    C_WF

W_M: CALL "SCALE"                               //m_w           FC105          -- Scaling Val
                                                ues
IN      :=#IN_m_w                                #IN_m_w        -- Analog INPU
                                                T of m_w
HI_LIM :=5.500000e+001                          //lo máximo son 5 l/min, pongo 5,5 l/min
LO_LIM :=0.000000e+000                          //lo mínimo es 0.25 l/min, pongo 0.0 l/min
BIPOLAR:=FALSE
RET_VAL:=MW0
OUT     :=#DB_m_w                                #DB_m_w        -- Indicate th
                                                e direction in which the value (m
easured/theoretical) must be stored

SPA    SEG5

```

Segm.: 4	EXCEL INTERFACE 2.0
----------	---------------------

h2, h3, rho_w...with the new measurements of the sensors (in case that they have been connected)their values might change

```

/**WITH THE DATA MEASURED WE HAVE TO OBTAIN rho_ref...
//SENT
//-->T1 measured, P1measured,P1_set,x1, P2mesasured, T2 measured, P3 measured, T3 measured
//--> Tin_chiller, Tout measured,

//RECEIVE
//-->h1_th,h1, h2,h3,rho_ref, rho_water, Cp_w

SEG5: NOP    0
      SPA    END

```

Segm.: 5	END
----------	-----

END segment

```

END: NOP    0

```

FC99 - <offline>

"DiagramIntermitencias"

Nombre:**Familia:****Autor:****Versión:** 0.1**Hora y fecha Código:****Versión del bloque:** 2

11/06/2014 16:46:08

Interface: 09/06/2014 17:55:42**Longitud (bloque / código / datos):** 00186 00078 00002

Nombre	Tipo de datos	Dirección	Comentario
IN		0.0	
intermitencias	Int	0.0	Controls the "movement" of the diagram in WINCC
ON_OFF	Bool	2.0	ON_OFF of the station
OUT		0.0	
IN_OUT		0.0	
TEMP		0.0	
Reset_end_timer	Bool	0.0	End of the time, reset the timer
RETURN		0.0	
RET_VAL		0.0	

Bloque: FC99 INTERMITENCIAS

In the HMI (WINCC) the diagram that shows the cycle, the refrigerant flux can be added. In other words, there is the possibility to create "intermitencias" and make the illusion that the user is actually seeing the refrigerant flux.

Segm.: 1 Timer

The timer would set when the variable "intermitencias", that controls the "movement" of the diagram, increase its value.

```

U   #Reset_end_timer  #Reset_end_timer  -- End of the time, reset the timer
FR  T   99

U   #ON_OFF           #ON_OFF           -- ON_OFF of the station
L   S5T#100MS
SE  T   99
U   T   99
=   #Reset_end_timer  #Reset_end_timer  -- End of the time, reset the timer
U   #Reset_end_timer  #Reset_end_timer  -- End of the time, reset the timer
SPB ADD
SPA END

ADD: L   #intermitencias  #intermitencias  -- Controls the "movement" of the diagram in WINCC
L   1
+I
T   #intermitencias  #intermitencias  -- Controls the "movement" of the diagram in WINCC

L   #intermitencias  #intermitencias  -- Controls the "movement" of the diagram in WINCC
L   9
==I
SPB RSET
SPA END

RSET: L   0
T   #intermitencias  #intermitencias  -- Controls the "movement" of the diagram in WINCC

END: NOP  0

```

DB10 - <offline> - Declaración

"Puestos1"

DB de datos globales 10

Nombre:**Familia:****Autor:****Versión:** 0.1**Versión del bloque:** 2**Hora y fecha Código:**

11/06/2014 16:31:09

Interface:

11/06/2014 16:31:09

Longitud (bloque / código / datos): 00862 00402 00000**Bloque:** DB10

Dirección	Nombre	Tipo	Valor inicial	Comentario
0.0		STRUCT		
+0.0	UDT1 1	"Vector Sensors & Quality"		
+64.0	UDT2 1	"ThermodynamicProperties"		
+198.0	UDT3 1	"Control Orders"		
+234.0	UDT4 1	"Sensors&Stations_Actives"		
+244.0	UDT5 1	"Conversions"		
+268.0	UDT6 1	"Aux Operations"		
+306.0	UDT7 1	"Coeff for the eff, PR"		
+354.0	UDT8 1	"WINCC var"		
+370.0	UDT9 1	"START/STOP"		
+372.0	UDT10 1	"AlarmSettings"		
+400.0	STOP_ALL	BOOL	FALSE	All the stations must be turned off simustaneously
+400.1	START_ALL	BOOL	FALSE	All the stations must be turned on simustaneously
=402.0		END STRUCT		

DB11 - <offline> - Declaración

"Excel_Interface"

DB de datos globales 11

Nombre: Familia:
Autor: Versión: 0.1
Hora y fecha Código: Versión del bloque: 2
13/06/2014 16:29:03
Interface: 13/06/2014 16:29:03
Longitud (bloque / código / datos): 00224 00086 00000

Bloque: DB11

Dirección	Nombre	Tipo	Valor inicial	Comentario
0.0		STRUCT		
+0.0	UDT11_1	"Excel_INPUTS"		
+38.0	UDT12_1	"Excel_OUTPUTS"		
=86.0		END_STRUCT		

UDT1 - <offline>

"Vector_Sensors_&Quality"

Nombre: **Familia:**
Autor: **Versión:** 0.1
Versión del bloque: 2
Hora y fecha Código: 04/06/2014 13:37:42
Interface: 04/06/2014 13:37:42
Longitud (bloque / código / datos): 00000 00000 00000

Propiedades del objeto:

S7_language 9(1) Inglés (Estados Unidos) 23/05/2014 13:19:47

Dirección	Nombre	Tipo	Valor inicial	Comentario
0.0		STRUCT		
+0.0	x1	REAL	0.000000e+000	Quality
+4.0	T1_m	REAL	0.000000e+000	Input temperature of the compressors refrigerant
+8.0	T2_m	REAL	0.000000e+000	Input temperature of the condenser
+12.0	T3_m	REAL	0.000000e+000	Output temperature of the condenser
+16.0	Tin_m	REAL	0.000000e+000	Water input temperature
+20.0	Tout_m	REAL	0.000000e+000	Water output temperature
+24.0	P1_m	REAL	0.000000e+000	Input pressure of the compressor
+28.0	P2_m	REAL	0.000000e+000	input pressure of the condenser
+32.0	P3_m	REAL	0.000000e+000	Output pressure of the condenser
+36.0	m_ref_m	REAL	0.000000e+000	Refrigerant flux
+40.0	m_w_m	REAL	0.000000e+000	Water flux
+44.0	P1_set	REAL	0.000000e+000	Pressure desired at point one
+48.0	Tin_chiller	REAL	0.000000e+000	Tin temperature fixed with the chiller
+52.0	Ref number	INT	0	0->R134A , 1->R410A, 2->R407C, 3->R22
+54.0	c111	INT	0	
+56.0	C12	REAL	0.000000e+000	
+60.0	C13	REAL	0.000000e+000	
=64.0		END_STRUCT		

UDT2 - <offline>

"ThermodynamicProperties"

Nombre:**Familia:****Autor:****Versión:** 0.1**Hora y fecha Código:****Versión del bloque:** 2

13/06/2014 15:11:53

Interface: 30/05/2014 17:17:00**Longitud (bloque / código / datos):** 00000 00000 00000**Propiedades del objeto:**

S7_language 9(1) Inglés (Estados Unidos) 23/05/2014 13:19:47

Dirección	Nombre	Tipo	Valor inicial	Comentario
0.0		STRUCT		
+0.0	Refrigerante	STRING[8]	'R134A'	
+10.0	h1_th	REAL	0.000000e+000	Enthalpy at point 1, according to the desired P1
+14.0	h2s_th	REAL	0.000000e+000	Theoretical enthalpy at the exit of the compressor , if it was isentropic
+18.0	h2c_th	REAL	0.000000e+000	Theoretical enthalpy at the exit of the compressor , no isentropic
+22.0	h2_m	REAL	0.000000e+000	Enthalpy at point 2, with measured data
+26.0	h3_m	REAL	0.000000e+000	Enthalpy at point 3, with measured data
+30.0	T2sat	REAL	0.000000e+000	Saturation temperature for P2
+34.0	T1sat	REAL	0.000000e+000	Theoretical temperatura ata point1, saturation temperature for P1
+38.0	T2c_th	REAL	0.000000e+000	Theoretical temperature at the exit of the compressor
+42.0	T2deseada	REAL	0.000000e+000	Desired temperatura at point 2, T2sat+delta_T_resistance
+46.0	s1	REAL	0.000000e+000	Entropy at point 1
+50.0	rho_ref	REAL	0.000000e+000	Refrigerant density at the entering og the compressor
+54.0	rho_ref_after_res	REAL	0.000000e+000	Refrigerant density after the heating resistance
+58.0	rho_water	REAL	0.000000e+000	Water density
+62.0	Cp_w	REAL	0.000000e+000	Especific heat
+66.0	delta_h_condenser	REAL	0.000000e+000	Difference of enthalpies in the condenser
+70.0	delta_h_res	REAL	0.000000e+000	Difference of enthalpies for the heating resistance
+74.0	delta_Pressure_EEV	REAL	0.000000e+000	Pressure's difference to achieve by the EEV
+78.0	delta_caudal_deseado_rea	REAL	0.000000e+000	Difference between the desired and the real water flux
+82.0	m_ref_th	REAL	0.000000e+000	Theoretical refrigerant flux (kg/s)
+86.0	m_w_th	REAL	0.000000e+000	Theoretical water flux (kg/s)
+90.0	Qcond_necesitado	REAL	0.000000e+000	Heat exchanged in the condenser
+94.0	Qres_necesitado	REAL	0.000000e+000	Heat exchanged by the resistance
+98.0	flow_w_lit_min	REAL	0.000000e+000	Desired water flux (l/min)
+102.0	rend_vol_th	REAL	0.000000e+000	Theoretical volumetric efficiency
+106.0	rend_iso_th	REAL	0.000000e+000	Theoretical isentropic efficiency
+110.0	rpm	REAL	0.000000e+000	Revolutions per minute
+114.0	displ	REAL	0.000000e+000	Displacement -->CC/rev
+118.0	h1	REAL	0.000000e+000	Enthalpy computed with the data of the sensor in the operating point 1
+122.0	delta_T_resistance	REAL	0.000000e+000	Extra temperature degrees above the sat.T° to be obtained by the resistance
+126.0	h2_th	REAL	0.000000e+000	Enthalpy at point 2, with theoretical data
+130.0	h3_th	REAL	0.000000e+000	Enthalpy at point 2, with theoretical data
=134.0		END_STRUCT		

UDT3 - <offline>

"Control Orders"

Nombre: **Familia:**
Autor: **Versión:** 0.1
Versión del bloque: 2
Hora y fecha Código: 04/06/2014 11:13:21
Interface: 02/06/2014 11:44:22
Longitud (bloque / código / datos): 00000 00000 00000

Propiedades del objeto:

S7_language 9(1) Inglés (Estados Unidos) 23/05/2014 13:19:47

Dirección	Nombre	Tipo	Valor inicial	Comentario
0.0		STRUCT		
+0.0	Orden_EEV_int	INT	0	Control signal of the EEV
+2.0	Orden_pump_int	INT	0	Control signal of the water pump
+4.0	Orden_resistance	BOOL	FALSE	Control pulse signal for the heating resistance
+6.0	Man_delta_T_res_int	INT	0	When manual mode is activated it gives the "order" for the resistance
+8.0	Man_delta_P_EEV_int	INT	0	When manual mode is activated it gives the "order" for the EEV
+10.0	Man_WF_pump_int	INT	0	When manual mode is activated it gives the "order" for the pump
+12.0	Man_delta_T_res_real	REAL	0.000000e+000	
+16.0	Man_delta_P_EEV_real	REAL	0.000000e+000	
+20.0	Man_WF_pump_real	REAL	0.000000e+000	
+24.0	C1	REAL	0.000000e+000	
+28.0	C2	REAL	0.000000e+000	
+32.0	C3	REAL	0.000000e+000	
=36.0		END_STRUCT		

UDT4 - <offline>

"Sensors&Stations_Actives"

Nombre: **Familia:**
Autor: **Versión:** 0.1
Hora y fecha Código: **Versión del bloque:** 2
04/06/2014 10:02:29
Interface: 04/06/2014 10:02:29
Longitud (bloque / código / datos): 00000 00000 00000

Propiedades del objeto:

S7_language 9(1) Inglés (Estados Unidos) 23/05/2014 13:19:47

Dirección	Nombre	Tipo	Valor inicial	Comentario
0.0		STRUCT		
+0.0	Puesto_habilitado	BOOL	FALSE	Indicates if the station is "built", if it can be turned ON
+0.1	T1_conectado	BOOL	FALSE	Indicates the connection state of the sensor T1
+0.2	P1_conectado	BOOL	FALSE	Indicates the connection state of the sensor P1
+0.3	T2_conectado	BOOL	FALSE	Indicates the connection state of the sensor T2
+0.4	P2_conectado	BOOL	FALSE	Indicates the connection state of the sensor P2
+0.5	T3_conectado	BOOL	FALSE	Indicates the connection state of the sensor T3
+0.6	P3_conectado	BOOL	FALSE	Indicates the connection state of the sensor P3
+0.7	Tin_conectado	BOOL	FALSE	Indicates the connection state of the sensor Tin
+1.0	Tout_conectado	BOOL	FALSE	Indicates the connection state of the sensor Tout
+1.1	Qw_conectado	BOOL	FALSE	Indicates the connection state of the sensor Qw
+1.2	Resistance_conectado	BOOL	FALSE	Indicates if a heating resistance can be used
+1.3	m_ref_conectado	BOOL	FALSE	Indicates the connection state of the sensor m_ref
+1.4	ON OFF	BOOL	FALSE	Indicates if the station is ON (ON=1, OFF=0)
+1.5	OFF	BOOL	TRUE	Indicates if the station is OFF (OFF=1, ON=0)
+1.6	AUXI_COMP	BOOL	FALSE	Its an auxiliar variable, in order to make the comparisons
+1.7	AUXI_COMP_MANUAL	BOOL	FALSE	Its an auxiliar variable, in order to make the comparisons in MANUAL mode
+2.0	c1	REAL	0.000000e+000	
+6.0	c2	INT	0	
+8.0	c3	BOOL	FALSE	
=10.0		END STRUCT		

UDT5 - <offline>

"Conversions"

Nombre: Familia:
Autor: Versión: 0.1
Hora y fecha Código: Versión del bloque: 2
 04/06/2014 11:13:05
Interface: 04/06/2014 10:01:57
Longitud (bloque / código / datos): 00000 00000 00000

Propiedades del objeto:

S7_language 9(1) Inglés (Estados Unidos) 23/05/2014 13:19:47

Dirección	Nombre	Tipo	Valor inicial	Comentario
0.0		STRUCT		
+0.0	orden_EEVreal	REAL	0.000000e+000	EEV control order
+4.0	orden_pump_real	REAL	0.000000e+000	Pump control order, REAL
+8.0	P1	REAL	0.000000e+000	
+12.0	P2	REAL	0.000000e+000	
+16.0	P3	REAL	0.000000e+000	
+20.0	P4	INT	0	
+22.0	P5	WORD	W#16#0	
=24.0		END_STRUCT		

UDT6 - <offline>

"Aux_Operations"

Nombre: Familia:
Autor: Versión: 0.1
Hora y fecha Código: Versión del bloque: 2
 13/06/2014 15:13:47
Interface: 04/06/2014 09:59:31
Longitud (bloque / código / datos): 00000 00000 00000

Propiedades del objeto:

S7_language 9(1) Inglés (Estados Unidos) 23/05/2014 13:19:47

Dirección	Nombre	Tipo	Valor inicial	Comentario
0.0		STRUCT		
+0.0	m_ref_grams	REAL	0.000000e+000	m_ref_th*1000--> [g/s]
+4.0	m_ref_div_rho	REAL	0.000000e+000	Is m_ref/rho--> displ[m^3/rev]*rps[rev/s]*rend_vol
+8.0	AUXI_2	REAL	0.000000e+000	
+12.0	AUXI_3	REAL	0.000000e+000	
+16.0	AUXI_4	REAL	0.000000e+000	
+20.0	AUXI_5	REAL	0.000000e+000	
+24.0	AUXI_6	REAL	0.000000e+000	
+28.0	AUXI_7	REAL	0.000000e+000	
+32.0	AUXI_8	INT	0	
+34.0	AUXI_9	INT	0	
+36.0	AUXI_10	INT	0	
=38.0		END_STRUCT		

UDT7 - <offline>

"Coeff for the eff, PR"

Nombre:**Familia:****Autor:****Versión:** 0.1**Versión del bloque:** 2**Hora y fecha Código:**

13/06/2014 15:10:31

Interface:

03/06/2014 11:56:02

Longitud (bloque / código / datos): 00000 00000 00000

Dirección	Nombre	Tipo	Valor inicial	Comentario
0.0		STRUCT		
+0.0	a_iso	REAL	0.000000e+000	Coefficient "a" of the second degree equation to calculate the isentropic eff.
+4.0	b_iso	REAL	0.000000e+000	Coefficient "b" of the second degree equation to calculate the isentropic eff.
+8.0	c_iso	REAL	0.000000e+000	Coefficient "c" of the second degree equation to calculate the isentropic eff.
+12.0	a_vol	REAL	0.000000e+000	Coefficient "a" of the second degree equation to calculate the volumetric eff.
+16.0	b_vol	REAL	0.000000e+000	Coefficient "b" of the second degree equation to calculate the volumetric eff.
+20.0	c_vol	REAL	0.000000e+000	Coefficient "c" of the second degree equation to calculate the volumetric eff.
+24.0	a1	REAL	0.000000e+000	
+28.0	a2	REAL	0.000000e+000	
+32.0	a3	REAL	0.000000e+000	
+36.0	PR	REAL	0.000000e+000	Pressure ratio P2measured/P1set--> To calculate the efficiencies
+40.0	PRint	INT	0	In manual mode Pressure ratio P2measured/P1set--> To calculate the efficiencies
+42.0	c1	INT	0	
+44.0	c2	REAL	0.000000e+000	
=48.0		END STRUCT		

UDT8 - <offline>

"WINCC_var"

Nombre:**Familia:****Autor:****Versión:** 0.1**Versión del bloque:** 2**Hora y fecha Código:**

11/06/2014 16:30:58

Interface:

09/06/2014 10:12:07

Longitud (bloque / código / datos): 00000 00000 00000

Dirección	Nombre	Tipo	Valor inicial	Comentario
0.0		STRUCT		
+0.0	Num_puestos	INT	1	Variable que indica el numero de puestos POSIBLES a indicar como implementados
+2.0	intermitencia	INT	0	It shows the "circulation" od the refrigerant in the WINCC diagram
+4.0	Mode_Automatic_Manual	BOOL	TRUE	It determine wehter the cycle works automatically (1) or in a manual way (0)
+4.1	Manual_compressor	BOOL	FALSE	Test the correct functioning of the compressor in the manual mode
+4.2	Manual_resistance	BOOL	FALSE	Test the correct functioning of the resistance
+4.3	Manual_EEV	BOOL	FALSE	test the correct funtioning of the EEV
+4.4	Manual_Pump	BOOL	FALSE	Test the correct functioning of the pump
+4.5	Mode_manual_automatic	BOOL	FALSE	It determine wehter the cycle works automatically (0) or in a manual way (1)
+4.6	Equipment_button	BOOL	FALSE	Itchanges the color when the quick acces botton of the stations equipment.
+4.7	Setup_button	BOOL	FALSE	Itchanges the color when the quick acces botton of the stations set up.
+5.0	Equip_ref_select_all	BOOL	FALSE	
+5.1	Equip_water_select_all	BOOL	FALSE	
+5.2	b2	BOOL	FALSE	
+5.3	b3	BOOL	FALSE	
+5.4	b4	BOOL	FALSE	
+5.5	b5	BOOL	FALSE	
+5.6	b6	BOOL	FALSE	
+5.7	b7	BOOL	FALSE	
+6.0	C1	BYTE	B#16#0	
+8.0	C2	INT	0	
+10.0	C3	INT	0	
+12.0	c21	REAL	0.000000e+000	
=16.0		END_STRUCT		

UDT9 - <offline>

"START/STOP"

Nombre: **Familia:**
Autor: **Versión:** 0.1
Versión del bloque: 2
Hora y fecha Código: 05/06/2014 17:21:41
Interface: 04/06/2014 09:53:00
Longitud (bloque / código / datos): 00000 00000 00000

Dirección	Nombre	Tipo	Valor inicial	Comentario
0.0		STRUCT		
+0.0	MAN_button_STOP	BOOL	TRUE	It is the stop order of the sation
+0.1	MAN_button_START	BOOL	FALSE	It is the start order
+0.2	Button_start_all	BOOL	FALSE	Just for the HMI
+0.3	Button_stop_all	BOOL	FALSE	Just for the HMI
+0.4	c12	BOOL	FALSE	
+0.5	c13	BOOL	FALSE	
=2.0		END_STRUCT		

UDT10 - <offline>

"AlarmSettings"

Nombre: **Familia:**
Autor: **Versión:** 0.1
Versión del bloque: 2
Hora y fecha Código: 16/06/2014 10:05:40
Interface: 11/06/2014 16:30:46
Longitud (bloque / código / datos): 00000 00000 00000

Dirección	Nombre	Tipo	Valor inicial	Comentario
0.0		STRUCT		
+0.0	DeviationP1	REAL	0.000000e+000	Maximum deviation of P1 allowed
+4.0	DeviationT1	REAL	0.000000e+000	Maximum deviation of T1 allowed
+8.0	MaxP2	REAL	0.000000e+000	Maximum value of P2 allowed
+12.0	MaxT2	REAL	0.000000e+000	Maximum value of T2 allowed
+16.0	T1_Low	BOOL	FALSE	Indicates when the temperaure 1 is beyond the minimum value
+16.1	T1_High	BOOL	FALSE	Indicates when the temperature 1 is above the maximum value
+16.2	T1_Error	BOOL	FALSE	Inticates when an error because of the temperature 1 (lower or greater)
+16.3	P1_Low	BOOL	FALSE	Indicates when the pressure 1 is beyond the minimum value
+16.4	P1_High	BOOL	FALSE	Indicates when the pressure 1 is above the maximum value
+16.5	P1_Error	BOOL	FALSE	Indicates when an error because of the pressure 1 (lower or greater)
+16.6	T2_Error	BOOL	FALSE	Indicates when the temperature 2 is greater than the limit, ERROR
+16.7	P2_Error	BOOL	FALSE	Indicates when the pressure 2 is greater than the limit, ERROR
+17.0	Stable	BOOL	FALSE	Indicates when the station has been stabilized-->1
+17.1	Alarm	BOOL	FALSE	The alarm setttings haven't been fulfilled (after been stabilized) for a X time
+17.2	UDT11_12	BOOL	FALSE	1-->import the data to UDT11, 0--> save the export data in UDT 12
+17.3	a2	BOOL	FALSE	
+17.4	a3	BOOL	FALSE	
+17.5	a4	BOOL	FALSE	
+17.6	a5	BOOL	FALSE	
+17.7	a6	BOOL	FALSE	
+18.0	CI	INT	0	
+20.0	C2	REAL	0.000000e+000	
+24.0	C3	REAL	0.000000e+000	
=28.0		END_STRUCT		

UDT11 - <offline>

"Excel_INPUTS"

Nombre: Familia:
Autor: Versión: 0.1
Hora y fecha Código: Versión del bloque: 2
 13/06/2014 16:23:32
Interface: 13/06/2014 16:23:32
Longitud (bloque / código / datos): 00000 00000 00000

Dirección	Nombre	Tipo	Valor inicial	Comentario
0.0		STRUCT		
+0.0	Ref number	INT	0	Is in UDT 1, for the excel interface
+2.0	P1_m	REAL	0.000000e+000	P1 measured, UDT1
+6.0	P1_set	REAL	0.000000e+000	P1 set, UDT 1
+10.0	x1	REAL	0.000000e+000	Quality of the refrigerant, UDT1
+14.0	Tout_m	REAL	0.000000e+000	Otput water temperature, UDT 1
+18.0	P2_m	REAL	0.000000e+000	Pressure after the heating resistance measured, UDT1
+22.0	delta_T_resistance	REAL	0.000000e+000	Delta T over the T2sat temperature to be chieve, UDT 2
+26.0	m_w_m	REAL	0.000000e+000	Water flux measured, UDT 1
+30.0	m_ref_div_rho	REAL	0.000000e+000	Auxiliar variable to calculate the refrigerant flux in the excel, UDT 6
+34.0	T2_m	REAL	0.000000e+000	Temperature after the heating resistance, UDT 1
=38.0		END STRUCT		

UDT12 - <offline>

"Excel_OUTPUTS"

Nombre: **Familia:**
Autor: **Versión:** 0.1
Versión del bloque: 2
Hora y fecha Código: 16/06/2014 10:10:46
Interface: 13/06/2014 16:27:42
Longitud (bloque / código / datos): 00000 00000 00000

Dirección	Nombre	Tipo	Valor inicial	Comentario
0.0		STRUCT		
+0.0	T1sat	REAL	0.000000e+000	Saturation temperature at pressure P1_set, UDT 2
+4.0	h1_th	REAL	0.000000e+000	Enthalpy computed at pressure P1_set, UDT 2
+8.0	h1	REAL	0.000000e+000	Enthalpy computed at pressure P1_m, UDT 1
+12.0	T2sat	REAL	0.000000e+000	Saturation temperature at P2_m, UDT 2
+16.0	h2_th	REAL	0.000000e+000	Enthalpy computed with T2desired, UDT 2
+20.0	h3_th	REAL	0.000000e+000	Enthalpy computed with P1_set, is h1_th, UDT 2
+24.0	T2desired	REAL	0.000000e+000	Desired temperature after the resistance--> T2sat+delta_T, UDT 2
+28.0	rho_ref	REAL	0.000000e+000	Refrigerant density at the entering of the compressor UDT 1
+32.0	h2_m	REAL	0.000000e+000	Enthalpy computed with T2_m, UDT 2
+36.0	h3_m	REAL	0.000000e+000	Enthalpy equal to h1, UDT 2
+40.0	m_ref_th	REAL	0.000000e+000	Theoretical refrigerant flux [kg/s], UDT 2
+44.0	m_ref_grams	REAL	0.000000e+000	Theoretical refrigerant flux [g/s], UDT 6
=48.0		END_STRUCT		



FINAL PROJECT

Date: 19.06.2014

Page: 294

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

34 HARDWARE & PLC- HMI CONNECTION

In STEP 7 de hardware connection of the twelve future stations, and their external modules, have been implemented. It was also needed to define the networks of the PLC, ET200 and the HMI to determine their interaction.

34.1 HARDWARE




Figure 55- Hardware connection, 12 stations



FINAL PROJECT

Date: 19.06.2014

Page: 295

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

34.2 PLC-HMI CONNECTION




Figure 56- PLC,HMI and remotes connection

Each component has its own IP address, belonging to the same network:




Figure 57- IP adress of the CPU, the HMI and the first station



FINAL PROJECT

Date: 19.06.2014

Page: 296

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

ANNEX VIII: UNCERTAINTIES

1 EES CODE

R\$='R134a'

m_ref=disp*rpm*eta_v*rho[1]
m_ref=0,007238 [kg/s]

disp=8,1/10^6 [m3]

rpm=2900/60 [rev/s]

eta_v=0,90

v[1]=1/rho[1]

P[1]=4 "uncertainty that comes from 1 measures"

P_2rm=25

T_2rm=70

h[2]=enthalpy(R\$;P=P_2rm;T=T_2rm) "uncertainty that comes from 2 measures"

Q_cond=m_water*Cp(Water;T=23;P=1,013)*(T_wo-T_wi) "uncertainty that comes from 3 measures"

T_wo=25

T_wi=24,50

m_water=8/60 [kg/s]

Q_cond=m_ref*(h_2rm-h[3]) "calculation of h[3]"

h[1]=h[3]

x[1]=quality(R\$;v=v[1];P=P[1])

h[1]=enthalpy(R\$;P=P[1];v=v[1])

u_x=0,009623/0,95*100



FINAL PROJECT

Date: 19.06.2014

Page: 297

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

2 RESULT




Figure 58- Uncertainties

As it is shown, the quality of the refrigerant at the entrance of the compressor, would be guarantee with a 1,013% of accuracy.

1 PUMP

USE AND MAINTENANCE INSTRUCTION MANUAL TO BE KEPT BY THE USER

1. INTRODUCTION

Follow the instructions contained in this manual to obtain the best performance and the proper operation of the electropump.

For any further information, please contact your nearest authorized dealer.

ALL TYPES OF REPRODUCTION, EVEN PARTIAL, OF THE ILLUSTRATIONS AND/OR TEXT IS PROHIBITED.

The following symbols have been used in the handbook:

ATTENTION Risk of damage to the pump or plant



Risk of damage to persons or property



Electrical hazards

2. INDEX

1. INTRODUCTION	pag. 5
2. INDEX	pag. 5
3. IDENTIFICATION DATA	pag. 5
4. WARRANTY AND TECHNICAL ASSISTANCE	pag. 5
5. GENERAL SAFETY PRECAUTIONS	pag. 5
6. TECHNICAL AND BUILDING FEATURES	pag. 5
7. INSTALLATION, DISMANTLING AND TRANSPORT	pag. 6
8. ELECTRICAL CONNECTION	pag. 6
9. USE AND RUNNING	pag. 6
10. SETTING AND OPERATING	
11. MAINTENANCE AND REPAIR	pag. 6
12. DEMOLITION	pag. 7
13. TECHNICAL DOCUMENTATION ATTACHED	pag. 7
14. TROUBLESHOOTING	pag. 7
15. DECLARATION OF CONFORMITY	pag. 7
16. INSTALLATION DIAGRAM	pag. 11

3. IDENTIFICATION DATA

3.1. MANUFACTURER

EBARA PUMPS EUROPE S.p.A.

Factory management:

Via Pacinotti, 32 - 36040 BRENDOLO (VI) ITALIA

Telephone: Tel. +39 0444 706811 - Fax: +39 0444/405811

Registered office:

Via Campo Sportivo, 30 - 38023 CLES (TN) ITALIA

Telephone: Tel. +39 0463 660411 - Fax: +39 0463/422782

4. WARRANTY AND TECHNICAL ASSISTANCE

Failure to comply with the indications supplied in this instruction book and/or any intervention on the unit not performed by our assistance centres, will make the warranty null and void and relieve the manufacturer from any liability in case of accidents to persons or damage to property and/or the unit itself.

5. GENERAL SAFETY PRECAUTIONS

Before operating the electropump, the user should know how to perform all operations described in this manual and apply them every time during the use or maintenance of the electropump.

The user must strictly observe the safety regulations in force in his country; he must also take into account the electropump features (see "data label"). The user must never carry out operations or interventions, which are not accepted in this manual, on his own initiative.



This device is not intended for use by persons (including children) with reduced physical, sensory and mental capabilities, or lack of experience and knowledge, unless they have been given supervision or instruction concerning use of this device by a person responsible for their safety.

During the repair or maintenance interventions of the electropump, take off the power supply, thus preventing the accidental starting that could cause damage to persons and/or property.



Any maintenance, installation or moving operations performed on the electropump with the electric system energized, can cause serious accidents or death to persons.

Do not start the unit when barefoot, or worse, in water and with wet hands.

5.1. INTENDED USE

The circulating pumps Ego (ER) -/40, Ego (ER) -/60, and Ego (ER) -/80 are designed for forced circulation of the fluid in central heating systems. They differ from standard fixed speed pumps by having the option of continuous adjustment of the pump operation to the actual needs of the system. This feature gives both great electrical and thermal saving together with reduced noise level in the installation. In order to guarantee a regular operating of the pump, a fluid which is appropriate for a central heating system, such as pure water or a solution of pure water and antifreeze, must be provided. The water must meet water quality standards, such as VDI 2035. Use the electropumps according to their specification.

5.2 NOT INTENDED USE

All uses not specifically mentioned in 5.1 are generally banned; in particular, the fluid must not contain aggressive or explosive additives, mixtures of mineral oils and/or solid or fibrous particles. The pump should not be used for pumping flammable or explosive media, or in an explosive atmosphere. To avoid formation of condensation in the pump, fluid temperature must be higher or equal to the ambient temperature.

6. TECHNICAL AND BUILDING FEATURES

6.1 TECHNICAL DATA

Supply voltage: 230V, 50Hz

Protection class: IP44

Insulation class: H

GB

Motor protection: the pump is provided with a draining labyrinth inside the electromotor casting; do not insulate the pump as this can cause serious damage.

Speed/ pressure curve	Ego (ER) -/40		Ego (ER) -/60		Ego (ER) -/80	
	Regulated mode [W]	Unregulated mode [W]	Regulated mode [W]	Unregulated mode [W]	Regulated mode [W]	Unregulated mode [W]
I	5-25	8	7-50	16	10-75	25
II	7-25	17	10-50	34	12-75	50
III	10-25	25	12-50	50	15-75	75

6.2 LIMITS OF USE

The allowed maximum pressure in the system is 1 MPa (10 bar).

The minimum pressure at suction shall be:

- 0.05 bar for medium at 50°C
- 0.40 bar for medium at 80°C

Relative humidity of the air: max 95%

WORKING TEMPERATURE

Water (medium)	Ambient Temperature
5-95°C	0-40°C

Working outside of recommended conditions can shorten life time and nullify the warranty.

7. INSTALLATION, DISMANTLING AND TRANSPORT

7.1 GENERAL ARRANGEMENT FOR INSTALLATION

- The pump must be mounted with electromotor shaft in horizontal position (fig. 3.1). Allowed and forbidden positions are shown in fig. 3.2
- The arrow on pump plate shows direction of medium flow
- If there is not enough space for electric connection, control box can be rotated by 90° (allowed positions are shown in fig. 3.3); rotate the motor as shown in fig. 3.4, 3.5 and 3.6. Before rotating the motor, the pump must be emptied of fluid.

7.2 DISMANTLING

In order to handle and dismantle the electropump you should:

- Take off the power supply.
- Lift the electropump with suitable means according to its weight and dimensions

7.4. TRANSPORT

The electropump is packed in a carton or, depending on its weight and dimensions, it is fixed on a wooden pallet; however, transport does not present many difficulties. In any case, check the total weight imprinted on the box.

8. ELECTRICAL CONNECTION

8.1. PROTECTIVE DEVICES

- ALL THE CONNECTIONS MUST BE EXECUTED ACCORDING TO THE LAW BY A QUALIFIED TECHNICIAN.
- ALL THE ELECTRICAL MASSES MUST BE CONNECTED TO THE EARTH OF THE PLANT ACCORDING TO THE ELECTRICAL STANDARDS IN FORCE IN YOUR COUNTRY: THE INSTALLER SHALL BE THE SOLE

RESPONSIBLE FOR IT.

- FOR THE THREE-PHASE AND SINGLE-PHASE TYPES, WE RECOMMEND INSTALLING A HIGH SENSITIVE DIFFERENTIAL SWITCH (0.03 A).

After installing the unit check again the feeding cable following the CABLE CONNECTION instructions and connect it to the control panel (1) that must be fitted, according to the actual rules, with:

- An omnipolar device for switching-off/separation of the net (minimum opening contacts 3 mm).
- A protection against short circuits (Am fuse) and magnetothermics, rated in compliance with the current plate.
- Possible devices against: lack of phases, electric dissipations, lack of water, atmospheric discharges and functioning-failure indicators.

IMPORTANT: ALL THE ELECTRIC MASSES MUST BE CONNECTED TO THE EARTH OF THE PLANT.



8.2. CABLE CONNECTION

- Connect the mains supply cable to the connector present inside the terminal box, as shown on fig. 3.7
- The electrical connection of the pump to the mains (230V, 50 Hz) must be carried out with suitable standardised connecting cord
- When connecting the mains cable ensure it never comes in contact with the casing of the device, due to the high temperatures of the casing.

Electrical connection of ER module (for Ego ER versions)

- The signal conductor for control signal 0-10 V should be led through a small gland along the hydraulic housing on the electric fuse box. The conductor should be temperature resistant at a temperature of >85°C. The polarity of the signal conductor is not relevant. See fig. 3.7

9. USE AND RUNNING

- Before the startup, the pump must be filled with fluid and vented (fig. 3.8)
- Pumps Ego (ER) -/40, -/60 and -/80 do not need to be manually vented, as this occurs automatically when the hydraulic system is being ventilated during the start-up. The air in the pump generates noise. After a short working period noise should disappear.
- For a proper functioning, a minimum pressure at suction must be guaranteed (see LIMIT OF USE)



During its running, it is normal for the pump to heat up, or to be heated by the pumped fluid - to prevent from risk of burns, it should therefore not be touched!

- The permitted operating area around the pump is determined by the diagram in these instructions.

10. SETTING AND OPERATION

10.1 OPERATION MODES

- Pump settings can be changed with the button on electric box top. It is possible to choose between the following operating modes:
 - “Proportional differential pressure” (Δp_v - regulated mode): in this mode the button pulsates and the duration of the pulse interval shortens along with the flow decreasing.

- b) **“Fixed speed” (unregulated mode)**: in this mode the setting button does not pulse, but remains constantly illuminated.
- Each mode enables a choice between three different preset curves at “proportional differential pressure” and three curves at “fixed speed”. The button lights up with the colour that indicates the selected level. The sequence is “blue-green-yellow”: the blue indicates the lowest speed/differential pressure curve, the yellow the maximum speed/differential pressure curve

How to set different operating curves and how to switch between the 2 modes

- If the pump is operating at proportional differential pressure (regulated mode – recognizable by the pulsating button), a short pressing of the button will change the operating curve according to a.m. sequence (blue-green-yellow).
- In order to switch from the “regulated mode” to the “fixed speed” (unregulated mode) it is necessary to press the setting button for at least 5 seconds: in this way the button will remain constantly lit (thus indicating the fixed speed mode has been set) and the current speed curve set will be according to the colour selected before long pressing the button. Shortly pressing the setting button will set the pump back to “proportional differential pressure” mode. In order to change the speed curve (in “fixed speed” operation) it is therefore necessary to select the requested curve while in “regulated mode” and after that to switch to the “fixed speed mode” by long pressing the setting button.

NOTE: the hydraulic response in the regulated mode is proportionate to the flow. The set head for single chosen level has an inclination angle of 50% (see table below).

10.2 PUMPS Ego ER-/40, 60, 80 – CONTROL BY ANALOG SIGNAL

The Ego ER -/40, 60, 80 are equipped with an additional module that allows controlling the pump with an analogue signal 0 -10 V.

“Unregulated mode” (fixed speed)

- The curve is determined by the value of the controlling

signal. This mode is set by pressing and holding the button on the primary circuit for 5 seconds (the light is on). If the value of the controlling signal is lower than 1 V, the pump enters in a stand-by mode. See diagram at the end of this manual.

“Regulated mode” (proportional differential pressure)

- The pressure curve of the pump is determined by the value of the controlling signal. If the value of the controlling signal is lower than 1 V, the pump enters in a stand-by mode. See diagram at the end of this manual.

External control works only if the input resistance is < 10kΩ. In this case, the input voltage must be considered. If the input resistance is > 50 kΩ, the pump will operate as a standard version without external control.

GB

11. MAINTENANCE AND REPAIR

Often control the plant trying to eliminate the disturbing causes such as sand, lime, etc. Keep efficient the parts exposed to damages (valves, filters, detectors and protections). For interventions always call qualified technicians.

In case of long rests provide to often start the electropump. Any replacement of the feeding cable as well as all other maintenance operations must be performed only by the assistance centre.

12. DEMOLITION

When demolishing the electropumps, follow strictly the regulations in force in your country.

The user is responsible for disposing the equipment by delivering it to a collecting point for recycling and disposal of electrical equipment.

For further information about the collecting points of equipment, contact your local authority for waste disposal, or the shop where you purchased your product.

13. TECHNICAL DOCUMENTATION ATTACHED

Installation diagram.

14. TROUBLESHOOTING

DESCRIPTION OF THE ERROR	POSSIBLE CAUSES	PROPOSED SOLUTION
INDICATOR LIGHT IS OFF, PUMP IS NOT WORKING	No voltage applied	Check electric installation and fuses
INDICATOR LIGHT IS PERMANENTLY ON	The unregulated mode may have been selected	Select regulated mode
INDICATOR LIGHT CHANGES COLOUR	The pump is blocked	Clean the pump
NOISES COMING FROM THE PUMP/THE HYDRAULIC SYSTEM	The pump or the system are not properly vented	Vent the hydraulic system
FLOW RATE TOO LOW	The selected setting is too low	Select a higher curve

15. DECLARATION OF CONFORMITY

The company EBARA PUMPS EUROPE S.p.A. declares under its own responsibility that its Ego products are in conformity:


2006/42/EC (MD), 2004/108/EC (EMC),
2006/95/EC (LVD), EN 809,
EN 60 335-1, EN 60 335-2-51,
EN 61000-6-3, EN 61000-6-1




Mr. SHU NAGATA
Managing Director
Date: Jan. 30, 2013

EBARA Pumps Europe S.p.A.
Via Pacinotti, 32 - 36040 Brendola (Vicenza) - Italy
Tel. +39 0444 706811 - Fax +39 0444 405811
www.ebaraeurope.com


3.4




3.5




3.6




3.7








0-10V



3.8








	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 304
PROJECT: “Compressors test live bench under wet compression conditions”		ANNEX: 2

2 WATER FLUX

1 Advertencia preliminar

1.1 Símbolos utilizados

- ▶ Requerimiento de operación
- > Reacción, resultado
- [...] Referencia a teclas, botones o indicadores
- Referencia cruzada
-  Nota importante
El incumplimiento de estas indicaciones puede acarrear funcionamientos erróneos o averías.

2 Indicaciones de seguridad

- Lea este documento antes de poner en marcha el dispositivo. Asegúrese de que el producto es apto para su aplicación sin ningún tipo de restricciones.
- El uso indebido o no conforme a lo estipulado puede provocar fallos de funcionamiento en el dispositivo o consecuencias no deseadas en su aplicación. Por este motivo, el montaje, la conexión eléctrica, la puesta en marcha, el manejo y el mantenimiento del dispositivo solo pueden ser llevados a cabo por personal cualificado, autorizado además por el responsable de la instalación.
- Compruebe en todas las aplicaciones la compatibilidad de los materiales del producto (→ 12 Datos técnicos) con los fluidos que se van a medir.

Para el ámbito de validez cULus:

El aparato debe recibir el suministro de tensión de una fuente de alimentación con separación galvánica que disponga en la parte secundaria de un fusible con homologación UL y una corriente nominal máxima de

- a) 5 A con tensiones de 0...20 Vrms (0...28.3 Vp) o
- b) 100/Vp con tensiones de 20...30 Vrms (28.3...42.4 Vp)



FINAL PROJECT

Date: 19.06.2014

Page: 305

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3 Utilización correcta

El equipo supervisa fluidos líquidos.

Registra 3 variables del proceso: cantidad de caudal, volumen de consumo, temperatura del fluido.

Campo de aplicación

Fluidos líquidos conductores con las siguientes características:

- Conductividad: $\geq 20 \mu\text{S/cm}$
- Viscosidad: $< 70 \text{ mm}^2/\text{s}$ a 40°C

4 Función

4.1 Procesamiento de las señales de medición

- El equipo muestra los valores actuales del proceso en una pantalla.
- Genera 2 señales de salida en función de los parámetros.

OUT1: 3 posibilidades de selección Parametrización

ES

Señal de conmutación para el valor límite de cantidad de caudal (→ 9.2.1)

o secuencia de impulsos para el contador de caudal..... (→ 9.3.1)

o señal de conmutación para el contador con preselección..... (→ 9.3.2)

OUT2: 4 posibilidades de selección

Señal de conmutación para el valor límite de cantidad de caudal (→ 9.2.2)

o señal de conmutación para el valor límite de temperatura..... (→ 9.4.1)

o señal analógica para la cantidad de caudal (→ 9.2.3)

o señal analógica para la temperatura (→ 9.4.2)

En vez de como salida, OUT2 (pin 2) se puede utilizar como

entrada para una señal externa de reseteo:..... (→ 9.3.5)

4.2 Supervisión de caudal

El fluido fluye a través de un campo magnético. Durante este proceso se genera una tensión de señal que es directamente proporcional a la cantidad de caudal.

- Se pueden emitir 2 señales de conmutación para valores límites de caudal (salida 1 y salida 2). Funciones de conmutación → 4.5.
- Se puede emitir una señal analógica proporcional al caudal (4...20 mA o 0...10 V) en la salida 2. Funciones analógicas → 4.6.

Además de la velocidad de caudal, el equipo también registra el sentido del mismo. El sentido positivo de caudal está indicado en el equipo con una flecha ("flow direction" → 5.2).



FINAL PROJECT

Date: 19.06.2014

Page: 306

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

- Sentido del caudal = "flow direction": valor de proceso e indicación positivos.
- Caudal en el sentido opuesto a la "flow direction": valor de proceso e indicación negativos.

Para la emisión de señales (valores límite y valores analógicos de caudal) se procesan solamente valores de proceso positivos.


4.3 Supervisión de volúmenes de consumo (función totalizador)

El equipo posee un contador de caudal interno, el cual va sumando de forma continua la cantidad de caudal. La suma se corresponde con el volumen de consumo actual desde el último reseteo.

- El contador realiza la suma con signos correctos.

Caudal correspondiente al sentido de caudal marcado (flecha "flow direction"): el contador suma. Caudal en el sentido opuesto a la marca indicada: el contacto resta.

Los impulsos contadores solo se emiten en caso de suma ascendente. Tras una sustracción (el volumen de consumo disminuye) no se emitirán más impulsos hasta que el volumen de consumo vuelva a exceder el valor máximo actual.



V = cantidad de caudal, Imp = impulsos de salida

- El valor actual del contador se puede mostrar.
- Asimismo se almacena el valor registrado antes del último reseteo. Este valor también puede ser mostrado.

El contador almacena cada 10 minutos el volumen de consumo sumado. Tras una interrupción de la tensión, este valor estará disponible como valor actual del contador. Si se configura un reseteo temporizado, también se almacenará el tiempo transcurrido del intervalo de reseteo configurado. La posible pérdida de datos puede, por tanto, ser como máximo de 10 minutos.

El contador se puede poner a cero de la siguiente manera:

- Reseteo manual (→ 9.3.3).
- Reseteo automático temporizado (→ 9.3.3).
- Señal externa de entrada en el pin 2 (→ 9.3.5).



FINAL PROJECT

Date: 19.06.2014

Page: 307

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

4.3.1 Supervisión de volúmenes de consumo con salida por impulsos

La salida 1 emite un impulso contador cada vez que se alcanza el valor configurado en ImPS (→ 9.3.1).

4.3.2 Supervisión de volúmenes de consumo con contador con preselección

Son posibles 2 tipos de supervisión:

- Supervisión de caudal en función del tiempo.
 - Configuraciones: [ImPS] = cantidad x, [ImPR] = [no], [rTO] = tiempo t.
 - Cuando se alcanza la cantidad x durante el tiempo t, la salida 1 conmuta y permanece en este estado hasta que el contador se ponga a cero.
 - Si no se alcanza la cantidad x una vez transcurrido el tiempo t, el contador se pone a cero automáticamente y empieza a contar de nuevo; la salida 1 no conmuta.
- Supervisión del caudal independientemente del tiempo.
 - Configuraciones: [ImPS] = cantidad x, [ImPR] = [na], [rTO] = [OFF].
 - Cuando se alcanza la cantidad x, la salida 1 conmuta y permanece en este estado hasta que el contador se ponga a cero.



4.4 Supervisión de temperatura

- Se puede emitir en la salida 2 una señal de conmutación para los valores límites de temperatura. Funciones de conmutación → 4.5.
- Se puede emitir en la salida 2 una señal analógica proporcional a la temperatura (4...20 mA o 0...10 V). Funciones analógicas → 4.6.



FINAL PROJECT

Date: 19.06.2014

Page: 308

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

4.5 Supervisión de caudal o temperatura / función de conmutación


OUTx cambia su estado de conmutación en caso de que los valores superen o estén por debajo de los límites de conmutación configurados (SPx, rPx). Se pueden seleccionar las siguientes funciones de conmutación:

- Función de histéresis / normalmente abierto: [OUx] = [Hno].
- Función de histéresis / normalmente cerrado: [OUx] = [Hnc].

Primero se fija el punto de conmutación (SPx) y después se configura el punto de desconmutación (rPx) con la diferencia deseada.

- Función de ventana / normalmente abierto: [OUx] = [Fno].
- Función de ventana / normalmente cerrado: [OUx] = [Fnc].

La extensión de la ventana se configura mediante la diferencia entre el SPx y el rPx. SPx = valor superior, rPx = valor inferior.



HY = histéresis; FE = ventana; ejemplos de supervisión de caudal

En caso de configuración de la función de ventana, los puntos de conmutación y desconmutación tienen una histéresis de configuración fija del 0,25% del valor límite del rango de medición. Esto hace que se mantenga estable el estado de conmutación de la salida en caso de fluctuaciones muy escasas del caudal.

4.6 Supervisión de caudal o temperatura / función analógica

- El punto inicial analógico [ASP] determina el valor de medición en el cual la señal de salida tiene 4 mA o 0 V.
- El punto final analógico [AEP] determina el valor de medición en el cual la señal de salida tiene 20 mA o 10 V.

Diferencia mínima entre [ASP] y [AEP] = 20% del valor límite del rango de medición.



FINAL PROJECT


Date: 19.06.2014

Page: 309

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

Salida de tensión 0 ... 10 V (ejemplo de supervisión de caudal)



MEW = valor límite del rango de medición


En el rango de medición configurado, la señal de salida se encuentra entre 0 y 10 V.

Además se señala lo siguiente:

Caudal por encima del rango de medición: señal de salida > 10 V.

ES

Salida de corriente 4 ... 20 mA (ejemplo de supervisión de caudal)



MEW = valor límite del rango de medición

En el rango de medición configurado, la señal de salida se encuentra entre 4 y 20 mA.

Además se señala lo siguiente:

Caudal por encima del rango de medición: señal de salida > 20 mA.



FINAL PROJECT

Date: 19.06.2014

Page: 310

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

4.7 Tiempo de espera al arranque [dSt]

Si el tiempo de espera al arranque está activo ($[dSt] > [0]$), se aplica lo siguiente:


En cuanto la cantidad de caudal supera el 0,5% del valor límite del rango de medición (MEW), tienen lugar los siguientes procesos:

- Se inicia el tiempo de espera al arranque.
- La salida 1 conmuta en función de la programación: se ACTIVA en caso de función NA, se DESACTIVA en caso de función NC.
- La salida 2 conmuta con la evaluación del caudal ($[SEL2] = [FLOW]$) en función de la programación: se ACTIVA en caso de función NA, se DESACTIVA en caso de función NC.
- $[dSt]$ solo tiene efecto sobre las señales de conmutación para la supervisión de caudal.

Tras el inicio del tiempo de espera al arranque pueden darse los siguientes 3 casos:

- El caudal aumenta rápidamente y alcanza el punto de conmutación / margen de aceptación dentro del dSt -> las salidas permanecen activas.
- El caudal aumenta lentamente y no alcanza el punto de conmutación / margen de aceptación dentro del dSt -> las salidas se restablecen.
- El caudal cae dentro del dSt por debajo de 0,5% -> las salidas se restablecen inmediatamente; el dSt finaliza.

Ejemplo: dSt en la función de histéresis



1	El caudal Q alcanza el 0,5% del MEW -> se inicia el dSt , la salida se activa.
2	El dSt ha finalizado, Q ha alcanzado el SP -> la salida sigue activa.
3	Q está por debajo del SP, aunque sigue estando por encima del rP -> la salida sigue activa.



FINAL PROJECT

Date: 19.06.2014


Page: 311

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

4	Q está por debajo del rP → la salida se restablece.
5	Q alcanza de nuevo el 0,5% del MEW → se inicia el dSt, la salida se activa.
6	El dSt ha finalizado, Q no ha alcanzado el SP → la salida se restablece.
7	Q alcanza el SP → la salida se activa.

Ejemplo: dSt en la función de ventana



ES

1	El caudal Q alcanza el 0,5% del MEW → se inicia el dSt, la salida se activa.
2	El dSt ha finalizado, Q ha alcanzado el margen de aceptación → la salida sigue activa.
3	Q aumenta por encima del SP (fuera del margen de aceptación) → la salida se restablece.
4	Q vuelve a caer por debajo del SP → la salida se activa otra vez.
5	Q cae por debajo del rP (fuera del margen de aceptación) → la salida se restablece de nuevo.
6	Q alcanza de nuevo el 0,5% del MEW → se inicia el dSt, la salida se activa.
7	El dSt ha finalizado, Q no ha alcanzado el margen de aceptación → la salida se restablece.
8	Q alcanza el margen de aceptación, la salida se activa.



FINAL PROJECT

Date: 19.06.2014

Page: 312


PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

5 Montaje


5.1 Lugar de montaje

- ▶ Montar el equipo de tal manera que el tubo de medición esté siempre completamente lleno.
- ▶ Prever los tramos de entrada y salida. De esta forma se compensan influencias perturbadoras causadas por codos, válvulas, estrechamientos o similares. En concreto se aplica lo siguiente: los sistemas de bloqueo y regulación no deben encontrarse directamente delante del equipo.



S = influencia perturbadora; D = diámetro de la tubería; F = sentido del caudal

- ▶ Montar en un tubo ascendente o antes del mismo.



F = sentido del caudal

- ▶ Se deben evitar los siguientes lugares de montaje:

- Justo antes de un tubo descendente.
- En un tubo descendente.




FINAL PROJECT

Date: 19.06.2014

Page: 313


PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2



F = sentido del caudal

- En el punto más alto del sistema de tubos.
- Justo antes de un tubo de salida.




ES

F = sentido del caudal

El equipo se puede montar en cualquier posición, siempre y cuando esté garantizado lo siguiente:

- Queda descartada la formación de burbujas de aire en el sistema de tubos.
- Las tuberías están siempre completamente llenas.
- En la zona de aspiración de una bomba.



F = sentido del caudal



FINAL PROJECT

Date: 19.06.2014


Page: 314

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2



En caso de montaje en un sistema de tubos que no esté puesto a tierra (p.ej. tubos de plástico), el sensor debe conectarse a tierra.




Abrazaderas de puesta a tierra para la conexión G $\frac{1}{2}$ disponibles como accesorios (ref. E40196).

A = terminal de cable (no incluido).

5.2 Instalación en la tubería

El equipo se instala en la tubería con ayuda de adaptadores. Estos se piden por separado como accesorios.

- Referencia E40199: 2 adaptadores para tubería R $\frac{1}{2}$ + 2 juntas.



1. Atornillar el adaptador (B) en la tubería (A).
2. Colocar las juntas (C) y montar el equipo en función del sentido del caudal indicado (flow direction).
3. Colocar el adaptador (B) en las conexiones (D) y apretarlo con la mano.
4. Apretar ambos adaptadores en sentido opuesto (par de apriete: 30 Nm).



FINAL PROJECT

Date: 19.06.2014


Page: 315

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

El equipo también puede utilizarse en racores $G^{3/4}$. Para ello enroscar primero un adaptador $G^{1/2} - G^{3/4}$ (B) con junta tórica (C) en ambas conexiones (D) del dispositivo.

Colocar las juntas (A) y montar el equipo en función del sentido de caudal indicado (flow direction).



Estos adaptadores se piden por separado como accesorios.

- Ref. E40189: 2 adaptadores $G^{1/2} - G^{3/4}$ + 2 juntas tóricas + 2 juntas.

Después del montaje pueden aparecer burbujas de aire en el sistema que podrían afectar a la medición. Solución:

- Aclarar el sistema después del montaje para purgarlo (cantidad de fluido de aclarado > 3 l/min.).

ES

En caso de montaje horizontal se aplica lo siguiente: debido a exigencias constructivas, después de apagar la bomba siempre permanece una pequeña cantidad del fluido en el canal de medición.

5.3 Protección en caso de elevadas temperaturas del fluido

Con temperaturas del fluido superiores a 50°C , algunas partes de la carcasa pueden calentarse a más de 65°C .

- Proteger la carcasa contra el contacto con sustancias inflamables y contra un contacto involuntario.



FINAL PROJECT

Date: 19.06.2014

Page: 316

PROJECT:
"Compressors test live bench under wet compression conditions"


ANNEX:
2

6 Conexión eléctrica



El dispositivo sólo puede ser instalado por técnicos electricistas.
Se deben cumplir los reglamentos tanto nacionales como internacionales para el establecimiento de instalaciones electrotécnicas.
Suministro de tensión según EN 50178, MBTS y MBTP.

- ▶ Desconectar la tensión de alimentación.
- ▶ Conectar el dispositivo de la siguiente manera:



Pin 1	Ub+
Pin 3	Ub-
Pin 4 (OUT1)	Señal de conmutación: valores límites de caudal. Señal de conmutación: el contador de caudal ha alcanzado el valor de preselección. Impulsos: 1 impulso cada vez que se alcance la cantidad de caudal indicada.
Pin 2 (OUT2/InD)	Señal de conmutación: valores límites de caudal. Señal de conmutación: valores límites de temperatura Señal analógica para caudal. Señal analógica para temperatura. Entrada para la señal "reseteo del contador".

Colores de los hilos para los conectores hembra de ifm:
1 = BN (marrón), 2 = WH (blanco), 3 = BU (azul), 4 = BK (negro)



FINAL PROJECT


Date: 19.06.2014

Page: 317

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

7 Elementos de manejo y visualización



De 1 a 8: LEDs indicadores

- LED 1 = caudal actual en litros/minuto.
- LED 2 = caudal actual en metros cúbicos/hora.
- LED 3 = volumen de consumo actual desde el último reseteo en litros.
- LED 3 parpadeante = volumen de consumo antes del último reseteo en litros.
- LED 4 = volumen de consumo actual desde el último reseteo en metros cúbicos.
- LED 4 parpadeante = volumen de consumo antes del último reseteo en metros cúbicos.
- LEDs 4 y 6 = volumen de consumo actual desde el último reseteo en 10^3 metros cúbicos.
- LEDs 4 y 6 parpadeantes = volumen de consumo actual antes del último reseteo en 10^3 metros cúbicos.
- LED 5 = temperatura actual del fluido en °C.
- LED 7, LED 8 = estado de conmutación de la salida correspondiente.

9: Display alfanumérico de 4 dígitos

- Indicación de la cantidad de caudal actual (en caso de configuración de [SELD] = [FLOW]).
- Indicación del valor del contador (en caso de configuración de [SELD] = [TOTL]).
- Indicación de la temperatura actual del fluido (en caso de configuración de [SELD] = [TEMP]).
- Indicación de los parámetros y de los valores de los parámetros

10: Botón Mode/Enter

- Selección de los parámetros y confirmación de los valores de los parámetros.

11: Botón Set


- Configuración de los valores de los parámetros (de forma continua si se mantiene pulsado el botón; uno por uno si se presiona el botón una sola vez).
- Cambio de la unidad de indicación en el modo operativo normal (modo Run).

ES



8 Menú

8.1 Estructura del menú



Ⓜ = [Mode/Enter] / Ⓢ = [Set]

l o m³ = valor actual del contador en l, m³ o 1000 m³

l* o m³* = valor del contador almacenado en l, m³ o 1000 m³



FINAL PROJECT

Date: 19.06.2014

Page: 319

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

8.2 Explicación del menú

SP1/rP1	Valor límite superior/inferior de caudal.
ImPS	Valor de impulsos.
ImPR	Repetición de impulsos activa (= emisión de impulsos) o no activa (= función del contador con preselección)
OU1	Función de salida para OUT1 (caudal o volumen de consumo): - Señal de conmutación para los valores límites: función de histéresis o función de ventana, respectivamente normalmente abierto o normalmente cerrado. - Impulso o señal de conmutación para el contador de caudal.
OU2	Función de salida para OUT2 (caudal o temperatura): - Señal de conmutación para los valores límites: función de histéresis o función de ventana, respectivamente normalmente abierto o normalmente cerrado. - Señal analógica: 4-20 mA [I] o 0-10 V [U].
	Otra opción: configurar OUT2 (Pin2) como entrada para una señal externa de reseteo; configuración: [OU2] = [InD].
SP2/rP2	Valor límite superior/inferior de caudal o temperatura.
ASP	Valor inicial analógico para caudal o temperatura.
AEP	Valor final analógico para caudal o temperatura.
DIn2	Configuración de la entrada (Pin2) para el reseteo del contador.
EF	Funciones avanzadas / acceso al nivel de menú 2.
HI	Memoria de los valores máximos de caudal.
LO	Memoria de los valores mínimos de caudal.
FOU1	Comportamiento de la salida 1 en caso de un fallo interno.
FOU2	Comportamiento de la salida 2 en caso de un fallo interno.
dSt	Tiempo de espera al arranque (startup delay).
P-n	Lógica de conmutación de las salidas: pnp / npn.
dAP	Amortiguamiento de los valores de medición / constante de amortiguamiento en segundos.
rTo	Reseteo del contador: reseteo manual / temporizado.
dIS	Frecuencia de actualización y orientación de la pantalla.
Uni	Unidad de medida estándar para caudal: litros/minuto o metros cúbicos/hora.
SELd	Magnitud de medición estándar de la pantalla: valor de caudal / valor del contador / temperatura del fluido.

ES



FINAL PROJECT

Date: 19.06.2014

Page: 320

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2




SEL2	Magnitud de medición estándar para la evaluación mediante OUT2: - Señal del valor límite o señal analógica para caudal - Señal del valor límite o señal analógica para temperatura
res	Restablecer las configuraciones de fábrica.

9 Parametrización

Durante el proceso de parametrización el sensor permanece en el modo operativo. Sigue llevando a cabo sus funciones de supervisión con los parámetros existentes hasta que la parametrización haya concluido.

9.1 Proceso general de parametrización

Cada configuración de parámetros requiere seguir 3 pasos:

1	Seleccionar el parámetro ▶ Presionar [Mode/Enter] hasta que aparezca el parámetro deseado..	
2	Configurar el valor del parámetro ▶ Presionar [Set] y mantenerlo pulsado. > El valor actual de configuración del parámetro parpadea en la pantalla durante 5 s. > Tras 5 s: el valor de configuración se puede modificar (uno por uno si se presiona una vez o de forma continua si se deja pulsado el botón)	
Los valores numéricos aumentarán de forma continua. Si desea disminuir el valor: pulsar el botón hasta que en la pantalla aparezca el valor máximo de configuración. Tras éste, empieza de nuevo a contar desde el valor mínimo de configuración.		
3	Confirmar el valor del parámetro ▶ Presionar brevemente [Mode/Enter]. > El parámetro se muestra de nuevo. El nuevo valor de configuración ha sido memorizado.	
Configurar otros parámetros ▶ Comenzar de nuevo con el paso 1.		
Finalizar la parametrización ▶ Presionar [Mode/Enter] tantas veces como sea necesario hasta que aparezca el valor de medición actual o esperar 15 s. > El dispositivo retorna al modo operativo.		



FINAL PROJECT



Date: 19.06.2014

Page: 321

PROJECT:
"Compressors test live bench under wet compression conditions"



ANNEX:
2

- Cambio del nivel de menú 1 al nivel de menú 2:

<ul style="list-style-type: none">▶ Presionar [Mode/Enter] hasta que aparezca [EF] en la pantalla.	
<ul style="list-style-type: none">▶ Presionar brevemente [Set]. > Se muestra el primer parámetro del submenú (en este caso: [HI]).	

- Bloquear / Desbloquear

El aparato se puede bloquear electrónicamente para evitar un ajuste erróneo no intencionado.

<ul style="list-style-type: none">▶ Asegurarse de que el equipo se encuentra en el modo operativo normal.▶ Presionar [Mode/Enter] + [Set] durante 10 s.> [Loc] aparece en la pantalla.	
Durante el funcionamiento: si se intentan modificar los valores de los parámetros, en la pantalla aparecerá brevemente [Loc].	
<p>Para desbloquear el equipo:</p> <ul style="list-style-type: none">▶ Presionar [Mode/Enter] + [Set] durante 10 s.> [uLoc] aparece en la pantalla.	

ES

Estado en el momento de entrega: desbloqueado.

- Timeout:

Si durante la configuración de un parámetro no se pulsa ningún botón durante 15 s, el aparato retorna al modo operativo sin que se produzca ninguna modificación de los valores.



Con temperaturas del fluido superiores a 50°C, algunas partes de la carcasa pueden calentarse a más de 65°C.

En este caso no pulsar los botones con los dedos; en su lugar utilizar un objeto auxiliar (p.ej. un bolígrafo).



FINAL PROJECT

Date: 19.06.2014

Page: 322

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

9.2 Configuraciones para la supervisión de caudal

9.2.1 Configurar la supervisión del valor límite con OUT1

<ul style="list-style-type: none">▶ Seleccionar [OU1] y configurar la función de conmutación:<ul style="list-style-type: none">- [Hno] = función de histéresis / normalmente abierto,- [Hnc] = función de histéresis / normalmente cerrado,- [Fno] = función de ventana / normalmente abierto,- [Fnc] = función de ventana / normalmente cerrado.▶ Seleccionar [SP1] y configurar el valor en el cual la salida tiene que conmutar.▶ Seleccionar [rP1] y configurar el valor en el cual la salida tiene que ser desactivada.	<i>OU 1 SP 1 rP 1</i>
---	-------------------------------

9.2.2 Configurar la supervisión del valor límite con OUT2

<ul style="list-style-type: none">▶ Seleccionar [SEL2] y configurar [FLOW].▶ Seleccionar [OU2] y configurar la función de conmutación:<ul style="list-style-type: none">- [Hno] = función de histéresis / normalmente abierto,- [Hnc] = función de histéresis / normalmente cerrado,- [Fno] = función de ventana / normalmente abierto,- [Fnc] = función de ventana / normalmente cerrado.▶ Seleccionar [SP2] y configurar el valor en el cual la salida tiene que conmutar.▶ Seleccionar [rP2] y configurar el valor en el cual la salida tiene que ser desactivada.	<i>SEL2 OU2 SP2 rP2</i>
---	-------------------------------------

9.2.3 Configurar el valor analógico para caudal

<ul style="list-style-type: none">▶ Seleccionar [SEL2] y configurar [FLOW].▶ Seleccionar [OU2] y configurar la función:<ul style="list-style-type: none">- [I] = señal de corriente proporcional al caudal (4...20 mA);- [U] = señal de tensión proporcional al caudal (0...10 V).▶ Seleccionar [ASP] y configurar el valor con el cual se emitirá el valor mínimo.▶ Seleccionar [AEP] y configurar el valor con el cual se emitirá el valor máximo.	<i>SEL2 OU2 ASP AEP</i>
--	-------------------------------------



FINAL PROJECT

Date: 19.06.2014

Page: 323

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

9.3 Configuraciones para la supervisión de volúmenes de consumo

9.3.1 Configurar la supervisión de volúmenes mediante emisión de impulsos

<ul style="list-style-type: none">▶ Seleccionar [OU1] y configurar [ImP]:▶ Seleccionar [ImPS] y configurar la cantidad de caudal con la que se emitirá 1 impulso respectivamente (→ 9.7).▶ Seleccionar [ImPR] y configurar [YES]> La repetición de impulsos está activa. La salida 1 emite un impulso contador cada vez que se alcanza el valor configurado en [ImPS].	
--	--

9.3.2 Configurar la supervisión de volúmenes mediante contador con pre-selección

<ul style="list-style-type: none">▶ Seleccionar [OU1] y configurar [ImP].▶ Seleccionar [ImPR] y configurar [no]> La repetición de impulsos no está activa. La salida se ACTIVA cuando se ha alcanzado el valor configurado en [ImPS]. La salida permanece conmutada hasta que el contador sea puesto a cero.▶ Seleccionar [ImPS] y configurar la cantidad de caudal hasta que la salida 1 conmute (→ 9.7).	
--	--

9.3.3 Configurar el reseteo programado del contador

<ul style="list-style-type: none">▶ Seleccionar [rTo] y continuar con a) o b).a) Restablecer el contador manualmente:▶ Presionar [Set] hasta que aparezca [rES.T] en la pantalla, a continuación presionar brevemente [Mode/Enter].b) Introducir un valor para el restablecimiento temporizado del contador▶ Presionar [Set] hasta que se muestre el valor deseado (intervalos de 1 hora hasta 8 semanas), a continuación presionar brevemente [Mode/Enter].	
--	--

9.3.4 Desactivar el reseteo del contador

<ul style="list-style-type: none">▶ Seleccionar [rTo] y configurar [OFF]. <p>El contador no se restablecerá hasta que se produzca un desbordamiento (= configuración de fábrica).</p>	
---	--



FINAL PROJECT

Date: 19.06.2014

Page: 324

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

9.3.5 Configurar el reseteo del contador mediante una señal externa

<ul style="list-style-type: none">▶ Seleccionar [OU2] y elegir [InD].▶ Seleccionar [Din2] y configurar la señal de reseteo:<ul style="list-style-type: none">- [Hi] = reseteo en caso de señal alta,- [Lo] = reseteo en caso de señal baja,- [+EDG] = reseteo en caso de flanco ascendente,- [-EDG] = reseteo en caso de flanco descendente.	
--	--

9.4 Configuraciones para la supervisión de temperatura

9.4.1 Configurar la supervisión del valor límite con OUT2

<ul style="list-style-type: none">▶ Seleccionar [SEL2] y configurar [TEMP].▶ Seleccionar [OU2] y configurar la función de conmutación:<ul style="list-style-type: none">- [Hno] = función de histéresis / normalmente abierto,- [Hnc] = función de histéresis / normalmente cerrado,- [Fno] = función de ventana / normalmente abierto,- [Fnc] = función de ventana / normalmente cerrado.▶ Seleccionar [SP2] y configurar el valor en el cual la salida tiene que conmutar.▶ Seleccionar [rP2] y configurar el valor en el cual la salida tiene que ser desactivada.	
---	--

9.4.2 Configurar el valor analógico para temperatura

<ul style="list-style-type: none">▶ Seleccionar [SEL2] y configurar [TEMP].▶ Seleccionar [OU2] y configurar la función:<ul style="list-style-type: none">- [I] = señal de corriente proporcional a la temperatura (4...20 mA);- [U] = señal de tensión proporcional a la temperatura (0...10 V).▶ Seleccionar [ASP] y configurar el valor con el cual se emitirá el valor mínimo.▶ Seleccionar [AEP] y configurar el valor con el cual se emitirá el valor máximo.	
--	--

9.5 Configuraciones de usuario (opcionales)

9.5.1 Fijar la unidad de medida estándar para caudal

<ul style="list-style-type: none">▶ Seleccionar [Uni] y fijar la unidad de medida: [Lmin] o [m3h]. La configuración solo afecta al valor de caudal. El valor del contador (volumen de consumo) es indicado automáticamente en la unidad de medida (l o m³) que ofrece la mayor precisión posible.	
--	--



FINAL PROJECT

Date: 19.06.2014

Page: 325

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

9.5.2 Configurar la indicación estándar

<ul style="list-style-type: none">▶ Seleccionar [SELD] y fijar la magnitud de medición estándar:<ul style="list-style-type: none">- [FLOW] = la pantalla muestra el valor actual de caudal en la unidad de medida estándar.- [TOTL] = la pantalla muestra el valor actual del contador en l, m³ o 1000 m³.- [TEMP] = la pantalla muestra la temperatura actual en °C.▶ Seleccionar [diS] y fijar la frecuencia de actualización y la orientación de la pantalla:<ul style="list-style-type: none">- [d1] = actualización del valor de medición cada 500 ms.- [d2] = actualización del valor de medición cada 1000 ms.- [d3] = actualización del valor de medición cada 2000 ms.- [rd1], [rd2], [rd3] = visualización como los d1, d2, d3; pero girado 180°.- [OFF] = el display está apagado en el modo operativo.	
---	--

9.5.3 Configurar la lógica de conmutación de las salidas

▶ Seleccionar [P-n] y configurar [PnP] o [nPn].	
---	--

9.5.4 Configurar el tiempo de espera al arranque

▶ Seleccionar [dSt] y configurar el valor numérico en segundos.	
---	--

9.5.5 Configurar el amortiguamiento de los valores de medición

▶ Seleccionar [dAP] y configurar la constante de amortiguamiento en segundos (valor t 63%).	
---	--

9.5.6 Configurar la reacción de las salidas ante errores

<ul style="list-style-type: none">▶ Seleccionar [FOU1] y fijar un valor:<ul style="list-style-type: none">- [On] = la salida 1 se ACTIVA en caso de fallo.- [OFF] = la salida 1 se DESACTIVA en caso de fallo.- [OU] = la salida 1 conmuta según los parámetros configurados independientemente de si se produce un fallo.▶ Seleccionar [FOU2] y fijar un valor:<ul style="list-style-type: none">- [On] = la salida 2 se ACTIVA en caso de fallo, la señal analógica alcanza el valor límite superior.- [OFF] = la salida 2 se DESACTIVA en caso de fallo, la señal analógica alcanza el valor límite inferior.- [OU] = la salida 2 conmuta según los parámetros configurados independientemente de si se produce un fallo. La señal analógica se corresponde con el valor de medición.	
---	--



FINAL PROJECT

Date: 19.06.2014

Page: 326

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

9.6 Funciones de asistencia

9.6.1 Leer los valores mín/máx para caudal

<ul style="list-style-type: none">▶ Seleccionar [HI] o [LO], presionar brevemente [Set]. [HI] = valor máximo, [LO] = valor mínimo. <p>Borrar la memoria:</p> <ul style="list-style-type: none">▶ seleccionar [HI] o [LO].▶ Presionar [Set] y mantenerlo pulsado hasta que aparezca [---] en la pantalla.▶ Presionar brevemente [Mode/Enter]. <p>Es recomendable borrar la memoria una vez que el aparato esté operando por primera vez en condiciones normales de funcionamiento.</p>	
---	--

9.6.2 Restablecer todos los parámetros a la configuración de fábrica

<ul style="list-style-type: none">▶ Seleccionar [rES].▶ Presionar [Set] y mantenerlo pulsado hasta que aparezca [---] en la pantalla.▶ Presionar brevemente [Mode/Enter]. <p>Los valores de fábrica se encuentran al final de este manual (→ 13 Configuración de fábrica). Es recomendable anotar en esta tabla las configuraciones propias antes de poner el equipo en funcionamiento.</p>	
---	--



FINAL PROJECT

Date: 19.06.2014

Page: 327

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

9.7 Configuración del contador con preselección/del valor de impulsos (ImPS)

El equipo dispone de 7 rangos de configuración:

	LED	Indicación	incremento	Valor
1	3	0 0 . 0 1 ... 9 9 . 9 9	0,01 l	0,01...99,99 l
2	3	1 0 0 . 0 ... 9 9 9 . 9	0,1 l	100,0...999,9 l
3	3	1 0 0 0 ... 9 9 9 9	1 l	1000...9999 l
4	4	1 0 . 0 0 ... 9 9 . 9 9	0,01 m ³	10,00...99,99 m ³
5	4	1 0 0 . 0 ... 9 9 9 . 9	0,1 m ³	100,0...999,9 m ³
6	4	1 0 0 0 ... 9 9 9 9	1 m ³	1000...9999 m ³
7	4 + 6	1 0 . 0 0 ... 3 0 . 0 0	10 m ³	10 000...30 000 m ³

ES

Proceso de configuración:

- ▶ Seleccionar [OU1] y configurar [ImP] (→ 9.3.2).
- ▶ Presionar [Mode/Enter] hasta que aparezca [ImPS] en la pantalla.
- ▶ Presionar [Set] y mantenerlo pulsado.
- > El valor numérico actual parpadea durante 5 s, a continuación se activará el primero de los 4 dígitos (el dígito parpadea, se puede modificar).
- ▶ Configurar el valor deseado como se indica en la siguiente tabla.
 - ▶ Seleccionar primero el rango de configuración deseado (1, 2, 3 ...).
 - ▶ A continuación introducir el número de izquierda (primer dígito) a derecha (cuarto dígito).
- ▶ Presionar brevemente [Mode/Enter] cuando los 4 dígitos estén configurados.

En cuanto parpadee el primer dígito, se pueden dar 3 posibilidades:

▶ Presionar brevemente [Set] 1 vez en cada caso.	El dígito que parpadea aumenta. Después de 9 sigue 0 - 1 - 2, etc.
	8 1 . 2 3
	[Set] pulsado 1 vez 9 1 . 2 3
	[Set] pulsado 1 vez 0 1 . 2 3
	[Set] pulsado 1 vez 1 1 . 2 3



FINAL PROJECT

Date: 19.06.2014

Page: 328

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

▶ Presionar [Set] y mantenerlo pulsado.	El dígito que parpadea aumenta, después de 9 sigue 0 y el siguiente dígito de la izquierda se activa. <div style="text-align: right;">8 1. 8 3</div> <div style="text-align: right;">[Set] pulsado permanentemente 8 1. 9 3</div> <div style="text-align: right;">[Set] se sigue manteniendo pulsado 8 1. 0 3</div>
	Si el dígito 1 aumenta de esta manera, la pantalla cambia al siguiente rango de configuración superior (después de 9 sigue 10; el punto decimal se traslada un puesto hacia la derecha o el indicador LED cambia). <div style="text-align: right;">8 1. 2 3</div> <div style="text-align: right;">[Set] pulsado permanentemente 9 1. 2 3</div> <div style="text-align: right;">[Set] se sigue manteniendo pulsado 1 0 1. 2</div>
▶ Esperar 3 s (no pulsar ningún botón).	El siguiente dígito de la derecha parpadea (= se activa). <div style="text-align: right;">8 1 2. 3</div> <div style="text-align: right;">Ningún botón pulsado; tras 3 s 8 1 2. 3</div> <div style="text-align: right;">tras 3 s 8 1 2. 3</div> <div style="text-align: right;">tras 3 s 8 1 2. 3</div>
	Si el cuarto dígito parpadea durante 3 s sin ser modificado, el dígito 1 volverá a activarse si tiene un valor > 0. <div style="text-align: right;">tras 3 s 8 1 2. 3</div>
	Si el dígito 1 tiene el valor "0", la pantalla cambia al siguiente rango de configuración inferior (el punto decimal se traslada un puesto hacia la izquierda o el indicador LED cambia). <div style="text-align: right;">0 1 2. 3</div> <div style="text-align: right;">tras 3 s 1 2. 3 0</div> <p style="text-align: center;">A continuación: modificar el dígito 4 o esperar 3 s y configurar el dígito 1.</p> <div style="text-align: right;">tras 3 s 1 2. 3 0</div>

Marcado en gris (1) = dígito parpadeante.

Nota: si se pulsa [Set] continuamente, por la pantalla irán pasando todos los rangos; tras el valor final se comienza de nuevo con el valor inicial. A continuación soltar brevemente [Set] y comenzar de nuevo con la configuración.



FINAL PROJECT

Date: 19.06.2014

Page: 329

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

10 Funcionamiento

Una vez conectada la tensión de alimentación y pasado el tiempo de retardo a la disponibilidad (aprox. 5 s), el aparato se encuentra en el modo Run (= modo operativo normal). Ejecuta las funciones de evaluación y medición y genera señales de salida correspondientes a los parámetros configurados.

- Indicación de funcionamiento → Capítulo 7 Elementos de manejo y visualización.
- Durante el tiempo de retardo a la disponibilidad, las salidas están conmutadas según se haya programado: se activan con la función N.A. (Hno / Fno) o se desactivan con la función N.C. (Hnc / Fnc)
- Si la salida 2 se configura como salida analógica, la señal de salida tendrá el valor máximo durante el tiempo de retardo a la disponibilidad.

10.1 Lectura de la configuración de los parámetros

- ▶ Presionar [Mode/Enter] hasta que aparezca el parámetro deseado.
- ▶ Presionar brevemente [Set].
- > El equipo muestra durante aprox. 15 s el valor correspondiente del parámetro. Tras otros 15 s, el dispositivo retorna al modo Run.

ES

10.2 Cambio de la unidad de indicación en el modo Run.

- ▶ Presionar brevemente [Set] en el modo Run. Cada vez que se pulsa el botón, se pasa a la siguiente unidad de indicación.
- > El equipo muestra durante aprox. 15 s el valor de medición actual en la unidad de indicación seleccionada, el LED correspondiente se enciende.

10.3 Indicación de errores

[SC1]	Cortocircuito en OUT1.
[SC2]	Cortocircuito en OUT2.
[SC]	Cortocircuito en ambas salidas.
[OL]	Rango de detección de caudal o temperatura superado; valor de medición entre 120% y 130% del MEW.
[UL]	Rango de detección de caudal o temperatura no alcanzado; valor de medición entre -120% y -130% del MEW.
[Err]	- Equipo defectuoso / fallo de funcionamiento. - Valor de medición superior al 130% del MEW o inferior al -130% del MEW.
[SEnS]	El sensor indica una medición errónea.
[Loc]	Botones de configuración bloqueados, la modificación de parámetros no es posible.

MEW = valor límite del rango de medición



FINAL PROJECT

Date: 19.06.2014

Page: 330

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

10.4 Condiciones generales de funcionamiento

► Evitar la acumulación de residuos, gas y aire en el sistema de tubos.


! Con temperaturas del fluido superiores a 50°C, algunas partes de la carcasa pueden calentarse a más de 65°C.

► En este caso no tocar el equipo.

► Proteger la carcasa contra el contacto con sustancias inflamables y contra un contacto involuntario.

► No pulsar los botones con los dedos; en su lugar utilizar un objeto auxiliar (p. ej. un bolígrafo).

11 Dibujo a escala



Dimensiones en mm



FINAL PROJECT

Date: 19.06.2014

Page: 331


PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

12 Datos técnicos

Campo de aplicación.....	Fluidos líquidos conductores
Conductividad.....	$\geq 20 \mu\text{S/cm}$
Viscosidad.....	$< 70 \text{ mm}^2/\text{s}$ a 40°C
Tensión de alimentación [V].....	19...30 DC ¹⁾
Corriente máxima [mA].....	2 x 200
resistente a los cortocircuitos; resistente a inversiones de polaridad / sobrecargas	
Caída de tensión [V].....	< 2
Consumo de corriente típ. [mA].....	120
Salida analógica.....	4 ... 20 mA / 0 ... 10 V; Rango de medición graduado
Carga máx. para la salida de corriente [Ω].....	500
Carga mínima para la salida de tensión [k Ω].....	2
Valor de impulsos.....	0,01 l...30 000 m ³
Duración de los impulsos [s].....	mín. 0,01 / máx. 2
Tiempo de retardo a la disponibilidad [s].....	5
Supervisión de caudal	
Rango de medición [l/min / m ³ /h].....	0,1...25 / 0,005...1,5
Resolución [l/min / m ³ /h].....	0,05 / 0,005
Margen de indicación [l/min / m ³ /h].....	-30...30 / -1,8...1,8
Tiempo de respuesta [ms].....	< 150 (si dAP = 0);
Amortiguamiento de la señal de caudal (dAP) [s].....	0,0...5,0
Tiempo de espera al arranque [s].....	0...50
Precisión.....	$< \pm (2\% \text{ MW} + 0,5\% \text{ MEW})$
Repetibilidad [% MEW].....	$\pm 0,2$
Pérdida de presión (dP) en función de la cantidad de caudal (Q)	

ES





FINAL PROJECT

Date: 19.06.2014

Page: 332

PROJECT:
"Compressors test live bench under wet compression conditions"ANNEX:
2

Supervisión de temperatura	
Rango de medición [°C].....	-20...80
Tiempo de respuesta [s]	T09 = 30 (Q > 1 l/min)
Resolución [°C].....	0,2
Precisión [°C].....	± 2,5 (Q > 1 l/min)
Temperatura ambiente [°C].....	-10...60
Temperatura del fluido [°C].....	-10...70
Resistencia a la presión [bar]	16
Materiales en contacto con el medio.....	inox (1.4404 / 316L); PEEK; FKM
Materiales de la carcasa.....	inox (1.4404 / 316L); PBT-GF 20; PC (Makrolon); EPDM/X (Santoprene)
Grado/clase de protección.....	IP 67 / III
Resistencia de aislamiento [MΩ]	> 100 (500 V DC)
Resistencia a choques [g]	20 (DIN / IEC 68-2-27, 11ms)
Resistencia a vibraciones [g].....	5 (DIN / IEC 68-2-6, 55 - 2000 Hz)
CEM	
IEC 1000/4/2 Descargas electrostáticas:	4 / 8 KV
IEC 1000/4/3 Campos electromagnéticos de alta frecuencia radiados:.....	10 V/m
IEC 1000/4/4 Transitorios eléctricos rápidos en ráfagas:.....	2 KV
IEC 1000/4/5 Impulsos de alta energía u ondas de choque:.....	0,5 / 1 KV
IEC 1000/4/6 Campos electromagnéticos de alta frecuencia conducidos:	10 V

¹⁾ según EN50178, MBTS, MBTP;

MW = valor de medición; MEW = valor límite del rango de medición

12.1 Rangos de configuración

FLOW	SP1 / SP2		rP1 / rP2		ASP		AEP		ΔQ
	mín	máx	mín	máx	mín	máx	mín	máx	
l/min	0,25	25,00	0,10	24,90	0,00	20,00	5,00	25,00	0,05
m ³ h	0,015	1,500	0,005	1,495	0,000	1,200	0,300	1,500	0,005

TEMP	SP2		rP2		ASP		AEP		ΔT
	mín	máx	mín	máx	mín	máx	mín	máx	
°C	-19,2	80,0	-19,6	79,6	-20,0	60,0	0,0	80,0	0,2

ImPS	mín	máx
	0,01 l	30 000 m ³

(ΔQ, ΔT = incremento)



FINAL PROJECT

Date: 19.06.2014

Page: 333

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

13 Configuración de fábrica

	Configuración de fábrica	Configuración del usuario
SP1	5,00	
rP1	4,90	
ImPS	0,05	
ImPR	YES	
OU1	Hno	
OU2	I	
SP2 (FLOW)	10,00	
rP2 (FLOW)	9,90	
SP2 (TEMP)	20,0	
rP2 (TEMP)	19,6	
ASP (FLOW)	0,00	
AEP (FLOW)	25,00	
ASP (TEMP)	-20,0	
AEP (TEMP)	80,0	
DIn2	+EDG	
FOU1	OFF	
FOU2	OFF	
dSt	0	
P-n	PnP	
dAP	0,6	
rTo	OFF	
diS	d2	
Uni	Lmin	
SELd	FLOW	
SEL2	FLOW	

ES

Datos técnicos y más información en www.ifm.com



FINAL PROJECT


Date: 19.06.2014

Page: 334

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3 REFRIGERANT FLUX



4 PRESSURE SENSOR

JUMO MIDAS S05 OEM pressure transmitter - universal

Applications

- HVAC (Heating, Ventilating and Air Conditioning)
- Refrigeration
- Compressor construction
- Machine and plant engineering
- Packaging industry

Brief description

The JUMO MIDAS S05 pressure transmitter is available with both relative pressure and absolute pressure measurement ranges.

The high-quality stainless steel welded measuring system with no seals ensures the instrument can be used in almost all media, even under harsh conditions. The design offers optimum protection against process medium escaping.

The instrument features a silicon sensor that is able to handle extreme overload, even in the

lowest measuring ranges, and is capable of millions of pressure cycles.

Customer benefits

• Economical

A high level of automation (digital compensation and calibration of the sensor assembly) reduces production time and manufacturing costs.

• Process safety

The piezoresistive silicon sensor is highly overload-resistant and long-term stable. The high quality of every pressure transmitter is ensured by the 100% final inspection within the fully automated measuring and calibration system.

• Time-saving, uncomplicated and versatile

There is little work involved in mounting the measuring instrument and electrical installation is simple. Universal: thanks to its modular configuration, it can be used in virtually every application.



Type 401010
with terminal box



Type 401010
with M12x1 connector

Special features

- 1 bar to 100 bar relative pressure, up to 25 bar in absolute pressure as well
- High level of process safety thanks to a welded measuring system with no seals
- Sturdy and maintenance-free measurement technology with extreme overload resistance
- 60% faster device installation with the Quickon fast-connection system
- Sturdy design for a long service life
- Parts in contact with media made of stainless steel

JUMO GmbH & Co. KG
 Delivery address: Mackenrodtstraße 14
 36039 Fulda, Germany
 Postal address: 36035 Fulda, Germany
 Phone: +49 661 6003-0
 Fax: +49 661 6003-607
 E-mail: mail@jumo.net
 Internet: www.jumo.net

JUMO Instrument Co. Ltd.
 JUMO House
 Temple Bank, Riverway
 Harlow, Essex CM20 2DY, UK
 Phone: +44 1279 635533
 Fax: +44 1279 635262
 E-mail: sales@jumo.co.uk
 Internet: www.jumo.co.uk

JUMO Process Control, Inc.
 8 Technology Boulevard
 Canastota, NY 13032, USA
 Phone: 315-697-5866
 1-800-554-JUMO
 Fax: 315-697-5867
 E-mail: info.us@jumo.net
 Internet: www.jumousa.com



Technical data

General information

Reference conditions	DIN 16 086 and EN 60770
Sensor	
Material	Silicon sensor with stainless steel separating diaphragm
Pressure transfer medium	Synthetic oil
Permissible load change	> 10 million
Location	
Mounting position	Any
Calibration position	Device standing upright, process connection on bottom

Measuring range

Relative and absolute pressure	Measuring ranges start at 0 bar.									
Measuring range	1	1.6	2.5	4	6	10	16	25	40	bar
Overload capacity ^a	4	6	10	16	24	40	60	100	100	bar
Bursting pressure	6	10	15	24	36	60	100	150	150	bar
Relative pressure	Measuring ranges start at 0 bar.									
Measuring range	60	100								bar
Overload capacity ^a	180	180								bar
Bursting pressure	250	250								bar
Relative pressure	Measuring ranges start at 0 bar.									
Measuring range	-1 – 0	-1 – 0.6	-1 – 1.5	-1 – 3	-1 – 5	-1 – 9	-1 – 15	-1 – 24		bar
Overload capacity ^a	4	6	10	16	24	40	60	100		bar
Bursting pressure	6	10	15	24	36	60	100	150		bar

^a All pressure transmitters are vacuum-proof

Output

Output signal^a	
Current	
Output 405	4 – 20 mA, two wires
Voltage	
Output 412	DC 0.5 – 4.5 V, three wires, ratiometric 10 – 90% of the supply voltage
Output 415	DC 0 – 10 V, three wires
Output 418	DC 1 – 5 V, three wires
Output 420	DC 1 – 6 V, three wires
Jump response	
T ₉₀	≤5 ms
Burden	
Current	
4 – 20 mA, two wires	$R_i \leq (U_B - 8 \text{ V}) / 0.02 \text{ A } (\Omega)$
Voltage	
DC 0.5 – 4.5 V, three wires	≥ 5 kΩ
DC 1 – 5 V, three wires	≥ 10 kΩ
DC 1 – 6 V, three wires	≥ 10 kΩ
DC 0 – 10 V, three wires	≥ 10 kΩ

^a Additional outputs are available on request.

JUMO GmbH & Co. KG
 Delivery address: Mackenrodtstraße 14
 36039 Fulda, Germany
 Postal address: 36035 Fulda, Germany
 Phone: +49 661 6003-0
 Fax: +49 661 6003-607
 E-mail: mail@jumo.net
 Internet: www.jumo.net

JUMO Instrument Co. Ltd.
 JUMO House
 Temple Bank, Riverway
 Harlow, Essex CM20 2DY, UK
 Phone: +44 1279 635533
 Fax: +44 1279 635262
 E-mail: sales@jumo.co.uk
 Internet: www.jumo.co.uk

JUMO Process Control, Inc.
 8 Technology Boulevard
 Canastota, NY 13032, USA
 Phone: 315-697-5866
 1-800-554-JUMO
 Fax: 315-697-5867
 E-mail: info.us@jumo.net
 Internet: www.jumousa.com



Mechanical properties

Process connection	
Material	Stainless steel 304 ^a
Membrane	
Material	Stainless steel 316L
Enclosure	
Material	Stainless steel 304
Electrical connection	
Material	
Fixed cable, Electr. connection 11	PBT-GF30, PVC
Quickon, Electr. connection 23	PBT-GF30
Round plug M12x1, Electr. connection 36	PBT-GF30, stainless steel 303
Bayonet connector, Electr. connection 53	PBT-GF30
Terminal box, Electr. connection 61	PBT-GF30, PA, silicon
Weight	approx. 80 g with process connection 502 (G1/4)

^a Pressure transmitters with process connection 521 come with an FPM seal.

Ambient conditions

Permissible temperatures	
Electrical connections 36, 53 or 61	
Medium	-40 – +125°C
Environment	-40 – +125°C
Storage	-40 – +125°C
Electrical connection 11	
Medium	-40 – +125°C
Environment	-40 – +100°C
Storage	-40 – +100°C
At ambient temperature -50°C	
Restricted function	Stationary use only, danger of broken cable
Permissible relative humidity	
In operation	100% rel. humidity, incl. condensation on the outer sleeve of the instrument
Storage	90% relative humidity, no condensation
Permissible mechanical loading	
Vibration resistance ^a	20 g, 10 – 2000 Hz
Shock resistance ^b	50 g for 11 ms 100 g for 1 ms
Electromagnetic compatibility	
Interference emission ^c	Class B
Interference immunity ^c	Industrial requirements
Enclosure protection^d	
Fixed cable, Electr. connection 11	
Relative pressure measuring ranges	IP66
Absolute pressure measuring ranges	IP67
Quickon, Electr. connection 23	IP66
M12x1 round plug, Electr. connection 36	IP66
Bayonet connector, Electr. connection 53	IP67
Terminal box ^e , Electr. connection 61	IP65

^a IEC 60068-2-6

^b IEC 60068-2-27

^c EN 61326-2-3

^d EN 60529

^e Connecting cable diameter is min. 5 mm, max. 7 mm.

JUMO GmbH & Co. KG
 Delivery address: Mackenrodtstraße 14
 36039 Fulda, Germany
 Postal address: 36035 Fulda, Germany
 Phone: +49 661 6003-0
 Fax: +49 661 6003-607
 E-mail: mail@jumo.net
 Internet: www.jumo.net

JUMO Instrument Co. Ltd.
 JUMO House
 Temple Bank, Riverway
 Harlow, Essex CM20 2DY, UK
 Phone: +44 1279 635533
 Fax: +44 1279 635262
 E-mail: sales@jumo.co.uk
 Internet: www.jumo.co.uk

JUMO Process Control, Inc.
 8 Technology Boulevard
 Canastota, NY 13032, USA
 Phone: 315-697-5866
 1-800-554-JUMO
 Fax: 315-697-5867
 E-mail: info.us@jumo.net
 Internet: www.jumousa.com



Accuracy

Relative and absolute pressure		Measuring ranges start at 0 bar.									
Measuring range		1	1.6	2.5	4	6	10	16	25	40	bar
Linearity^a		0.3	0.25	0.25	0.25	0.25	0.25	0.2	0.2	0.2	% of FS
Accuracy, 20°C ^b		0.6	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	% of FS
Accuracy, -20 – +100°C ^c		1.5	1.4	1.3	1.2	1.2	1.0	1.0	1.0	1.0	% of FS
Relative pressure		Measuring ranges start at 0 bar.									
Measuring range		60	100								bar
Linearity^a		0.2	0.2								% of FS
Accuracy, 20°C ^b		0.5	0.5								% of FS
Accuracy, -20 – +100°C ^c		1.0	1.0								% of FS
Relative pressure		Measuring ranges start at 0 bar.									
Measuring range		-1 – 0	-1 – 0.6	-1 – 1.5	-1 – 3	-1 – 5	-1 – 9	-1 – 15	-1 – 24		bar
Linearity^a		0.3	0.3	0.3	0.3	0.25	0.25	0.25	0.2		% of FS
Accuracy, 20°C ^b		0.6	0.6	0.6	0.5	0.5	0.5	0.5	0.5		% of FS
Accuracy, -20 – +100°C ^c		1.5	1.5	1.4	1.3	1.3	1.2	1.0	1.0		% of FS
Long-term stability^d		< 0.2% of FS									

^a Linearity based on limit point setting

^b Includes: linearity, hysteresis, repeatability, deviation from initial and full scale values of the measuring range

^c Includes: linearity, hysteresis, repeatability, deviation from initial and final values of measuring range, thermal effect on initial value of measuring range and span

^d EN 61298-1

Auxiliary power

Supply voltage U_B^a	
4 – 20 mA, two wires, output 405	DC 8 – 30 V, nominal power supply DC 24 V
DC 0.5 – 4.5 V, three wires, output 412	DC 3 – 5.25 V, nominal supply voltage DC 5 V, radiometric output 10 – 90% of the supply voltage
DC 0 – 10 V, three wires, output 415	DC 11.5 – 30 V, nominal power supply DC 24 V
DC 1 – 5 V, three wires, output 418	DC 8 – 30 V, nominal power supply DC 24 V
DC 1 – 6 V, three wires, output 420	DC 8 – 30 V, nominal power supply DC 24 V
Power consumption	≤ 25 mA
Reverse polarity protection	Yes
Circuit	SELV

^a Residual ripple: Peak voltages must **not** exceed or fall below the values specified for the supply voltage!






JUMO GmbH & Co. KG
 Delivery address: Mackenrodtstraße 14
 36039 Fulda, Germany
 Postal address: 36035 Fulda, Germany
 Phone: +49 661 6003-0
 Fax: +49 661 6003-607
 E-mail: mail@jumo.net
 Internet: www.jumo.net

JUMO Instrument Co. Ltd.
 JUMO House
 Temple Bank, Riverway
 Harlow, Essex CM20 2DY, UK
 Phone: +44 1279 635533
 Fax: +44 1279 635262
 E-mail: sales@jumo.co.uk
 Internet: www.jumo.co.uk

JUMO Process Control, Inc.
 8 Technology Boulevard
 Canastota, NY 13032, USA
 Phone: 315-697-5866
 1-800-554-JUMO
 Fax: 315-697-5867
 E-mail: info.us@jumo.net
 Internet: www.jumousa.com



Connection diagram

Connection		Terminal assignment ^a				
						
		11 Fixed cable	23 Quickon	36 Round plug, M12x1	53 Bayonet	61 Terminal box
4 – 20 mA, two wires, output 405						
Supply voltage 8 – 30 V DC	UB/S+ 0 V/S-	White Brown	1 3	1 3	1 2	1 2
DC 0.5 – 4.5 V Ratiometric, output 412						
Supply voltage DC 3 – 5.25 V	UB 0 V/S-	White Brown	1 2	1 2	1 2	1 2
Ratiometric output 10 – 90 % of the supply voltage	S+	Yellow	3	3	3	3
DC 0 – 10 V, three wires, output 415						
Supply voltage DC 11.5 – 30 V	UB 0 V/S-	White Brown	1 2	1 2	1 2	1 2
	S+	Yellow	3	3	3	3
DC 1 – 5 V, three wires, output 418 DC 1 – 6 V, three wires, output 420						
Supply voltage DC 8 – 30 V	UB 0 V/S-	White Brown	1 2	1 2	1 2	1 2
	S+	Yellow	3	3	3	3

^a Illustration shows the pressure transmitter connector

Color assignment: Round plug, M12x1	1 bn Brown	4 bk Black	The color assignment applies
	2 wh White	5 gy Gray	only to A-coded standard cables!
	3 bu Blue		

JUMO GmbH & Co. KG
 Delivery address: Mackenrodtstraße 14
 36039 Fulda, Germany
 Postal address: 36035 Fulda, Germany
 Phone: +49 661 6003-0
 Fax: +49 661 6003-607
 E-mail: mail@jumo.net
 Internet: www.jumo.net

JUMO Instrument Co. Ltd.
 JUMO House
 Temple Bank, Riverway
 Harlow, Essex CM20 2DY, UK
 Phone: +44 1279 635533
 Fax: +44 1279 635262
 E-mail: sales@jumo.co.uk
 Internet: www.jumo.co.uk

JUMO Process Control, Inc.
 8 Technology Boulevard
 Canastota, NY 13032, USA
 Phone: 315-697-5866
 1-800-554-JUMO
 Fax: 315-697-5867
 E-mail: info.us@jumo.net
 Internet: www.jumousa.com



Dimensions

Electrical connection

11 Fixed cable	23 Quickon	36 Round plug, M12x1	53 Bayonet connector	61 Terminal box

Process connection

501 G1/8	502 G1/4	504 G1/2	511 1/4 - 18 NPT

521 G1/4	562 7/16-20 UNF	563 7/16 UNF inside

A = G1/4 profile seal

B = 7/16-20 UNF inside, with valve core depresser

JUMO GmbH & Co. KG

Delivery address: Mackenrodtstraße 14
36039 Fulda, Germany
Postal address: 36035 Fulda, Germany
Phone: +49 661 6003-0
Fax: +49 661 6003-607
E-mail: mail@jumo.net
Internet: www.jumo.net

JUMO Instrument Co. Ltd.

JUMO House
Temple Bank, Riverway
Harlow, Essex CM20 2DY, UK
Phone: +44 1279 635533
Fax: +44 1279 635262
E-mail: sales@jumo.co.uk
Internet: www.jumo.co.uk

JUMO Process Control, Inc.

8 Technology Boulevard
Canastota, NY 13032, USA
Phone: 315-697-5866
1-800-554-JUMO
Fax: 315-697-5867
E-mail: info.us@jumo.net
Internet: www.jumousa.com



Order details

(1) Basic type

401010/000 JUMO MIDAS S05 pressure transmitter
401010/999 JUMO MIDAS S05 pressure transmitter, special design

(2) Input

454 0 – 1 bar relative pressure
455 0 – 1.6 bar relative pressure
456 0 – 2.5 bar relative pressure
457 0 – 4 bar relative pressure
458 0 – 6 bar relative pressure
459 0 – 10 bar relative pressure
460 0 – 16 bar relative pressure
461 0 – 25 bar relative pressure
462 0 – 40 bar relative pressure
463 0 – 60 bar relative pressure
464 0 – 100 bar relative pressure

478 -1 – 0 bar relative pressure
479 -1 – 600 mbar relative pressure
480 -1 – 1.5 bar relative pressure
481 -1 – 3 bar relative pressure
482 -1 – 5 bar relative pressure
483 -1 – 9 bar relative pressure
484 -1 – 15 bar relative pressure
485 -1 – 24 bar relative pressure

488 0 – 1 bar absolute pressure
489 0 – 1.6 bar absolute pressure
490 0 – 2.5 bar absolute pressure
491 0 – 4 bar absolute pressure
492 0 – 6 bar absolute pressure
493 0 – 10 bar absolute pressure
494 0 – 16 bar absolute pressure
495 0 – 25 bar absolute pressure

998 Special measuring range for absolute pressure
999 Special measuring range for relative pressure

(3) Output

405 4 – 20 mA, two wires
412 DC 0.5 – 4.5 V, three wires
415 DC 0 – 10 V, three wires
418 DC 1 – 5 V, three wires
420 DC 1 – 6 V, three wires

(4) Process connection

501 G 1/8 to DIN EN 837
502 G 1/4 to DIN EN 837
504 G 1/2 to DIN EN 837
511 1/4-18 NPT to DIN 837
521 G1/4 to DIN 3852 T11
562 7/16 - 20 UNF
563 7/16 - 20 UNF inside, with valve opener

(5) Process connection material

20 CrNi (stainless steel)

(6) Electrical connection

11 Fixed cable ^a
23 Quickon
36 Round plug, M12x1
53 Bayonet instrument connector DIN 72585^b
61 Terminal box EN 175301-803, Form A, ex DIN 43650

JUMO GmbH & Co. KG
 Delivery address: Mackenrodtstraße 14
 36039 Fulda, Germany
 Postal address: 36035 Fulda, Germany
 Phone: +49 661 6003-0
 Fax: +49 661 6003-607
 E-mail: mail@jumo.net
 Internet: www.jumo.net

JUMO Instrument Co. Ltd.
 JUMO House
 Temple Bank, Riverway
 Harlow, Essex CM20 2DY, UK
 Phone: +44 1279 635533
 Fax: +44 1279 635262
 E-mail: sales@jumo.co.uk
 Internet: www.jumo.co.uk

JUMO Process Control, Inc.
 8 Technology Boulevard
 Canastota, NY 13032, USA
 Phone: 315-697-5866
 1-800-554-JUMO
 Fax: 315-697-5867
 E-mail: info.us@jumo.net
 Internet: www.jumousa.com



(7) Extra codes

- 000 No extra code
- 591 Throttle in pressure channel
- 624 Free of oil and grease
- 630 Enlarged pressure channel^c

Notes on the order details

- a Electrical connection 11**
 Standard: 2 m fixed cable, other lengths available on request
- b Electrical connection 53**
 Bayonet connector DIN 72585-A1-3.1-Sn/K1
- c Extra code 630**
 Diameter 6 mm for process connection 501
 Diameter 8 mm for process connections 511 and 521

	(1)	(2)	(3)	(4)	(5)	(6)	(7)	(7)
Order code	<input type="text"/>	- <input type="text"/>	- <input type="text"/>	- <input type="text"/>	- <input type="text"/>	- <input type="text"/>	/ <input type="text"/>	, ...
Sample order	401010/000	- 459	- 405	- 504	- 20	- 61	/ 591	, 624

Minimum order quantity for production orders: 5 units
Minimum order quantity for storage orders: 1 unit

Stock versions

Order code	Description	Part no.
401010/000-456-405-502-20-61/000	0 – 2.5 bar; 4 – 20 mA; G1/4; terminal box	43012486
401010/000-457-405-502-20-61/000	0 – 4 bar; 4 – 20 mA; G1/4; terminal box	00517155
401010/000-458-405-502-20-61/000	0 – 6 bar; 4 – 20 mA; G1/4; terminal box	00517148
401010/000-459-405-502-20-61/000	0 – 10 bar; 4 – 20 mA; G1/4; terminal box	00517139
401010/000-459-405-563-20-61/000	0 – 10 bar; 4 – 20 mA; 7/16-20UNF; terminal box	43012540
401010/000-460-405-502-20-61/000	0 – 16 bar; 4 – 20 mA; G1/4; terminal box	00517133
401010/000-461-405-502-20-61/000	0 – 25 bar; 4 – 20 mA; G1/4; terminal box	00523660
401010/000-483-405-563-20-61/000	-1 – 9 bar; 4 – 20 mA; 7/16 - 20 UNF; terminal box	00531777
401010/000-491-405-502-20-61/000	0 – 4 bar abs.; 4 – 20 mA; G1/4; terminal box	43012517
401010/000-492-405-502-20-61/000	0 – 6 bar abs.; 4 – 20 mA; G1/4; terminal box	00526283

Accessories

Description	Part no.
Cable connector, straight, 4-pin, M12x1, 2m PVC cable	00404585
Cable connector, angled, 4-pin, M12x1, 2m PVC cable	00409334

5 TEMPERATURE SENSORS

Screw-in thermocouples with compensating cable


- for temperatures from -200 to +600°C
- available with different thermocouples
- as single or twin thermocouple
- compensating cable in silicone or with metal braiding

Screw-in thermocouples are preferred for measuring temperatures in liquids and gases. An important selection criterion is their reliable sealing against both negative and positive pressures. Applications include heating installations, ovens, furnaces and plant engineering.

Depending on the version, the compensating cables are suitable for use in dry and humid areas within a temperature range from -20 to +350°C. The connection of the cable to the protection tube incorporates strain relief and can be provided with a cable protector (option).

Protection tubes in stainless steel protect the measuring insert from chemical influences and mechanical damage.

The measuring insert is fitted with thermocouples to EN 60 584 and DIN 43 710. Versions with two thermocouples are also available.



Technical data

Connection

available with cable ends as: bare wires, ferrules, with receptacles or multipole connector

Compensating cable

silicone, ambient temperature -50 to +180°C

metal braiding, ambient temperature -20 to +350°C

Process connection

thread, stainless steel 1.4571

Protection tube

stainless steel 1.4571, 6mm and 8mm dia.

Measuring insert

insulated assembly:

1 x Fe-Con L, DIN 43 710, Cl. 2, operating temperature -200 to +600°C

1 x NiCr-Ni K, EN 60 584, Cl. 2, operating temperature -200 to +600°C

2 x Fe-Con L, DIN 43 710, Cl. 2, operating temperature -200 to +600°C

2 x NiCr-Ni K, EN 60 584, Cl. 2, operating temperature -200 to +600°C

Accessories

pockets, Data Sheet 90.9721


JUMO GmbH & Co. KG
Delivery address: Mackenrodtstraße 14,
36039 Fulda, Germany
Postal address: 36035 Fulda, Germany
Phone: +49 661 6003-0
Fax: +49 661 6003-607
E-mail: mail@jumo.net
Internet: www.jumo.net

JUMO Instrument Co. Ltd.
JUMO House
Temple Bank, Riverway
Harlow - Essex CM20 2DY, UK
Phone: +44 1279 63 55 33
Fax: +44 1279 63 52 62
E-mail: sales@jumo.co.uk
Internet: www.jumo.co.uk


JUMO Process Control, Inc.
8 Technology Boulevard
Canastota, NY 13032, USA
Phone: 315-697-JUMO
1-800-554-JUMO
Fax: 315-697-5867
E-mail: info@jumo.us
Internet: www.jumo.us




Dimensions



Type 901050/10



Type 901050/20



Type 901050/30

JUMO GmbH & Co. KG
 Delivery address: Mackenrodtstraße 14,
 36039 Fulda, Germany
 Postal address: 36035 Fulda, Germany
 Phone: +49 661 6003-0
 Fax: +49 661 6003-607
 E-mail: mail@jumo.net
 Internet: www.jumo.net

JUMO Instrument Co. Ltd.
 JUMO House
 Temple Bank, Riverway
 Harlow - Essex CM20 2DY, UK
 Phone: +44 1279 63 55 33
 Fax: +44 1279 63 52 62
 E-mail: sales@jumo.co.uk
 Internet: www.jumo.co.uk


JUMO Process Control, Inc.
 8 Technology Boulevard
 Canastota, NY 13032, USA
 Phone: 315-697-JUMO
 1-800-554-JUMO
 Fax: 315-697-5867
 E-mail: info@jumo.us
 Internet: www.jumo.us



Order details: Screw-in thermocouples with compensating cable

(1) Basic version

901050/10	Screw-in thermocouple with fixed screw fitting
901050/20	Screw-in thermocouple with loose screw fitting
901050/30	Screw-in thermocouple with screw-in protection tube



(2) Operating temperature in °C / compensating cable

x x	150	-200 to +600°C / metal braiding
x x x	380	-50 to +200°C / silicone
x x x	390	-50 to +300°C / metal braiding
x x	402	-50 to +400°C / metal braiding

(3) Measuring insert

x x x	1042	1 x Fe-Con L
-------	------	--------------

	FINAL PROJECT	Date: 19.06.2014
		Page: 346
PROJECT: "Compressors test live bench under wet compression conditions"		ANNEX: 2

x	137	137mm
x x	...	please specify in plain text (50mm steps)

(6) Process connection

x	104	thread 1/2" pipe
x	105	thread 3/4" pipe
x	106	thread 1" pipe
	111	thread M 8
x	114	thread M 10 x 1

(7) Compensating cable end

x x x	03	bare cable ends
x x x	11	ferrules to DIN 46 228 Part 4 (standard)
x x x	13	receptacle 6.3 to DIN 46 247
x x x	80	multipole connector (please specify type in plain text)

(8) Compensating cable length AL in mm (500 ≤ AL ≤ 500000)

x x x	2500	2500mm
x x x	...	please specify in plain text (500mm steps)

(9) Extra codes

x x x	000	no extra code
x x x	309	uninsulated assembly (thermocouple welded to tip)
x x x	315	cable protector: coil
x x x	316	cable protector: tube

Order code (1) - (2) - (3) - (4) - (5) - (6) - (7) - (8) / (9) , ...
Order example 901050/10 - 150 - 1042 - 6 - 100 - 104 - 11 - 2500 / 000¹

1. List extra codes in sequence, separated by commas.



FINAL PROJECT

Date: 19.06.2014

Page: 346

PROJECT:
"Compressors test live bench under wet compression conditions"ANNEX:
2

ANNEX X: OFFERS

1 EMERSON

SUMARIO

Item	Cant.	Descripción	Precio unitario (EUR)	Precio total (EUR)	Plazo de entrega (semanas)
1	1	F025S115CCANSZZZ Micro Motion Coriolis F-Series sensor; 1/4-inch; 316L stainless steel	2.774,70	2.774,70	5
1,1	1	1700I13ABMSZZZ Micro Motion Coriolis MVD single variable flow transmitter	691,65	691,65	5
2	1	ASISTENCIA TECNICA MICRO MOTION (Opcional) <i>1 día de asistencia en planta para la puesta en servicio del caudalímetro</i>	680,00	680,00	
Total material (EUR):				3.466,35	
Transporte (EUR):				69,33	
Embalaje (EUR):				INCLUIDO	
Total (EUR):				3.535,68	

Condiciones particulares

Pedido mínimo	:150,00 € (portes no incluidos)
Precios	:Los precios son fijos durante el período de validez de la oferta.
Plazo de entrega	:Empieza a partir de la fecha de recepción de su pedido oficial en nuestras oficinas. El pedido deberá venir acompañado de toda la documentación técnica y comercial necesaria para su tramitación y suministro sin interrupciones. En caso de recibir un pedido incompleto o incorrecto, el plazo empezará a contar en el momento de la compleción de la información necesaria.
Transporte	:
Condiciones de entrega	: CPT Transporte Pagado Hasta destino peninsular
Validez	: 30/05/14
Forma de pago	:Contado al pedido / Transferencia Los términos de pago ofertados y la aceptación de cualquier pedido resultante de esta oferta están sujetos a la aprobación de nuestro departamento de control de créditos.
Hitos de pago	:En caso de pedidos que incluyan equipos y servicios, los equipos se facturarán a la entrega y los servicios se facturarán una vez completados.
Destino final	:España
Garantías	:A) Estándar: 12 meses desde la puesta en marcha ó 18 meses desde la entrega del material, siendo de aplicación la fecha que se cumple en primer lugar.

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 347
PROJECT: "Compressors test live bench under wet compression conditions"		ANNEX: 2

Pedidos	<p>B) Extensión: Por cada 6 meses de ampliación de garantía, se aplicará un 3% del importe total del pedido.</p> <p>:Solo se aceptarán pedidos oficiales. No se procesarán comunicaciones de intención de pedido o pedidos verbales.</p>
Modificaciones de pedido	<p>:La cancelación de un ítem o el cambio en su especificación pueden ocasionar costes o variaciones en la fecha de entrega que variarán según la envergadura y el momento del cambio y que se notificarán en su caso. Se procesarán las modificaciones una vez recibido el pedido definitivo.</p>
Documentación	<p>:Salvo indicación contraria, la documentación incluida es la documentación estándar de Emerson para los equipos ofertados. En caso de necesitar documentación específica rogamos nos lo comuniquen antes de formalizar su pedido.</p>

Esta oferta está sujeta a las condiciones generales de Emerson Process MANAGEMENT, S.L., y las condiciones particulares indicadas anteriormente.

"La presente oferta, la aceptación de cualquier pedido bajo la misma y el cumplimiento de cualesquiera obligaciones contractuales derivadas de ella estarán sujetos al cumplimiento de cualesquiera normas aplicables en materia de control a la importación y la exportación y su normativa sancionadora, incluidas, en su caso, las normas de los EE.UU. No obstante lo anterior, dichas normas podrán ser modificadas en cada momento, incluyendo durante el procesamiento de un pedido. En el caso de que EMERSON PROCESS MANAGEMENT, SL (la Compañía) no obtenga las licencias, autorizaciones o aprobaciones que sean necesarias o convenientes, aun en el caso de que la falta de obtención se deba a la falta de respuesta de las autoridades administrativas competentes para ello, o en el caso de que dichas licencias, autorizaciones o aprobaciones sean denegadas o revocadas, la Compañía quedará relevada y exonerada de todas sus obligaciones derivadas de cualquier oferta realizada, sin penalización alguna. Del mismo modo, la Compañía quedará relevada y exonerada de todas sus obligaciones sin penalización alguna si existiera algún cambio en las leyes, órdenes u otra normativa aplicable que prohibiera a la Compañía el cumplimiento de cualquier pedido o que, a juicio razonable de la Compañía, le exponga a algún riesgo en aplicación de dichas leyes, órdenes o normativa en caso de cumplimiento del pedido."

"Emerson Process Management SL (La empresa) está comprometida con los estándares más estrictos de conducta ética y comercial y puede requerir la cumplimentación de un cuestionario de diligencia debida (DDQ por sus siglas en inglés). Si se requiere esta cumplimentación, la aceptación de cualquier pedido resultante de esta oferta estará sujeta a la revisión favorable por la empresa del DDQ enviado."

	FINAL PROJECT	Date: 19.06.2014 Page: 348
PROJECT: "Compressors test live bench under wet compression conditions"		ANNEX: 2

RESUMEN DE EQUIPOS

Item	Cant.	Descripción
1	1	F025S115CCANSZZZ
		F025S Modelo: Micro Motion Coriolis F-Series sensor; 1/4-inch; 316L stainless steel
		115 Conexiones de proceso: 1/2-inch CL600 ASME B16.5 F316/F316L Weld neck flange Raised face
		C Opciones de estuches: Compact case
		C Interfase de los electrónicos: For integral mount 1700/2700 transmitter
		A Conexiones de conductos: No gland
		N Aprobaciones: Micro Motion Standard / PED compliant
		S Idioma: Spanish installation manual
		Z Opción futura 1: Reserved for future use
		Z Calibration,for liquids only) 0.20% mass flow and 0.002 g/cc density calibration
		Z Software de aplicación de medidas: No measurement application software
		Z Opciones de fábrica: Standard product

Item	Cant.	Descripción
1,1	1	1700I13ABMSZZZ
		1700 Modelo: Micro Motion Coriolis MVD single variable flow transmitter
		I Montaje: Integral mount transmitter
		1 Alimentación: 18 to 100 VDC and 85 to 265 VAC; self switching
		3 Pantalla: No display
		A Output (1700): One mA; one frequency; RS485
		B Conexiones de conductos: 1/2-inch NPT - no gland
		M Aprobaciones: Micro Motion Standard (no approval)
		S Idioma: Spanish installation manual and Spanish configuration manual
		Z Opciones de software 1: Reserved for future use
		Z Opciones de software 2: No software options 2
		Z Opciones de fábrica: Standard product
		Tag Calibracion
		0 – 120 g/seg

Item	Cant.	Descripción
2	1	ASISTENCIA TECNICA MICRO MOTION (Opcional)
		<i>Revisión de la instalación eléctrica y mecánica</i>
		<i>Configuración del instrumento según hoja de datos.</i>
		<i>Realización del cero y</i>
		<i>Pruebas de lazo en señales analógicas</i>

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 349
	PROJECT: "Compressors test live bench under wet compression conditions"	ANNEX: 2

2 EBARA

Fecha: 01/05/2014

OFERTA Nº.: EEZA - 20140501 30.733

Referencia:

A continuación le detallamos la oferta solicitada:

Item	Uds.	Descripción	Precio neto unitario	Total neto
1	1	Tipo: BOMBA SIMPLE ROTOR HÚMEDO ELECTRÓNICA Pot. [kw]: 0 r.p.m.[1/min]: 0 Modelo: EGO EGO 15/40-130 Construida en: HIERRO FUNDIDO Tensión: 1 * 230V VERSION ESPECIAL ER PORTES: 9,90 € EN FRA.	202,80€	202,80 €

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 350
PROJECT: "Compressors test live bench under wet compression conditions"		ANNEX: 2

CONDICIONES DE VENTA:

Precios según tarifa vigente.

Forma de pago: De acuerdo con la ley 15/2010 de lucha contra la morosidad.
Validez de la oferta: 1 mes.
Plazo de entrega: 1 semana laboral aproximadamente.
Impuestos: No incluidos.

Condiciones de entrega: Portes pagados hasta pie de obra / su almacén, para importes superiores a 600 €. Descarga a cargo del cliente.

Garantía: La garantía de los equipos estará supeditada al estricto cumplimiento de los requisitos de funcionamiento reflejados en la Documentación Técnica.

Gastos de almacenaje: Los gastos de almacenaje son del 2,5% por mes pasados los primeros 15 días. En el caso de retraso, por causas ajenas a EBARA, en la entrega de la mercancía fabricada, se emitirá la factura en el plazo de 15 días desde la fecha de finalización de

Devoluciones: El comprador dispone de un plazo de 15 días contados a partir de la fecha de recepción de las mercancías, para devolvernos cualquier equipo. En ningún caso se admitirán devoluciones que no hayan sido previamente acordadas con nuestro departamento comercial. En caso de acuerdo, y siempre dentro del plazo anteriormente establecido, el material deberá ser remitido perfectamente embalado (embalaje original) y a PORTES PAGADOS, indicando datos de su expedición y/o facturación (nº y fecha de albarán, nº de factura, etc.)

En todas las devoluciones la mercancía se depreciará un 15% del valor neto facturado, en concepto de participación de nuestros costos de revisión y acondicionamiento.



FINAL PROJECT

Date: 19.06.2014

Page: 351

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

3 JUNO

En relación a su consulta, nos es grato cotizarles como sigue:

Página.1

Item	Descripción	Cant	Precio	Desc	Total	Plazo
1	Termopar NiCr-Ni tipo "K", con dimensiones de inserción medición en accesorio pos. 2, rosca M10, con 3000 mm longitud de cable de silicona con malla metálica Ref.: 901050/10-380-1043-5,6-29-114-03-3000/31	5,00	61,00		305,00	4 semanas
2	Soporte para tubería de ½", entrada y salida Ref.: 902442/11-000-104-104-000	5,00	45,00		225,00	10 días laborables
3	Transmisor de presión con rosca de ¼". Ref.: 401010/000-464-405-502-20-61/000	3,00	144,00		432,00	3/4 semanas

Total: 962,00

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014 Page: 352
PROJECT: "Compressors test live bench under wet compression conditions"		ANNEX: 2

En caso de formular pedido, hacer referencia al número de oferta

Condiciones comerciales

Precio: franco fábrica, sin IVA, sin embalaje
Envío: Portes debidos, envío no incluido en la oferta. (Sus medios).
Forma de pago: primer pedido al contado sino según condiciones habituales
Validez de la oferta: 30 días
Pedido mínimo: € 75,00
La oferta no incluye otros servicios ni prestaciones, no recogidas expresamente en la oferta

Oferta válida según nuestras condiciones generales de venta y suministro (visibles en www.jumo.es)

Aun cuando Jumo Control de su apoyo por escrito o verbalmente, en la selección de sus productos para la aplicación por el cliente, es responsabilidad final del comprador comprobar la idoneidad del producto para la aplicación a la que se le destina.
El riesgo de uso es del comprador, a no ser, Jumo hubiera suscrito un acuerdo explícito de uso con el comprador



FINAL PROJECT

Date: 19.06.2014

Page: 353

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

4 IFM



Oferta y compra online
en www.ifm.com

Contacto ifm RUBIO David (DAR)
Teléfono - Fax -
E-mail general: info.es@ifm.com
solo pedidos: eorders.es@ifm.com
asistencia técnica: soporte.es@ifm.com

Copia 1 Pagina 1

Dirección de entrega BSH ELECTRODOMESTICOS
ESPAÑA SA
CRTA.TAFALLA 17
31132 VILLATUERTA
ESPAGNE



Pos	Fecha entrega estimada	Articulo	Cantidad	Precio neto unit. EUR	Total sin IVA EUR
10	22/04/2014	SM6000 SMR12GGXFRKG/US-100 Caudalímetro magneto-inductivo efector300 5 años Garantía	1 pcs	304,0000	304,00
20	22/04/2014	EVC005 ADOAH040MSS0005H04 Conector hembra ecomat400 5 años Garantía	1 pcs	4,2000	4,20
950	22/04/2014	PV01 Portes			14,70

Condiciones de entrega : Standard (max.5 días)- Portes en factura	Total base imponible :	322,90 EUR
Transportista : UPS	IVA 21,0 % :	67,81 EUR
Condiciones de pago : 75 DIAS NETO	Total a pagar :	390,71 EUR
Forma de pago : PAGARE/TALON		

Identificación : Ingenieurgesellschaft fuer Messtechnik Electronic S.L.
Inscrita en el RM Barcelona, Tomo 40787, folio 96, Hoja B-375041, inscripción 1ª
CIF: B64956873

Domiciliación bancaria : Commerzbank AG: IBAN ES68 0159 0002 8056 2380 6978 BIC/Swift COBAESMXBAR

Ver nuestras condiciones de venta en www.ifm.com

Los datos personales facilitados por Usted serán incorporados a un fichero automatizado de ifm electronic con la finalidad de realizar las tareas administrativas/comerciales y de gestión necesarias para el cumplimiento de las obligaciones legales derivadas de la relación mercantil. Usted puede ejercitar los derechos de acceso, rectificación y cancelación legalmente establecidos, mediante comunicación a ifm electronic, en C/Garrotxa 6-8 de El Prat de Llobregat, Barcelona (CP08820).

	<h1>FINAL PROJECT</h1>	Date: 19.06.2014
		Page: 354
PROJECT: "Compressors test live bench under wet compression conditions"		ANNEX: 2

5 OMEGA

Su N ° de pedido	EMAIL RFQ	Enviar por	U P S
Fecha del pedido	8 May 14	Número de cuenta del transportista	-
Fecha de envío	8 May 14	Condiciones de envío	SHIPPING POINT
Comprador	N. MEDINA	N ° de IVA	ESA28893550
Agente de ventas	GAIZKA NUNEZ (gnunez@omega.co.uk)	Condiciones	NET 30 DAYS

Número de pieza	Descripción	Ctd Pedida	Ctd Restante	Precio unitario EUR	Ext EUR
1	CSH-5082000/240V CARTRIDGE HTR 3/4"X8" 2000W	1	1	56.280	56.280
2	*CARRIAGE-C UPS ROAD SERVICE	1	1	15.000	15.000
Entrega: En stock. Oferta válida durante un periodo de 60 días.				Subtotal	EUR 71.280
				TOTAL	EUR 71.280

Omega Engineering Limited, One Omega Drive, River Bend Technology Centre, Northbank, Irlam, Manchester M44 5BD. Reino Unido
Teléfono Gratuito: 800 900 532 (Solo desde España), Tel: 911 776 121, Fax: 911 776 122, Email: ventas@es.omega.com

N ° de IVA GB 620 0439 89 Company No. 2564017 Todos los bienes son propiedad de Omega Engineering Ltda hasta que se reciba el pago en su totalidad

6 ELECTROLUMEN

CÓDIGO	RESUMEN	CANTIDAD	PRECIO	IMPORTE
CAPÍTULO 01 OPCION 1 - PLC UNICO PARA 6 PUESTOS				
SUBCAPÍTULO 01.01 PLC S7-315 PARA 6 PUESTOS				
01.01.01	Ud Perfil soporte 480mm SIMATIC S7-300, Perfil soporte longitud =480mm	2,00	28,99	57,98
01.01.02	Ud Unidad central CPU 315-2PN/DP SIMATIC S7-300 CPU 315-2 PN/DP, Módulo central con 384 Kbyte . Memoria principal, Interface 1: MPI/DP 12 MBits/s, Interface 2: Ethernet Profinet, con Switch de 2 Puertos. Requiere Micro memory card.	1,00	2.193,17	2.193,17
01.01.03	Ud Micro Memory Card 512kB SIMATIC S7, Micro Memory Card para S7-300/C7/S7-200 IM 151 CPU, 3,3 V NFlasch, 512 Kbyte	1,00	179,02	179,02
01.01.04	Ud Interfase IM-365 SIMATIC S7-300, interfase IM 365 para conectar un bastidor de ampliación, 2 Módulos + cable 1m. Sin Bus K	1,00	127,27	127,27
01.01.05	Ud Módulo de termopares 6 canales SIMATIC S7-300, Módulo entradas analógicas SM331, canal galvánico AC250V, 6 termopares tipo B, E, J, K, L, N, R, S, T Tensión +/-25MV hasta +/-1V 16 Bits, 50 ms, 1 x 40 polos	5,00	858,89	4.294,45
01.01.06	Ud Módulo de entradas analógicas 8 canales en tensión SIMATIC S7-300, Módulo entradas analógicas SM 331, con aislamiento galvánico, 8 EA, Resolución de 13 Bits, U/I/Resistencia/PT100, NI100, NI1000, LG-NI1000, PTC / KTY, tiempo con versión 66MS, 1 x 40 polos	4,00	406,68	1.626,72
01.01.07	Ud Módulo de salidas analógicas 8 canales tensión/corriente SIMATIC S7-300, Módulo de salidas analógicas SM 332, con separación galvánica, 8 SA, U/I; con diagnóstico, resolución 11/12 Bits, 40 polos, posible conexión y desconexión con bus protector activo	2,00	922,02	1.844,04
01.01.08	Ud Módulo de salidas digitales 16SD 24Vcc SIMATIC S7-300, Módulo de salidas digitales SM 322, con separación galvánica, 16 SD, 24 V DC, 0,5 A, conector 20 polos	1,00	214,20	214,20
01.01.09	Ud Conector frontal 40 polos tornillo SIMATIC S7-300, conector frontal 392 con terminales de tornillo, 40 polos	11,00	35,69	392,59
01.01.10	Ud Conector frontal 20 polos tornillo SIMATIC S7-300, conector frontal para bloques de entrada/salida con terminales de tornillo, 20 polos	1,00	22,55	22,55
01.01.11	Ud Pantalla táctil 9" SIMATIC TP900 Comfort Panel, Windows CE 6.0, Display TFT panorámico de 9 , 12 MB de Memoria de config., configurable con WinCC V11	1,00	1.625,56	1.625,56
TOTAL SUBCAPÍTULO 01.01 PLC S7-315 PARA 6 PUESTOS.....				12.577,55
TOTAL CAPÍTULO 01 OPCION 1 - PLC UNICO PARA 6 PUESTOS				12.577,55

CÓDIGO	RESUMEN	CANTIDAD	PRECIO	IMPORTE
CAPÍTULO 02 OPCION 2 - PLC CENTRAL + REMOTA POR PUESTO				
SUBCAPÍTULO 02.01 PLC CENTRAL				
02.01.01	Ud Perfil soporte 160mm SIMATIC S7-300, Perfil soporte longitud =160mm	1,00	18,64	18,64
02.01.02	Ud Unidad central CPU 315-2PN/DP SIMATIC S7-300 CPU 315-2 PN/DP, Módulo central con 384 Kbyte . Memoria principal, Interface 1: MPI/DP 12 Mbits/s, Interface 2: Ethernet Profinet, con Switch de 2 Puertos. Requiere Micro memory card.	1,00	2.193,17	2.193,17
02.01.03	Ud Micro Memory Card 512kB SIMATIC S7, Micro Memory Card para S7-300/C7/S7-200 IM 151 CPU, 3,3 V NFlasch, 512 Kbyte	1,00	179,02	179,02
02.01.04	Ud Pantalla táctil 9" SIMATIC TP900 Comfort Panel, Windows CE 6.0, Display TFT panorámico de 9 , 12 MB de Memoria de config., configurable con WinCC V11	1,00	1.625,56	1.625,56
TOTAL SUBCAPÍTULO 02.01 PLC CENTRAL				4.016,39
SUBCAPÍTULO 02.02 REMOTA (ET200S) PUESTO 1				
02.02.01	Ud Módulo interfase IM 151 PN para ET200S SIMATIC ET 200, módulo de interfase IM151-3 PN ST para ET 200S, velocidad de transmisión 100Mbit/s máximo 63 módulos (potencia, electrónicos, arrancadores de motor), hasta 2 metros de ancho, conexión al bus mediante 2 x RJ45 , incluye módulo terminador de ET	1,00	232,19	232,19
02.02.02	Ud Módulo de potencia PM-E 24Vcc SIMATIC ET 200, 1 módulo de potencia PM-E para ET 200S; DC 24V con diagnóstico	1,00	12,26	12,26
02.02.03	Ud Módulo de terminales para alimentación SIMATIC ET 200, 1 módulo de terminales TM-P15S23-A1 para ET 200S, para módulos de potencia, 15 mm de ancho, bornes de tornillo, 2 x 3 conexiones, con bornas de acceso a AUX1, continuación de AUX1	1,00	6,94	6,94
02.02.04	Ud Módulo electrónico para 2EA termopar SIMATIC ET 200, 1 módulo electrónico para ET 200S, 2EA TC (termopar) HIGH FEATURE, 15mm de ancho, 15bit + signo, con compensación interna de temperatura	3,00	147,77	443,31
02.02.05	Ud Módulo de terminales para termopar SIMATIC ET 200, 1 módulo de terminales TM-E15S24-AT para ET 200S, para módulos electrónicos 2 EA TC HIGH FEATURE, 15 mm de ancho, bornes tornillo, con bornas de acceso a AUX1, continuación de AUX1	3,00	19,01	57,03
02.02.06	Ud Módulo electrónico para 2EA intensidad 2 hilos SIMATIC ET 200, 1 módulo electrónico para ET 200S, 2EA STANDARD I-2DMU, 15mm de ancho, 4 .. 20mA; 13 bit, para transmisores de medida a 2 hilos, tiempo de ciclo 65ms/canal, con LED SF (fallo agrupado)	3,00	118,17	354,51

CÓDIGO	RESUMEN	CANTIDAD	PRECIO	IMPORTE
02.02.07	Ud Módulo electrónico para 2SA tensión SIMATIC ET 200, 1 módulo electrónico para ET 200S, 2 SA U (tensión), 15mm de ancho, +/-10V; 13 bit + signo :, 1..5V; 12 bit, tiempo de ciclo menor de 1 ms, con LED SF (fallo agrupado)	1,00	117,68	117,68
02.02.08	Ud Módulo electrónico para 2SA intensidad SIMATIC ET 200, 1 módulo electrónico para ET 200S, 2 SA I (corriente), 15mm de ancho, +/-20mA; 13 bit + signo :, 4 . .20mA; 12 bit, tiempo de ciclo menor de 1 ms, con LED SF (fallo agrupado)	1,00	117,68	117,68
02.02.09	Ud Módulo electrónico para 2SD 24Vcc SIMATIC ET 200, 5 módulos electrónicos para ET 200S, 2 SD STANDARD DC 24V/0,5A, 15mm de ancho, 5 unidades por embalaje	0,20	98,72	19,74
02.02.10	Ud Módulo de terminales SIMATIC ET 200, 5 módulos de terminales TM-E15S24-01 para ET 200S, para módulos electrónicos, 15 mm de ancho, bornes de tornillo, 2 x 4 conexiones, sin bornas de acceso a AUX1, continuación de AUX1, 5 unidades por embalaje	1,20	34,77	41,72



FINAL PROJECT

Date: **19.06.2014**

Page: **358**

PROJECT:
"Compressors test live bench under wet compression conditions"

ANNEX:
2

E.T.S. de Ingeniería Industrial,
Informática y de Telecomunicación

Compressors test life bench under wet compression conditions



Grado en Ingeniería
en Tecnologías Industriales

PLANES

Natalia Medina Cabello

Jose Ignacio Arocena

Pamplona, 26 de Junio del 2014





FINAL PROJECT

Date: **19.06.2014**


Page: 1

PROJECT:
"Compressors test live bench under wet compression conditions"

PLANES:
3


PLANE'S INDEX

1	PID OPTION1	<u>1</u>
2	PID OPTION 2	<u>2</u>
3	TEST RIG BENCH	<u>3</u>






	Sensors-Inputs
	Actuators-Outputs
	Thermodynamic equipment
	Refrigerant circuit
	Water circuit

	E.T.S.I.I.T. INGENIERO TECNICO INDUSTRIAL E.	DEPARTMENT: DEPARTAMENTO DE AUTOMATICA Y CONTROL
	PROJECT: <h2 style="text-align: center;">TEST BENCH</h2>	
AUTHOR: MEDINA CABELLO, NATALIA		DATE: 27/06/2014
SIGNATURE: 		ESCALE: 1 : 100
PLANE: PID OPTION 1		Num. PLANE: 1



○	Sensors-Inputs
○	Actuators-Outputs
□	Thermodynamic equipment
—	Refrigerant circuit
—	Water circuit

 Universidad Publica de Navarra Nafarroako Unibertsitate Publikoa	E.T.S.I.I.T. INGENIERO TECNICO INDUSTRIAL E.	DEPARTMENT: DEPARTAMENTO DE AUTOMATICA Y CONTROL
	PROJECT: <h2 style="text-align: center;">TEST BENCH</h2>	
AUTHOR: MEDINA CABELLO, NATALIA		SIGNATURE: 
PLANE: PID OPTION 2		DATE: 27/06/2014
		ESCALE: 1 : 100
		Num. PLANE: 2



LEYEND	
— Water circuit	Manual Expansion Valve (MEV)
— Refrigerant circuit	Electronic Expansion Valve (EEV)
 Thermodynamic equipment	Compressor
○ Sensors-Input signals	Variable speed pump
○ Actuators-Output signals	

Universidad Publica de Navarra Nafarroako Unibertsitate Publikoa	E.T.S.I.I.T. INGENIERO TECNICO INDUSTRIAL E.	DEPARTAMENT: DEPARTAMENTO DE PROYECTOS E ING. RURAL	
	PROJECT: <h2 style="text-align: center;">TEST BENCH</h2>		AUTHOR: MEDINA CABELLO, NATALIA SIGNATURE:
PLANE: <h2 style="text-align: center;">DISTRIBUTION</h2>	DATE: 27/06/2014	ESCALE: 1 : 25	Num. PLANE: 3